677א

THE

STUDENTS' COTTON SPINNING.

BY

JOSEPH NASMITH,

MEMBER INSTITUTION MECHANICAL ENGINEERS; PAST-PRESIDENT MANCHESTER
ASSOCIATION ENGINEERS; EXAMINER IN COTTON SPINNING FOR THE CITY AND
GUILDS OF LONDON INSTITUTE; EDITOR OF THE "TEXTILE RECORDER";
AUTHOR OF "MODERN COTTON SPINNING MACHINERY," "RECENT
COTTON MILL CONSTRUCTION.'

TWELFTH THOUSAND

CONS
TS
1577
N25
1896

PREFACE TO THE THIRD EDITION.

THE present edition has been in great part rewritten, and has been entirely reset from new type, the number of illustrations having also been doubled. Owing to the great length of the book, that portion of it which appeared in the preceding editions and dealt with the construction and engineering of mills has been omitted. The subject has, however, been much more fully treated in the author's " Recent Cotton Mill Construction and Engineering."

Among the new features will be found a complete series of illustrations of the growth and structure of the cotton fibre; a treatment of the hopper feeding machine; a section dealing with card clothing, in which, for the first time, the constructive details are fully discussed; a complete description of the Heilmann combing machine with full illustrations; and a long demonstration of the principle of winding on the roving frame and mule, the treatment of the latter portion of the subject being, in parts, quite new. In addition to these features the commerce of cotton is fully dealt with, the aim being to make the book a reliable reference on all points comprised within its title. In order to aid the object named a synopsis is given at the head of each chapter, and the index is also enlarged.

The drawings, showing the structure of the Cotton Fibre, Figs. 6 to 34 inclusive, are the work of Mr. ABRAHAM FLATTERS, 16, Church Road, Longsight, Manchester, and are copyrighted by him.

The two preceding editions—each consisting of 2,000 copies—have been very favourably received, and the author has confidence that the efforts made to render the present one even more complete will meet with equal encouragement. His thanks are tendered to all those who by suggestion and criticism have aided him in making clear any points which were doubtful in the previous issues

October, 1896.

28983

TABLE OF CONTENTS.

THE STUDENTS' COTTON SPINNING.

CHAPTER I.

THE EVOLUTION OF COTTON SPINNING.

Note.—The reference numbers in the synopsis of each chapter refer to the paragraphs and not to pages.

(1) THE theory of evolution is made to account more than plausibly for the existence of things both great and small, animate and inanimate. On the one hand by means of the nebular hypothesis, the origin of the sun and its planets, including our earth, as well as that of numerous other galaxies, is accounted for; and on the other, the genesis of the minutest speck of animal life. It has often occurred to us that the original progress and subsequent development in not only cotton spinning but in the working of all textiles does not apparently accord with the current doctrine of development. For this reason. The votaries of evolution assert that all progress takes place in order of time in gradual changes, but this is certainly not the case with textile industries. As regards minor inventions, it is, of course, perfectly true, but it does not satisfactorily explain the fact that the art of spinning with the distaff and spindle remained the same for thousands of years and

was entirely revolutionised and rendered obsolete by a few inventions brought out practically within the last century. To be consistent, believers in the theory of evolution must accept as an explanation of this very striking fact the hypothesis that still more wonderful development will take place at some time in the machinery used in these industries, not minor improvements in detail merely, but radical improvements in principle. That such will take place at some time or other is firmly believed, and also, that after working on the newly discovered lines for some time another radical improvement will occur. Many will probably smile at a suggestion that any great improvement in the present method of, say cotton spinning, is possible, without considering how vast and extensive an improvement the present system is over the mode that preceded it. Suppose, however, that radical improvements do occur, even if at intervals of thousands of years, the case stands on all fours with the theory of evolution. The greatest step that was ever made in advance in the whole art of cotton spinning was when some untutored savage invented twist, or thought of what to us is the very elementary idea of twisting two or more fibres or filaments together to make (perhaps not yarn) but thread or string, the latter more correctly describing it. It is not possible to discover his name or country, but whoever he was he certainly deserves a niche in the temple of fame. Before his time probably ligatures of some kind were in use, made, most likely, by knotting or plaiting together the strands of bark. Whether the first efforts of making string were with wool as a material, as many believe, or were confined to vegetable fibres, filaments, or strips of bark, cannot be ascertained with exactitude, but our opinion inclines to the latter view. The fact remains, however, that the greatest discovery in spinning was the invention of "twist," and with so much accomplished we have the whole basis of spinning. Commencing with the twisting together of a few filaments of approximately the same length, the discovery would not be long delayed that by overlapping one set of fibres by another the twist would be successively introduced into each set. This

is modern spinning, which differs from the primitive system only by this fact of continuous twisting of fibres round each other.

(2) With the knowledge available, it must be understood that only the probabilities of the order in which things would naturally occur are spoken of. When the art of spinning had been followed for some ages, most likely in the above way, it is easy to imagine that from making very coarse cords or bands from vegetable fibres, it became possible, with an increase of skill, to produce them tolerably fine, and to spin wool on this system also with a much better and finer result. The product would then be not a rough cord, or even a string; it would approach more nearly what we call yarn, the fineness of which would, of course, depend on the skill of the spinners, for by this method it would always require two to make a yarn. It was, however, observed that to require the services of two persons to produce a single end of yarn was to expend much labour upon a small result. Consequently, the first great improvement is reached, which consisted in the invention of the distaff and spindle, although, at first, the former was not absolutely necessary. The material was held by a slit or cleft in the end of the spindle in which it was placed. With this simple apparatus yarn was made in the following way. Some of the fibre was taken in one hand and some was also placed in the slit. With the other hand the spindle, which was allowed to hang freely and vertically, was revolved by the spinner twirling or twisting the material with her fingers. As the yarn was spun the spindle approached the ground, when, a sufficient length having been made, the spindle was taken up and the yarn wrapped upon it, after which another and succeeding part of the material was fixed in the slit and the operation proceeded with as before. In this case the spindle was perfectly free, and it was, doubtless, soon observed that it was easier to twirl and that it could be revolved for a longer period when its weight was increased by that of the yarn coiled upon it. This led to weighting the spindle with a ball of clay or a lump of metal.

The distaff is not an absolutely essential part of the apparatus, being merely a staff upon which some of the raw material is placed, but was commonly employed. The process, as carried out by a Greek spinster, has been described by several classic historians. It seems to have been preferred in Europe to the wheel and spindle as a means of spinning until about 200 years ago, so remarkable was its persistence. It is stated in an interesting little book published in 1819, that there were persons using it in North Britain (Scotland) so late as 1817.

(3) The distaff consists of a rod of wood shaped with a taper blade to hold the material, which is placed upon the longer part, and is fastened by a garter or string. The lower portion was fixed in the spinner's belt by means of which the distaff is kept steady. The spindle was turned quickly by the spinner's right hand, and upon it was twined the fibrous material drawn from the distaff by the other hand. The twisted material was wound upon the spindle at its upper end, and below the latter point a small wheel, or whorl, generally made of stone, was fixed. This acted as a fly, and the revolution of the spindle on its lower point, which rested on the floor, completed the operation.

(4) The next most important step in advance, was when some one invented the means of multiplying speed by the aid of a small and large pulley, round which a band was wrapped, the large one being driven. The great utility of this invention as a means of revolving the spindle is easily recognised. An improvement almost as great, in fact as great, for without it the means of multiplying the speed would not be available, was the discovery that any hook could be dispensed with by slitting the point of the spindle. The yarn when spun was wound on the spindle in an elongated ball, now termed a cop. Another remarkable invention consisted in dispensing with the slit previously used. As the process has been so far described, it will be observed that the axis of the thread being operated upon and the axis of the spindle are approximately in a straight line. It was, however, discovered that by holding the yarn at a considerable angle with the spindle, not quite a right angle,

it would pass over its point, and for every revolution made by
it one twist would then be transferred to the yarn.   It is this
system which is used in mule spinning, this invention being
really the precursor of it.

(5) The earliest machines used for spinning, so far as can be
ascertained, were of the rudest construction, having a wooden
spindle driven by a heavy wheel, and at first were used only for
producing coarse yarn from a bundle of unprepared fibrous
material.   But as skill in the art increased and knowledge
respecting textile fibres extended, it is easy to see how cotton
came to be employed as the raw material.   At first the cotton
was probably brought to the spindle as it was picked, without
any preparation whatever.   To spin cotton, a finer spindle,
without being absolutely necessary, would be very advantageous,
and consequently the wheel was fitted with a metallic spindle,
and eventually spinning was done sometimes with and some-
times without the distaff.   The following was the mode of
operation :—Some cotton being attached to the spindle, the
wheel was turned with the left hand.   A further quantity of
cotton was supplied by the right hand, the fingers of which,
according to Baines, were kept dry by the use of a chalky
powder.   When a piece of yarn had been spun of the required
degree of tenuity, which was accomplished by the spinster
holding it between the finger and thumb and withdrawing
her hand to the extent demanded, twist being meantime put in
by the revolution of the spindle, the yarn so produced is wound
on the spindle by turning the latter the reverse way to what it
ran when spinning.   With apparatus of this rude character
yarns of an extraordinary fineness have been for generations
produced in India.   It has lately been pointed out that Indian
cotton as spun in the organised factories now existing cannot be
drawn into yarn of any degree of fineness.   It is tolerably
certain that the materials which the earliest Indian weavers of
whom we have records had at their disposal were substantially
those existing to-day.   It speaks volumes for the cultivated
skill of the progenitors of the present Indian operatives that

yarns so fine as to produce muslins of the exquisite character of those obtained from India could be spun from cotton which is not now looked upon as a tractable material. A wheel which was extensively used was known as the flax or Saxony wheel. It consisted of a strong frame, which carried a wheel from which by a band the spindle and flyer was driven. The spindle had a bobbin loosely placed upon it, but driven so as to cause it to lag behind the flyer, and so wind the yarn. The spindle was sustained by a post fixed into the frame, and the wheel was driven by the treadle. The material was placed upon the equivalent to the distaff, and was withdrawn thence by the hand of the spinner.

(6) So far the fibre treated had undergone no previous manipulation in the spinning process, when it was doubtless discovered that the operation would be facilitated and a better product be obtained if the cotton was brought to the spinner in a more open and fleecy condition. In all probability, therefore, the next improvement was the introduction of a preparatory process. This consists of bowing the cotton, a description of which operation is given. This process of bowing has been in use by some hat makers until quite recently. The bow employed in India was rather different to the hatters' bow, being simpler. It consists of two stretched strings attached to one of the extremities of a crescent-shaped crosspiece fixed on the staff, and tightened by some means at its other extremity. The cotton being spread on a table, the staff is held with one hand, and with the other, by means of a mallet or a rough piece of wood, the workman strikes the stretched cord nearest to him, thereby causing it to vibrate. This causes the other cord to oscillate also, and the latter, being in contact with the heap of cotton, jerks up the fibres to another part of the table almost separately, and effectually clears the mass of dirt and knots. All who are acquainted with the modern cotton trade will recognise that the operations of willowing and opening are used mainly for the same purpose. The seeds in the cotton pod were got rid of by another rude form of machine called a

"Churka," which consisted of two horizontal rollers with a few longitudinal flutes. The rollers are revolved by a handle attached to the axis of the upper one. The cotton is drawn through the rollers, the space between which is insufficient to allow the seeds to pass, so that the fibre is separated from them. The cleaned cotton, therefore, is delivered at the far side of the rollers, while the seeds remain on the feed side. An illustration of this machine and the bow is given in Baines' "History of the Cotton Manufacture," to which the student can refer.

(7) A still more primitive process is that still pursued in some parts of India, by which a bundle of cotton is placed upon a flat stone, and a roller is passed over it by the foot of the operator— a woman generally. The roller receives a short reciprocal movement, and the seeds are removed by the hand, a sitting stooping posture being adopted for the purpose. The account thus given is on all grounds of probability the order in which the successive stages in cotton spinning, as it is practised in the East, and till comparatively recently in Europe, were developed. But within a comparatively short period of the intro-duction of the art into England, of which our earliest records fix the year 1538 as the date, very considerable improvements occurred. The process of carding, however slow and laborious, was making progress towards its present perfection, and was, as far as can be discovered, an entirely English invention. Its origin, however, was due to the workers in wool, from which it was transferred to the cotton trade, to improve the working in which it was subsequently developed.

(8) The employment of cards such as were used for wool to straighten out and make a fleece of cotton marked another epoch in the spinning of cotton. It was a further stage in that development of the art which has found its culmination in the splendid series of inventions of the present century. The preparation of the cotton into a fleece, however short, enabled a greater length of yarn to be spun than was possible when the cotton was taken from the mass, and an approximation to con-tinuous spinning became possible. But the action of any human

being in drawing out the fibres by an extension of one arm
during the time a spinning wheel was being manually rotated by
the other, necessarily is more or less uncertain.   Great as the
advance thus made was upon the previously crude method of
spinning from a distaff, even when by the addition of a treadle
the spinning wheel was revolved, and both hands left at liberty,
the element of manual treatment remained.   It is true that the
Hindoo workers had demonstrated the possibility of overcoming
to a large extent the natural defects of such a system, and had
produced yarn of the delicate character previously described.
The extraordinary skill thus attained was, however, the property
of a comparatively limited circle, and it became necessary, as
the demand for cotton goods grew, to depend for its supply
upon spinners less reliable and skilful.   Thus the need arose for
some method of drawing out the carded fleece at a regular rate
which was independent of human skill.   Hence was originated
the system of drawing by rollers, with which the name of
Arkwright is ordinarily associated, but which undoubtedly, found
its originator in John Wyatt, of Birmingham, about the year
1738.   Immediately following this was the invention of a
method of carding cotton by a revolving cylinder, by Lewis
Paul, of Birmingham, in 1748.   At this point the modern period
of invention is reached, about which a little time may be
profitably spent.

(9) If thought is given to the modern system of spinning, it
will become abundantly clear that the use of rollers by which
the requisite degree of tenuity in the yarn is obtained forms the
key to it.   It is quite clear that if the element of continuous
drawing is removed the essence of modern spinning machines is
destroyed.   Therefore the contrivance of a machine by which
the fleece or sliver of cotton could be drawn out while being
continuously delivered, at once revolutionised the whole process,
and introduced possibilities never before dreamed of.   With this
system of spinning the name of Arkwright is commonly coupled,
but, as has been observed, it is more than doubtful whether he
ought to have the credit.   The history of Arkwright up to the

time when he was supposed to have invented a spinning frame
in which drawing rollers were used is all against the presumption
that he had the necessary skill to invent and construct a
machine.   It is well known and established that he was
acquainted with a man named Thomas Highs or Hays, of
Leigh, and also with one John Kay of the same place.   Now it
is alleged that Highs, or Hays, was the real inventor of the use
of drawing rollers, and that Arkwright, who afterwards employed
Kay, who was also extremely intimate with Hays, perfected the
machine by appropriating the ideas of the latter.   This at least
was alleged at a trial of an action which Arkwright brought
against Colonel Mordaunt for an infringement of his patent.
That action failed, and it is therefore on record that in the
opinion of the jury trying it Mr. Arkwright was not the real
inventor.   But there is conclusive proof that John Wyatt, of
Birmingham, was the real inventor, and in 1738 his partner,
Lewis Paul, obtained Letters Patent for his invention.   Ark-
wright did not obtain a patent until 1769, and if it can be
shown, as it undoubtedly can, that the mode of operation, if not
the precise details, of the two inventions is similar, there can be
little doubt of the falsity of the Arkwright claim.   Now Lewis
Paul in his specification uses these remarkable words : " The
wool or cotton being thus prepared one end of the mass, rope,
thread, or sliver, is put betwixt a pair of rollers, cylinders, or
cones, or some such movements, which being twined round by
their motion draws in the raw mass of wool or cotton to be spun
in proportion to the velocity given to such rollers, cylinders, or
cones ; as the prepared mass passes regularly through or betwixt
these rollers, cylinders, or cones, a succession of other rollers,
cylinders, or cones, moving proportionably faster than the first,
draw the rope, thread, or sliver, into any degree of fineness
which may be required."   Although this document, which is a
very remarkable one, is signed by Lewis Paul, there is little
doubt that Wyatt was the true inventor.   The evidence on this
point is conclusive ; the establishment of the fact that in 1738,
31 years prior to Arkwright's patent, the principle of using

rollers had been not only described but applied, entirely destroys any claim on the part of Arkwright to novelty. There is further evidence that the latter knew of the existence of Wyatt's invention, and being a man who did not stick at trifles he was quite prepared to accept the results accruing from the successful use of a prior invention.

(10) The specification of Lewis Paul, or of Wyatt, has been described as a remarkable document. Let us just look, for a little, at what it describes. There is first the idea of drawing in the sliver by means of a pair of revolving rollers; next there is the idea of placing in front of these a second pair, rotating at a superior speed, thus ensuring the attenuation of the sliver to a degree corresponding to the variation in the speed of the two pairs. Now, what is there in the modern system which differs in principle from this? True, the details are altered, but the continuous drawing of a sliver by rollers rotated at defined but different speeds remains to-day the recognised method of procedure. What is necessary to make a special note of, however, is that this invention is really the commencement of the modern era of spinning, and that without it, so far as cotton is concerned, at any rate, the present perfection is impossible. The wide difference between delivering a roving to a spindle in short lengths drawn by the spinner's hand from the mass of prepared fibre, and delivering the same roving at a steady and continuous speed for an indefinite time, is easily recognisable, and placed within the reach of the spinner a mode of working much superior to that previously possible. A little later on the application of this device to various spinning machines will be dealt with, but before doing so it is advisable to say a little upon the development of machines for preparing the material for drawing.

(11) In 1847 Lewis Paul invented a carding machine which consisted of a small cylinder, on the surface of which a number of narrow cards were fastened, and beneath which was a correspondingly curved surface also fitted with cards. The cotton being passed between these two surfaces was carded and afterwards stripped by a needle, stick, or comb; and by an ingenious

contrivance the strips of carded cotton, which had a length equal
to the width of the cylinder, were joined into one strand or
sliver.   The chief points to notice in this machine are the use
of a cylinder covered with carding points, the employment of a
stripping comb, and the possibility of a continuous operation
involved in the easy rotation of the cylinder.   In the same year
Daniel Bourne invented a machine for the same purpose, and
of much the same construction.   A few years after the invention
by Paul, a machine constructed on this principle was introduced
into Lancashire, and was adopted by Mr. Peel, the grandfather
of Sir Robert Peel.   He, however, employed Hargreaves to
construct a machine in which more than one cylinder was used,
and the rotation of these in contact carded the cotton.   Up to
this period the only vital constructive principle adopted was
that of the wire-covered cylinder.   The operations of feeding
the uncarded and removing the carded cotton were both manual,
and the next step was the provision of mechanical means for
this purpose.   The apron feed was invented in 1772 by one
John Lees, of Manchester, and shortly after Arkwright devised
a method of forming the cotton into a lap to feed it, and the
doffer to remove it.   Therefore, at this early date, 1774, we
have got evidence of the existence of a machine which possessed
the essentials of to-day—a continuous feed, a continuous carding
surface, and a continuous stripper.   The next step was the
adoption of a method by which the fleece deposited on the
doffer could be taken from it, and about the same time the
doffer comb was invented.   The web, in its removal, was, as
to-day, collected by a trumpet compressed by rollers and col-
lected into a can for further treatment.   The carding was done
by flats placed above the cylinder and easily removable for
cleaning.   Before leaving this subject it might be said that
the use of rollers and clearers belong to a little later stage in the
process, with which there is no present intention to deal.   The
revolving can, however, was used by Arkwright to put twist into
the rovings, but it was not until the early part of this century
that the idea of the coiler was originated.   It has been generally

asserted that this was the invention of Mr. David Cheetham, of
Rochdale, but there is reason to believe that the perfecting of
the coiler was the work of his employer, Mr. Tatham. Be that
as it may, the point it is desired to emphasise is that before the
end of the last century the carding engine possessed all its main
features.

(12) It was time for further invention to take place, because
the introduction in 1738 of the fly shuttle, by John Kay, of
Bury, enormously increased the power of the weaver, and there
was hardly yarn enough to be got from all the existent hand
wheels. In 1769 Arkwright's spinning machine saw the light,
and, in addition to the rollers, it consisted of spindles driven by
bands and having flyers upon their upper ends by which the yarn
was twisted. The spindles had bobbins mounted upon them—in
short, this machine was the progenitor and predecessor of the
throstle or fly spinning frame which was so long in extensive
employment. Arkwright's machines were gradually improved,
but in their main features were unchanged, and owing to the
fact that they were usually driven by water power, received the
name water frames, whence the phrase water twist. But con-
temporaneously with the evolution of the water frame was that
of the spinning jenny, which was the work of James Hargreaves,
of Blackburn, and was invented by him in the period between
1764 and 1767. The jenny consisted of an arrangement of
framework which carried a series of spindles to which rotation
was given by means of a hand wheel. A band or cord passing
over this drove a light cylinder, and a series of cords from these
drove the spindles. The spindles were vertical in position, and
the rovings were attached to them at one end, and at a distance
of a few inches were clasped by a holder forming part of a frame
sliding on the main framework. The rovings were held in a
creel within the framework, and being secured, the sliding frame
was drawn back, thus stretching them, the twist being put in by
turning the wheel during the drawing out. A wire guide
pressing upon the twisted yarn was worked by the foot of the
attendant during the time the winding was taking place, so as

to place the yarn properly on the spindle in the form of a cop. With this crude machine as many as 120 threads at a time were spun, but the process was necessarily a slow one.   It is well to observe here that this machine of Hargreaves' touches both the period before and after its production.   In this machine the old principle of drawing out the yarn in short lengths and twisting as an operation prior to winding it into a cop, was found, the only difference being in the number of threads dealt with.   On the other hand, we find here the principle of drawing the roving by its recession from the spindle which, in its reverse form, is the action of the mule in spinning wool to-day ; the method of twisting the yarn by the rotation of a vertical spindle, and of winding it on the spindle while guiding it by means of a depressed wire.

(13) Thus we have arrived at a period when machines had been invented by which yarn could be spun in several lengths at once by one person in either of two ways—by a flyer or by a spindle.   It has been shown that neither of these methods were novel, hand wheels having been made both with the plain spindle and the flyer, but the idea of utilising these old parts in such a way that several of them could be actuated at once was novel.   It will be noticed that the spinning machines of Arkwright and Hargreaves possessed respectively features which were peculiar to them.   Arkwright's machine had the power of continuously delivering and twisting the yarn by means of rollers, while that of Hargreaves was constructed to draw and twist a number of rovings of a definite length.   Both these are elements of value, and the next step accordingly was taken when Samuel Crompton about the year 1779 produced the machine which from its hybrid nature has been called the mule. The mule as made by Crompton was a crude machine, as an inspection of the original model shows, but it contained within it several of the elements of the modern mule.   There was found the delivery by rollers, and the sustainment of the spindles in a carriage to which an alternate motion in a horizontal direction was given.   Although in a very incomplete state, the

invention speedily became largely employed. In about the year 1790 the Crompton mule was driven by water power, and it was immediately afterwards made into a double machine with the headstock in the centre, a form which it has retained since that period. The increase in its dimensions speedily led to the adoption of improved methods of drawing out the carriage, and of the adoption of bands by which it was drawn out equally throughout its length. The counter-faller wire, as it is now called, appears to have been invented in a rude and imperfect form about the year 1790, as was also the use of an inclined plate for the guidance of the faller and the shaping of the cop. After this the most important improvement was made by Kennedy, of Manchester, who invented a method of actuating the rollers and spindles by three pulleys, two fast and one loose. Up to this point, however, three of the most essential features of the mule remained manual operations. The actuation of the faller in its guiding of the yarn was done by the spinner, and partook of all the irregularity of hand work. The reversal of the direction of rotation of the spindles, which is necessary to uncoil the yarn between the nose of the cop and the point of the spindle, and to which the name "backing-off" is given, was also done by the spinner. Upon the latter also was thrown the duty of regulating the speed of the spindles during winding so as to ensure a regular rate of taking up the yarn. Mechanicians speedily recognised the fact that although a machine of great complexity it was not beyond their power to make it self-acting, and patent after patent was taken out for various improvements. Of these the most important was an invention of a self-acting copping motion, by Mr. William Eaton, in 1818, by which the three operations just detailed were made purely automatic. We may pass over the intermediate attempts made, and come to the time of Richard Roberts, a mechanician to whom, hitherto, scant justice has been done, but who was undoubtedly one of the giants of an age distinguished for clever mechanics. As we have seen, Eaton had demonstrated the possibility of mechanically operating all the motions of a mule, which was one step in advance, but

there were several features in his invention which were imperfect.
The differential motion of the spindles was got by mechanism
of some complication, and the whole of the arrangements
connected with the formation of the cop were faulty.   Roberts
went into the matter at the request of a number of spinners,
and in a period of five years produced a machine which was
undoubtedly an enormous advance, and which contains motions
which remain to the present day those in common use.   Space
will not permit us to deal with the Roberts' mule in detail, but
it may be pointed out that in this machine the first use is made
of the winding quadrant with a traversing nut by which the
variation of the velocity of the spindles is so easily regulated.
The employment of a cam shaft was also to be found for the first
time in this mule, and the faller and counter-faller wires were also
actuated in a thoroughly efficient manner.   The backing-off
friction clutch was also a novelty in this machine. The Roberts'
mule soon became recognised as a perfect spinner, and it
possessed every essential feature of the present day machine,
although it is not, of course, comparable with it in detail.
Thus, the development of the mule may be classified.   First
came the invention of continuous drawing by rollers, followed
by the employment of several vertical spindles actuated at the
same time.   The combination of these two produced the first
mule, which had within it the intermittent delivery of roving by
the rollers, the rotation of the spindles during the delivery, and
their recession from the rollers, the reversal of the direction of
the motion of the spindle to unwind the top coils, the depression
of a wire to guide the yarn as the spindles were being revolved
to wind it, and the drawing in of the carriage during the latter
operation.   The next step was the application of power, which
was accompanied by a change in the position of the headstock.
Then came the adoption of the counter faller, and of an inclined
plate to guide the faller wires.   Following these was the appli-
cation of the self-acting principle by Eaton to several of the
motions, and then the enormous advance of the Roberts' mule,
which was automatic in the whole of its movements.   Since

that day, although there have been improvements in details, there has been no real improvement in principle, and the era of construction rather than invention was reached.

(14) The water frame of Arkwright, being much more simple in its operation than the mule of Crompton, speedily took shape. At first the guiding of the yarn upon the bobbin was effected by hecks upon the flyers, but it was not long before the traverse rail was adopted, and the heart-shaped cam (in common employment to-day) applied to this object. From the first, the retardation of the bobbins sufficiently to wind on the yarn was effected by the use of flannel washers placed beneath them, so that at that early day the throstle was practically developed. The Danforth cup throstle had for a time considerable popularity, but practically, until the advent of the ring frame the throstle was not endangered. Ring spinning is of modern origin, its inception not having an earlier date than 1828, so that it is not necessary to deal with it in a sketch of this kind. It has had, however, three stages : (1) The employment of spindles of the throstle type, but without flyers ; (2) the employment of spindles self-contained, but with a bearing within the bobbin ; and (3) the employment of spindles with self-adjusting bearings which compensate for any irregularity in the balance of the bobbins.

(15) While the principal spinning machines were being developed, a like process was going on with those which were employed to prepare the cotton for twisting. In 1793 Mr. Whitney invented the saw gin, by means of which not only was the separation of the seed from the lint much better performed than it had been previously, but the amount produced in a given time was largely increased. This was the first application of machinery to this important object, and to Whitney belongs the honour. In cleaning the cotton from dirt and sticks, the first machine used was called the "willow," and there is little doubt that the machine was so called because the earliest form employed was a cylindrical cage, angularly disposed, constructed of willows. After the success of the cylindrical carding machine, it was not a great step to adopt a cylinder surrounded by a grid or cage for

the purpose of beating the cotton, and as the lineal successor of
the machine just mentioned, it acquired its name. Although the
purely cylindrical form had the greatest employment, a conical
willow was soon devised, and was extensively adopted. The idea
here is that underlying the method of mounting the old willow
cage, the axis of which was arranged diagonally. The removal
of the dirt and dust speedily became a difficulty, but was solved
by the application of a fan which created such a current of air
as to draw the dirt away and discharge it. Thus the room in
which this operation is carried on became known as the blowing-
room. It ought to be pointed out that the shaking of the cot-
ton by the cylinder, and the dropping of the dirt in consequence,
is in all essentials the same as the process of bowing previously
named. The scutching machine was invented in 1797, by Mr.
Snodgrass, of Johnstone, near Glasgow. The name of this
machine is evidently derived from the use of scutches or rods to
beat the mass of cotton and knock out the dirt, which was
another method of procedure. For the same reason the pro-
cess was called " batting," a name which still lingers in the
Southern States of America, and which is incorporated in the
French name of the machine, " batteur." The lap machine was
the invention of Mr. Crighton, of Manchester, and its use as
an attachment to the scutching machine was common early in
this century. The employment of perforated cages on which to
form the sheet or web was a development of the dust fan, and it
is certain that very early in the history of the machine these
were applied, only one cage being used, however, in combination
with a delivery apron. In 1830 they were in regular employ-
ment, and the machine was in most respects of similar con-
struction to that at present adopted. The addition of the feed
roller and piano motion by Mr. E. Lord, of Todmorden, about
1862, however, further improved it. Although in many of its
details this motion has been materially changed, in its substance
it remains practically as it was when it was patented by Mr. Lord.
The changes made have largely increased the sensitiveness of
the motion.

(16) The drawing frame was a natural growth from the invention of drawing rollers, and was very early employed by Arkwright as a distinct machine in a series. The twisting of the slivers into roving was at first carried out by Arkwright by means of a machine approximating to the drawing frame in construction. The combined slivers were delivered into a can to which a rapid rotary movement was given, so that as the sliver was delivered it received a certain amount of twist. The roving so produced was drawn from the can and wound on bobbins by a separate operation, and the bobbins thus obtained were placed in the creel of the mule preparatory to spinning. A modification of Hargreaves' jenny was employed for some time for the same purpose, but both of these methods were superseded by the bobbin and fly frame. A contrivance known as the " Jack-in-the-box " was devised to effect the same object, and consisted of a cylinder revolving within a box and carrying a bobbin. By the rotation of the cylinder the sliver was twisted, and was wound upon the bobbin by means of a wire guide eye to which a reciprocating motion was given. It was not long, however, before Arkwright endeavoured to employ the principle of the ordinary flax hand-spinning wheel to the production of roving. The wheel referred to was constructed with a flyer fixed upon the spindle, upon which and within the flyer a bobbin was placed. The twist was put in by the rotation of the flyer and the winding effected by the frictional retardation of the bobbin, the roving being traversed along the bobbin by hand. In Arkwright's fly-frame the bobbin was positively driven at a speed sufficient to take up the yarn delivered by the rollers, and the twist given by the rotation of the forked flyer. The difficulty always remained of regulating the velocity of the bobbin, so that it would just take up the right quantity of roving whatever its diameter might be, and this involved the giving of a differential speed, as is now well understood. Several inventors made attempts to solve this problem, and in 1823 a Mr. Green, of Mansfield, devised a method of driving the bobbin from the rollers, thus ensuring that the alteration of the velocity of the

latter necessarily involved a similar variation in the other. He also thought of such a train of gearing as would vary the speed of the bobbins as they filled; but his mechanism was complex, each spindle being actuated independently, and it never came into general use. In 1826 Mr. Henry Holdsworth, of Manchester, patented the present differential motion, by which an accurate variation was obtained. The principle of Holdsworth's motion is practically that of the old sun and planet motion, which, prior to the invention of the crank, had been employed in steam engines. In E. J. Donnell's "History of Cotton" it is stated that the application of this mechanism was the work of Mr. Asa Arnold, a native of Rhode Island, and that he did so in 1822. Mr. Donnell also states that a model of the apparatus was taken to Manchester in 1825, so that there are some doubts whether the patent taken out by Holdsworth in the next year was not the result of an inspection of Arnold's model. Holdsworth had invented a combination of wheels for coupling the movements of the spindle and bobbin in 1825, but it was not until the next year that the differential motion was patented. The cone which had been previously used to differentiate the speed of the bobbin was retained, but the difficulties of adjustment previously existing when a different amount of twist was required were entirely obviated by the employment of the differential or "equating" motion. At first one cone only was used, and the necessary unequal movement of the strap was obtained by the use of a parabolic rack. This was found to be very difficult to make and regulate, and it was not long before a second cone was employed, by which means the same object was attained. In the early stages the roving was wound upon double-ended bobbins of the type employed on the flax wheel, but it was found to be better, on account of the adhesion of the yarn, to use plain tubes, and by coupling the building motion to the lifter a gradual shortening of the traverse of the bobbin rail was obtained, thus producing roving bobbins of the shape now familiar.

(17) The joint effect of these improvements was very great,

especially when they were aided by the comparatively enormous
driving power given by the steam engine.   Prior to the per-
fecting of the latter, cotton mills were located on the banks of
running streams, and many were found in Derbyshire, Notting-
hamshire, and even so far afield as Birmingham.   The steam
engine, however, changed all that.   Lancashire became the
centre of the industry, and although cotton mills like those of
Messrs. Strutt of Belper, Messrs. Evans of Derby, and a few
others, are still found in Derbyshire and Nottingham, in the
main cotton spinning is confined in England to this county.   It
is somewhat interesting to note that in 1679 1,976,359lbs.
represented the weight of cotton imported into England.   This
remained practically stationary for some years, but after the
invention of Hargreaves' jenny and Arkwright's spinning
machine it rapidly increased.   In 1764, 3,870,392lbs. were im-
ported; in 1774, 4,764,589lbs. ; in 1784, 11,482,083lbs. ; while
in 1795 the amount exported from the United States alone
exceeded the whole importation into England in 1774, only 20
years before.   In 1815, 82,998,747lbs. of cotton were exported
from the United States, shewing the enormous increase which
had taken place in the use of this material.   In 1825, the
year of Richard Roberts' first patent for a self-acting mule,
199,272,665lbs. of cotton were imported into this country, an
increase in 30 years of about 1,500 per cent.   The first import
of cotton from the East Indies was made in 1798.   In 1835,
five years after the perfecting of the self-acting mule by
Roberts, the importation of cotton into Great Britain was
364,000,000lbs., or nearly double that of 1825.   It may also be
of interest to know that in 1789 the steam engine was first
used to drive a cotton mill in Manchester, and the parish of
Oldham had a population of 13,916 only.   In 1790 the
production by a spinner of 40's yarn was only one hank per
spindle per day; in 1812 it reached two hanks, and in 1830
$2\frac{3}{4}$ hanks.   Nothing can be more convincing of the enormous
advances made in this art than these figures, which refer to
periods of such recent date, within the lifetime of many persons

now living. The remark made in the early part of this chapter as to the possibilities of future developments will not, when viewed in the light of those of the past, appear to be so wild or far-reaching as at first sight.

(18) It will be noticed that this brief review shows that the sequence of the development of the art of spinning is as follows : In the first place the fibre was obtained and utilised by plaiting or knotting it, this method of employing it being prior to the discovery of the advantages to be gained by twisting two or more fibres together. When the art of twisting or twining was discovered, the invention of implements by which it could be effected followed as a matter of course. These began with the simplest form of tool and terminated with the best type of hand spinning wheel. Simultaneously with the application of the art of spinning or twisting came the knowledge that with most fibres a drawing process was advantageous, and accordingly the attenuation of the material while it was being twisted became recognised as an essential part of the process. In India the purification of cotton by roughly ginning it and opening it in the manner described is the precursor of the modern system of cleaning, while the application of the hand card to the formation of a fleece of cotton, in a similar manner to the production of a woollen fleece, still further developed the series of processes which make up the art of cotton-spinning to-day. The brilliant series of inventions of the latter part of the last half century and the beginning of this transformed what had been a slow manual operation into a speedy mechanical one, and completely revolutionised the industrial system hitherto prevailing. It is, however, worth emphasising, in conclusion, that the germ of every modern practice is to be found in the primitive manipulation of cotton, and that modern systems are the mere developments of ancestral treatments.

CHAPTER II.

THE DISTRIBUTION AND VARIETIES OF COTTON.

(19) COTTON is grown from a plant of the natural order of Malvaceae, and of the genus Gossypium, and at the present day is widely distributed throughout the world within the latitudes of 40° N. and 30° S. There is abundant evidence to prove that from the earliest historical periods this fibre has been known, cultivated, and worked in India. The earliest writer of history, in its modern sense—Herodotus—mentions the existence of " wild trees bearing fleeces as their fruit," and the making of cloth by the Indians from these trees. The same writer states that a cuirass sent to Sparta from Amasis, King of Egypt, was adorned with gold and with fleeces from trees. It is interesting, in passing, to note that the German word " Baumwoll "—tree wool—which is used to denote cotton, is evidently founded on

the idea of the fibre being fleecy like wool.   There are, there-
fore, two districts in which the cultivation of cotton is extensively
practised to-day, where it has existed from the earliest historic
times.   But there is the further significant fact, that when the
Spaniards obtained a footing on the continent of America, they
found cotton being used and cloth made of it.   Magellan, in
1519, found the Brazilians using cotton in making beds ; and in
1536 De Vica found the cotton plant in Texas and Louisiana.
In 1519 cotton was also cultivated on the coast of Guinea.   Now
as America had been a *terra incognita* prior to its discovery by
Columbus, there is an extreme probability that the plant had
existed there for an indefinite period, and thus we arrive at the
fact, that over a belt of the earth's surface, practically coincident
with the cotton-growing zone of to-day, the plant was found in
the earliest ages of which there are records.

(20) At the present day the cotton-growing zone includes the
whole of India, part of China and Central Asia, the Nile Valley
and Delta in Egypt, Syria, certain of the Southern States or
North America, Brazil, Peru, and several of the Islands in the
Pacific Ocean.   With the exception of Egypt there is little culti
vation of cotton in any part of Africa, although there is a vast
tract of country which is admirably adapted for it.   According
to the latest statistics available to us, which relate to the
season 1894-95, the whole of the cotton-growing lands in the
United States are included in the boundaries of ten states, the
number of acres in each being as follows : North Carolina,
1,296,522 ; South Carolina, 2,160,391 ; Georgia, 3,610,968;
Florida, 201,621 ; Alabama, 2,664,861 ; Mississippi, 2,826,272 ;
Louisiana, 1,313,296 ; Texas, 6,854,621 ; Arkansas, 1,483,319 ;
Tennessee, 879,954.   The total acreage in the United States
was in 1894-95, 23,687,950.   In 1870, the total acreage in the
same states was only 8,666,217, so that the production has
enormously increased.   The quality of the cotton produced in
each of these states will be dealt with at a later stage.

(21) After the United States, India is the greatest cotton-
growing country, and from a statistical treatise published

in Bombay in 1889, the following figures of acreage are
extracted :—

	Acres.
Bombay	5,350,000
Scinde	75,000
Berar	1,960,000
Central Provinces	610,000
Central India	290,000
Rajputana	550,000
North-West Provinces	1,550,000
Oudh	80,000
Punjab	860,000
Nizam's Territory	970,000
Bengal	162,000
Madras	1,675.000
Mysore and Coorg	42,000
Assam	40,000
Burmah (Lower)	8,080

Total acreage 14,222,000

This acreage does not vary much year by year, and in the
reason 1895-6 was 14,617,000.

(22) As a matter of fact, almost the whole area of India is
more or less a cotton-growing area ; but the proportion which the
lands devoted to its culture form of the whole varies consider-
ably in different districts.   In many of the provinces the
percentage is less than ten, and only in a small proportion does
it reach more than thirty.   Still, the fact remains that there is a
large and increasing area in India in which cotton is cultivated.
In Egypt the cotton-growing district lies in the Delta and along
the banks of the Nile, and the area under cultivation is about
890,000 acres.   The Brazilian acreage is not accurately known,
and that of Peru is also not accessible.   Great efforts have been
recently made by the Russian Government to extend the growth
of cotton in Central Asia, all sorts of facilities having been
created to encourage it.   In the provinces of Erivan, Merv,
Bokhara, and Turkestan, along the slopes of the Aralo-Caspian
mountains, the chief cotton-growing area is found.   The country
is somewhat sterile, but several good streams flow through it,

rendering irrigation comparatively easy.   The area within which the cultivation of cotton is possible, if irrigation works are properly carried out, is watered by several large streams like the Amu Daria and Murghab.   The flow of the former is only surpassed by the Volga and Danube in Europe, and is equal to that of the Nile, so that there is ample scope for the irrigating engineer.   It is not known what is the exact area under cultivation, but it is probably about 700,000 acres.

(23) Thus the area over which cotton is cultivated is very extensive, and embraces a great variety of soil.   There are well-defined climatic conditions which are essential to the successful production of cotton.   The mean temperature in degrees Fahrenheit, for a period of five years, from 1886 to 1890, in the ten cotton-growing states of America, are for the month of May 71·9, June 77·76, July 80·96, and August 79·14.   In the winter months the temperature falls below zero in many of these states but the summer temperature is high enough and lasts sufficiently long to ripen and mature the plant, and to enable it to be well harvested.   In India the mean annual temperatures range from 73·3° in the Dharwar district to 81·9° in Madras.   The mean annual temperature in Brazil is about 79°F.; that of Egypt is not accessible to us, but probably approximates to that of India. In Central Asia the mean temperature is lower—from 55° to 58° —but rises during the cotton-growing months to a much higher point.   Observations taken show that at Samarcand the mean temperature in the three years 1889-90-91 ranged from 23·2°F. to 28·2°F. in January; from 61·7°F. to 65·7°F. in May; 74·7°F. to 76·3°F. in June; 75·9°F. to 77·7°F. in July; 71·6°F. to 73·8°F. in August; and from 64·9°F. to 65·8°F. in September. The temperature in Tashkend was about 3° higher.

(24) The cotton plant, as will hereafter be shown, produces a better fibre in some situations than in others, and there is no doubt that other conditions—such as the character of the soil and the humidity of the atmosphere—have much to do with the character of the fibre.   There is a well-known analysis of the ash produced when Sea Island cotton is carefully burned and

the residuum incinerated, which was made by Dr. Ure.   The
composition of the ash was as follows :—

MATTERS SOLUBLE IN WATER.	Parts.
Carbonate of potash	44·8
Muriate of potash	9·9
Sulphate of potash	9·3

MATTERS INSOLUBLE IN WATER.	
Phosphate of lime	9·0
Carbonate of lime	10·6
Phosphate of magnesia	8·4
Peroxide of iron	3·0
Alumina, water, and loss	5·0
	100·0

(25) In Dr. Royle's work on the " Culture of Cotton in India,"
two analyses of ash obtained by the combustion and subsequent
incineration of Orleans cotton fibre and seed made in 1843 are
interesting.   The analysis of the ash obtained by burning the
fibre is :—

	Parts.
Carbonate of potash	44·29
Phosphate of lime	25·34
Carbonate of lime	8·97
Carbonate of magnesia	6·75
Silica	4·12
Sulphate of potash	2·90
Alumina	1·40
Chloride of potassium	
Chloride of magnesium	
Sulphate of lime	and loss 6·23
Phosphate of potash	
Oxide of iron (a trace)	
	100·00

(26) From this it is deduced that in 10,000lbs. of cotton the
following amounts of the substances named are abstracted from
the ground :—

	Lbs.
Potash	31
Lime	12
Magnesia	3
Phosphoric acid	12
Sulphuric acid	1

(27) The analysis of the cotton seed removed from the same cotton showed that the proportion of phosphoric acid and lime was much in excess of that existing in the cotton. Thus, 45·35 per cent of phosphoric acid existed in the ash of the seed against 12·32 in the cotton ash, the percentage of lime being 29·79 and 17·09 respectively. The fibre of the cotton is pure cellulose, with a chemical composition of $C_6H_{10}O_5$, while the wax which coats the fibres of American cotton is composed—according to Dr. Bowman—as follows :—

	Per cent.
Carbon	80·38
Hydrogen	14·51
Oxygen	5·11

(28) The particulars thus briefly collated throw some light upon the situations in which the plant may be expected to flourish. From the analysis of Sea Island cotton ash, given by Dr. Ure, it would appear that a situation near the sea is most advantageous to the growth of the plant. Many of the salts evidently present in the fibres are such as would be extracted from a saline or marshy soil, and accordingly we find that the land on which Sea Island cotton is grown does contain a proportion of saline matter. In Georgia, the land, which is a sandy loam mixed with much vegetable matter, contains less saline substances, but a fair percentage of lime. In the plains of the states of Mississippi and Alabama, which are unmistakably alluvial in their origin, the soil is of a loamy character. It is stated by Dr. Mallet, in a book referred to presently, that the soil of good lands in Alabama is so tenacious as to polish when a wheel passes over it in dry weather. It is universally remarked that the nearer the cotton-growing lands are to the sea, the better the staple of the cotton grown, even if it be of one of the inferior varieties. In an extremely interesting book, written by Dr. J. W. Mallet, who was Professor of Chemistry in the University of Alabama, a very exhaustive statement is given of a long series of investigations into the composition of the soil in that State. Dr. Mallet selected a sample from a plantation in the cane-brake region, where the number of streams is small. In conducting

the tests, he was able to analyse several specimens of Indian soils and compare the results. The samples were all air-dried, and were treated with water, and hydrochloric and sulphuric acids, in order to extract all the soluble salts. It was found that in the surface soil there was 16 per cent of alumina, and in the sub-soil 20 per cent. In this respect the Alabama soil resembled the Indian, and the presence of so much alumina involves the free absorption of moisture by the soil, which, in an ill-watered country, is important. Of the sequioxide of iron there was about 8 per cent, and about ·1863 per cent of phosphoric acid in the surface, and ·2376 per cent in the sub-soil. Lime is found in Indian cotton soils on an average of about 7 per cent; while in the case of Alabama the surface soil contained 3·39 per cent, and the sub-soil ·83 per cent. Magnesia is found in Indian soils to the extent of from ·2 to 2 per cent, and in Alabama ·66 in the surface and ·74 per cent in the sub-soil. Potash in the Indian soils varies from ·193 to 2·24 per cent, and in the American ·31 in the surface and ·36 in the sub-soil. It is a notable fact, which is confirmed by the analysis quoted from Dr. Ure, that the earth, from the districts where Sea Island cotton is grown, contains much more potash than soda. The latter substance is found in Indian soil and Alabama surface and sub-soil in the following percentages respectively: ·5 to 1; ·25; and ·25. The organic matter is easily soluble in water, and consists largely of humus derived from the leaves or stalks which drop on and are ploughed into the land. In Turkestan the soil is evidently of an alluvial character, and is a conglomerate of lime and clay. When it contains a fair percentage of sand it is admirably fitted for this purpose, otherwise it tends to clog. The Indian black cotton soil is described as a highly argillaceous, somewhat calcareous clay, very adhesive when wet, and contracting so as to form large fissures during the hot weather. In Egypt there are two main classes of soil, one of a blackish colour and another which is light coloured and sandy. Of these the black soil is the most suitable, but it varies in its fertility. The best cotton lands in Brazil have a loamy

character, and extend to a great depth below the surface. They produce cotton for many years without the aid or use of any kind of fertiliser. Dr. Mallet sums up his examination of the soil of Alabama by saying: "It is shown to be a stiff, aluminous clay, containing moderate amounts of organic matter and of the mineral substances required by the plant as food—of great uniformity, and in an exceedingly fine state of division; above all, possessing a very high capacity for absorbing and retaining heat, moisture, gases, and soluble mineral matter."

(29) Dr. Ure long ago came to the conclusion that the best soil was one which was a compost or loam, and in which there was "neutro-saline matter with alkaline, calcareous, and magnesian bases." It will be noticed that nothing is said by Dr. Ure about the presence of phosphoric acid, but there is no doubt as to this being required. In one case there were used as fertilisers $3\frac{1}{2}$ tons of phosphate of lime and $3\frac{1}{2}$ tons of cotton seed meal on a farm of 70 acres extent. Now, remembering that the soil of Alabama is a rich dark alluvial soil containing much organic matter, and also remembering what a large percentage of phosphoric acid existed in the analysis of the seed, it is not too strong an inference to draw that in addition to the saline, alkaline, calcareous, and magnesian substances the presence of phosphorus is absolutely imperative. This is confirmed by the analysis of the cotton fibre made by Dr. Ure. The condition of the soil is thus seen to be one of extreme interest, and has a determinate effect upon the plant. A loamy soil easily penetrable by the roots of the plant is preferable to a heavy one, and its sustenance will be much affected by the character of the soil, especially as the plant is one of those possessing tap roots. Dr. Mallet states that the average depth of the root is 2ft. 1in., and the lateral spread about 2ft. 9in., so that about 5 cubic feet of soil was penetrated. The tap root, however, sometimes descends five feet. In like manner the process of irrigation is aided by a porous surface or sub-soil, and as there are many places in which cotton can be grown, but in which the atmospheric conditions are fatal to its complete

B

success, irrigation is absolutely essential, and can be made a great help to extended cultivation. The experience gained in Turkestan is especially valuable in this respect. The climate there being dry and hot, the application of water by irrigating channels is absolutely necessary; but care must be taken to apply the water at the right time. Being sown in April, the plants appear in from 10 to 15 days, and the first watering takes place about the end of May. The period of watering during the subsequent growth depends on the evaporation, which varies with the season. Careful observation enables the period of application to be determined. In Egypt the land is well soaked by admitting water to the intermediate trenches prior to sowing, and after the plants are thinned it is watered every 12 to 15 days.

(30) This brings us to consider the question of the rainfall, with which that of humidity is closely connected. In the United States of America the rainfall is considerable, and the plant is rarely left without a sufficiency of moisture. The mean annual rainfall for a period of five years, 1886—1890, in the ten cotton-growing States was 3·75 inches in the month of. May, ranging from 2·21 inches in 1889, to 5·57 inches in 1890. In June the mean rainfall was 5·19 inches, ranging from 3·97 in 1887, to 7·59 in 1886. In July, 4·99 inches was the mean, with a rain-fall in 1888 of 3·02, and in 1889 of 6·06. In August the mean was 4·67 inches, the lowest fall in 1889 4·02 inches, and the highest, in 1888, 6·24 inches. The four months given are those during which the plant is growing, and there is thus a con-siderable rainfall during that period, sufficient to feed and nourish it. During the year 1880 the rainfall of the Southern States ranged from 50 to 60 inches, so that it is evident the cotton plant in the United States is amply watered. In India there is a completely different condition of things. There the rainfall occurs in one season of the year only, which varies in different parts of the country. The western coast receives the rain during the continuance of the south-west monsoon, which strikes the coast near the end of May, the rains reaching Bombay between

the 5th and 15th of June.   The Madras district is watered by
the north-east monsoon, and receives its rain from the end of
September to the middle of October.   Thus there is a great differ-
ence existing between the rainfalls at different periods of the year.
For instance, in the Broach district, the mean rainfall during the
months of January, February, March, April, and May amounted
only to 0·22 inches ; in June 6·67 inches fell ; in July, 15·33
inches ; in August, 8·87 ; in September, 7·18 ; in October, 1·72 ;
in November, 0·13, and in December, 0·5.   Thus, 39·77 inches
fell in the five months June to October, and 0·4 inch during the
remaining seven.   Now Broach is a province which lies near
the sea coast on the Gulf of Cambay, and the conditions with
regard to rainfall are much more favourable there than in many
parts of India.   The following table is given, which shows the
mean rainfalls in the five months June to October, and in the
other seven months of the year.

| Growths. | RAINFALL IN INCHES. | | Number of Observing Stations. |
	Five Months, June to October.	Seven Months, October to June.	
Dholleras	27·84	·45	5
Broach	39·77	·40	1
Khandeish	28·87	1·38	2
Barsee...........................	25·03	2·62	2
Coomptas and Dharwars ...	27·22	5·82	4
Westerns ..../......	24·34	3·81	8
Tinnevelly	11·60	16·28	3
Sind.............../........	5·49	1·28	3
Oomras	28·25	2·28	3
Hingunghat	41·66	4·28	3
Bengals	28·90	3·85	22

(31) In Central Asia the rainfall in Tashkend, Samarkhand
and Bokhara from 1885 to 1891 inclusive, was respectively
13·7, 12·5 and 4·5 inches, and the result is that except by an

extensive use of irrigation works the growth of cotton is not
possible. In Egypt the rainfall is small, but the cotton being
grown on the lands which are annually flooded by the Nile, the
growth depends more upon the moisture thus derived than upon
the rainfall. In addition to this there are extensive irrigation
works which aid in the provision of the necessary moisture, irri-
gation taking place eight times during the growth of the plant.
The Brazilian rainfall is considerable, as much as 25 inches
falling in a month and 109 inches in the year, the average on the
sea coast being stated to be about 78 inches. Darwin in " The
Voyage of a Naturalist" states that 1·6 inch of rain fell in the
course of one morning. In addition to this, cotton is grown
on the lands along the coast, and this fact has a considerable
influence upon its condition. In Peru the rains only fall once
in seven years in the cotton growing districts, and irrigation
although practicable has not been resorted to, but, as in Egypt,
the rivers overflow their banks and so render cultivation possible.

(32) We now come to consider the question of humidity,
which is distinguished from that of rainfall. There is in every
district along the sea or pierced by rivers a certain quantity
of moisture in the air, and although this naturally differs with the
season it is an item which requires taking into consideration. It
is quite clear that if the air in which the cotton fibre is ripened
possesses a high degree of humidity the lack of rainfall is com-
pensated for, and even where rain falls abundantly the contained
moisture is readily absorbed by the leaves and flowers of the
plant and by the soil. Thus in situations where the plantations
adjoin the sea there is not only the moisture percolating through
the soil, which acts advantageously, but there is also a vast
amount of aqueous vapour in the air which plays its part in the
development of the plant. Thus a warm, mo'st or steamy atmos-
phere is the ideal one for cotton growing, and wherever it is found
a good grade of cotton is produced. Where it does not exist
constant and skilful irrigation goes far to take its place, especially
where the soil is of an alluvial nature. In short, it may be stated
as an axiom that the possession of an insular—that is a humid—

atmosphere is the most favourable atmospheric condition for the growth of cotton.   It does not necessarily follow that the plantation must be in the vicinity of the sea, although this for the other reasons detailed is preferable, only that it shall be in such a situation as to be acted upon by an atmosphere charged with watery vapour, which is the case when a plantation is situated on rising grounds along which the vapour-charged winds can blow.   Thus the relative percentage of humidity on June 8th, 1880, was 85 at Atlanta in Georgia; 82 at Cape Hatteras, N.C.; 77 at Charleston, S.C.; 71 at Galveston, Texas; 78 at Mobile and 92 at Montgomery, Alabama (south wind blowing); 86 at Vicksburg, Miss.; and 86 at Wilmington, N.C.   The average humidity during the months of July and August for three years in succession was for the South Atlantic States, 74; for the Eastern Gulf States, 76; and for the Western Gulf States, 72.   Dr. Mallet puts the conditions as follows : The atmosphere may contain water in a vaporous state up to the point of saturation.   It may be super-saturated so that rain falls from it.   The soil may contain a greater or less quantity of water, which can be readily absorbed until the point of saturation is reduced. If the soil is so far saturated as to be muddy, cotton will not thrive.   He further says : Aqueous vapour in the air and abundant hygroscopic moisture in the soil itself are the sources from which the moisture necessary for growth is to be obtained.

(33) The cotton plant is liable to the attacks of a caterpillar, which is regularly developed like all other moths, and is most prolific during a moist season, which is not too hot or too cold. When in the worm form it feeds upon the leaves, bulbs, and bark of the plants, and does an immense amount of damage. The moth is not so destructive, but as it is migratory, the eggs are laid over large areas.   The loss of crop has, in some cases, been total, but there may be very little damage done.   The most favourite ground for the development of the moth are the low-lying, alluvial lands, in which the plant rapidly attains maturity.   There is also a moth which is developed from a worm called the boll-worm, which is hatched from eggs in the

usual way.   It hibernates in the chrysalis form in the ground, and many of the species are killed by the exposure caused by ploughing.   The boll-worm feeds upon the flowers and bolls of the plant, and by penetration into the latter often completely destroys them.

(34) This very brief survey enables a clear conception to be obtained of the conditions under which cotton can be best cultivated.   These are, 1st, a soil of a loamy character, containing saline, alkaline, and calcareous substances ; 2nd, a temperature ranging from 68° F. to 82° F. during the months in which the plant is growing and maturing ; 3rd, an ample rainfall ; and 4th, a humid atmosphere.   When these four conditions are found existing together the best results may be confidently expected. It is possible in the absence of some of these features to substitute them by artificial aids, producing the same result.   For instance, a light siliceous soil can, by the aid of abundant fertilisers and skilful irrigation, be made to produce a better quality of cotton than is possible in its natural state, but the conditions under which these artificial aids can be profitably applied are, of course, limited.   In order to give some idea of the commercial position of cotton growing, a statement is appended on page 39 which is one of the latest authenticated, and gives the cost of production from 26 farms in various states.   The cost is obtained after making allowances for rent, labour, fertilisers, sale of surplus seed, interest, and all legitimate items.

The most successful cultivators work the crop at regular intervals, but never while the land is wet.   They, however, work all through the dry weather, plough deep, and run the plough through the cultivated crops every ten days.   An extensive use of fertilisers is made, and where they are used a more profitable result follows.   The fertilisers are mainly acid phosphates and natural phosphoric rocks which exist in large quantities in the Southern States.   The cost of growing cotton in Turkestan varies from $3\frac{1}{2}$d. to 4d. per lb. of lint cotton, a price which is much increased before shipment by various charges.   The cost in India is difficult to get, but is

COST OF PRODUCTION.

No.	State.	Acreage.	Total Yield. Lbs.	Net Cost Total. Dollars.	Per lb. Cents.	Season.
1	North Carolina...	106	30,150	2,260·51	7½	1891-92
2	do. ...	32	11,500	688·40	6	do.
3	do. ...	40	9,000	839·00	9⅜	do.
4	do. ...	40	15,980	1,119·20	7	do.
5	do. ...	25	13,400	716·00	5⅓	1892-93
6	South Carolina...	36	9,526	605·97	6⅜	1891-92
7	do. ...	50	20,000	1,401·80	7	1892-93
8	Georgia	500	100,000	7,065·00	7	do.
9	do.	20	10,000	416·05	4⅓	1891-92
10	do.	65	11,000	826·30	7½	do.
11	do.	180	21,500	1,489·00	6·92	do.
12	do.	35	6,000	401·03	6⅔	do.
13	do.	150	28,520	1,778·70	6¼	do.
14	Alabama	75	12,500	969·00	7¾	do.
15	do.	25	4,000	316·00	8	do.
16	do.	30	7,500	352·75	4⁵⁄₇	do.
17	do.	50	25,000	1,263·00	5	do.
18	do.	150	32,000	2,575·00	8	do.
19	do.	360	118,000	8,537·00	7¼	do.
20	Mississippi	45	11,500	699·50	6⅛	do.
21	do.	75	18,000	1,674·00	9¼	1892-93
22	Louisiana	500	200,000	9,690·00	4¹⁷⁄₂₀	1891-92
23	do.	2,000	1,000,000	52,000·00	5⅛	do.
24	Arkansas	100	16,500	904·00	5½	do.
25	do.	25	6,000	425·50	7¹⁄₁₂	do.
26	do.	121	45,500	1,816·85	4	do.

stated to be from 1¼d. to 1¾d. per lb. of lint cotton in the Punjaub. In Egypt the cost of production is from 1¾d. to 2½d. per lb.

(35) Having thus ascertained the conditions under which the growth of cotton can be best conducted, a few words may be

said about the method of cultivation. What is aimed at is the production of the largest possible quantity of good stapled cotton, of good colour, and in a clean condition. In sowing it, therefore, all danger of frost is, as far as possible, avoided, and the time of planting is arranged to be after the date at which frosts are expected. A damp condition of the soil when planting, or a good fall of rain subsequently, are advantageous. Two tabulated statements are now given which furnish a number of particulars relating to the cultivation of cotton in the United States and in India. The first is extracted from Shepperson's "Cotton Facts," and in the shape given, the tables are convenient for reference.

COTTON CULTURE IN THE UNITED STATES.

STATES.	Usual date to begin preparing land.	Usual date to begin sowing.	Usual date to finish sowing.	Usual date to begin picking.	Usual date to finish picking.	Average length of staple (inches).	Average yield per acre (U.S. Agricultural Bureau, Nov. 1885, 1885-86 crop).
North Carolina	Feb. 25	April 15	May 10	Sept. 1	Dec. 10	$\frac{3}{4}$ to $\frac{7}{8}$	157
South Carolina	Mar. 5	,, 15	,, 7	Aug. 15 to Sept. 1	,, 1	$\frac{3}{4}$ to $\frac{7}{8}$	142
Georgia	Feb. 1	,, 10	,, 1	Aug. 15 to 20	,, 1	$\frac{3}{4}$ to $\frac{7}{8}$	150
Florida	Jan. 20	,, 1	,, 1	Aug. 10	,, 1	$\frac{3}{4}$	105
Alabama	Feb. 1	,, 5	,, 10	Aug. 10 to 20	,, 15	$\frac{7}{8}$	145
Mississippi	,, 1	,, 5	,, 10	Aug. 10 to 20	,, 15	1	165
Louisiana	,, 1	,, 1	,, 10	Aug. 1 to 15	., 15	1	223
Texas (South of 30° 50″ N.)	Jan. 15	Mar. 15	,, 10	Aug. 1	,, 20	1	182
Arkansas	Feb. 15	April 15	,, 15	Aug. 15 to 20	Jan. 15	1	200
Tennessee..........	Mar. 1	,, 15	,, 15	Sept. 1 to 10	,, 15	$\frac{3}{4}$ to 1	155
Long Staple or Sea Island Cotton in South Carolina ..	Feb. 1	,, 1	,, 1	Aug. 25	Dec. 10	$1\frac{3}{4}$	125

Note.—In the northern part of Texas the date for preparing the ground for sowing is about four weeks later than that given

above.   Sea Island is sowed a little later than that given in Georgia and Florida.   The average yield of the cotton-growing districts of the United States during the season 1890-1891 was, according to Ellison, 195lbs. of lint cotton per acre.   The termination of the picking season is, to a large extent, determined by the frosts which are prevalent in the early winter.   If these are severe enough they rapidly kill the crop.   The earliest period at which killing frosts have taken place recently are—October 2nd at Memphis, October 26th at Mobile, December 5th at Galveston, November 18th at Pensacola, and November 8th at Charleston.

COTTON CULTURE IN INDIA.

DISTRICTS.	Usual Date to prepare Land.	Usual Date of Sowing.	Usual Date to begin Picking.	Usual Date to finish Picking.	Usual Length of Staple.	Yield of Lint Cotton per acre.
Bengal	May & June	June	Oct.—Nov.	Dec.—Jan.	Inches. $\frac{3}{4}$ to $\frac{7}{8}$	96
Oomrawuttee ..	Do.	Do.	Nov.—Jan.	Mar.—Apr.	$\frac{3}{4}$ to 1	52
Broach	Do.	Do.	February	April	$\frac{3}{4}$ to 1	98$\frac{1}{2}$
Dhollera	Do.	Do.	Feb.—Apr.	Apr.—May	$\frac{15}{16}$	74
Coompta and Dhharwar ..	July & Aug.	August	March	May	$\frac{3}{4}$ to 1	50
Tinnevelly	Aug. & Sep.	Oct. & Nov.	Feb.—Mar.	Mar.—Apr.	$1\frac{1}{8}$ to $1\frac{1}{16}$	54
Westerns	July & Aug.	Aug. & Sep.	Mar.—Apr.	May	$\frac{3}{4}$ to 1	41
Hingunghat	May & June	June	Nov.—Dec.	Feb.—Mar.	$\frac{7}{8}$ to $1\frac{1}{16}$	42

In India cotton is not often sown in the same field in successive years, the rule being to sow it only once every three or five years, growing other crops, such as wheat or millet, in the interim.

(36) In Egypt, in preparing for the crop, the land is usually ploughed in December, this extending to the end of February, and planting takes place in March and April.   Picking begins in September, and lasts at times until the 1st January.   The staple of Egyptian cotton varies from 1in. to 1$\frac{1}{2}$in., and the yield is about 340lbs. per acre.   In Brazil, planting takes place

from December 15th to June 1st, according to the position of the plantation, and picking extends from July to February. About Pernambuco the plants have open bolls during the entire year. The length of Brazilian cotton is 1in. to 1¼in. In Turkestan the sowing takes place in April, the land being ploughed as soon as the weather permits. Picking begins about the middle of July and extends for a short time only, as about the end of August the nights get chilly, and this prevents the bolls from ripening. The yield is from 190lbs. to 240lbs. of lint cotton per acre.

FIG. 1.

(37) The system of cultivation in the United States is to plough deep furrows in the land and make a free application of fertilisers, which are ploughed in thoroughly. A considerable space—from five to six feet—is left between the furrows or ridges, so that when the plants have grown, a clear passage between them is left. The seed is sown by drills or dibbles, the former plan being adopted in the United States, a groove of 1½ to 2 inches deep being made along the crest of the ridge. The

seeds are dropped into this groove by the sower in fair numbers, and are immediately covered either by a harrow running along the ridge, or by means of hoes. In dibbling, holes are formed in the ridges, into which four or five seeds are dropped, and immediately covered. In a few days the plant appears, if the weather is favourable (its appearance being as in Fig. 1), and after it has grown a little, a few are thinned out, leaving two to

FIG. 2.

four together. Subsequently, these are reduced to one (the plant then being as in Fig. 2), and the plants are periodically banked up by passing a plough between the ridges. The three illustrations given in Figs. 3, 4, and 5 show the development of the plant, Fig. 5 showing the plant at full maturity. Weeds are kept clear by ploughing and hoeing, and constant

Fig. 3.

Fig. 4.

attention to this point greatly improves the crop. Careful cultivation has a wonderful effect upon the character of the cotton obtained, and even on poor soils the quality can be greatly improved in this way. In India the land is cultivated by hand, and the seeds sown either by a drill or broadcast. Substantially the same procedure as described is followed, but more work is done by hand. In Central Asia the seed is sown by dibbles, and as the season is short, the plants during growth are often cropped to lessen the rapidity of their growth. In Egypt ploughing is resorted to, furrows about 2ft. apart being made. A space of from 12 inches to 18 inches is left between each group of seeds.

(38) As was said at the beginning of this chapter, the cotton plant is of the order Malvaceae or mallows, and of the genus Gossypium. It was pointed out that the earliest historic records spoke of wool growing on trees, and it is still found in this shape in India, Arabia, Senegal, and Brazil. For many reasons the tree form, which is known as Gossypium Arboreum, has given way to the shrub and herbaceous varieties, which are most extensively cultivated. There are a large number of apparently distinct varieties of the plant existing in different parts of the world, but it is now generally conceded that most of these are variations of a few well known types. Dr. Forbes Royle, on p. 132 of " The Culture of Cotton in India," and again on p. 151, expresses the opinion that all the existing varieties can be classed under the following four heads: (1) Gossypium Peruvianum; (2) Gossypium Indicum; (3) Gossypium Barbadense; (4) Gossypium Arboreum. The first class includes most of the cotton grown in Pernambuco, Brazil, and Peru; the second, the several varieties indigenous to India; the third includes Bourbon, West Indian, Sea Island, Uplands, New Orleans, Mexican; and the fourth all the varieties of the tree cotton. There is a more detailed classification made by Professor Parlatore, which is quoted in the works on the " Cotton Fibre," by Dr. Bowman and Mr. Hugh Monie. There is one distinctive feature in connection with the Peruvian species

which is worth noting, namely, that it is a perennial plant, whereas all other varieties of cultivated cotton plants are annuals. Further, it does not fully bear fruit until the second year of its growth.   The most fruitful and most generally cultivated variety is the herbaceous, and from this the greatest weight of supply is obtained.

(39) It is intended to give a somewhat complete description of the cotton plant and the varieties of products obtained from it, and to illustrate it by means of special micro-drawings. These are the work of a careful microscopist, Mr. Abraham Flatters, and are made to a uniform scale, the general views being enlarged 200 and the cross sections 280 diameters, each of the vertical lines representing $\frac{1}{1000}$ inch.   It may be pointed out that between the leaf of the cotton plant and that of the black mulberry there is a considerable likeness, and the same remark applies to the leaf of the vine. Theophrastus noted these likenesses when accompanying the expedition of Alexander the Great into India.   The leaves of the Indian varieties have five lobes, that of the Barbadoes variety usually three, and the Peruvian variety sometimes three, sometimes five, lobes.   When the plant attains maturity, the blossoms form, and, as they mature, burst open.   The blossom exists for about a day, and is immediately followed by the seed pod, which develops until the growth of the fibres within it causes it to burst.   As soon as this happens, the fruit should be gathered along with the seed ; and it is a peculiarity of this plant that the fruit pods do not all burst at one time, but successively, so that it is not uncommon to see ripe and fully developed cotton on the same plant as pods only just begun to develop.   This is clearly shown in Figs. 4 and 5.   In some cases, in India, the pods do not fully but only partially open, and this is also the case with cotton grown in Central Asia.   All native Asiatic cotton appears to possess this characteristic, the cause of which is probably a defective method of cultivation.

(40) The process of growth commences with the formation of the seed from which the hairs of cotton are gradually built

FIG. 5.

up and developed. The latter absorb in their growth the viscous substance filling the seed, and are gradually developed until the full length of the fibre is obtained. When it is so formed, a fully ripe fibre is an elongated, hollow, slightly flattened tube, a little oval in section. During growth the hollow space acts as a conduit for the circulating fluid of the plant, but as maturity is approached this is withdrawn into the centre of the seed, so that the previously cylindrical fibre is flattened. While this absorption is going on the fibre turns on its axis and becomes a sort of spiral, the regularity of the turns depending on the resistance of the walls and the rate of absorption. The better the quality of the fibre the more pronounced is the convulute structure, this giving a corrugated appearance to the edges, which is of immense value from a manufacturing point of view. The fibre is covered with a coating or sheath of wax, the composition of which has been previously noted, and which plays a very important part in the subsequent manipulation of the cotton. It is generally assumed that the cotton fibre is cellular in structure and many observers allege this to be the case. It has been recently stated that this theory is incorrect, and that it is a continuous tube of a fibrous nature. So far as its influence upon spinning is concerned it does not matter which theory is correct, because the fibre is in either case admirably adapted for spinning. The convolute structure is also of great importance, and in most varieties the number of convolutions is great. Thus, in Egyptian cotton they reach 180 to the inch. There is, however, a good deal of variation, as will be clearly shown by the illustrations of the different growths which are subsequently given. Mr. Midgely, of Bolton, a very capable microscopist, has found fibres in which the twists ran in opposite directions in different parts. From this fact he has drawn the deduction that the fibre twists along the thinnest part of its wall, a very probable cause. This subject, however, is one for the microscopist and only bears partially upon the subject of spinning. The length of the fibre in any particular growth of cotton is known as its " staple." In Figs. 6 and 7, photographic

views are reproduced of 40 kinds of cotton, showing the length of staples, the views being half the actual size. The reference

FIG. 6.

numbers are only given for the first and last of each series, but the intermediate references can be readily made. The varieties

photographed are as follows: No. 1, Sea Islands, extra fine;
2, Georgia; 3, Florida; 4, Tahiti; 5, Gallini; 6, Brown

FIG. 7.

Egyptian; 7, White Egyptian; 8, Ashmouni; 9, Smyrna; 10,
Peruvian Smooth; 11, Rough; 12, Rios; 13, Ceara; 14, Maceio;

15, Pernam ; 16, Maranham ; 17, Paraiba ; 18, Peruvian Red ; 19, Allanseed ; 20, Peelers ; 21, Benders ; 22, Nashville ; 23, Orleans ; 24, Memphis ; 25, U.S. Ordinary ; 26, Uplands ; 27, Texas ; 28, Hingunghat ; 29, Oomrawuttee ; 30, Broach ; 31, Rangoon ; 32, Tinnivelly ; 33, Dharwar ; 34, Coomptah ; 35, Dhollera ; 36, Scinde ; 37, China ; 38, Lagos ; 39, Bengal ; 40, Assam.   The lengths and diameters given subsequently are approximate only, but are sufficiently near for practical purposes.

(41) Remembering what has been said as to the essential characteristics of successful cultivation, we will now proceed to

Sea Islands "Extra Fine."

FIG. 8.

give a brief account of the different varieties of cotton used commercially.   The best cotton produced is grown in the plantations along the coasts of South Carolina, Georgia, and Florida, and in some of the islands contiguous to them.   Here the soil contains the saline and other substances previously referred to ; the temperature is moderately high—from 70 to 80 degrees during the growth of the plant ; there is a fair volume of rainfall, about 5 to 6 inches, in each of the four months of growth ; and last, but not least, there is a humid atmosphere arising from the contiguity of the sea and the prevailing breezes.   Thus the whole of the conditions are favourable, and as a result, the cotton is fine and silky, with a light creamy tint ; the length

occasionally reaches 2 inches, but a mean length is 1·7.   Its
mean diameter is about ·000635 of an inch.   As with all
vegetable fibres, the length of individual ones vary considerably,
and the mean length can only be approximate.   The same remark
applies to the diameter, but with this reservation the dimensions
given may be accepted as fairly accurate.   The Sea Island
variety grown in South Carolina is the finest, but there are
several other varieties, such as Florida, Fiji, Tahiti, and Peruvian,
which are shorter in the fibre, and not so good in other respects.
The mean lengths of the three varieties named are, respectively,

FIG. 9.

FIG. 10.

1·58, 1·7, 1·5, and 1·56 inch.   In Figs. 8, 9, and 10, illustrations
drawn to scale are given of extra fine and Georgia fibres, and the
cross section of various growths of Sea Islands, including extra
fine Tahiti, Florida, and Georgia.   It will be seen that the con-
volute form is regular and that the walls of the fibres are thin.

(42) Cotton grown in Egypt is divided into two classes which
vary very considerably in quality and length.   What was formerly
the best variety, Gallini, was grown on lands adjoining the Nile,
which are alluvial in character, and are irrigated to a greater or
less degree by water obtained or stored from that river.   Gallini

cotton has, it is stated, practically disappeared, in consequence of the deterioration of its quality. Gallini was of the same variety as Sea Island—Gossypium Barbadense—and had a mean length of 1·35 inch. Its diameter was ·000675 inch, and it was light golden in colour. Its convolute form was very perfect; it was very strong, and although considerably coarser than Sea Island, was a very useful cotton. Ashmouni cotton is of a light brown colour, with a staple of 1 inch. Brown Egyptian is of the herbaceous variety, and is grown in the Delta of the Nile and at other points further south. Mit-Afifi is the most common of

FIG. 11.

FIG. 12.

this variety. The colour of this cotton is, as indicated, darker than Gallini, to which it is inferior in many respects, although grown on land of a similar character and under similar conditions of irrigation. The difference is probably a natural one, and could not be cured by cultivation. The fibres are strong and tough but coarser than Gallini, being shown in Fig. 11, the convolute form being less regular and the wall of the fibre denser. In this illustration the peculiar appearance of unripe or immature fibres is clearly shown. The cross sections of (1) Brown, (2) White, (3) Gallini, (4) Ashmouni, (5) Smyrna cottons are shown in Fig. 12. It will be seen how fine

the walls are. The mean length of Brown Egyptian cotton is 1·3 inch and its diameter ·000738. White Egyptian cotton is grown also in the Nile Delta, and is of two distinct species—the native Hirsutum, the cotton from which is called Abiad, and exotic Peruvianum, the growth of which is called Bamieh. This cotton is of a light gold colour with strong and fairly pliable fibres, but the convolute form is not so marked as in the other varieties. The mean length is 1¼ inch, and the diameter ·000769.

(43) The cotton grown in Peru is of three qualities, the best grade of which is of the Sea Island variety, being grown from

FIG. 13.

seed obtained from the United States. It is cultivated principally in the vicinity of the sea coast, and the colour is slightly golden. It is inferior both in fineness and cleanliness to Sea Island cotton, being about ·000675 inch diameter and having a mean length of 1·56 inch. The two principal varieties of cotton grown in Peru are, however, indigenous to the country—Gossypium Peruvianum—and are known respectively as rough and smooth. Between these two varieties so many differences exist that they almost form distinct species. Rough Peruvian, so called on account of a hairy feel, is harsh; the fibres vary

considerably in length, and are also more nearly straight than
Sea Island cotton.   The appearance of the fibres of this variety
are shown in Fig. 13, and their cross section in No. 1 of Fig. 14.

Peruvian   American

FIG. 14.

Peruvian.   Smooth.

FIG. 15.

It will be seen that the convolute form is fairly good, but that
the walls of the fibres are thicker than preceding examples. The
mean length is 1·28 inches, and the diameter ·000781 inches.
Smooth Peruvian is soft, and is not so strong as the rough

variety.   This is shown in Fig. 15, and its cross section in No. 2 of Fig. 14.   The lengths of the two varieties are about equal, as are also the diameters.   Peruvian cotton is sometimes used in the United States to mix with wool.   There is a variety known as Red Peruvian, from its colour, and this is shown in cross section in Fig. 14 at 3.

(44) It has been previously noted that the species Gossypium Peruvianum grows throughout South America, and there are several other growths, three of which, Pernambuco (shortly Pernams), Maranhams, and Cearas, are largely used.   Of these

FIG. 16.

the former (Fig. 16) is the best in quality, but is harsh in the fibre, which is about $1\frac{1}{4}$ inch long.   The convolutions of this cotton are regular, and this fact makes it a good commercial product. Maranhams are structurally inferior to Pernams, and are nearly $\frac{1}{4}$ inch shorter in average length.   This variety is shown in Fig. 17, its cross section at 3 in Fig. 18.   Ceara cotton is largely grown, and about the same length as Pernams.   The colour of these three varieties differs considerably, the first named being light gold, Maranhams much the same shade but dull, and Ceara a dull white.   There are several smaller growths of Brazilian cotton which possess the general characteristics of those named

but are slightly inferior. The cross sections of Ceara and Maceio are shown at 4 and 5; another variety, Paraiba, at No. 2, and a sixth, Rio-Grande, at No. 1 in Fig. 18. It will be seen that although the walls are thick, the tubular formation is fairly maintained. The culture of cotton in Brazil is mostly confined to the vicinity of the sea, but could be largely extended, owing to the enormous number of streams piercing the country in many parts.

(45) In addition to Sea Island, the United States produces a large crop of cotton which is, perhaps, the most reliable product

Brazilian ⸺ Maranham.

FIG. 17.

in the world. The length of the staple is more regular and it is marketed in a much better condition than most varieties. Most of the American cottons are of the species Gossypium Hirsutum, but they are divisible into a few varieties, the quality of which differs considerably with the geographical position of the plantation. Thus, Orleans cotton, which is grown in the States of Mississippi and Louisiana, is the best of the ordinary varieties of American. This fact can be accounted for by the character of the soil, the uniformity of the temperature, the fairly abundant rainfall, and above all, the humidity of the atmosphere, owing to the

immense volume of water in the immediate vicinity of the plant-
ations.   Texas cotton, which is obtained from the state of that
name, is not grown under such favourable climatic conditions.
The temperature in the southern part of the state, at any rate, is
higher, but there is an abundant rainfall, and by careful culti-
vation the staple of cotton produced has been much improved.
Uplands cotton, as its name implies, is grown on the rising lands
of the states of South Carolina, Georgia, and Alabama, and in
the southern part of Tennessee and Arkansas.   Here the soil is
of a light loamy character, but the temperature is regular and the

FIG. 18.

winds from the south and east carry with them a large amount
of moisture.   The fourth variety, known as Mobile, from the
port whence it is shipped, is generally inferior, and is grown in
the States of Alabama, Mississippi, and Louisiana.   It has
already been pointed out, more than once, that the position of a
plantation has a determining effect upon the quality of the
cotton grown.   No better instance of this can be found than in
the various grades of American cotton.   Thus, that grown on
the Uplands of Alabama and the other states is inferior to
cotton grown on the swamp lands in the same states.

(46) Orleans cotton has a mean length of 1·1in. and a diameter of ·000757in. It is white in colour, with soft, pliable, but fairly strong fibres. It is, as shown in Fig. 19, moderately convolute

U.S.A.   'Orleans'.

FIG. 19.

U.S.A.   'Texas'.

FIG. 20.

in form, and its pure colour renders it a favourite grade. It, like most American cottons, is carefully cultivated and is, therefore, very uniform in quality. Texas cotton, shown in Fig. 20, is an instance of how much can be done by care in cultivation.

Although the natural advantages of the district are inferior to those of the plantations in Louisiana the attention given to its proper cultivation has made Texas a very fine cotton, with a length of 1 in. and a thickness practically equal to that of Orleans. Its colour is tinged with brown and its strength is inferior to Orleans. Uplands cotton, see Fig. 21, consists of fibres which are very pliable and elastic, and of a white or slightly creamy colour. Its mean length is a little under an inch, and its diameter equal to that of Orleans.   As it is very soft, however, it is not so strong as the other varieties grown in the United States.   Mobile cotton is

U.S.A.   "Uplands".

FIG. 21.

short in the staple, being only about ⅞ in. long.   It is a curious fact and worth noting that all the varieties of ordinary cottons grown in the United States are, practically, of the same mean diameter, although they vary greatly in their other characteristics. There are a number of special cottons produced in the United States to which specific names are given.   These are grown in Alabama, Mississippi, Louisiana, and Arkansas, in the better lands, from special seeds.   They have a staple of 1⅛ to 1⅝ inch, and are known as " Benders," " Peelers," " Allen," and other names.   The illustration of Benders given in Fig. 22 shows

how good they are in quality. In Fig. 14 the cross sections
numbered 4, 5, and 6 are respectively those of ordinary Mobile,
Uplands, and Texas cotton, while in Fig. 23 the cross sections

U. S. A.   Benders.

FIG. 22.

American

FIG. 23.

of (1) Orleans, (2) Benders, (3) Memphis, (4) Peelers, (5) Nash-
ville, and (6) Allenseed are given. It will be seen how com-
pletely the tubular form is kept, and how comparatively fine are
the fibres.

(47) After America, the chief source of supply is India, where there are a number of cottons grown of more or less value and merit, all from the herbaceous variety of plant. Generally the cotton is much inferior to that grown in America, which is accounted for by the high temperature prevailing in the greater part of India, and the lack of sufficient moisture. The conformation of India also detracts from it as a cotton-growing country, because there are many districts in which the moisture obtainable is too little to sustain growth properly. Where the plantations are located either on uplands, so that the temperature is modified,

East Indian   Hingunghat.

FIG. 24.

or adjoining the rivers or sea, especially the latter, the best results are got. The best quality produced in India is found in the Hingunghat cottons, which are grown on the uplands in the Central Provinces of India, comprising Berar and Nagpur. The rainfall in these provinces is, during the monsoon, very heavy, being from 27½ to 29¾ inches in the months of June to October. Hingunghat cotton (which is shown in Fig. 24) is a little dark in colour, but is strong, and the length of its fibre is equal to Orleans. It is, however, slightly thicker than any American cotton, being ·000833 diameter. The convolute form

of the fibre is much less marked than in cottons grown in a
humid atmosphere, or a well-watered district.   Broach cotton,
see Fig. 25, which shows also the appearance of the unripe fibres,

East-Indian   Broach

FIG. 25.

East-Indian.   Oomrawuttee.

FIG. 26.

is obtained from the Bombay Presidency, principally from the
districts of Broach and Surat.   In these there is a rainfall of 40
and 43 inches respectively during the monsoon, and they are

moreover, not far from the sea.   This variety of cotton is much esteemed, although it is of a darkish colour, and the fibres are short, being only about $\frac{7}{8}$ in. long.   They are, however, regular, but not convolute, and the diameter is nearly equal to that of Hingunghat.

(48) Dharwar cottons are grown in the Bombay Presidency, and are of the same character, but inferior in length, being only about ·8 inch long.   Oomrawuttee or Oomra cotton (see Fig. 26) is grown principally in the Provinces of Bombay, Berar, and Hyderabad.   It is a fairly good quality when cleaned, and the

Cotton.
East Indian.   "Dhollerah."

FIG. 27.

fibres have a mean length of about ·9 inch.   It is a little thicker than Broach, but is not so good in many respects.   Dhollera cotton (see Fig. 27), which is perhaps the most widely known of Indian cottons, is also the product of the Bombay Presidency from the districts of Rathrawai, Ahmedabad, Baroda, and Cutch. This variety has a whitish colour, and the fibres are about $\frac{15}{16}$ inch long, and of the same diameter as Dharwar.   The strength of Dhollera is less than of some other varieties of Indian cotton, but in structure it resembles them.   Coomptah cotton is grown in the Central Provinces of India, and has a weak fibre of about

C

$\frac{13}{16}$ inch long.   The fibres are weak and brittle, and are generally
inferior, although in diameter equal to Dharwar and Dhollera.
The variety produced in Bengal is the most inferior of all Indian
cottons, although it has a length of a little over an inch.   It is
very harsh and wiry, and generally of an inferior character.   This
is probably due to the conditions under which it is cultivated
and to the character of the soil.   The fibres are very thick, but
are fairly strong.   The cotton grown in Scinde (see Fig. 28) is
cultivated under the worst possible conditions, the rainfall in
this district being only from four to eight inches annually.

Cotton.
East Indian.   Scinde.

FIG. 28.

Irrigation is therefore largely depended on, but the character of
the soil does not compensate for the small rainfall and dry
atmosphere.   In consequence the fibres are short and only
about ·65 inch, but are comparatively strong.   All the varieties
of Indian cotton just described are obtained from the Northern
and Central Provinces, but there are two varieties which are
obtained from the Madras Presidency.   The best of these is
Tinnevelly, which is grown in a district in the south of the
Presidency, opposite the Island of Ceylon.   A certain proportion
is also grown in Trichinopoly.   Owing to the fact that these

provinces lie near the southernmost point of India the influence of the sea is apparent.   The heat in all parts of the Madras Presidency is, however, very great.   For all that, Tinnevelly cotton is a fairly good variety, the fibres being moderately strong and 7/8 inch long.   In their natural structure they show the influence of their native climate very perceptibly, as the walls are much thicker than is the case with cotton grown in a milder climate, this being also indicated by the absence of the convolute form.   The second variety of Madras cotton is known as Westerns, which are very inferior to Tinnevelly, especially in

FIG. 29.

FIG. 30.

uniformity.   Being strong, however, they can be mixed with other varieties.   The cross sections of Indian cotton given in Figs. 29 and 30, show them to be generally inferior to the American varieties.   In these figures the cross sections are given of (1) Rangoon, (2) Assam, (3) Broach, (4) Bengal, (5) Tinnevelly, (6) Dharwar, (7) Coomptah, (8) Oomrawuttee, (9) Hingunghat, (10) Scinde, and (11) Dhollera.   It will be seen that in some cases the flattened oval and tubular appearance is nearly absent.

(49) In addition to the foregoing varieties of cotton there is a small supply drawn from the West Indies, of cotton of the

Peruvian type. The West Indian cotton, according to Mr. Monie, has the spiral or convolute formation more perfectly developed than any other variety, and as it is of a good length, 1 ⅓ inch,

"China"

FIG. 31.

China

FIG. 32.

it is valuable in many respects. There is also a small supply obtained from Asia Minor, Queensland, South and West Africa, and the Islands of the Pacific, but the details given nearly cover

the ground, so far as chief commercial qualities are concerned. A good deal of white cotton of fair quality is grown in China, being shown in Fig. 31, but it is entirely utilised in that country.

African   Zagos.

FIG. 33.

African Zagos

FIG. 34.

The cross section given in Fig. 32 shows the fibre to be very like the Indian cotton in structure.   The measurements given are all approximate, and as different observers give different

lengths for the same staple, it is difficult to determine the accurate figures.   On the whole, the lengths given in the table on pages 74 and 75 are approximately accurate.   Some cotton is grown in Africa, and its general character will be gathered from the view given in Fig. 33, and the cross sections in Fig. 34.

(50) The description thus given of the various qualities of cotton will enable the following remarks to be more readily comprehended and their significance understood.   The commercial value of a cotton is determined by several features, viz., its length, fineness, strength, pliability, smoothness, uniformity, colour, and cleanliness.   As a rule, the cotton which is the longest is the finest, but it is by no means the strongest.   Thus Sea Island cotton has the longest fibre with the least diameter, and Hingunghat is much inferior to it in both respects.   The strength of the latter, however, is 50 per cent greater than that of the former.   As in every other essential, however, Sea Island is in advance of Hingunghat, it is the most valuable, especially for the production of fine yarns.   The most regular cotton is Orleans, in which the length of the staple only varies a small fraction of an inch.   In consequence a certain loss is experienced in some of the processes through which it has passed, but this loss is much less than is the case with other cotton, the fibres of which vary considerably in length.   When the carding and drawing processes come to be dealt with the importance of regularity or uniformity will be seen.   Cleanliness is a cardinal point in the commercial creed, because the impurities found in cotton add so much to its weight, as purchased, that their removal involves a serious charge upon the millowner.   This defect is a very serious one in most Indian cottons, and many even of the better qualities are deteriorated in value on this account. The waste at the opener and scutcher becomes largely increased if through carelessness or wilful negligence the amount of sand and dirt is increased.   There is always in cotton a certain portion of unripe and short fibre which it is impossible to avoid altogether, as they are found in a pod which is to all appearances quite ripe and ready for picking.   At a later stage the presence

of broken fibre and its cause will be explained.   The question of moisture has also been one over which a good deal of angry controversy has raged.   The natural moisture in the cotton fibre varies, as might be expected, from year to year, according to the character of the season and of the weather during picking. Making due allowance for this, however, there is more than a suspicion that the amount is added to wilfully, and this, of course, means a considerable loss to the spinner.   In order to set the matter at rest the Cotton Spinners' Association have taken the matter up and have determined upon a certain standard.

(51) A special oven has been designed by Messrs. Hall and Kay, of Ashton-under-Lyne, to deal with this question, it being so constructed that the cotton is subjected to a radiated but not direct heat.   In testing cotton, a sample is taken from the ecntre of several bales, and smaller portions of each of these—as nearly equal in weight as possible—are taken, until their total weight is 1,000 grains.   This sample is then opened by hand, care being taken to receive any sand shaken out, and placed on the tray in the oven.   The temperature of the air within the latter should be 170° to 180° F., and it should be kept at that heat for the one and a half hour it takes to make the test.   At the expiration of that time the cotton is taken out and re-weighed, the difference in its weight before and after drying being noted. Inasmuch as 1,000 is easily divisible by ten, the percentage of loss is arrived at without calculation.   Suppose the cotton has lost 110 grains, or 11 per cent, from this must be deducted 80 grains, or 8 per cent (it being found, by a large number of experiments, that cotton so dried will recover 8 per cent on exposure to the atmosphere for 24 hours); this leaves 3 per cent of moisture in the cotton in excess of the assumed standard. This is not a very excessive loss, some lots having been found to contain 5 per cent and over, whereas in a dry season most cotton shows not more than 1 to 2 per cent of moisture over the standard.   Texas cotton not unfrequently shows ·3 to ·5 per cent, and Surat ·5 to 1·3 per cent dryer than the standard.

(52) A somewhat similar treatment with cops helps to solve another vexed question where manufacturers buy their yarn. In this case it is better to take a larger weight, say, 10,000 grains. This must remain in the oven five hours, and an allowance of 5 per cent requires to be made from the gross loss, experiments having conclusively shown that yarn taken direct from the spinning room will lose 5 per cent at 170° to 180° F., therefore any loss more than this shows what is the moisture gained over the weight when fresh from the spindle. Example:

	Grains.
Weight put in oven	10,000
Weight from the oven when dry	9,150
	850
Deduct 5 per cent to bring up to spinning room standard.	500
	350

showing 350 grains, or 3·5 per cent of moisture gained over the weight when fresh from the spindle.

(53) It has been indicated that the character of the different growths of cotton fibre varies considerably. Some are strong and others are weak, some harsh and wiry, others soft and pliable. Accordingly it is possible to divide them into cottons suitable for twist, where a hard strong fibre is wanted, and others for weft, where a softer and more pliable thread is desired. When the fibres are of such a character that when arranged side by side they lie closely together and twist into a perfectly even cylindrical thread, the best results are obtained. Generally speaking, the best yarn is that in which the greatest number of fibres are found in the cross section. There are, of course, exceptions to every rule, but the rule may be a good one, in spite of the exceptions. A table (on pp. 74, 75) gives the characteristics of the cottons respectively suitable for making twist or warp and weft yarns.

(54) It is not an uncommon thing to hear complaints of the quality of the cotton as imported, not only on the ground of dampness, but also on many others. The brief review given of

the method of growth shows that there must always be a certain proportion of short and immature fibre present. The amount of this however, varies from year to year, and there is every reason to believe that with some kinds of Indian cotton especially it is the practice to mix a certain amount of short staple with the better grades before exporting it. The presence of short stapled cotton is not only detrimental to its value, but it is alike a source of annoyance and a cause of considerable expense in subsequent stages. There are two classes of natural adherent impurities which will always be more or less present, viz., broken leaf and sand or dirt. The latter are present in varying quantities which depend largely upon the character of the season, and are found in the greatest weight in the various Indian grades, reaching as much as five per cent. The presence of broken leaf and seed is mainly caused by lack of care in ginning, and is the result of a forced production at the ginning factories. The former especially is bad to eliminate, and does not always finally disappear until the cotton has been considerably treated. To the same cause may be attributed broken fibre and stringy cotton, and there is also caused in the ginning process a good deal of "nep." The latter is the name given to little knots which are composed mainly of dried-up fibres, and are always formed by the rubbing together of the fibres: These are very hard to remove, and appear in the sliver even though it may be well carded, only the specially thorough treatment by combing removing them. It is a very rare thing to see a carded web entirely free from the little white specks or "neps," and until methods are improved they are not likely to disappear. There is, however, a good deal of nep which is artificially caused during the whole series of cleaning processess. The cotton fibres are most brittle at their ends, and if they are heavily scutched these points get broken off and are rubbed up into nep. That this action takes place is certain, and a series of careful measurements of fibres before and after scutching show that in many cases the breakage of fibre is very great. This will be referred to at greater length in the next chapter, but it is worth specially noting at this point.

VARIETIES OF COTTON AND CHARACTERISTICS.

Variety of Cotton.	Sub-Variety of Cotton.	Mean Dimensions.		Yarn Produced.		Characteristics.
		Length. Inch.	Diameter. Inch.	Counts.	Twist or Weft.	
SEA ISLAND	Carolina	1.8	$\frac{1}{1700}$	up to 400s	T and W	Length, small diameter, regularity, silkiness.
	Florida	1.6	$\frac{1}{1670}$	up to 200s	do.	Do. do. do.
	Fijian	1.8		do.	do.	Similar to preceding, weaker, more irregular, and more unripe fibres.
EGYPTIAN	Peruviar	1.5	$\frac{1}{1450}$	up to 140s	do.	Inferior in chief qualities to preceding, light golden tint.
	Gallini	1.4	$\frac{1}{1450}$	up to 150s	do.	Strong, fine, light golden colour, easy to spin.
	Brown	1.3	$\frac{1}{1350}$	up to 90s	do.	Strong, clean, easily spun, golden colour.
	White	1.25	$\frac{1}{1300}$	up to 70s	do.	Moderately strong, light golden, not so clean.
PERUVIAN	Rough	1.28	$\frac{1}{1080}$	do.	T	Light cream, harsh feel, wiry, clean, moderately strong, mixes well with wool.
BRAZILIAN	Smooth	1.28	$\frac{1}{900}$	do.	W	Soft, smooth, flexible, easily spun.
	Pernams	1.3	$\frac{1}{1270}$	up to 6cs	T	Rather harsh and wiry, light golden.
	Maranhams	1.2		up to 50s	T and W	Dull gold, weaker than Pernams, rather harsh.
	Ceara	1.1	$\frac{1}{1350}$	do.	do.	Dull white colour, moderately strong, harsh and wiry.
	Paraiba	1.1	$\frac{1}{1270}$	do.	dc.	Moderately strong, harsh and wiry.
	Maceio	1.1		do.	do.	Do. do. do.

					T or W	
AMERICAN	Orleans	1·1	$1\tfrac{3}{10}$	up to 50s	T or W	Soft, moist, fairly strong, white to light cream colour, easy and economical to work.
	Texas	0·9		do.	do.	Similar to above generally, light gold colour.
	Upland	1·0	$1\tfrac{3}{10}$	up to 42s	W	Like Orleans, soft, clean, excellent for weft.
	Mobile	1·0		up to 36s	do.	Not so clean as preceding, weaker in fibre.
SYRIAN	Symrna	1·2 to 1·4	$1\tfrac{3}{16}$	up to 42s	T or W	Harsh, irregular twist in fibre, medium strength, dull white colour
WEST, INDIAN	West Indian	1·0	$1\tfrac{2}{10}$	up to 40s	do.	Harsh, rather dry, moderate strength, varies in colour.
AFRICAN		1·0		up to 30s	T	Harsh, but good colour, lacks cultivation.
INDIAN	Hinghunghat	1·0	$1\tfrac{3}{10}$	up to 36s	T	Strong, light golden tints, variation in diameter.
	Broach	0·8		up to 28s	T or W	Moderately strong, clean, golden tinted.
	Tinnivelly	0·8	$1\tfrac{2}{10}$	up to 26s	T	Strong, elastic, dull cream, fairly clean.
	Dharwar	0·7		up to 20s	T or W	Moderately strong, light gold, fibres variable and broken.
	Oomras	0·8	$1\tfrac{1}{10}$	do.	do.	Strong, regular, cream colour, rather dirty.
	Dhollerah	0·7		do.	W	Moderately strong, dull white dirty.
	Madras or Westerns	0·7	$1\tfrac{2}{10}$	do.	T	Strong, dark coloured, dirty, uneconomical.
	Coomptah	0·3		up to 15s	W	Weak, brown tint, dirty.
	Bengal	0·3	$1\tfrac{1}{4}$	do.	T	Strong, harsh, golden tint, dirty.
	Scinde	0·4		up to 12s	T or W	Poor, fairly clean, dull white tint.

(55) Cotton is picked by hand—no really successful machine having hitherto been applied to this purpose—and the proportion of leaf extracted with the ripe boll is dependent on the dexterity of the picker. The pickers are able to collect a considerable quantity prior to delivering it at the end of the row or furrow in which they work. The cotton thus obtained is collected in bulk and is treated by a gin usually driven by power. The early methods of freeing the cotton from seed were very primitive, and were afterwards displaced by a double roller machine. Subsequently to this, Eli Whitney introduced his saw gin, which has been successfully worked. Its chief feature is the employment of a number of saws in the form of a roller, which seize the cotton and draw it between the interstices of a grid suitably arranged so as to strip off the seed. The cotton is beaten off by a revolving brush. The action of this machine is harsh and severe, and results in a good deal of damage to the cotton. At the same time it is still extensively used in the United States, although the bending of the fibres nearly double in the process of ginning is very deleterious. If the saw gin is overfed it speedily breaks the cotton. The machine which is probably in all respects the most satisfactory is the roller and double knife gin, an illustration of which, as made by Messrs. Platt, is given in Fig. 35. This machine consists of a hopper, into which the cotton is fed. At the bottom of the hopper is the roller G covered with walrus leather, which has a rough surface so that it readily seizes the fibres. Against the face of this roller a fixed knife I is pressed, so that, as the roller revolves, it draws the fibres between its surface and this knife. In doing so the seed, which adheres to the cotton, is drawn to to the point where the knife I presses against the roller G. While the seed is so held the two blades F^1 and F^2 strike it alternately, so pushing it away from the point where it is held. These are fixed at the upper ends of vertical rods which receive a reciprocal motion from a crank shaft. The seed is thus gently removed from the cotton without damage to the fibre, which is carried onward by the continued rotation of the roller

G. In order to avoid any danger to the attendant, a self-feeder C, actuated by a crank, is fitted, which always keeps the roller well supplied with cotton. The seed grid used is arranged so as to be movable, and thus considerably aids the delivery of the seed, which, when a stationary grid is used, tend to choke it. The choking of the gin is practically avoided, even when cotton containing a large quantity of seed is used. The advantage of a double knife machine is that the number of


Fig. 35

blows given per minute being more numerous, the machine can be driven at a slower speed without reducing its capacity, and, as a matter of fact, the output of a double knife machine is, at the speed of 600 revolutions per minute of the crank shaft, greater than that of the single machine at 900 or 1,000. The objects desired in ginning, viz., the removal of the seed without breaking or crushing the fibre or seed and without the production of nep, are well attained by this machine. Its production

ranges from 25lbs. per hour of the inferior Indian cottons in
which there is a maximum of seed to a minimum of cotton, to
45lbs. of the better qualities of Indian staples and proportionate
yields of American. It is not desirable to overload the gin at
any time, and this should be remembered. A form of gin which
is used in Egypt is shown in Figs. 36 and 37, in this case there
being only one oscillating knife H, operated from the crank
shown by the connecting arm I. The peculiar method of

FIG. 36.

grooving the leather roller is shown in the partial front view
given in Fig. 37. The knife H is given a peculiar movement
by means of the radial arm J, and the cotton is placed as in the
gin just described—on a feed table F with a grid G near the
knife. There is a fixed upper blade C kept in position by the
spring clamps D and E. It may be mentioned that the method
of operating the arms H and H¹ in Fig. 35 is similar to that
shown in Fig. 36.

(56) After the cotton has been ginned, and the lint obtained, it is packed into bales for transport. It is the custom in the United States to give it a light compress prior to sending it to some convenient centre for final compression. In the United States almost the whole of the cotton is baled by steam presses, which exert a comparatively light pressure upon it, while in Egypt and India the use of powerful hydraulic presses is customary. The cotton is wrapped in a coarse jute bagging,


FIG. 37.

which should be of sufficient strength to ensure the bale reaching its destination with its cover intact. The bale, after compression, is secured by iron bands wrapped round it and riveted, or otherwise fastened at the ends. American cotton has suffered hitherto from bad packing, which has caused it to reach its destination in a dilapidated state. The size of the bales made in different countries varies. The Indian bale is about 48in. long by 20in. wide and 18in thick, with a cubic capacity of 10ft.,

its weight being about 396lbs. The Egyptian bale is about
51in. long by 31in. wide and 22in. thick, having a cubic capacity
of 20ft., and a mean weight of 720lbs., although this varies
somewhat. The American bales vary considerably in size,
being from 54in. to 80in. long, from 24in. to 40in. wide, and
from 18in. to 27in. thick. With such a variation it is impossible
to give any mean weight which is more than approximately
accurate, but it is about 480lbs. The Brazilian bales have a size
of about 49in. long by 20in. wide and 18in. thick, with a cubic
capacity of about 10ft. and a mean weight of 220lbs. This
matter is one of some importance in view of the stowage of the
bales on board ship, or on railway trucks during transportation.
A tightly-packed bale is less liable to damage from fire or other
causes, but the extent of pressure must be strictly graded in
accordance with the character of the cotton used. Thus the
pressure put upon Egyptian and American cotton ought not to
be more than will give a density of about 35lbs. per cubic foot,
while Indian cotton has been pressed up to 60lbs. per cubic
foot without damage. In consequence of the insufficient pack-
ing of American cotton, a system has been introduced in which
the cotton is rolled up into a sheet as it leaves the gin, being
subjected to compression during the process. In this way a roll
or cylinder of cotton, with a density of about 40lbs. per cubic
foot, and easily handled, is produced.

(57) The various growths of cotton are, according to their
qualities, graded in values, and are classified roughly as
follows :—

American.	Brazilian.	Egyptian.	Indian.
Good Ordinary.	Middling Fair	Fair.	Fair.
Low Middling.	Fair.	Good Fair.	Good Fair.
Middling.	Good Fair.	Good.	Good.
Good Middling.	......	... ...	Fine.
Middling Fair.	......	......	......

Of these, the first-named is always the poorest quality.   It may, however, be remarked that between each grade there are sub-grades which are always taken into account in purchasing cotton.   For instance, American is classified as fair, barely fair, strict middling fair, and so on with each grade.   In New York these distinctions are adhered to.   The full grades are those stated above; the half grades have the prefix "strict"; the quarter grades, the prefix "barely," indicating the point midway between the half grade and the next full grade above; or "fully," meaning the point midway between the half grade and the next full grade below.   When cotton is bought by the spinner in this country, it is purchased from a broker, samples being furnished to the seller at the time of purchase.   The terms of purchase are $1\frac{1}{2}$ per cent discount in ten days from date of purchase, with an allowance from the gross weight of 4 per cent for tares.   That is, a bale of 400 lbs. would be regarded as one of 384lbs. only.   Owing to the heavy tares which have become habitual with American cotton the buyer has now the option of claiming the actual tare, which is ascertained by stripping 10 bales and weighing the covering and hoops.   This is a troublesome matter, and it is not resorted to unless there is reason to believe that the tare is excessive.   In paying for a purchase the buyer can pay cash, receiving a discount at the rate of 5 per cent per annum, or if the term of payment is extended the same rate is charged as interest.

(58) The following are the details of what is known as C.I.F. 6 per cent terms, on which a good deal of American cotton is sold :—

Grade, Colour and Staple are specified as agreed upon. Also whether the cotton is "Orleans," "Texas," "Gulf," "Memphis," or simply "Uplands."

Weights.—The invoice to be for American actual gross weight, less an allowance of six [6] per cent to cover bands and tare.   The gross landing weight guaranteed to be within one per cent of gross invoice weight.   Gross

landing weight to be ascertained by weighing the cotton in Liverpool on arrival, before sampling (or if already sampled an allowance to be made for the samples drawn), due notice of weighing having been given in writing by the buyer to the seller. Any excess in weight of bands over 900lbs. for each 100 bales to be deducted from the "landing weight." Allowances to be made for missing bands and ship's pickings. Should weight of bagging exceed 4lbs. per 112lbs. the buyer shall have the right to claim for such excess at invoice price, but the claim must be made and properly substantiated within two months from the last day of landing.

Route of Shipment.—To be fully stated (as "by Rail and Steamer from Memphis to Liverpool, via any Atlantic port"), etc., etc., or as the case may be.

Date of Shipment.—To be specified as "during October," or "prompt shipment," or "immediate shipment," or "shipping or shipped," as stipulated. "Prompt" or "immediate" shipment means to be shipped not earlier than the date of the contract nor later than 14 days after. "Shipping or shipped" means the shipment shall be within 14 days either before or after the date of contract.

Declaration of Marks and Vessel's name, or particulars contained in through bill of lading, to be declared within four weeks of the date of bill of lading.

Marine Insurance.—To be provided by the seller, with a first-class company, covering particular average and five per cent in excess of invoice cost.

Samples.—When sold to equal an American drawn sample of the identical cotton, an allowance of $\frac{1}{32}$ of a penny per pound is made between it and the Liverpool re-drawn samples.

Arbitrations and Rejections.—No allowance to seller. Should arbitration be demanded by the buyer, the cotton shall be subjec to mutual allowances except in the case

of average shipment.   Should any lot prove not in
accordance with the contract the buyer to have the
option of rejecting it.

Reimbursement is specified in Contract Drafts usually at
60 days' sight with shipping documents attached.   Pay-
ment is usually made in exchange for shipping documents
on or before arrival of vessel (at buyer's option).

(59) In some cases cotton is bought under contracts for
future delivery, which have been made the medium of many
gambling transactions.   These contracts may, however, be
used in a legitimate manner, for there are many cases where
a spinner, having sold his production, may desire to cover
himself by purchasing cotton to cover the transaction.   In this
case cotton will be tendered at the due date in satisfaction of
the contract, and it is not to transactions of this nature that
any condemnatory terms can be applied.   It is only when the
contract is entered into without there being any intention or
accepting cotton at any time in satisfaction of it, but merely to
realise any profit which may accrue by reason of the higher
selling price at the time of its completion, that the transaction
becomes a harmful one.   The following are the terms of the
Liverpool Contract : It is for 47,200lbs. net weight in about 100
bales of cotton, of United States growth, to be delivered from
warehouse.   The price is to be upon the basis of Middling,
Liverpool classification ; nothing below Low Middling to be
delivered, and the additions or deductions to be settled by
arbitration.   The delivery is at the seller's option within the
time specified, which is usually during two months, but the
seller must intimate to the buyer his readiness to deliver; and
the buyer has a like option as to time, but must take the cotton
within ten days after the date of the seller's declaration.   The
declaration must contain particulars of the marks of the bales,
and the cotton must be ready for immediate delivery.   If the
cotton is purchased as a speculative venture, weekly settlements
are made, and the differences are paid to the party requiring
them.   It is often the case that these differences will go through

many hands before the contract is finally worked off; and a clearing-house system is in operation for this purpose. The following allowances are made in determining the net weight of cotton tendered :—2lbs. per bale for draft; actual weight of iron bands, 4lbs. for each 112lbs. for tare; the remainder being the net weight. Payment is to be made before delivery, and a transfer order is given which gives the buyer the control of the cotton. A discount of 1½ per cent for cash is allowed. The Liverpool classification for Strict Low Middling to Middling is about half a grade lower than the New York classification; whilst for the grades below that named, it is a quarter to half a grade higher. The New York contract differs from the Liverpool one in a few particulars, more especially as to the grade which is tenderable. Any grade will be taken from Good Ordinary to Fair; but if the cotton is stained, nothing less than Low Middling. The price is based on Middling, and the necessary additions or deductions are settled by an Inspector appointed by the New York Cotton Exchange authorities. The option is for some specified month, and a deposit or margin can be demanded by either party to the contract up to $5 per bale. The sum deposited is lodged with a Trust Company until the settlement of the contract, but must be demanded within 24 hours of the transaction, when both parties must deposit an equal amount. It may be of interest to give the various weights used in different cotton growing countries, as prices are often quoted in these terms. These are given below and the equivalents in lbs. avoirdupois are appended.

Bengal 1 maund (82·28lbs.) = 40 seers (seer = 2·057lbs.)
Madras 1 candy (493·71lbs.) = 20 maunds (maunds = 24·68lbs.) = 800 seers. For convenience a candy is taken at 500lbs.
Bombay 1 candy (560lbs.) = 20 maunds = 80 seers.
Egypt 1 cantar = 98·046lbs.
Brazil 1 quintal = 101·186lbs.
China and Japan 1 picul = 133·33lbs. = 100 katties.

(60) According to the most recently published statistics, the acreage under cotton in the United States was for the season 1894-5, 23,687,950. From this there was produced a commer-

cial crop, that is, one including all deliveries, whether grown in that season or not, amounting to 10,533,000 bales of 450lbs. each.   The average weight per bale is said to have been in the season 1894-95, 509lbs.   The acreage in India for the season of 1895 was 16,450,000, and the production was 2,688,000 bales of 400lbs.   The Egyptian acreage in 1894-95 was 1,050,000, and the yield 638,957 bales.   The Brazilian crop in the season 1892-93 was 438,000 bales.   The production of cotton in Turkestan from American seed was in 1893, 300,000 bales of 400lbs. each.   The disposition of the American cotton crop for the season 1894-95 was as follows :—To Great Britain, 2,938,000 bales ; to the Continent of Europe, 3,261,000 bales ; the United States of America, 3,148,000 bales.   The Indian crop was disposed of as follows :—To the United Kingdom, 86,283 bales; the Continent of Europe, 681,635 ; consumed in the Indian Mills, 1,375,000 ; to China and Japan, 132,628 ; consumed locally, 413,000.   The estimated number of spindles existing in the United Kingdom according to the latest statistics are 45,400,000 in Great Britain.   The number of spindles at work in India in 1895 was 3,810,000 ; in Japan, 513,926 ; in the United States, Northern Mills, 13,700,000 ; Southern Mills, 2,240,000.   These figures are the latest that are available at the time of writing.

(61) The cotton fibre, from its nature, requires different treatment to others, and necessitates the employment of an entirely distinctive set of machines.   The number of processes through which it is passed is greater than that needed for any other fibre, this arising from its shorter staple and its peculiarly good spinning qualities.   When the various stages are analysed, however, they may be easily grouped, but it will be seen that many of the groups overlap—that is, some of the objects of one are also those of another.   The following is a fairly accurate tabulation of the various processes commencing immediately after the cotton is received at the mill.   It may, of course, be objected that the earlier of these do not strictly come within the meaning of the phrase "spinning," but they are absolutely

necessary, and have such an influence upon the staple that it is difficult to avoid including them :—

1st STAGE.—
             (A) Mixing or blending.
2nd STAGE.—Operation for cleaning fibres.
             (B) Opening.
             (C) Scutching.
             (E) Carding.
3rd STAGE.—Operation of parallelising and attenuating collected strand.
             (F) Drawing.
4th STAGE.—Operation of further attenuating and twisting strand.
             (G) Slubbing.
             (H) Second slubbing or intermediate.
             (I) Roving.
             (J) Spinning $\begin{cases} (a) & \text{Mule.} \\ (b) & \text{Flyer.} \\ (c) & \text{Ring frame.} \end{cases}$
5th STAGE. —Operation of twisting threads together.
             (K) Doubling $\begin{cases} (a) & \text{Twining.} \\ (b) & \text{Ring doubling.} \end{cases}$

In addition to the above, there is an additional stage, when fine yarns are spun, which may be called 3A stage. The operation is one of parallelisation and cleaning, which occurs before drawing, and consists of three manipulations :—

STAGE 3A.—
             (L) $\begin{cases} \text{Formation of lap for sliver.} \\ \text{Doubling and attenuation of laps.} \\ \text{Combing.} \end{cases}$

And in addition also a process by which the partially twisted strand is further reduced and twisted prior to spinning, which may be called—
             (I^1) Second roving or jacking.

The above form a practical subdivision of the whole process, which is not without some value as a guide to the method of procedure. The object of all the various manipulations is to produce a thread perfectly cylindrical in form without variation in its thickness, and with as many fibres as possible in its cross section. To obtain these results with the minimum of loss of available fibre is the desideratum of the cotton spinners, and the whole of the machines are designed with this object.

CHAPTER III.

MIXING, OPENING, AND SCUTCHING.

(62) When cotton is presented to the spinner it is, owing to the pressure to which it is subjected during packing, in a matted state, and the first operation which is necessary is that of opening out the bale. This is sometimes done by hand, especially in mills which are of small size, but it is becoming the usual practice to effect it by machine. There are many incidental advantages to be derived from the latter procedure, to which subsequent allusion will be made. The bale breaker, of which an illustration is given in Fig. 38, consists of a feed table of the lattice type. This is constructed of a number of slats or laths of wood, which are attached to two endless chains passing over rollers placed at any desired distance apart. One of the rollers is driven, and the lattice apron—shortly, lattice—

is moved at a regular rate, and from its construction forms a flexible feed table, admirably adapted for its purpose. The cotton is taken from the bale in moderate sized pieces, and is placed upon the lattice, by which it is carried forward and delivered into the range of the first pair of rollers. Of these, there are either two or four pairs, but in either case they are driven by spur gearing at different speeds. The rollers are differently constructed, the first pair being always made with coarsely pitched blunt teeth, by which the cotton is readily seized and drawn into the machine. The next pair immediately grip it, and as they revolve at a considerably higher velocity, the

Fig. 38.

lumps are effectively drawn out. The third pair has finer teeth, and the fourth are, as a rule, formed with longitudinal grooves of coarse pitch. It is customary to make the first three rollers of a number of discs threaded on the shaft and bolted together, so that in the event of a breakage of the teeth one can be easily broken off and a new one added at the end. The top rollers are weighted by spiral springs, so that when an extra large piece of cotton, or any very hard substance passes, the roller can yield, and so avoid damage. The speed of the various pairs, as has been said, increases rapidly, and the effect is that, if four rollers are used, the cotton is well pulled before being delivered. In some cases, in addition to the difference in

the velocities of each pair of rollers, there is a differential speed given to each roller in a pair, the idea being to exercise a draft between them. The extent to which the length of the cotton is increased is known as the " draft " of the machine, and this phrase is applied to all the processes of attenuation occurring in the whole series of machines.

(63) As has been indicated, there is a divergence of opinion as to the correct draft of a bale breaker, but the balance or advantage lies with the adoption of a large one. It is desired to get the cotton into the best possible condition for opening, and this can be best done by putting it into a free, loose condition, at the earliest stage. There are limitations to this procedure, and different cottons require different treatment ; but a draft of from 1 in 20 to 1 in 30 is, in the author's opinion, the best for practical purposes. There is an advantage gained, when very short stapled cotton is used, in partially opening by the bale breaker and completing the operation by a small porcupine cylinder ; but for most classes the bale breaker will be found sufficient. There cannot be in this, as in many other operations in cotton spinning, any hard and fast rule laid down, but the advantages of a large draft are greater than those of a small one. Messrs. Dobson and Barlow, Limited, apply the principle of the pedal motion used in a scutcher, as afterwards described, by which the cotton is held in sections, so to speak, across the face of the rollers, and thus any danger of large pieces slipping through unopened is obviated.

(64) It has been pointed out that there is in cotton as received a large amount of dirt and sand, and when the bale breaker is constructed so as to open the cotton well much of this is shaken out of it at this stage. It will be shown how important it is to cleanse the material as well as possible at the earliest moment, and anything which removes even a small percentage of dirt prior to the first recognised cleaning process is of considerable value. That such is the result of the breaking up of the closely packed cotton into smaller pieces by the bale breaker no one who will watch its action will deny, and this fact

forms an additional reason for the system recommended. It is, of course, necessary to observe every precaution against damage to the fibres, but this is hardly likely to happen if the machine be kept in good condition, and if the top rollers are not unduly weighted.

(65) The bale breaker is now almost invariably used in connection with the arrangements for mixing. Before proceeding to deal with its employment in this manner, it will be preferable to describe the methods and principles of mixing cottons. It was shown in the preceding chapters that some of the various grades of cotton possess characteristics which are the complements of those possessed by others. It is therefore possible, instead of using one class of cotton only for spinning, to use two or three, by combining them in a judicious manner. The purpose of this practice is to enable a material to be finally obtained which will be more economical than if any single variety be used, and the object of mixing is a purely commercial one. Thus certain grades of Orleans and Surat cottons can be employed in combination, which will provide a cheaper raw material than if Orleans cotton only were used, and the resultant yarn, while maintaining its strength and commercial value, will be more cheaply produced. In the hands of a man who can skilfully blend various qualities, the economical results obtained are surprising. To be successful, however, a thorough knowledge of the different kinds of cotton available is absolutely necessary, and any one who neglects, or is ignorant of, this side of the subject will make a woeful failure. There are a large number of points to be considered in making a mixing, of which the following are the principal :—Length of staple, spinning qualities, colour, and price.

(66) Of these the first-named is the most important, although the others are also worthy of attention. When the process of drawing is treated of it will be seen how necessary it is to have the fibres in a given sliver as nearly as possible one length. Unless this is the case the setting of the rollers becomes a difficult task, and much damage may arise. In twisting, also, the

short fibres, not having the same grip of the adjoining ones as those of greater length, are not properly twisted in, and the result is that a hairy "oozy" yarn is produced. The tendency in carding and combing, also, is to separate the short and long fibres and to eliminate the former. Thus a mixture of different varieties which are not of equal length is a practice which is prejudicial to good and economical work. It is absolutely necessary, if full economy is to be obtained, that care should be taken to mix only such staples as work well together, and this is the cardinal principle of mixing. Thus Orleans cotton and Hingunghat cotton mix very well, both having the same mean length. Mobile and Broach will also mix well, so far as length of staple is concerned, but the yarn produced is apt to be high coloured. But if, in addition to the length of the staple, other desirable properties are taken into consideration, it will be seen that cottons which would other-wise mix well are not usable on account of the difference in their spinning qualities or colour. Thus a harsh, wiry fibre like rough Peruvian and a soft, pliable one like Uplands, however well their length might agree, would make an unsuitable mixture, because the treatment which is absolutely essential in one case would be quite fatal in the other. It is therefore necessary to remember that the character of the fibre, as well as its length, is an essential item in mixing, and that the facility with which fibres will twist has an important bearing upon the subject. It is quite possible to strengthen a weak cotton by an admixture of a stronger one, and thus obtain a yarn which it would be impossible to produce cheaply enough in any other way. The colour of the cottons mixed is also important, as upon it depends the appearance of the finished yarn. Some cottons, like brown Egyptian and Broach, for instance, are deep coloured ; others, like Orleans, of a light shade. It is therefore undesirable, if a white thread is wanted, to use the higher coloured cottons, but if by judicious blending a shade can be obtained which is that desired, there can be no harm in using the higher coloured material. There is another point in which the colour

of the material is important, viz., whether it is to be used for twist or weft. A mixing which is to be spun into twist will be several shades darker than if it is spun into weft. The former, it may be explained, is spun with more turns per inch than the latter, and is technically "harder twisted." It is a singular fact that owing to this increase the colour of warp yarn is deeper. The reason for this is not far to seek, and is found in the varying reflection of the light from the surface of the yarn owing to the different disposition of the fibres. It is well known that the difference in shade depends on the number of rays reflected, and there is no doubt of this being the correct solution of the apparent puzzle just stated. It is therefore essential in mixing different brands of cotton to remember the purpose to which it is to be put. The element of price is, of course, an important one, and must not be neglected. Suppose, for instance, that 2,000lbs. of cotton is being prepared for spinning, and consists entirely of middling Orleans cotton at, say, 4½d. per lb. This will give a cost for the quantity named of £37 10s. Now let the yarn be spun from a mixture of middling Orleans and good Broach at, say, 3⅞d. per lb., in equal proportions. The mixing then will cost £34 17s. 11d., a net saving of £2 12s. 1d., or ·31d. per lb. Now, suppose this is applied to the case of a mill using 20,000lbs. per week, there is a weekly saving of £26 0s. 10d., which is a very considerable sum. There is, therefore, a great advantage to be gained from proper mixing, and nothing will be lost by a very careful study of the qualities and values of different grades of cotton. To ascertain the average length of staple, a good plan is to detach a tuft, reduce it to a manageable size, and then hold it down upon a rule divided into sixty-fourths of an inch. A knife or chisel is a good thing to hold the cotton by, and by removing the fibres gradually from each side the average length of the staple can be easily got. This method requires a little practice, but is soon mastered, and it is very valuable in enabling a judgment to be formed as to the propriety of mixing two fibres. By practice the staple can be ascertained

by gradually reducing a tuft of cotton by pulling it with one hand while held with the other until the length of individual fibres can be seen, and this is the most common course. The four rules for successful mixing are—

First.—Choose cottons of practically equal staple.

Second.—Mix strong harsh fibres with others a little weaker and softer for warp yarn, but only soft pliable ones for weft.

Third.—Select cottons of colours which, blended, produce the right shade when spun into twist or weft.

Fourth.—Take into account the price of the cottons mixed so as to arrive at an average value.

(67) Having determined the character of the mixing, the next thing is to produce it. It is customary to stack the mixed cottons in bins, and for this purpose a special room is generally provided. If the cotton is mixed by hand, a layer of about a foot thick is laid all over the floor of the bin or stack from one lot of bales. Upon this a second layer of the cotton to be mixed is laid, and this procedure is carried out until the stack is completed. In mixing by the aid of a bale breaker, the bales containing the various qualities to be mixed are opened and placed near the machine. A layer from each bale is taken in succession and placed upon the lattice feed apron of the machine, and is thus opened out at once. The machine delivers it on to a lattice, by which it is carried to an ascending double lattice, which in turn delivers it to other lattices running over the mixing bins. This arrangement is shown in Figs. 39 and 40, where A is the bale breaker, B the ascending lattice, and C the horizontal conveyer to the bins E. It will be seen that the cotton can be delivered at any point which may be desired. It is obvious that by a procedure of this kind a much more intimate mixture can be made of the various grades than is otherwise possible, and this is a matter of great moment. It is clear that, if any advantage is to be gained from mixing, the earlier the fibres are thoroughly diffused from the mass the better; and much of the work of the earlier machines is removed if this object is attained at this stage. It is very desirable that

a mixing should be made large enough to last several weeks, as in this way more regular spinning is obtained. To test the working qualities, a small stack of a few pounds should be made from the mixture proposed, be passed through the machines, and spun into yarn. In this way it can be ascertained whether any change is required before finally proceeding with the larger mixture. It is only necessary to say, in conclusion, that by means of the lattices used the cotton can be conveyed from place to place without handling, and these useful appliances can be made to run in any desired direction. It is often the custom to feed the cotton from the stack directly into some form of

FIG. 39.   J. N.

opening machine, but the trend of modern practice is in the opposite direction. There can be no doubt that the less the work of beating out lumps of cotton is thrown upon the opening machine, the more effectually it will perform its function of cleansing. If there is any virtue in the restoration of the cotton to an open fleecy condition, there can be little room to doubt that the earlier this happens the better. Now, in this respect, the use of a feed roller or table is of service, especially when combined with dust trunks. It is not desirable to use a bale breaker for this purpose, as the draft of the rollers is such that the cotton is merely broken up or

pulled into comparatively large lumps, and the full effect of the operation is not obtained. A porcupine roller of 15 or 18in. diameter is much preferable when revolving at a speed of from 800 to 1,000 revolutions per minute, and receiving the mixed cotton through the agency of a pair of feed rollers suitably speeded. The treatment thus given opens the cotton fairly well, and delivers it into the dust truck, or on to a lattice, in a moderately open or fleecy condition. Thus, even assuming that no further action takes place between the feed table and the opening machine, the material is in a much better condition than it would otherwise be, and the work thrown upon the opener is considerably reduced. This arrangement is shown in Fig. 39, where the cotton is taken from the bins and conveyed by the lattice F to the porcupine feed roller G, by which it is effectually opened. An arrangement of this kind actually carried out is shown in plan in Fig. 41. The bale breaker B delivers on to the lattice J, which in turn is arranged to deliver on to the three transverse lattices K, which convey the cotton to the mixing bins M. From these it is taken and placed on the feed lattices of

FIG. 40.

the porcupine feeds F, which deliver it into the dust trunks T, by means of which it is conveyed to the opening machines placed in the room below.

(68) Another form of feeding machine has of late years come into extensive use, and bids fair to supersede all others. This is what is known as the Automatic Hopper Feeder. It is an adaptation of a machine which has been long

FIG. 41.

in use in the woollen trade, where it has been instrumental in abolishing the practice of weighing the wool. It is well known in that connection in this country, but its adoption as an instrument for feeding cotton is the work of the machinists of the United States, from whence it was reintroduced into this country, by Messrs. John Hetherington and Sons. It may be said that all the various forms of this machine which are now made possess the same general characteristics, but that

which is illustrated in Fig. 42 has some additional points or interest. As there illustrated, it is made by Messrs. Howard and Bullough. It consists of a large hopper or receiver R, at the lower end of which is a travelling lattice apron A moving from right to left. At one side of the hopper, placed at an angle, is the apron B, which is formed of an endless canvas band, to which is secured transverse laths with spikes fixed in them. The cotton is fed into the hopper R, and the lattice A aids in bringing it up to the apron B, and within the range of

Fig. 42.

the pins, but as the hopper is usually kept well filled, the cotton is in contact with a large area of B. At the upper corner of the hopper a revolving drum is placed, consisting of a cylinder smoothly turned on its periphery, and having a number of holes bored in transverse rows parallel to its axis. Through these the points of pins can project, these being fixed in slides which terminate in a frame surrounding an eccentric C mounted on the shaft. Thus, as the drum revolves, the pins are alternately pushed out of and drawn into the cylinder. As the function

D

of the pins is to strip from the lattice B the surplus cotton, it may happen that some of it adheres to them. If this occurs their withdrawal in the manner described strips them of this cotton, which falls back into the hopper. The relative distance of the centre of the drum and the lattice is capable of adjustment, so as to permit a greater or lesser quantity of cotton to pass. Immediately behind the bend of the lattice B is a revolving spiked roller H, which is so placed that it receives any large pieces of cotton, and carries them round so that they can be acted on by the pins in the stripper E. In this way the lumps are drawn out, and the delivered fleece is evened. At the back of the apron B is a stripper E, which in this case is six-armed, the alternate arms being usually fitted with pins F and leather strips G. As its name indicates, this is employed to strip off the cotton from B and deliver it. In this specific instance the procedure is substantially that of scutching. The cotton is flung on to the grid K, thence over the longitudinal grid and dirt box L, on to cages coupled to an exhaust fan in the usual way. After this it is passed through the calender rollers shown, by which it is compressed and delivered, either on to a lattice apron or into an air trunk, as desired. In most cases, the cotton, when beaten off by the stripper, is simply passed through a pair of rollers, and is then delivered.

(69) There are many modifications of the details of the machine as thus described. Thus, in place of the evener C, Messrs. Taylor, Lang and Co. employ a second spiked lattice revolving at a slow rate, and having its teeth opposing those of the apron B. It is so set that from a wide space as the cotton enters, the distance between the teeth of the apron and those in B gradually diminishes until they nearly touch. It being essential that the rate of feed by B shall be as far as possible constant, it is desirable to keep the hopper constantly and uniformly charged with cotton, or failing this, to regulate the supply. Messrs. Dobson and Barlow use a patented arrangement by which an alteration in the height of the cotton is met by the regulation of the area of the inlet, thus ensuring a uniform delivery. By

Corrigan's patent, made by Messrs. Lord Bros., the machine is made so that the cotton is delivered when struck off by the stripper E into a box or reservoir, from which it is drawn by feed-rollers at the bottom and delivered on to a lattice. If the box is overfilled, a special lattice removes the overplus and returns it to the hopper, thus ensuring a regular delivery. In other cases, a piano feed regulator is fitted to the delivery end of the machine, and this is employed to regulate the velocity of the ascending apron B whenever a thin place occurs in the fleece as it is delivered. Most of these devices are intended to give an even fleece when delivered—that is, one in which the weight of successive yards is the same, and this has been the chief point round which controversy has raged. Although this is, in the opinion of the author, of subsidiary importance, yet it has a certain value, and may be discussed shortly. From what has been said, it will be seen that means are provided to even the delivery so as to ensure the production of a fleece of equal substance. There is one set of conditions under which it is contended it fails to do this. If the hopper is kept well filled with cotton it is generally agreed that the quantity carried forward is greater than when the hopper is partially empty, but this is a matter the importance of which may be greatly exaggerated. In saying this, care must be taken to avoid misunderstanding. It is not intended to convey the idea that it does not matter whether the hopper is at one time quite full and at another nearly empty. Any such procedure would inevitably entail a difference in the quantity of cotton taken up during the ascent of the apron. In addition to this, the density of the cotton as it is delivered is a factor which cannot be neglected. It is well known that this varies considerably according to the character of the bale or mixing, the compression being greater in some cases than in others. In other words, the volume of the cotton and its weight are not necessarily proportionate. So important is this matter that all makers lay stress upon the uniformity of the filling of the hopper, and, as previously said, in some cases special mechanism has been provided for the purpose.

It is, of course, highly desirable that at the earliest stage possible
the sheet or body of cotton presented to the action of the
opening beaters shall be as even as can be obtained, but it
must be remembered that at the worst the feed is as regular as
that obtained by any of the previously existing types of machines.
Owing to the character of the machine, it is obviously nearly
impossible to regulate the velocities of the three essential parts
which operate prior to or during the time in which the cotton is
being taken up, while on the other hand, a regulation subsequent
to its passage through the machine is attended with the difficulty
that a certain time must elapse between the formation of the
irregularity and its detection.   Regulation should precede
fleecing, and if this cannot be done, then it appears to be a pre-
ferable course to apply a regulator to the feed roller of the next
machine in which the beating of the cotton is conducted.   This
matter may be somewhat elaborated.   Suppose that it is desired
to obtain the necessary regulation of the velocity of the feed
lattice.   It is clear on a casual inspection that this cannot be
done until the sheet is fully formed, and it is equally clear that at
the time the thick or thin place is dealt with, exactly the reverse
formation of cotton may be occurring in the hopper.   Instead
therefore, of evening, the operation would be one of unevening.
This remark is, of course, subject to the limitation made by the
special contrivances previously described.   If, however, the
regulation be applied to the resultant fleece prior to subjecting it
to the action of the beater in the next machine, by varying the
velocity of the feed roller which is delivering it, then the same
result is substantially obtained.   This is the course adopted in
more than one case, and it is on the whole a satisfactory one.

   (70) The feed apron ought to be so driven that any chance
of slip is entirely avoided, and to ensure this, the largest sized
pulleys which can be conveniently arranged should be employed.
It is not desirable that the angle which the face of the apron
forms with the horizontal should be too obtuse, as otherwise the
tendency is to carry up too much cotton, and not to exercise
that tearing effect which is desired.   It will be easily under-

stood that the nearer the approach to a horizontal line the more readily is the cotton removed from the bin, while, if a vertical line were followed, the cotton would be torn away more slowly, and in less quantity than is desirable. If the face of the apron is disposed at an angle of 120 degrees relatively to the lattice forming the bottom of the bin, or, say, 30 degrees to a vertical line drawn from the front of the bottom pulley, good results both as to quantity and quality of work are obtained. The apron should be strong enough to avoid bagging, and, if necessary, should be sustained between the pulleys. All these points have an effect upon its carrying capacity, and the quantity of cotton which it will remove is to a large extent influenced by the shape and disposition of the needles fixed in the slats. The function of the evener is primarily, of course, to reduce the size of the lumps which are being carried over by the apron, and, in addition, to throw back such of them as are too large. It is clear that where pieces are firmly held by the spikes, the teeth of the evener will tend to tear them apart, and will inevitably have that result if they are of undue size. It is true that the pitch of the teeth of the evener is not such as it would be if it were intended at this point to effect an absolute reduction to small-sized pieces; but, at the same time, the operation is an important one, and should be duly considered. One of the essential features of the evener is that it shall deal with the cotton at a point where the apron is well supported, as otherwise the latter may yield and larger pieces pass than should. The importance of this factor will be recognised when the function of this particular part is considered. In the final stripping of the cotton, the work is done by the rapid revolution of a spiked drum or stripper, which beats off the cotton from the feed apron and delivers it. Here, also, it is necessary to note the desirability of removing the cotton at a point where there can be no yielding of the apron, so that the stripping shall be evenly effected. It is also worth noting that the rapidity of the rotation of the stripper—reaching 800 revolutions per minute—causes it to act as a beater, and leads to considerable dis-

integration of the pieces.   For this reason it is desirable at this
point to use bars and grids through which the dirt loosened by
the blow can readily fall.   The net result of the various devices
thus detailed is that the cotton is broken up effectually, and is
delivered in a fleecy or semi-fleecy condition in the form of a
thick sheet.   It is a subsidiary consequence of this treatment
that a large portion of the dirt is deposited at this point, and
that not alone in respect of the fleecing is the work of the
opener lessened, but it has less dirt to remove during the
operation.   It is obvious that the pins of a stripper having a
circumferential speed of 2,932 feet per minute will knock out
a good deal of dirt, especially when bars are provided to receive
and arrest the cotton.   The most important lesson to be derived
from a consideration of the hopper feeder is, however, that it is
possible to open cotton by means of a gentle combing action
as effectually as by the brutal treatment usually accorded to it.
It is not surprising to learn that one consequence of the
adoption of this machine, especially in its employment for
American cotton, is the reduction of the number of processes
of scutching by one, the intermediate scutcher having been
abolished where hopper feeders are used.

(71) It may, however, be pointed out that the establishment
of a fleece which is of even substance for its entire length is of
little value unless the distribution of the fleece in the width also
takes place.   The object of the piano feed in the scutcher, for
instance, is mainly to even the sheet of cotton so far as its
longitudinal substance is concerned.   When the sheet is formed
into a roll, as afterwards described, it is technically known
as a "lap."   But a lap should, when finally produced, be
even not only longitudinally but also transversely, and the
same thickness should exist at the edges as in the middle.
In short, there are two problems involved—one affecting
the feeding of a definite weight and substance in a definite
time, and the other the proper distribution of the cotton trans-
versely when fed.   In this respect, the arrangement of a hopper
feeder with cages beyond the stripper is likely to improve the

result, because, with perfectly working fans, the lateral distribution of the cotton is improved. Although it is now admitted that the use of the hopper feeder is attended by a saving of labour, and that the cotton is, on the whole, better prepared for subsequent treatment, there are many cases in which very effective results are obtained by the employment of other combinations. For instance, by such an arrangement as that illustrated in Fig. 43, the whole requirements of the case are met. In this arrangement the cotton is fed to a porcupine beater by a lattice apron, the velocity of which is controlled by a piano regulator, and is thence discharged into a dust trunk, then passing over a travelling dirt lattice, being finally discharged into the opener. The arrangement of exhaust fans is such that in addition to being well fed so far as the weight per yard is concerned, the lateral distribution also takes place properly. The test of an evenly-formed lap is the maintenance of the weight over its whole area, so that a square foot cut from it at any part, either in the centre or at the sides, will be of the same weight. This is the thing to be aimed at in scutching; and experience shows that it is not unattainable. If a lap, when finally presented to a carding engine, is of uneven substance across its width, it will follow that, as the feed in that machine is constant, more fibres will be presented to the carding surface at one point in its width than at another. This is as fatal to the best work as inequalities in the weight of successive yards of lap. Now it is obvious, that where laps of this character are desired the application of an automatic feeding machine can, in most cases, only partially produce the result. It must never be forgotten that the appliances for evening the cotton are far in excess of any used in wool spinning, and that the characters of the two fibres are widely different. Probably there has never been a machine which has been so widely accepted as inevitable as the hopper feed. Cost is an important matter now-a-days, and a machine which will deal with 35,000lbs. of cotton weekly without any specific attention plays an important part in that respect. It ought to be premised that the full advantage of a

hopper feed is only obtained when it is used in combination and the combination is a purely mechanical one.   An installation

FIG. 43.

inspected by the author was one in which the cotton was taken from the bale, passed through a bale breaker, taken by a lattice to the hopper of the machine, from which it was delivered by a

lattice to a porcupine feed, thence through a dust-trunk to the opener, finally emerging as a lap. Only one person was required for the whole of that service, although over 30,000lbs. of cotton were opened weekly. The economy of such a procedure is manifest, and this is only one instance of many equally serviceable combinations.

(72) The full benefit of the plan of stacking cotton and using a feeder is not derived, unless the feeder is combined with the opening machinery. It is well known that it is customary to place the opening and scutching machines in a different room to that in which mixing takes place, and that by the action of a fan the cotton can be conveyed within a tube or trunk B, Fig. 43, from one room to another. The dust trunk is ⌂ shaped, with the

FIG. 44

flat side down, for a part of its length, as at K, Fig. 41, and is not merely employed as a conduit, but fitted in the lower part of the ⌂ with fins or plates, against which the cotton strikes in its onward course and is temporarily retained. The effect of this arrestment is that the fibres receive a sudden check or shake, by means of which the intermingled dirt is shaken out to a certain extent and falls into the spaces below, from which it is periodically removed. In dealing with dust trunks it is essential to remember that they require regular cleaning, for if the dirt is allowed to accumulate until the spaces are full, it is drawn onward by the air current, and part of the object of the trunk is destroyed. In this respect the travelling self-cleaning lattice made by Messrs. Platt Brothers and Co., shown in Fig. 44 and in Fig. 43 at B, is of service. It consists of the employment of an endless

band K fitted with a number of blades or teeth, so as to form chambers or receptacles for the dirt or dust. The band is driven in the direction of the arrow Q by suitable gearing, thus delivering the collected dirt on to a flap P, which is balanced by the weighted lever shown. It will be seen that the direction of the traverse of the band K is in opposition to the air current, as indicated by the top arrow. It is essential that the whole of the joints of a trunk shall be smoothly made and air-tight. In the event of any projection occurring at the joints, cotton is apt to accumulate, more especially if there is an opening between the lengths, and the trunk becomes choked; while, if air finds entrance, the effect of the fan is partially destroyed, and the cotton travels too slowly and collects. It is indeed often found that after the covers have been opened for the removal of the droppings the pneumatic action is not perfectly restored until enough dirt has again fallen and sealed up the joints made by the cover and the edges of the trunk. The dust trunk, properly used, plays an important part in the economy of a cotton mill, and it is obvious that this early removal of a large proportion of the dirt reduces the work required in subsequent stages, and materially enhances the possibility of adequate cleaning in the opener and scutcher.

(73) Having got the cotton into the dust trunk, it is in modern practice delivered into the opening machine. There are three principal forms of this machine in general use—a modified willow, the porcupine, and the Crighton—which may be distinguished from each other by the construction and position of the beater cylinder. In all of these the cotton is treated by rapid blows from revolving beater arms which fling it against specially prepared surfaces. The blow given should be quick and clean, so as to detach the fibres from each other without rupturing them, and the grids against which they are flung must be constructed so as to give the best results by permitting the easy fall of dirt, etc., during the period of arrest of the fibres. Many elements go to make up a successful opening machine. The manner in which the cotton is introduced, the construction,

size, and speed of the beaters, are all essential features construc-
tively.   The cleansing power of a machine depends mainly on
two points, viz., the quantity of cotton passed into it in a given
time and the shape and position of the projections on the dirt
grid.   Upon these depends the commercial success of the
machine—that is, whether it can be used so as to restore the
material to its natural open fleecy condition without damaging
it, and at the same time enable the various impurities to be
easily dropped.

(74) The machine illustrated in Fig. 45 is a modification of
the willow as made by Messrs. Taylor, Lang and Co. It consists
of a feed apron Q which conveys the cotton into the sphere of
two rollers which thrust it into the path of teeth on the surface

FIG. 45.

of the cylinder O.   This revolves in the direction shown by the
arrow, striking the cotton upwards and flinging it against the
projecting teeth on the inside of the case P.   As shown at H, a
grid is fixed through which the dirt is ejected by the rapid
revolution of the cylinder O.   The cotton is caused to strike
against the bars of the grid H and is thus scraped or cleaned.
By the influence of an air current created by a fan placed below
the two dust cages S S¹ the cotton is drawn over the two grids
R and M, and when it reaches the cages is formed into a sheet
in a way which will be more particularly described at a little
later stage.   It is taken from the dust cages through the two
small rollers shown, thence through the calender rollers T, and is
rolled up into a lap like L¹ at the point L.   There is a large

cleaning area in this machine, and it is very suitable for cottons
of good staple.   A machine somewhat similar in principle is

illustrated in Fig. 46, being
made by Messrs. Dobson and
Barlow. It consists of a cylin-
der, the surface of which is
fitted with a number of teeth
placed in rows a few inches
apart. The cotton is fed along
the lattice table L, and is
delivered to the cylinder by
means of a feed roller disposed
above a pedal nose by which
the rate of feed is regulated as
afterwards described in dealing
with the scutcher.   As the
cotton is thrust past the feed
roller the teeth on the cylinder
strike it and pitch it against
a circular grid K nearly sur-
rounding the cylinder.   This
type of machine, as previously
remarked, is constructed so as
to strike the cotton upwards
and not downwards, it being
urged for this practice that less
damage is caused to it than
when it is struck in the ordinary
way.   The data for this claim
appear to the author to be
somewhat unconvincing, but
there is no doubt that with
certain varieties of cotton the
work is as well done as by any
other type.   The area of the
grid K is large, and provides

Fig. 46.

an ample cleaning service, and to this feature may be attributed the good cleaning property of the machine. After leaving the grid K the material passes on to a grid U, which is disposed at such an angle that the material passes readily over it while a great part of the dirt is deposited at this point. After leaving the grid U the cotton passes to the scutching machine, of which a description will be given later.

FIG 47.

(75) The porcupine beating cylinder is usually placed just beyond the exit of the dust trunks, and is made in one of two forms. That shown in Fig. 47 is used for long-stapled cotton, and consists of a number of beater blades secured to discs, which

FIG 48.

in turn are fixed on a central shaft with which they revolve. The blades are constructed so as to be easily reversed when worn. The form shown in Fig. 48 is used for short-stapled cotton, like Indian, and is made in a similar manner to the bale-breaker rollers, of a number of discs securely bolted and fitted together

so that they can be easily replaced. Porcupine beaters are made from 18 to 24 inches diameter, and revolve from 800 to 1,200 times per minute. They are enclosed within a suitable case, and a dirt grid is fitted below the cylinder, so as to clean the cotton by the checks given to its onward progress.

(76) The Crighton opener is of different construction to either of the two just described. It is shown in section in

FIG. 49.

Fig. 49, and consists of a conical beater constructed either with a number of strong discs secured to the shaft or in lieu of discs, two arms in one piece with, and radiating from, a central boss are used, but in either case blades D are secured to them. The length across the points of the blades increases from 18 to 33 inches, the smallest diameter being at the bottom. The beater

arms are surrounded by a case or grid, which is also conical, in exact accordance with the increase in the diameter of the beaters. The grids rest upon a truncated conical dish into which the cotton is fed by the tube C. The latter at its exit into the dish is given a slightly upward direction so as to guide the cotton upwards, and the dish is corrugated on its inner surface. The shaft of the beater is sustained by a footstep E, which is constructed so that the foot of the shaft constantly revolves in some lubricant. The upper end is kept in position by a long bearing A, and the driving pulley is placed above this point. Immediately below the orifice of the tube C a fan is placed, when the opener is combined with a feed-table and dust trunk, so that the suction of the cotton to that point is independent of that which carries it through and out of the machine. The blades D are now usually made reversible, so that they can be easily turned round when worn at one end.

(77) Before passing on to say anything of the action of the beater, it is worth while specially noting that in most cases it is now the custom to provide a fan at the very commencement of the machine, the function of which is to draw the cotton onward to that point and deliver it within the range of action of the beater. From this action of exhaustion or suction the machine has been sometimes called the " exhaust opener," a name which is now applied to many types in which this action occurs. The reason for this procedure is obvious. The exhaust fan placed at this point brings the cotton gently within the action of the beater, which is thus enabled to strike it with considerable force. Assuming the fan to be placed beyond the beater, it is clear that to convey the cotton into the sphere of its influence, the air current must be also strong enough to draw the cotton past the beater and place it upon the cage, if a lap is to be formed, or to eject it, if not. A little reflection will show that in this case there will be a chance of the material being drawn over and past the beater without receiving that amount of treatment which is essential to proper cleaning. Both theory and practice justify the fan being placed in the position named,

and it is, as was remarked, practically universal. Referring to Fig. 50, which is a view of a combined porcupine feed and exhaust opener as arranged by Messrs. Lord Bros., two views

FIG. 50.

are given, one a sectional elevation of the combined machine, and the other a plan of it in combination with a porcupine feeding machine. The lattice feed A delivers the cotton to the porcupine roller C by which it is passed into the dust trunks D. These terminate in the tube H leading into the opener F. At the entrance to the delivery tube of F two flap valves Q are placed. The opener is of the Crighton type, the beating blades E being fixed to malleable iron arms L fastened to the shaft. At the foot of the vertical shaft within the bearing O a loose washer P is placed, this being free to rotate with the pressure of the shaft, thus reducing the friction. At each side of the exit of the tube fans N are placed, which can be given a sideward adjustment in order to lay the opened cotton evenly upon the dust cages T. Before it reaches the latter it passes over grids R, and after leaving T the fleece is beaten by means of the scutching beater W which flings the cotton upon a second grid, after which it is formed again into a sheet by the cages S, being afterwards rolled into a lap. The course of the cotton is clearly indicated throughout by the arrows. The arrangement forms a good combination, and it will be noticed that by means of a stop rod M, actuated from the setting-on handle of the lap machine when the latter is stopped for any purpose, the supply of cotton to the opener is checked. This arrangement can be extended so as to shut off the supply of cotton to the dust trunks by stopping the porcupine roller, and where this is done it is necessary to time the operations so that no blank places shall occur in the feed, or too great an accumulation of cotton take place in the trunks.

(78) The cotton when brought within the range of action of the beaters, is struck by the arms or blades and flung against the grids, through the interstices in which much of the dirt is ejected. In connection with this part of the subject there are two or three of the mechanical details which may be noted. These are—the shape of the beater blades, the setting of the grids, and the construction of the latter. For most varieties of cotton—indeed, almost without exception—when it is struck

loosely, the flat beater blade, such as is shown in Fig. 47, is preferable. It strikes the cotton fully and with considerable force, and it can, moreover, be easily reversed when worn. It should always be remembered that it is bad practice to strike cotton with a blade that is too dull to give it a sharp blow, and that the risk of damage is much increased if the blade is shaped so as to crush the fibres. For very short stapled cotton, more especially if it is previously formed into a sheet, the porcupine beater shown in Fig. 48 can be advantageously employed.

(79) With reference to the setting of the dirt grids, there is necessarily a different procedure with the various types of machines. The Crighton beater, being placed vertically and being conical in shape, has similarly shaped dirt grids surrounding it. These grids are made with raised surfaces, against the face of which the cotton strikes, and between each pair of these an opening is made through which the dirt can be easily ejected. The distance from the points of the blades and the inner surface of the grids should not be too great, as, in that case, much of the cotton will be drawn upwards by the air current without being beaten. On the other hand, if the space be too far reduced, the cotton is likely to be crushed and damaged, thus producing considerable waste. A space of about $\frac{3}{8}$in. is, in most cases, ample, and this should be preserved. The dirt bars behind a porcupine beater do not require setting specially, otherwise than to fix them so as to subject the cotton to checks, and thus permit the dirt to fall freely without running the risk of fibre being passed.

(80) The construction of the Crighton grid has been much improved recently, and the form latterly adopted by Messrs. Crighton and Sons (sections of which are given in Figs. 51 and 52) possesses many advantages. It is so shaped that pockets are formed in which the cotton periodically rests until the beater arm has passed, after which it is drawn out by the air suction thus induced. The brief periods of rest thus given allow the dirt to fall freely, and the cleaning is more effective. The velocity of the air-current should be regulated so as to provide

sufficient power to carry the cotton through the beater chamber in the Crighton, and if a combined machine is used, place it on the cages. This part of the subject will be again reverted to at

FIG. 51.

a later stage. The velocity of the beater in a Crighton machine varies from 520 revolutions per minute when used for American cotton to about 720 revolutions for Indian. All other things

FIG. 52.

being equal, the longer the staple cleaned the slower the revolution of the beater. The porcupine cylinder can be run at a velocity of about 800 revolutions per minute with advantage with most lengths of staple when 18 inches diameter.

(81) It is the custom to form the opened cotton into a "lap" at as early a stage as possible, instead of ejecting it loosely into the room. There are a number of advantages in this course, especially when the machine is combined with a scutching machine. Whether this course be followed or not there is much to be gained by forming a lap, because however uneven in weight that may be, it is not likely to be so variable as a mass of loose cotton placed on a lattice. As will be shown hereafter, the earlier an evenly weighted feed is obtained the better the chances of obtaining laps which are equal in substance. In addition to this there are all the advantages arising from easier handling, which reduces the cost for labour to a considerable extent.

(82) The scutching machine is designed to provide means by which the removal of the dirt and sand is still further facilitated, and if properly constructed and worked there should practically be nothing left for the carding engine to remove but nep, short fibre, and motes. A sectional elevation of the Lord machine is given in Fig. 53, and some detailed drawings will be afterwards referred to. It is constructed with a revolving beater A, which is enclosed within a case, and is driven from a counter shaft at a speed of about 1,200 revolutions. The beater consists of solid arms, forged with a central boss, which is bored to fit the shaft and is secured fixed thereon. There may be either two or three arms, but whatever may be the construction in this respect they are accurately made and smoothly finished. Upon feet formed on the ends of the arms blades of a special section—shaped so as to present a comparatively sharp beating edge to the fibre— are secured. The beater is most carefully balanced both before and after the attachment of the blades, and it is highly important that this should be so, as otherwise the velocity given to the beater would set up considerable vibration, which is detrimental to good work.

(83) The cotton is fed, in all cases in which laps have been previously formed, from two to four laps F, which rest upon a lattice apron G, by which they are unrolled. The lap end is

FIG. 53.

passed between a feed roller suitably weighted and the nose of
a pedal lever B, to which reference will be made a little later.
The cotton is thus thrust into the range of action of the beater,
and is struck by it, so that tufts of the fibres are flung upon the
grid H, which surrounds the beater for a certain portion of its
path.   After leaving the bars or grid H, the cotton passes over
a grid consisting of a number of longitudinal bars with spaces
between them, and is conveyed to the dust cages J J^1.   These
are drums, the surfaces of which are formed either of wire
netting or perforated sheet zinc, and the ends of which open
into vertical dust trunks, from which the air is exhausted by a

FIG. 54.

fan I, placed in the position shown.   Care is taken in con-
structing and fixing the cages that no air can be drawn out
between their ends and the framing, and one method is well
arranged for this purpose.   The frame-work is recessed and the
cage fitted into it, a guard ring being fixed so as to make a perfect
joint. The cages J revolve loosely upon fixed shafts, being driven
by sleeves on which the wheels are fixed, and segmental damper
plates N are sometimes fitted within them, as shown in Fig. 54.
These dampers can be fastened in position on the shaft for the pur-
pose afterwards referred to.   The cotton is laid upon the cages in

uch a way that when taken off it is in the form of a fleece or sheet,
which is then passed between two smooth " calender " rollers K,
by which it is somewhat compressed.   After undergoing this
treatment it is rolled up into a " lap " M, as shown, being wound
on to a round bar or " lap rod."   The ends of this are fitted
under a bracket formed at the upper end of a vertical bar T,
on which is a rack with which the pinion S engages.   The latter
forms part of a train of gearing shown in the drawing, and as

Fig. 55.

soon as the right size of lap is made—that is, when a definite
number of yards is wound—a catch is released and the handle
U falls, thus transferring the belt from the fast to the loose
pulley and stopping the machine.

(84) The feed motion is shown in side elevation, plan, and
end view in Fig. 55.   The feed roller D is placed so as to
rotate above the nose of the " pedal " lever B.   The latter is
loosely pivoted on a shaft, or, as is much better, upon a knife-
edged fulcrum, and has at its tail end a pendant lever C hung

upon it.   The pedal noses extend across the whole width of the
machine, as shown in the end view in Fig. 56, and partially in
the plan view in Fig. 55.   The lower ends of the pendant levers
pass through a box or frame F, and are slightly swelled as shown
at H.   Between each pair a friction roller G is placed, the
axle of each roller being borne by and revolving in bars

FIG. 56.

sliding in grooves formed in the box F.   The last of
the series of pendants C¹ is formed with a slot to which
is coupled, as shown in Fig. 56, a lever O forming the first of a
series which are coupled to sectors E (Fig. 55), which control
the movement of a strap N upon the cones D, D¹.   When a
pendant lever rises, which it does when the nose B of the pedal
is depressed owing to the passage of a thick piece of cotton

between the feed roller and pedal, the swelled portion H of the pendant being unable to pass through the space between the two adjoining bowls, sets up a pressure which causes the bars holding the bowls to move and the whole series of pendants to swing in one direction. This movement is communicated to the strap N in the way described, and it is thus moved on the cones D, D^1. When the pendant falls, which it does as soon as the pressure is relieved, the pedal nose again rises, and the weight of the various parts again restores the strap to its normal position. In the event of a thin place occurring the action is the reverse of that described. The cone D^1 is driven as afterwards shown, and drives D by the strap N. Upon the upper end of the shaft of D is a worm P which engages with a worm wheel R on the axis of the feed roller. Thus any variation in the position of the strap caused as described, reduces or accelerates the velocity of D, and rotates the feed roller at a proportionately slower or quicker speed. It is not enough that the speed shall be varied, it is also necessary that it shall be proportionate to the difference in the substance of the material; that is to say, that the length of lap delivered by the feed rollers must be in inverse proportion to its thickness. This substantially results, if graphically described, in a curve which is purely hyperbolic in outline. The same problem arises in connection with the roving frame, and is there fully treated. The governing factor in the case of a scutching frame is the constant diameter of the feed roller, one revolution of which delivers at any given speed a definite length of lap. The starting point is therefore the normal thickness of the lap, and the lap, when thicker or thinner, bears a certain ratio to it. Thus, if the lap be normally a half-inch thick a variation of one-sixteenth will be equivalent to establishing a ratio of 9:8, so that the roller requires to travel $\frac{8}{9}$ of its former speed, which is the same as saying that the driven cone must move at that relative velocity. As the effect of any movement of the pedal lever, whether up or down, on the strap guide can be calculated, it follows that the range of velocities can be easily arrived at. If the calculation be made in this way, it will be seen that the form

of cone required to give accurate results is one with a hyperbolic
profile, but it is not necessary to give here a demonstration
which is practically that given at greater length in connection
with the roving frame.

(85) There are two chief methods of construction adopted in
arranging the pedal levers and feed roller.   The one is to use a
single roller, which rotates above the nose of the pedal and feeds

FIG. 57.

the cotton by the pressure exerted on it as it passes between them.
The other plan is to feed the cotton by a combination of a roller
arranged as described and a second pair of rollers rotating between
the nose of the pedal and the beater.   These different methods
are shown respectively in Figs. 57 and 58.   It is the practice for
short stapled cotton to use the former, and with longer staples
the latter, the theory being that the cotton being struck round a

FIG. 58.

less acute surface is less liable to damage.   There is ample
justification for the theory, but not so much for the practice.
The whole thing resolves itself into a question of expediency;
and it must be remembered that this is not a case where, as in
the carding engine, the fibres are removed in groups by the
action of a combing tooth, but one where they are struck off
across the whole face by a transverse bar.   It is, therefore,

necessary that the blow of the beater blade shall be able to strike off the cotton without breaking it, and the question of the distance from the point at which the lap is held and that at which it is struck becomes of importance.   If the distance between these points is too great, the blow of the beater first bends down the lap end and then strikes off the fibres.   It is obvious that unless the cotton is removed regularly in this way there exists a danger in the second blow of some bruising of the material.   It is the practice of many makers to shape the nose of the pedal in such a way that the necessary rounded surface for the deflection of the fibres, which must take place in any event, is provided without using the three-roller principle. Accordingly in Fig. 55 two forms of pedal nose are shown which possess the characteristics necessary for different staples of cotton.   A careful examination of the profiles of the two types will show that—the staple of the cotton being in each case equal—it will be bent round the bottom roller when struck from a pair, as in Fig. 58.   When, as in Fig. 55, it is struck from a pedal nose, it is quite clear that the end of the lap, although projecting from the nip of the roller as far as in the other case, is sustained by the pedal in a nearly horizontal position, and consequently receives the blow of the beater blade more squarely.   There is thus no possibility of the crushing action which has been mentioned, and, on the whole, the arrangement shown in Fig. 55 meets all the requirements of the case.   It will be easily understood that the distance between the path of the beater blade and the edge of the roller or pedal nose is comparatively small, so that if a beater is not well balanced, and vibrates at all, it will tend to crush the fibres between the beater blade and roller or pedal.   This furnishes another reason for care in the construction of the beater, and for careful attention to the condition of the bearings.   It is also essential that the setting of the pedal nose or the feed rollers relatively to the beater shall be accurately made.   Unless this is attended to, the cotton is sure to be damaged.   If the distance is too great the fibres are struck off in pieces, which form

into stringy lumps, or "cat tails," as they are sometimes called. If it is too small, the fibres will be crushed and broken.

(86) There is now an almost universal practice in connection with the bowls used in the pedal motion, which consists in the use of two or three bowls between each pair of pendants instead of one. The reason for this practice is to take off the

FIG. 59.

friction which naturally arises when one bowl only is used, and adjoining pendants are moving in opposite directions simultaneously. In Figs. 59 and 60 two alternative methods are illustrated, the three-bowl system used being simple and effective, and it will be noticed that one of the pendants has a

FIG. 60.

special rib cast on it to engage with the small bowls. The use of three bowls, U, V, U, as in Fig. 61, fixed so as not to rub against each other, has the same effect.

(87) It is absolutely imperative to keep the whole of the parts of the regulator quite clean. The custom of using knife-edged fulcrums renders it necessary to see that no fly collects on or about them, and every joint wants the most careful attention to

ensure that it is kept free and unclogged. The bowls should be removed frequently, as often as once a week, and well treated with black lead, being at the same time freed from everything

FIG. 61.

likely to impede their rotation, the boxes being cleaned at the same time. A modification of the piano regulator, as made by Messrs. Asa Lees and Co., Limited, is shown in Figs. 62 and 63. The pedals E are hinged at one end, and rest upon vertical

FIG. 62.

rods J, the lower ends of which rest on the extremities of the balanced plates B. Each of these is suspended on a larger plate C, of similar construction, which in turn rests on the extremity of a plate D. The latter is suspended by its centre from a

lever F, which is fulcrumed on a knife edge at H. The lever F
is coupled in the manner shown to the strap guide lever I, which
is moved by means of the horizontal bar shown, sliding upon
guide runners. The cones A A¹ are placed horizontally, the
advantage claimed for this position being that the strap has a
much easier motion along the cones than is the case when the
latter are vertical. It will be observed that the whole of the
balanced plates are in equilibrium, and are suspended on the end
of the lever F, the arrangement being of the same character
mechanically as the steelyard. Thus a slight movement of one

FIG. 63.

of the smaller plates B is multiplied before it acts upon the
lever F, and the regulation of the strap is thus rendered more
sensitive.

(88) There is some difference of opinion with regard to the
employment of two or three winged beaters. The former is
more easily made and balanced, and is ordinarily about 14in.
diameter. The three-winged beater is made 16in. to 18in.
diameter, and is revolved at a slower rate than the two-
winged. The respective velocities are 900 to 1,000 revolutions,
and 1,200 to 1,500 revolutions. Thus the two-winged beater
gives a sharper blow, leaves the cotton more quickly, and is not

so liable to vibrate.   For these, among other reasons, it is
preferable, and gives quite as regular a blow as the three-winged
type.   It has been argued with some plausibility that the con-
struction of the three-bladed beater is such that its centre of
gyration is further from the centre of the shaft, and that a
heavier blow is thus given ; but it is admitted that it is necessary
to minimise this blow by a reduction of the speed of the beater.
These propositions are contradictory, and are founded on a
misapprehension of the necessary conditions.   It is eminently
desirable that the blow given should be sharp and light rather
than slow and heavy, and that beater which best meets this
requirement is the best.   It is a question not only of the
character of the blow, but of the number of times the cotton is
struck in every inch delivered.   This is a matter of some
importance, and immense variations exist in practice.   Usually
cotton of average staple is struck about 50 blows in each inch
delivered, but records exist of double that number being given in
finisher machines.   No empirical rule can be stated, but as this
is a point which is often lost sight of, it behoves every one
practically engaged in spinning to bear it in mind and closely
observe the result on the cotton.

(89) When a two-winged beater is revolved at a velocity from
1,200 to 1,500 per minute, the blow given to the cotton is
sharp, regular, and clean.   It is essential that the bearings of
the beater shaft be kept in good condition, and the beater
blades, which are sometimes made so as to be readily reversed,
should be kept with a good edge, for the reasons given in dealing
with the opening machine.   As the blow given by the scutching
machine beater is transversely of the fibres, it is essential that
it should neither be given by a blade which will cut the fibres
nor by one which will crush them, and care must therefore be
taken to avoid either of these defects.   The setting of the feed
rollers and the construction of the pedal nose both bear upon
this subject, and care should be taken to see that these are set
correctly.   The same rule holds good as in the case of the dish
feed plate in a carding engine, and the correct setting depends

practically upon the length of staple being scutched. In every case the avoidance of a sharp angular surface over which the cotton can be bent is desirable, but it is possible to use a much more abrupt surface in dealing with a cotton with such a short staple as Indian than it would be if Egyptian or American of the better qualities were being used.

(90) The setting of the dirt bars below the beater is a matter of importance. The earlier of the series, as shown in Fig. 64 at C, should approach the path of the beater more closely than those further round, as at D. The arrangement shown in Fig. 64 is that adopted by Messrs. Howard and Bullough, the position of the bars and of the spaces between them being regulated by the handle E. At first the cotton requires to be arrested quickly, so that it receives a shock which frees the dirt and sand. The bars should subsequently subject the cotton to a scraping action, for which reason the angle presented to the cotton by the face of the bar should become less acute, so that the cotton can roll over the bars. In this way many of the motes and a good deal of leaf are removed. The space between each pair of bars should in a similar manner be graduated, as there is less dirt to fall at the last than at the first of the series. The exact setting of the bars cannot be empirically stated, as this is a matter of practice ; but if the earlier bars are set with their upper forward edge rather in advance of a radial line drawn from the centre of the beater to the lower edge, and this angle gradually reduced until the last of the set has this edge a little behind the radial line, an approximately correct setting is obtained. When dirty cotton is being scutched, an opening of one-eighth inch is permissible between the bars. It is perhaps needful to say that the edges of the bars should be kept sharp and clean.

(91) It is now necessary to deal with the question of the air current and its proper regulation, and in connection with this question will come a series of others of more or less importance. The problem of the regulation of the current of air in a scutching room is a most important one, and its proper solution depends

upon such a number of points that constant watchfulness is wanted both in laying down and working the machines. Broadly stated, the principle underlying this subject is that such a balance of pressure must be established that only sufficient

Fig. 64.

suction is set up to draw the cotton evenly upon the cages. For this purpose, large fans running slowly are better than small fans running at a high velocity. The propulsion given by the beater is sufficient to throw the cotton forward to the cages, and

H

all that the fan is required to do is to attach it to the surface of the cage. The efficiency of a large fan for the removal of a given volume of air is much greater than that of a small fan. The importance of this element is found in the fact that an excessive current of air would prevent the falling of the dirt through the grids, the air, which is confined in the chamber below the grids, being quiescent, and therefore in a good condition to permit the easy fall of the dirt. It is therefore advisable to leave an inlet for the air below the feed rollers, so that a current can be created by the rotation of the beater. The American custom of admitting air by the beater shaft—which is made hollow for the purpose—does not appear to the author to possess many advantages, as the air is liable to enter at a point and in a manner which is not calculated to attain the object aimed at.

(92) There are a number of important considerations to be borne in mind in arranging the air passages leading from the blowing-room to the open air. It is not unusual to find the air discharged into a passage or flue in which there are several sharp turns, each of which offers an obstruction to the passage of the air and increases the friction. An instance coming under the personal observation of the author may be cited. The scutching machines were placed longitudinally of the room and the air was discharged into flues running in that direction. These flues terminated in a flue at a right angle to them, the second flue being carried a short distance—in fact, the width of the room—afterwards discharging into a third one at right angles to it but parallel to the first. The third flue ran the whole length of one side of the room and terminated in the upcast flue, by which the air was discharged into the atmosphere. Although there are worse schemes in existence than this, there are not many. It is quite evident that for some reason or other the machines are wrongly placed, because it would have been quite easy by reversing them to have avoided two of the bends, and to have carried the flues from the scutching machine into the side flue by a curved passage.

(93) This case has been cited because it is by no means uncommon. Each of the corners formed is, in plain terms, a trap for the accumulation of dirt and fly, and a cause of obstruction to the air. It is often a source of annoyance and complaint that laps are uneven in substance, although the mechanism is in perfect order. In the majority of cases the cause will be found in the construction and condition of the flues. Great care should be taken to keep these clean, and in building them easy curves and ample areas should be substituted for sharp angles and contracted sections. This is of the more importance if the plan is adopted of having a slow velocity of air current, as the effect of an obstruction is proportionately greater. The area of the dust flues should always be a little in excess of the combined areas of the fan outlets. Thus, if the latter have an area of 300 square inches, an area of 310 square inches is about the right one for the dust flue.

(94) Sometimes a lap has a ragged, uneven, or thin edge, the cause of which is difficult to discover. It may be fairly presumed either that one of the fans is not working properly, which may arise from an obstruction such as that named, or that the dampers—which are fitted to the cages—are not properly set. In either case the effect is that the cotton is drawn on to one side of the cage only. This fault may also arise from a back pressure set up when the wind is blowing in a certain direction if the outlet is not perfectly free to discharge, or is subjected to down draughts. It is absolutely imperative that the closest attention be given to this point, and instances are not rare where a slight alteration of the size, construction, or direction of the flues has resulted in making a scutching machine work admirably where previously it had been impossible to get good work. The system of gradually diminishing the width of the machines is not without its advantages. Thus, if a lap 45 inches is formed at the opener, it will be fed to a machine, say 42 inches wide on the cage, and the laps then made to a 40 inch machine. In this way good " selvedges " are obtained, but these can be got if the draught is arranged so as to draw the cotton equally across the whole face of the cage.

(95) Sometimes laps lick on the cages and afterwards split. When one cage only was used this fault was most rare, the reason being that there was only one surface on which it was drawn.   At present the cotton is drawn on both the upper cage J and the lower cage J^1, and as a result the laps sometimes divide when unrolled.   The cause of this is undoubtedly that the air current is strong enough to cause the attachment of the cotton to both cages equally.   The remedy is obvious, viz., to ensure that the draught is so regulated that the suction is principally through the top cage, or, at any rate, that the preponderance is there found.   This is very often a structural defect, and machines are made in which the tendency to split appears to be inherent, while there are others where it is practically absent.   As shown in Fig. 53, the top cage J is of larger diameter than the bottom one, and naturally presents a larger area than the latter, through which the air is drawn.   This results in the deposition of the cotton on the top cage as a single sheet, the function of the lower cage being thus reduced to aiding in the removal of any dust which might be loose upon the surface of the cotton.   The top cages are often fitted with dampers N (Fig. 54), which can be utilised to close the holes on one side or over a portion of their surface, so that the point where the draught exercises its influence can be accurately regulated. This is a matter of great importance and requires attending to. This formation of a divided sheet is aided by any irregularity in the proper relative speed of the beater and feed roller, and the latter is a fruitful source of uneven laps—that is, laps in which the weight of a yard varies in different portions.   The scutching-room should be kept dry and at a temperature of about 75° F., as any excessive moisture in the cotton will cause licking, and so produce a faulty or split lap.

(96) In the general description of the machine which was given at an earlier stage, it was said that the lap was formed after the fleece left the cages J, and it is desirable that the exact action should be followed.   In Fig. 65, the method of weighting the calender rolls is shown.   On the axle, and at each side of the

upper roller K, a saddle is fitted, and upon a projecting nipple
of this the lever K^2 presses. This lever is connected by a link
V^1 with a weighted lever V which is fulcrumed at V^2, the
arrangement being clearly shown in the drawing. If, as is
sometimes the case, four calender rollers are used, a similar
arrangement is adopted, except that the weight is applied by saddles
coupled by two rods to a corresponding cross bar below. From
the cross bar the link connecting it to the weighted lever is
suspended. When four rollers are used the fleece is taken

FIG. 65.

first through the nip of the two top rollers, round the second,
between the second and third, thence round the latter, between
it and the bottom roller, from whence it passes on to the lap
rod. In this way there is a considerable pressure put upon the
lap, which is thus consolidated sufficiently to enable it to resist
rupture when being unrolled. After passing the calender rolls,
the sheet is wound on the lap rod, which may either be solid or

a tube mounted on a solid rod, the latter being preferable, as it can be left in the lap and thus facilitates its being moved about, or stored till needed. The lap tube is the width of the lap, and when the latter is put upon the carding engine a fresh rod can be put in, the lap rods always projecting sufficiently to enable them to come into contact with the brackets on the scutching machine or carding engine at the feed end. The lap rod rests on the two rollers L L¹, the rotation of which winds on the fleece.

Fig. 66.

Referring now to Fig. 66, the lap rod M¹ has at each end a roller T¹ held in the head of the bar T pressing on it. T is formed with a rack on its inner edge, with which the pinion S engages. By means of the gearing shown in dotted lines, S is connected with the brake pulley S¹, against which the brake block S² presses. In some cases a strap has been used instead of the block, but the action is the same. The block S² is kept con-

tinually pressed against the pulley S^1 by the weighted lever W fulcrumed at W^1.   A foot lever X fulcrumed at X^1 is so arranged that by pressing on it with the foot it raises the weighted end of W, and so relieves the brake.   It is evident that as the bar T has to rise against the pressure of the brake, it will do so with difficulty, and will put a considerable pressure on the lap.   The resistance offered depends upon the total friction of the brake pulley, the weight exerted on the brake block, and the leverage of the gearing.   By means of a stop pin fixed in one of the wheels, a catch which supports the setting-on lever U (Fig. 53) is released, and the latter falls, thus transferring the strap to the loose pulley and stopping the machine.   This trip pin can be adjusted to knock off at any point, thus giving any length of lap.   When the machine has stopped, the attendant relieves the weight on the brake, so permitting the bar T to be quite free.   Owing to the pressure which has been exerted on the lap, it expands a little at first.   After the full lap is removed, the lap rod is placed in position to form a new lap, the bar T falls on to it, the lap is drawn under the rod, and the setting-on lever U raised, thus restoring all the parts to position and restarting the machine.

(97) In dealing with the scutching machine, it is desirable tc say a few words about the speeds of the various parts, and for this reason the diagram given in Fig. 67 has been prepared. By its aid it will be possible to show how the relative velocities of the various parts of the machine are obtained, and the trains of gearing, employed for the purpose, can be clearly followed. It is also useful to enable the changes, which it is necessary to make when it is desired to vary the weight or substance of the lap, to be clearly comprehended.   The sketch given is a representation of the gearing of a single scutching machine, as made by Messrs. Lord Brothers.   In this, as in most others, the feed and lap parts of the machine are, to all intents and purposes, independent, although the necessary driving for each is obtained from the same point.   It is, however, as will be shown, quite possible to obtain the necessary regulation of one part without interfering with the train of gearing driving the other ; or, if

desired, both can be regulated simultaneously. The pulley A is fixed on the beater shaft, as is also the pulley F, which is the key to all the movements of the machine, and drives by means of a strap the pulley F^1 fastened on an intermediate shaft. From this shaft the two portions of the machine are driven, the feed part by the strap driving the feed cone D^1 and the lap part by the strap driving the pulley H, from which all the rest of the gearing of the lap end obtains its motion. The spindle of the cone D^1 has fixed on it a pulley G^1

FIG. 67.

which is driven from the pulley G on the intermediate shaft. The cone D^1 drives the cone D by the usual strap, and at the upper end the spindle of D has a worm P fixed which drives the worm wheel R fastened on the feed roller spindle. By means of the wheels E and E^1 the lattice roller is driven. In order to ascertain the velocity of the feed roller it is only necessary to multiply the diameters or number of teeth of the driving wheels or pulleys and divide that product by the product of the driven wheels, afterwards multiplying the quotient thus

obtained by the velocity of the beater shaft.   Putting this into the shape of a formula, and assuming the beater to revolve at a speed of 1,500 revolutions per minnte, the calculation is as follows :— $\frac{F}{F^1} \times \frac{G}{G^1} \times \frac{D^1}{D} \times \frac{P}{R} \times 1500$.   To ascertain the velocity of the lattice the product of the above formula must be multiplied by $\frac{E}{E^1}$.   It is only necessary to substitute for the letters given above the diameters of the pulleys and the diameters or number of teeth in the wheels to ascertain the requisite velocity of the feed roller or lattice.

(98) The lap machine includes three distinct parts which require driving, viz., the cages, the calender rolls, and the lap rolls.   The whole of these are driven by trains of wheels from the pulley H^1 driven from a pulley H.   The cages are driven by the train consisting of the pinion I which drives the wheel I^1 which is compounded with the pinion M driving the wheel M^1. M^1 has a pinion Q on its axis which engages with a wheel Q^1 engaging with a wheel J^1 on the spindle of the lower cage. The upper cage is driven also from J^1 by a wheel on the spindle of the lower cage.   The formula for the two can be thus stated, beginning as before at the beater shaft.   For the lower cage (1) $\frac{F}{F^1} \times \frac{H}{H^1} \times \frac{I}{I^1} \times \frac{M}{M^1} \times \frac{Q}{J^1} \times 1500$, and for the upper cage the same formula with the addition of the factor $\frac{J^1}{J}$.   (2) Let x and y represent the results, then the upper cage being 19 inches diameter or 59·69 inches circumference its delivery is equal to $x \times 59·69$, and the lower cage being 11¾ inches diameter with a circumference of 36·92 inches its surface velocity is $y \times 36·92$.   These two products should as nearly as possible correspond, but it is of course difficult to get them to do so absolutely.

(99) The calender rolls are driven by a train of gearing which consists of the same factors to the pinion Q, which is fixed on the axis of the lower calender roll.   The formula for this train

is (3) $\dfrac{F}{F^1} \times \dfrac{H}{H^1} \times \dfrac{I}{I^1} \times \dfrac{M}{M^1} \times 1500.$ The lap rolls are driven by the same train up to the pinion M, which in this case is substituted by a second pinion O, which gears with a wheel O^1, fixed on the axis of one of the lap rolls. The second lap roll is driven by a carrier wheel from the first at the same speed. (4) If the factor $\dfrac{O}{O^1}$ be substituted for $\dfrac{M}{M^1}$ in the formula given, the velocity of the lap rolls can be obtained. (5) The calender rolls are 5 inch diameter and 15·7 inch circumference, so that if the product of formula (3) be multiplied by the latter figure the delivery in inches of the calender rolls will be got. The lap rolls are 9½ inch diameter and 29·84 inch circumference, and the product of formula (4) and the latter gives the length delivered by them.

(100) The foregoing brief description will have made it clear that the controlling element in the speeding of this machine is the velocity of the beater shaft. By changing the pulley F on that shaft the velocity of both the feed and lap portions of the machine are altered, although that of the beater is unaltered. This is the method of obtaining the variation when it is desired to produce a greater or less weight of laps without altering their individual weight. If it is required to produce laps varying in weight from those for which the machine is set the pulley H is changed for one of the necessary diameter, the size of which can be easily calculated. This procedure gives a longer or shorter lap for the same length of feed, which, of course, gives a corresponding variation in the weight. As a rule this is all that is required to make the changes, but if it is found desirable to alter the speed of the feed and so produce a heavier or lighter lap for the same length of rollers the pulley G is changed.

(101) The drafts in a scutching machine are of importance. There is a slight draft between the lattice and the feed roller, a larger one between the feed roller and the cages, and a draft between the cages and the calender rolls, and between the calender and lap rolls. A good draft for ordinary cotton is

three, for Egyptian four, and generally the draft should be equal
to the number of laps fed. The draft of the machine is obtained
by dividing the number of inches of cotton formed into a lap
per minute—that is, the surface velocity of the lap rollers—by
the inches of cotton fed, or the surface velocity of the feed
roller. These are obtained, as shown, by calculating the value
of the wheel trains which drive the various parts.

(102) Sometimes scutching machines are made with the cones
driven from the gearing at the lap end of the machine by means
of a side shaft. In this case it is convenient to change one of

FIG. 68.

the bevel pinions on the shaft so as to give the required variation
in the speed of the driving cone. In Messrs. Asa Lees and
Co.'s machines, the beater, cones, and cages are driven, as
shown in Fig. 68, by an endless band. The direction of
driving is shown by the arrows, and it will be seen that any
failure of the rope will cause a stoppage of all the parts and
avoid accumulations of cotton. There is a friction clutch on
the beater shaft, which permits of it being stopped independently.

(103) It is a very common practice to combine the opening
and first scutching machines, as shown in Fig. 50. There is
the advantage in this procedure that the cotton is very early
made to assume the lap form, in which it is much more easily

treated than when in a loose condition. In doing this it is
after leaving the opener, passed over pedal noses in some cases,
as in Fig. 46, and the regulation of the feed at once commences
to take place. The cotton when rolled into a lap is so much
more easily handled, and it lends itself, also, to the process
known as doubling. The latter is the plan of feeding the
finishing scutcher from two to four laps, and is a very convenient
method of obtaining a lap in which the inequalities existing in
those first made are reduced. This is the theory of doubling,
and it is to a certain extent true, but not wholly so. The
pedal motion is much more to be relied on for this purpose
than the mere feeding from two or three laps. The most im-
portant feature of the practice is that it greatly aids the
incorporation of the cotton, and still further mixes the various
constituents of a bin. This is a matter of some moment. It is
often the practice to mix various cottons at this point by putting
up two or three laps of one variety and one of another, or other
variations which are thought advisable. As only a small portion
of the lap is struck off at once, and as the fibres are flung into
the machine, the incorporation of the various constituent
portions is very thorough. This is naturally aided by the
attenuation of the lap, because if four laps of a given weight
each are fed to the machine the finished lap is only the same
weight as one of those fed. Thus any irregularity in weight is
diminished, while at the same time the fibres are thoroughly in
corporated. After cotton has been scutched a second time, the
machine being fed from laps, the mixture of the cotton is very
complete. This appears to us to be the chief advantage of
doubling. Before leaving the question of combined machines,
such an arrangement as that shown in Fig. 43 enables the
finished laps for carding to be obtained with a minimum of
handling, while, at the same time, the weight of the laps does
not vary more than five per cent. The finished lap should be
straight on the edges and even in substance, and no other
should satisfy the manager of a mill.

CHAPTER IV.

CARDING.

(104) WHEN cotton is presented to the action of the carding
machine, it has been, as stated, cleaned and opened, although it
has not been thoroughly freed from all impurities. The pro-
portion of the latter, however, speaking comparatively, is not
large, and with the improvements gradually taking place in the
scutching machine is yearly growing less. Owing to the method
in which the material has been dealt with in the earlier stages,
it is not in a fit condition to be sent to the machines for drawing
and spinning, there being in the lap a good many short fibres
and " nep " or knotted pieces, the effective removal of which is
absolutely essential to the production of a good yarn. Thus
the operation resolves itself into one of cleansing, alike by the
removal of any remaining " motes," short fibre, or " nep." That

machine best fulfils the object of the spinner which removes the whole of the impurities referred to, with the least admixture of fibres which could be advantageously used in spinning. It is often assumed that the fibres are laid in parallel order in the web produced in the carding machine, but this is only effected to a very limited extent, as will be subsequently shown.

(105) A reference to Fig. 69 will enable the essential parts of a carding engine to be understood. The main operating instrument is a cylinder marked A, which is from 40 to 50 inches diameter, and from 37 to 50 inches wide. It is now invariably made of cast iron, and is built up. Its periphery (see Fig. 74) is a light, cylindrical shell A, with an internal flange at each end at right angles to the shell, and strengthened between the ends by light longitudinal and cylindrical ribs. The ends are bored out, and a spider B, which is turned to correspond, is fitted in and secured by bolts. The spider consists of a number of arms attached to a central boss, which is bored previously to the end of the arms being turned to fit the shell. The cylinder so constructed is accurately and carefully turned on its periphery, and is afterwards drilled with several rows of small holes, into which plugs of wood are inserted for the purpose of attaching the wire fillets. After completion the cylinder is carefully balanced, and is finally tested for its accuracy in this respect.

(106) The cotton is fed from the finished lap Q, resting on a roller B, and delivered over a specially-shaped feed-plate C—to which further reference will be made—by means of a feed roller D. The feed roller revolves in the curved part of the feed-plate C, and is from 2 to 3 inches diameter, having its peripheral surface covered with longitudinal and circumferential flutes on that part of it between its bearings. The end of the lap is brought by the feed roller into the range of a number of teeth fixed to a small roller E, which is called the "taker" or "licker-in." This is usually from 8 to 9 inches diameter, and is the same width as the cylinder. Like the latter, it is made of cast iron, and is equally carefully constructed, being mounted on a wrought-iron shaft on which it revolves. The

FIG. 69.

direction of the rotation of the licker-in is shown by the arrow.
Its function is to strike off the fibres from the end of the lap
in detail, and present them to the action of the wire points on
the cylinder.

(107) At the other side of the cylinder is a smaller cylinder
J, called the "doffer," constructed in a similar manner, and of
the same materials; its diameter being from 22 to 26 inches,
usually 24.   It is prepared with equal care to the cylinder,
and is also covered with a similar material, as will be afterwards
described.   The doffer rotates in the direction indicated by the
arrow.   In front of the doffer is a thin bar of steel, slightly
serrated on its under edge, which is fastened on the end of short
arms affixed to a rocking shaft, to which a rapid oscillating
movement, through an arc of about an inch, is given by means
of an eccentric suitably driven.   A short distance past the
"doffer comb" K, as the blade is called, a trumpet-shaped
guide is placed, by means of which the carded web is collected
into a sort of rope, the collection being aided by a special
V-shaped plate.   A short reciprocal horizontal traverse is given
to the trumpet guide in front of a pair of steel calender rollers
L L^1, by which the cotton is slightly compressed.   The cotton
is then passed to the coiler, of which an illustration is given in
Fig. 70.

(108) The coiler consists of a light framework I, within
which is a vertical shaft B, driven by means of the wheel C
from the calender rolls.   The coiler plate L is annular, having
an angularly disposed tube M formed in it, the centre of the
upper opening of the tube being directly below the trumpet T,
through which the cotton enters the coiler.   Between this
opening and the upper end of the tube a pair of calender rolls O
are fixed (one of these being removed in the view).   The lower
opening of the tube is almost at the edge of the plate M, and
the latter has an annular rack L on its edge, with which a wheel
K engages and by which it is driven.   At the lower end of the
frame a light circular disc J, with a toothed edge, and carrying
the can in which the cotton is received, rotates, being driven by

a train of gearing from the shaft B in a direction contrary to that of the coiler plate M, the direction of motion of all the parts being shown by the arrows. The disc J is eccentric to the trumpet, as shown.

FIG. 70.

(109) The parts just described are common to most carding machines whatever may be their remaining constructive details. The cylinder, doffer, licker-in, feed-plate, and roller, and the

calender rolls, are sustained by a strong frame securely fastened together by transverse stay beams. The cylinder revolves in long bearings bolted to the framing and lined with phosphor bronze bushes, the diameter of the cylinder shaft being usually about $3\frac{1}{2}$ inches. The velocity of the cylinder ranges from 160 to 200 revolutions per minute, according to the variety of cotton being treated, a long staple necessitating a slower speed than is permissible with a short staple. The licker-in revolves at a speed of from 350 to 400 revolutions per minute, the velocity being carefully adapted to suit the length of fibres in the cotton being treated. The doffer revolves at a slow speed, from 10 to 25 times per minute, and the doffer comb makes about 1,100 beats per minute.

(110) The action of the parts just described is simple. The scutched lap is carried on a rod and placed upon the top of a roller to which a slow rotatory movement is given at a definite speed equal to or a little slower than that of the feed roller. The lap rod projects beyond its end, and takes into vertical slots in brackets attached to the framing, shown at Q in Fig. 72, so that the lap rotates but does not roll forward. The lap is thus unrolled, and is gradually drawn forward by the feed roller along the dish feed plate, over the front lip of which it is pushed. If two feed rollers are used the action is identical except that the lap end is projected beyond their nip. The lap is thus thrust into the range of action of the licker-in teeth, by which it is struck, and the fibres beaten off. The latter are carried round and brought into the path of the teeth upon the cylinder, by which they are seized and held until they are deposited as a thin fleece upon the wire-covered surface of the doffer. This fleece or web is beaten off the doffer by the doffer comb, and is collected by the plate and trumpet into a sort of rope, which, after passing the calender rolls, is laid in coils in the can by the action of the coiler.

(111) This is the action of the machine as it would be if there were no other treatment of the fibres by any additional mechanism. But the treatment thus accorded to the cotton

would result in nothing more than an attenuation of the lap to an extent depending upon the difference of the velocities of the parts, and the cleaning effect would be very small. It is therefore necessary to provide between the point where the fibres are received by the cylinder and that where they are removed from it, some means whereby they are subjected to a cleaning and straightening process, so that the impurities and imperfections named will be effectually removed. This can only be done by providing a special surface, by which the cotton fibres as they lie upon, and are carried round with, the cylinder are combed and carded. There are two main methods of effecting this object; first to surmount the cylinder between the points named with a number of revolving wire-covered rollers; or second, to surmount it with a series of bars with their under surfaces covered with wire. The second class may be subdivided into systems in which (a) the flats move simultaneously with the cylinder, or (b) they remain stationary. Of these the latter system is now rapidly becoming obsolete, although it still lingers in the United States and on the Continent, and need not be treated in detail.

(112) The first of the two main divisions of mechanism is employed when what is called the roller and clearer carding machine is used. This is shown diagrammatically in Fig. 69, already referred to. It consists of a series of small rollers disposed above the cylinder surface, between the taker-in and the doffer. The first of these, F, is usually called the " dirt " roller, and is from 5 to 6 inches diameter, being covered with a wire fillet, the teeth in which are set in the direction shown. The direction of the rotation of the dirt roller is shown by the arrow, and its object is to remove from the surface of the cylinder wire the heavy impurities, such as motes and sticks. After passing the dirt roller (of which there may be two), the cotton is treated by a series of rollers H, known as " worker " rollers, which are from 5 to 6 inches diameter, and have their wire teeth set at such an angle that they receive the fibres from the cylinder and draw them bodily away. The surface velocity of the worker rollers is only about 20 feet per minute,

so that the cotton is easily deposited on them and stripped from the cylinder.   They carry the fibres with them in the direction indicated by the arrows until the material is caught by the teeth on a small roller G, called a "clearer," which is about 3 to 3½ inches diameter, and has a surface velocity of about 400 feet per minute.   The teeth of the clearer roller are set in the

FIG. 71.

reverse direction to those of the worker, so that the cotton is easily transferred to the cylinder.   The whole of the rollers are borne in brackets fixed to a semicircular frame bolted on the lower f.ame P, and known as the " bend," the brackets having open bearings formed at their heads, and being set, as shown in Fig. 71, by screws of fine pitch.   In this way an easy and accurate adjustment is obtained, which enables the various wire

surfaces to be brought into close proximity to each other. The worker rollers are driven by means of small, double flanged pulleys fixed on their spindles at one end, over which an endless band, passing over, and driven by, a pulley on the driving shaft, is stretched. In some cases toothed chain-wheels are used instead of pulleys, and the driving is obtained from the doffer shaft, or ropes may be employed. The clearers are driven in a similar manner at the other side of the machine, this arrangement enabling the driving gear to be compactly arranged. The whole of the worker and clearer rollers are encased in a cover M, so as to avoid, as far as possible, a discharge of short fibre into the air.

(113) The action of this type of machine is as follows : The lap being fed by the feed roll, say at a speed of seven inches per minute, is struck by the teeth of the licker-in, and those fibres which are held loosely enough are beaten down by them. As the licker-in, if 8 inches in diameter, and with a velocity of 350 revolutions per minute, has a surface speed of 8,796 inches per minute, it is obvious that the substance of the cotton will be reduced 1,256 times at this point. The cylinder which, if 50 inches diameter and revolving 180 times a minute, has a surface velocity of 28,273 inches, thus travelling 3·21 times as fast as the licker-in, the lap being, therefore, attenuated up to this point 4,039 times. Now, as the worker roller is only revolving at a surface speed of 20 feet, it follows that the difference between this and that of the rapidly revolving cylinder will cause the fibres to be laid upon the worker, and that, in short, a condensation of the layer of cotton will occur. As this fleece, which is 471 times as thick as the layer on the cylinder, is carried round, it is caught by the more rapidly revolving and contrary set teeth of the clearer, and is again attenuated 20 times, thus being practically restored to its original thickness prior to being taken off the clearer by the cylinder. These alternate condensations and attenuations of the fleece continue throughout the whole passage of the fibres, from the licker-in to the doffer. The result of this undoubtedly severe treatment is that the short

fibres and nep are removed, and are capable of periodic strip-
ping from the worker rollers, in which they become embedded.
When the cotton reaches the doffer, the surface velocity of
which is 904 inches per minute, it is deposited upon this slower
moving surface, and is again condensed into a web 31 times as
thick as that on the cylinder. Thus the lap has in its passage
become attenuated 130 times, and is finally produced as a
sliver, thinner in that ratio than the lap from which it is pro-
duced. In other words, the "draft" of the card worked under
these assumed conditions is 130. These calculations are made
without regarding the length of the wires on the various parts,
which will slightly vary the results without affecting the
principle.

(114) When double carding is resorted to—that is, when the
cotton is passed over two carding cylinders—the latter are
usually placed one behind the other on the same framing, the
cotton being transferred from the first to the second cylinder by
a small drum similar to the doffer, which is called a "tummer."
In some cases, however, a number of slivers produced on the
carding engines are combined in a special machine called a
"Derby doubler," and are formed into a lap, which is fed to the
finisher carding engine. So far as this country is concerned
this practice may be fairly described as obsolete, and need not
be dealt with at length. At a later stage something will be
said of the principle of this system of treating cotton.

(115) The first (a) of the second division of machines is
what is known as the "revolving flat" card. This name is given
to it because the carding surface is fixed to an endless chain of
narrow bars or flats, sustained and sliding upon a curved surface
or plate, attached to the framing of the machine. This plate is
called, like the frame itself in the roller and clearer machine, the
"bend," a name which, though carelessly used, should be
confined to the surface bearing the carding organs. In the
roller machine these are the various rollers and clearers, which
are capable of individual adjustment, while in the revolving
flat machine they are the chain of flats, which, being coupled

together, must be simultaneously adjusted. The bend sustaining
the flats must therefore be capable of adjustment, and the
principle which underlies this procedure can now be dealt with.
It is sufficient to say at this point that the construction of the
flats is such as to ensure the faces upon which they rest on the
bend and their wire faces being in parallel planes. Therefore,
if the flats are borne upon a surface which is concentric with the
surface of the cylinder, but so far from the centre of the latter
as to compensate for the length of wire on both—and provided
that the two wire surfaces are accurately and evenly ground—it
will be clear that over the whole of the surface there will be the
same distance between the points of the wires. That is the
condition which is absolutely the best for carding; but its
constant maintenance is the problem. If it be assumed that
the machine is starting after being clothed with wire, that the
cylinder is 50 inches diameter, the surface of the wire on the flat
projects half an inch beyond the surface on which the flat rests,
and that the points of the wire on the cylinders are half an inch
from its surface, the ends of the flats must be sustained by a
surface which has a radius of a fraction more than 26 inches.
What the excess over 26 inches will be depends entirely upon
the distance which is maintained between the points of the teeth
on the cylinder and flats respectively. It is obvious that it
would be quite easy, if the conditions named were maintained,
to provide a sustaining surface of the required radius. It is,
however, necessary to provide for the reduction in the length or
the wire teeth on the cylinder and flats, which takes place when
they are ground to re-sharpen them after wear. This involves
the provision of means whereby the bend can be so adjusted as
to re-establish the concentricity of the cylinder and flat surfaces.
If it be supposed that circles 51 and 52 inches diameter
respectively be struck from a common centre, and that one
represents the cylinder surface and the other that of the bend,
it is clear the distance between the two will be maintained so
long as these conditions prevail. If now the circle representing
the cylinder be reduced to 50½ inches diameter, and the

arc of the crown of the circle representing the flat course be dropped in a radial line, it is obvious that, when the crowns of the two arcs touched, there would be a space between them at each end. Unless, therefore, some means are provided by which the concentricity of the two is re-established, the correct conditions would be destroyed. The same thing arises if the circle formed by the points of the teeth on the flats is enlarged, as it would be if the teeth are ground. The shortening of the teeth by grinding is an easy matter, but as the bend is made of cast iron it is not so easily reduced, and the action of moving it nearer the centre without changing its form is equivalent to changing the position of its centre. The concentricity of the two surfaces being essential to good carding, it is necessary to provide means whereby the bend can be made to assume a circle having the reduced radius. There is not only this factor to reckon with, but another, which is of importance. The cylinder rotates, as was said, in bearings fixed on the main frame; but as its weight is considerable (about 10 cwts.), the speed at which it rotates great— from 150 to 230 revolutions per minute—and the pull of the driving belt in a forward direction—there is a great tendency for the bearings to wear forward and downward and thus move the centre. Instances of this action are so numerous that special provision is made in constructing the bearings to enable the wear to be taken up. It is singular that the wear takes place much more rapidly in the case of new machines than in those which have been in use for a longer time, this arising probably from the fact that the parts have not settled into working positions. The practical effect upon the bend is that, as before, it is necessary to provide means by which it can be adjusted. The various arrangements employed for this purpose will be described at a later stage. The flats are bars of a ⊥ section, the flat face of which has the wire clothing attached to it, and is therefore of sufficient length to receive a strip of full width. It is important that the flat should be strong enough to resist deflection, whence its shape. Projecting beyond the flat face at each end is that portion of the flat on which the faces sliding

on the bend are formed.   On the upper side of this portion of
the flat is the small bracket to which the chain is attached, its
position being specially designed to avoid any twisting of the
flat.   After the flat face has been ground fairly true, the upper
faces at each end are milled true, and subsequently all the other
working surfaces are accurately machined.

(116) Referring now to Fig. 72, which is a perspective view
of a carding engine on this principle, it will be seen that the
flats U are arranged in an endless chain, and are coupled by
means of screws at each end to chains with pitched links, which
are driven, in a manner to be afterwards described, at a slow
speed in the same direction as the cylinder.   They are guided
by rollers, and at the doffer end of the card are stripped of their
accumulations of short fibre, etc., by a rapidly oscillating strip-
per comb X, and are afterwards brushed out by a revolving
spirally arranged brush V.   Each flat has its bearing surfaces
so arranged that when sliding upon the bend its wire surface
assumes a tangential position to the cylinder periphery—that
is to say, it is further from the latter at the edge nearest to the
point from which the cylinder wires approach it, and nearest
the latter at the point where they leave the flat.   This arrange-
ment of bearing surface is technically called putting in the
" heel," and the part of the flat nearer the cylinder is spoken of
as the " heel of the flat."   The object of this arrangement is to
ensure that the fibres will readily enter the space beneath the
flat, without rolling up at the front of it, thus ensuring their
through carding.   The amount of heel put into the flat is about
·029 inch for each inch of width of the flat ; and, if the flats
moved on a plane surface, this would mean that there would be
that difference between the wires of the cylinders and flats at
the front and back of the flat.   As a matter of fact, this is
diminished by the curvature of the cylinder, because between
the two bearing points of the flat there is an arc which has a
certain altitude from the chord.   There is not, therefore, a
gradual reduction of the distance as at first sight appears, but an
irregular one unless the flat be ground to the curve.

FIG. 72.

(117) In treating cotton by a machine of this description the action of the various parts common to this and roller machines is identical. The flats act, however, as a sort of scraper or comb, as afterwards shown, and effectually remove the short fibre and neps as they pass below them when the cylinder is revolving. The steady onward movement of about an inch a minute is sufficient to ensure that the flats will continue, so long as they are above the cylinder, to comb or card the cotton, without becoming so charged with fly or motes before being stripped as to cease to discharge that important duty. It is absolutely necessary to take care of the flats, and to see that, as

Fig. 73.

far as possible, their bearing surfaces are kept in good condition, and that cleanliness of the whole of the parts is preserved. At one time it was the practice to make flats about two inches wide, but it is now not often that they are found wider on their carding surface than 1⅛ inch. There are many important advantages in this course. The cotton is treated by a greater number of carding points, the flats are not so heavy, and the space between each pair is not so great in working. The number of flats in the chain varies from 100 to 110, but, as the arc formed by the bend is about 120°, only from 40 to 45 flats are in working position at one time, but this, when calculated, gives a large carding surface.

(118) In paragraph 116 reference was made to the necessity which existed for the provision of means by which the bend could be adjusted first to the cylinder when its diameter had been reduced by grinding, or when the flat teeth themselves had been ground; and, second, to the means of restoring the cylinder centre if it moved from wear of the bearings.   With

FIG. 74.

regard to the first point, there are quite a number of devices used for the purpose. The simplest and best known is the "flexible bend," as it is called. This consists (Fig. 73) of a flat plate curved on its upper edge to a circle corresponding to the correct one required to sustain the flats. The depth of the plate varies, being less at the ends than at the centres, gradually

increasing as it approaches the centre. The object of this formation is to enable the bend to be drawn inwards or pushed outwards by setting screws without distortion of the curved profile. The bend is provided at three or five points with downwardly projecting screws of fine pitch, which passing through brackets on the fixed bend, enable the flexible to be set by means of nuts. The section given in Fig. 74 may be referred to. The bend D is coupled to the slide or frame G by the pin H. The fixed frame C extends on each side of the bend D and has screws E fitted in it. The setting screws F pass through the frame G and press against the boss on C into which E fits. By rotating the screw F the bend is drawn down or

FIG. 75.

raised to any required position. It will be easily understood that the setting screws not only act as flectors, but also as struts, taking up the weight of the bend at the point of attachment. The action of setting the flexible bend in this form is very simple, being merely the drawing down of the bend to the required curve, and when this is attained locking it to the fixed bend by bolts provided for the purpose.

In another form, the "Simplex," shown in Fig. 75, the bend A is a band of metal with pins fixed in its side which rest on the edges of three brackets fastened to the frame B. These edges are shaped to carefully plotted curves, so as to ensure the bend A taking its proper form. At one end the bend is connected to the crank E, and at the other

has a pin fixed which engages with the inside of the bracket C, also suitably curved. At this point the inner edge of the bend is formed with a rack, with which a small pinion, compounded with a worm wheel engages. The wheel is rotated by the worm, and as the pitch of the worm and wheel is a fine one, a delicate setting can be given, the amount of which can be ascertained by a graduated scale on the latter. It will be seen, on consideration, that this bend is held in tension between the crank E and the rack, so that it is drawn down on to the edges of the brackets which sustain it, an action aided, of course, by the weight of the flats.

Another form of bend is that shown in transverse section and plan in Figs. 76 and 77. In this the flat G is sustained on a

FIG. 76.   FIG. 77.

triangular segmental ring C, which in turn rests on a heavier segmental ring A, borne by a bracket formed on the fixed bend H. The surfaces of the rings C and A and of the bracket are all accurately turned, and by means of five micrometer screws B, which engage with nuts D graduated on their edges, and pressing on the face of the bend H, the ring A can be advanced or receded towards the cylinder J, thus raising or lowering the ring C to any desired extent. C being flexible, is bent to a smaller circle by the weight of the chain of flats.

In the form of flexible bend shown in section in Fig. 78, the bend A rests on the heads of five screws D, which

after passing through an arm formed in the fixed bend B, are threaded into a nut F fitting in the space shown. Through the bend at the same points are passed screws E, which take into threaded brackets G, fitting against the under-

Fig. 78.

side of the arm named. The flexible bend A fits loosely between flanges B and C formed on the fixed bend. The screws D are formed with **T** heads, curved on their upper surface, so as to act as supports to A, and the latter is pressed down on them by the screws E. As the line of pressure of the latter is the resultant of two, one vertical and the other horizontal, the

bend is pushed on to the heads of the screws D and against the
flange C of the fixed bend and the proportionate distribution of
the thrust depends upon the angle at which the screw E acts
relatively to the vertical. In this way the bend receives a
support, not only from the heads of the screws D, but also from
its friction on the inner surface of the flange C. The screws D
are formed with a fine thread, and the edges of the nuts F are
graduated so as to act as an indicator. In all these three forms
the indicators register a vertical movement of the flexible bend
of $\frac{1}{1000}$ inch.

FIG. 79.

The arrangement shown in Fig. 79 consists in placing upon
the semicircular fixed bend a number of thin steel bands F, which
are kept in tension by being fastened on the pin G, and drawn
to the fixed bend by the nut and screw placed at C. The bend
and cylinder pedestal are formed in one piece, but the bearing
brasses are sustained by a screw K with a micrometer thread
fitting into the pedestal and locked by a nut. The head of the

screw is graduated on its edge, so that its rotation through one division raises or lowers the bearing $\frac{1}{1000}$ inch. The bands vary in thickness, the thickest being $\frac{1}{30}$ inch, and by the removal of one of them the flats are lowered a definite distance, the cylinder being adjusted subsequently, if necessary, by the screw; that is to say, if the removal of any band lowers the flats too much the

FIG. 80.

cylinder can be raised so as to give the correct setting between it and the flats.

In the device shown in Fig. 80, the flats are borne on a ring E forming the periphery of a wheel D, which is centred on a boss C bolted to the cylinder pedestal. The wheel is quite loose on C, which can be adjusted by suitable setting screws. The ring is fitted tightly on the wheel D, and can be

F

renewed when necessary. The flats F rest upon the two wheels
—one on each side of the machine—and owing to their weight
establish such a friction as to rotate the ring at the same speed
as they move. There is obviously no wear of the flat ends in
this arrangement, as they do not slide but move with their
sustaining surface. When the ring is first fitted it is turned of
sufficient size to maintain the correct separation between the
cylinder and flat wires, but as wear of the latter occurs it is

FIG. 81.   FIG. 82.

necessary to provide some means for reducing the diameter of
the sustaining circle. These are obtained by the employment
of milling cutters G fixed on a transverse shaft, which is borne
by two sliding frames, Figs. 81 and 82, one on each side of the
machine, and driven by a band from the cylinder shaft. These
are borne by brackets attached to the bend, and are operated by
a worm L and wheel I, the latter being threaded on the screw H.
The worm L is rotated by means of a graduated disc, the whole
arrangement being based on the micrometer principle. One

division on the disc implies a movement of $\frac{1}{500}$ inch. After wear has occurred, the bush C is loosed and gradually lowered by the setting screws, which permit the amount of movement to be ascertained. As soon as the teeth touch, which is indicated by a click, the total amount the bush has dropped is ascertained, and it is then raised to its normal position, making it again concentric with the initial position of the cylinder. The distance it is desired to keep the teeth apart is then deducted from the total movement, and the remainder indicates the amount to be taken from the diameter of the rings. The milling cutter is

FIG. 83.

accordingly set in to that extent, and as the discs D revolve in ordinary working they are gradually reduced to the correct diameter. It will be noticed that this arrangement only permits of the dropping of the flats, while in all the other devices they can also be raised when required. On the other hand, if the wheels are properly set and milled, and the cylinder centre is in its true position, the flats move on a surface which is truly concentric. By suitable arrangements the bush can be adjusted to the cylinder centre, but it is much better to readjust the latter.

(119) It has been said that wear of the cylinder bearings occurs, causing the cylinder centre to move from its correct

position. Although from careless handling this fault may be serious, if the machines are carefully looked to there is no necessity for its occurrence. There are several methods of adjusting the bearings, which are all, however, substantially the same in principle. In one case, as shown in Fig. 83, the bearing is contained within two eccentric bushes, which can be adjusted to move the cylinder centre in any direction to any desired extent. In the device, Fig. 84, the pull of the belt is taken up by a fixed bush C, within which the shaft, and on which the

FIG. 84.

driving pulley A, revolves, the motion being communicated to the fast pulley by a carrier or coupler D. Another arrangement permits the bearing to be raised vertically within the pedestal by an eccentric, while the lateral adjustment is effected by sliding the pedestal by a screw. The employment of wedge-shaped plates below the bearing is also an effective device, the best form of it being that in which two wedges are employed, the one upon the other (Fig. 85), so that by careful adjustment of them and the side screws any desired position can be given to the cylinder centre. A combination of a single wedge and lateral

adjustment of the pedestal is also used, but the best arrangements are those in which the pedestals are fixed and the adjustments made within them.

(120) A twisted strand of cotton—that is, yarn—possesses a certain strength which arises to a large extent from one factor, viz., the number of fibres in its cross section. It is true that the length of the staple has a very important bearing upon this

FIG. 85.

subject, because it enables the successive sets of fibres contained in a length of yarn to be more readily twisted or bound together ; but, in the main, it is the sum of the individual strength of each fibre in a strand of yarn which gives it its strength. That being so, it follows that the larger the number of fibres in any cross section, the greater will be the strength. There are, of course, exceptions to this, as to every other general principle,

but as a broad statement it is accurate.   Admitting, therefore, that this is a correct statement of fact, its bearing upon carding is obvious.   The yarn eventually spun depends for its evenness upon the roving frame from which it is twisted, the roving upon the drawn sliver, and the drawing upon the carded sliver.   It is quite clear that if the fibres are stripped from the doffer in a tangled or cross condition they will not lie so closely together when first drawn as they will if laid in the practically parallel order of a combed sliver, and the labour involved in reducing them to parallel order will be much increased.   It is true that in combing cotton a large amount of waste is produced which it is impossible to sanction in a carding machine working under the commercial conditions of to-day, but it is worth considering whether anything can be done to obtain a further parallelisation of the fibres in the carded sliver.

(121) The first point which requires consideration is the condition of the lap as it is fed to the carding engine.   At one time this subject did not receive the attention it deserved, and laps were fed which were neither so well cleaned nor so even in weight as they should have been.   It cannot be too strongly insisted on that it is absolutely imperative for the complete success of a card that the material when presented to it should be in as perfect a condition as it is possible to get.   It is not enough that the cotton should be made into a lap of the required thickness.   Every impurity which can be expelled by the beating action of the opening and scutching machines should be eliminated, and the only work thrown upon the card teeth should be the removal of short fibres and those adherent impurities which, without breaking the fibres, cannot be detached during scutching.   If the extreme delicacy of the fine points of the carding surface be borne in mind, it will be seen that to put upon them the task of removing heavy impurities is at once an error in principle and practice.   It is a noteworthy fact that, in this country at least, it is widely if not universally recognised that the improvement in the instrument for carding cotton must be accompanied by a like amendment in the machines

employed to prepare the cotton for that process. Accordingly, as was shown in the last chapter, by careful attention to the details of the scutching and opening machines cotton is now submitted to the action of the carding machine in a much more perfect state than at one time was thought possible. This is one of the causes for the large productions got from modern cards, and is by no means the least important. Not only, however, must there be a perfectly clean lap, but it should be very regular in weight. The means adopted in the scutching machine for regulating the passage of the cotton so that thick places are beaten out are absent in the carding machine, and, whatever may be the inequalities in the lap, no means are at hand by which they can be removed during carding, although they are, of course, reduced by the attenuation of the cotton before it is coiled in the sliver can. The end of the lap is presented to the action of the teeth of the licker-in at a steady rate, and, if one part in the lap is thinner than another, fewer fibres will be removed during each revolution of the licker-in than when the thicker part is being presented to its action. Consequently, during the time the cylinder is revolving, the number of fibres presented to it varies according to the thickness of the lap. Assuming the cylinder to be charged with cotton, is it unreasonable to suppose that it will retain more fibres at one period than at the other, and consequently that when these are transferred to the doffer the number on the surface of the latter will vary in like manner? It must not be understood that all the fibres taken up by the cylinder are necessarily transferred to the doffer during the first revolution with the cylinder, but that, if it were possible to attain this object, it would be of material advantage. At any rate, whether this be so or not entirely, it is so to a large extent, and it is easy to understand that a limitation of the fibres fed would necessarily be followed by a diminution in the number of fibres doffed after a due interval had elapsed. If the variations in the lap were great and prolonged, this point could be easily demonstrated, but as the difference in the thickness in the lap is, in the present day, not

great, and as the thin places are not of great length, it is more difficult to trace their effect.

(122) Broadly speaking, however, there is no doubt that the irregularities of the lap are reproduced in the sliver, and that, while the irregular weight of the latter is not wholly attributable to this factor, it plays an important part in connection with it. Further, as the sliver is very thin, any variation in the number of fibres delivered to it speedily becomes of importance, and the percentage of variation noticeable. It is not a good thing to lay too much stress upon this argument, but it is necessary to emphasise the fact that an uneven lap cannot possibly be an aid, and may be an immense hindrance to the production of a regular sliver. It may be taken as an axiom that the avoidance of intermittent work by the card teeth is a necessary factor in the successful performance of their duty, and nothing can tend more directly to bad work than to have the cylinder choked with cotton at one time, and nearly bare at another. The abolition of the old plan of weighing the cotton in scutching does not necessarily imply uneven laps, because, thanks to the ingenuity, perseverance, and skill of our mechanicians, the machines now do better work than at any previous time. Having secured an evenly weighted lap, the next thing necessary is to so feed it that the fibres shall be removed with the minimum of risk of damage. Upon this it will be necessary to say a few words.

(123) The general arrangement of the licker-in relatively to the cylinder is shown in Fig. 86. The licker-in B is surrounded by a cover F, which is jointed to a similar plate, acting as a cover to the cylinder when the revolving flat type is used. In roller and clearer machines the cover is of a different construction. The dish-feed plate C, of which something more will be said presently, is fixed as shown, so as to be readily adjustable, and two blades D called "mote knives" are placed immediately beneath it. These are intended to scrape off the motes from the cotton as it is carried on by the licker-in, and they are arranged to be easily adjusted along with the feed-plate and the grid or casing E, from the outside of the frame of the machine.

The casing E and the knives are, as shown, carried by a frame, which is supported at the inner end by pins taking into curved slots, thus ensuring that when the plate is pushed in, in consequence of the necessary setting in of the licker-in after the length of the cylinder teeth has been reduced by grinding, or those of the licker-in from wear, the relative position of the dish feed-plate, knives, and undercasing are accurately preserved. Below the

FIG. 86.

licker-in a packing piece L is fitted, which closes the gap that would otherwise be left, and thus prevents any gathering of fibres which might occur if this care were not taken to prevent it.

(124) The ordinary method of feeding the lap is by the dish or shell feed. This is shown at C in Fig. 69, and is also shown in detail in Figs. 87, 88, and 89, and consists of a flat polished plate, over which the lap is drawn, and which at its inner end is curved upwards to correspond with the curvature of the feed roller. Between the periphery of the latter and the surface of

the dish plate the lap is passed, and a definite downward pressure being maintained on the roller, which is revolved at a regular rate, the lap is carried forward and its end thrust into the path of the teeth of the licker-in. It is obvious that this action may be so carried on that large lumps or pieces of the cotton would be struck from the end of the lap. This, however, would be fatal to the efficiency of the machine, and the removal of the material should be as nearly as possible the detachment of the fibres separately, and not in bulk. In point of fact, the action of the licker-in teeth should be first one of combing out

FIG. 87.

the end of the lap, in this way detaching the fibres without running the risk of breakage. In the attainment of this object the dish feed plays an important part. It is desirable that only those fibres which are practically freed from the nip of the feed roller should be removed by the teeth of the licker-in, and from the fact that only when they are projected over the edge of the feed plate are they released, they are not so likely to be forcibly removed as if the fibres were struck from the nip of two rollers. This can be very readily understood, as it is obvious that a much greater length of cotton necessarily exists between the nip of a pair of rollers and the extreme point of the projecting part of the lap, than is found lying over the nose of the dish feed

plate. In other words, the teeth of the licker-in have less material to pull at, and are therefore more liable to remove the fibres in detail. This is easily seen if vertical lines be

FIG. 88.

drawn though the nipping point of the feed roller and plate, or of the two feed rollers, when it is made visually evident how much greater the length is in the latter than in the former case.

FIG. 89.

The shape of the nose of the dish feed is varied to suit the cotton treated. Thus, Fig. 87 shows the shape for Surat cotton, Fig. 88 for American, and Fig. 89 for Egyptian.

(125) The action of the licker-in tooth is, indeed, one of extreme interest.   There is a dual operation always going on, viz. : a cleaning and a combing or straightening of the fibres. Owing to the shape of the teeth and the manner in which they are set, there is no danger of their becoming choked, and they are, therefore, always in the best possible condition for acting upon the lap.   When they strike the projecting end of the lap, they pass through it at such a velocity that the heavy adherent impurities are struck down and partially removed.   At the same time the teeth remove the fibres which are sufficiently loosened, but it is important to note that those which are not so ready for detachment are simply divided and combed by the rapidly revolving teeth.   Thus, after a few revolutions of the licker-in, the end of the lap is so far straightened and combed out that the removal of the fibres is much easier, and the risk of damage to them proportionately reduced.   Now, it is obvious that the preparation of the end of the lap in the manner described would be much more difficult if so great a length of fibre projected beyond the nipping point that there was any likelihood of the cotton being removed in tufts or lumps of considerable size. This detailed or separate detachment of the fibres is aided by the dish feed, and, when thoroughly carried out, is of great importance in diminishing the work thrown on to the cylinder and flat teeth.   The full advantage of the dish feed, however, is only obtained when the surface from which the fibre is struck is specially shaped and set to suit the staple of the cotton which is being worked.   When a short stapled cotton is being dealt with, the space between the inner face of the dish plate and the tips of the licker-in teeth is very small, and the projection of the fibre over the nose of the feed plate is immediately followed by the combing action of the teeth which has been described. When the staple of the cotton treated is longer, the extreme end of the fibres can be attacked at a greater distance from the nip of the feed roller, and, it being desirable to comb out the cotton as described, the nose of the dish plate is shaped to allow of this being done.   Although the dish feed is attended

with so many advantages, it is quite possible to so manipulate it as to break and damage the cotton. It is, therefore, essential in setting it that due regard is given to the staple which is being carded, and a little observation will speedily lead to the determination of the correct setting distance. The gradual and not the sudden detachment of the fibres is what is wanted, and to this end the action of the licker-in teeth in combing out the end of the lap is very useful. It must not be supposed however, that in speaking of the detailed removal of the fibres it is meant that they are struck from the end of the lap singly, because this is not the case. They are removed in numbers simultaneously, and, owing to the method of setting the teeth on the licker-in, the work of removal never ceases, as can be seen if an examination is made of a card in work. The condition of the detached fibres is such that they are readily taken up by the cylinder teeth in their revolution. More depends upon the feeding of the cotton to the cylinder than is sometimes thought.

(126) Assuming the fibres to have been delivered to the cylinder, it is desirable to get a clear understanding of the treat ment they undergo before being finally stripped from the doffer. It is necessary to know something of the construction of the fibre itself to get a rational idea of its manipulation by a carding machine. The cotton fibre, as was shown in Chapter II., is possessed of a natural twist which causes it to endeavour to curl round any adjoining fibre, a tendency which makes it much more difficult to straighten. Even when it is drawn straight it requires little provocation to twist up again, and it is in this fact that much of the difficulty of carding is found. For a moment or two let us consider the process of combing, which will be described in full later, but from which some useful hints can be obtained. In combing, the end of the lap is caused to project for a certain distance beyond the feed rollers, and is firmly held while the circular combs are passed through it. The construction and arrangement of the combs is such that the short fibres are at once removed from the end of the lap, the remaining fibres being straightened by the successive passage of needles of

decreasing diameter and pitch. Before the fibres composing the straightened end of the lap have time to bend up they are gripped by the half lap and detaching roller. Indeed, as only one end of each fibre is free, the other end being firmly held as described, the fibre is not able to assume its natural position. As the comb cylinder continues to rotate, it completely detaches a tuft of cotton, and in the course of doing so draws the uncombed end through the points of the top comb which has dropped into the lap. During the latter part of this period the first portion of the combed tuft is joined on to the previously formed sliver, so that at no time are the fibres free to fall into their natural position or to curl round each other. Now what it is desired specially to point out is that the straightening of the fibres in combing is effected by treating a small number at one time, and that immediately they have been drawn out by the action of the comb, they are so held that it is nearly impossible for them to fall out of the parallel order into which they have been reduced.

(127) A calculation, which can be readily made, will show that it is not easy for the licker-in to feed sufficient cotton to the cylinder to enable the latter to be always taking up fibres. The number of teeth on the licker-in and cylinder and their respective velocities render it practically impossible for each point on the cylinder to take up at each revolution one fibre, which it is theoretically supposed to do. Indeed it is more than probable that there are considerable periods—that is, comparatively—during which the teeth in various parts of the cylinder do not take up any fibres at all. In short, there are not enough fibres to go round, and they will be held by the carding points in a practically free manner. A properly made card tooth should only grip the fibre for a short distance, and the hold which it retains upon it will depend very largely on the "keen" of the tooth, that is to say, the angle to which it is bent between the foundation and the point. There ought not to be anything like a film or complete covering of cotton. On this point the author is strongly of opinion that it would be fatal to

efficient carding if the cylinder had taken up so many fibres that every tooth was charged, and that it is when such a condition is approached that a cylinder becomes over-charged and its work becomes bad. It is necessary that a certain freedom from restraint should be left to the fibres, or otherwise they could not be effectively treated by the flat or roller teeth ; for it is obvious that if a fibre were embedded in a mass of others it could not be easily raised from the surface so as to be combed along its free portion. Herein lies at once the strength and weakness of carding. The strength is found in the fact that the fibre can be readily drawn through the superposed teeth on the flats, or can be easily lifted by the roller teeth and cleansed. Unless this freedom existed, not only would the actual work of carding be badly done, but there would be a considerable risk of the rupture or fracture of the fibres owing to the excess of power required to detach them. Now if the description of the process of combing, given a short time since, be borne in mind, it will be seen that the state of the cotton fibre is nearly the reverse of what it is during combing. In the one case each fibre is free, or nearly so, being held only slightly at one end, while in the other it is firmly gripped during the whole of its treatment. In other words, the natural inclination of the fibre to twist is left uncurbed during carding which is the exact opposite of its condition during combing.

(128) With regard to the character of the treatment under-gone by the fibre as it is drawn through the wire teeth on the flats, there is not much probability of that effect of centrifugal action which is sometimes laid stress upon. It is certainly true that the velocity of the cylinder is so great that the fibres, if left at liberty, will tend to be thrown outwards, but it is more than probable that owing to the method in which they are held, and to the resistance of the air surrounding the cylinder, they would be bent back so as to lie on the surface of the cylinder in nearly circumferential lines. It is obvious that even the comparatively coarse setting of the flats which is often made could not be easily effected if the fibres stood straight out in the manner

sometimes imagined, and the importance of the accurate settings of the flats now obtained lies mainly in this fact. What happens is that the fibres being held by the cylinder wire, and to a certain extent raised from the surface, are subjected to the combing action of the superposed teeth, their free portion being drawn along the points and thus cleansed. The other end of the fibre—that is, the part held by the cylinder, is combed or carded when it is transferred to the doffer, the slower running of which causes the fibre to be received and held so firmly that its transferral from the cylinder to the doffer is easily accomplished. In addition to this, the number of wire points on the doffer are in excess of those on the cylinder, and the fibres are therefore easily held. The action of the roller teeth is entirely different to that of flats, because they are so set as to lay hold of and remove the fibres from the cylinder, to which they are again restored by the action of the clearer. In these alternate and repeated transferrals the fibre is effectually cleaned, and every time it is flung into the roller wire the short fibres and motes accompany it and remain.

(129) Between the moment of leaving the flats and being deposited on the doffer there is a period of time during which the carded fibre is free at one end. The tension into which it has been put during carding naturally causes it to contract as it is released, and this, along with its natural tendency to curl, is largely responsible for the manner in which it is placed upon the doffer. Remember a fibre is being dealt with which, when it flies over as it is released by the wire, falls on to a surface provided with points, by which it can be tenaciously held, so that if it once falls out of the circumferential line it will have some difficulty in assuming it again. Remember also that although every care is taken to prevent currents of air from forming, it is impossible to prevent air from entering, and a slight draught would be sufficient to influence the disposition of the fibre. It is to the causes thus detailed that we mainly attribute the lack of parallel order observable in the fibres composing the sliver from a carding engine. It will be noticed that

the individual fibre is permitted to assume a position which it is entirely debarred from taking in combing, and that while on the one hand it is held sufficiently to enable it to be well carded, on the other it is sufficiently free to enable it to assume a position which is controlled as described. Although the lack of parallel order in the fibres constitutes one of the evils of the system of carding, yet if the explanation given of its cause be a sound one, it is better not to so load the cylinder with cotton as to prevent the fibres from having this free action. The alternate attenuation and condensation of the cotton during carding is not of great importance, except in so far as it tends to permit of the establishment of the freedom named. It may, however, be pointed out that as the doffer surface moves so much slower than that of the cylinder, the cotton on a large area of the latter is deposited on a much smaller area on the former. Thus, although it is true that the charging of the cylinder is not a regular, but in a sense an intermittent process, any inequalities which are likely to arise in this way tend to be removed by the difference of the peripheral velocities of the two parts named.

(130) The existence of air currents plays an important part in the work of a carding machine, and it is surprising how rapidly they act upon the material. The modern method of forming and setting the flats, and the general arrangement of the framework, on the whole, prevents any blowing out of the air at the sides until the fleece or web is deposited on the doffer. The framing is now either brought close up to the edge of the cylinder, or the bend is put in that position (as shown in Fig. 74), or the gap between the framing and the cylinder edge is closed in some other way. This tendency to blow out and towards the formation of air currents is much greater in roller than in flat cards. But there are a few points at which the air can enter, and it does not need much thought to show that the great velocity of the cylinder will set up very powerful induced currents. Now, in this fact one explanation can be found of the cloudiness often noticed in the carded web, and of the existence of thin or bare places.

(131) The web is often marked or dotted with white specks, which, as can be plainly seen, are neither motes nor sticks. There is not much doubt that these are neps formed from damaged or broken fibres, which become knotted or matted together, and escape the cleaning action of the flats. This appearance, however, is very different from the cloudiness referred to, which is often visible over a large space. There is a ready explanation of this defect, which arises from an aggregation of fibres which have become overlaid and matted, being much worse in their lack of parallel order than the ordinary web. It is quite clear that if, in any given space, the fibres, when laid upon the doffer, are bent over, or deposited transversely, they will present quite a different appearance to that which they assume when laid in parallel circumferential lines. This, however, is what happens, and it remains to discover its cause.

(132) Between the last roller or flat and the doffer there is a considerable space, this part of the cylinder being covered by a metal plate correspondingly curved. In Figs. 72 and 90 this plate is shown, and it will be noticed that it completely covers the breast of the cylinder and is jointed to the cover which surrounds the doffer. As shown, the plate or cover descends into the space between the doffer and cylinder, and quite fills it up, thus preventing the accumulation of fly, which otherwise takes place. There is great care taken to fit the covers to their places, and they are provided with ample means for accurate adjustment. The surface of the steel plates, of which they are made, is kept bright and smooth, this being a matter of great importance. At the upper end of this plate there is a mote knife or sharp edge, by means of which a little further cleaning is obtained. If this plate or cover were not fixed in the position named there would be nothing to prevent the fibres from standing out in radial lines while held by the wire, and it is obvious that if they did so project they would be at the mercy of every current of air. This furnishes one explanation of cloudy webs. If by any possibility the air can be put into such motion

as to traverse across the face of the cylinder, the fibres will be immediately bent over in the same direction. A case is known where, in consequence of the existence of a considerable space between the wire on the cylinder and this covering plate, the fibres could be seen to gather up and bend over, often becoming practically doubled. The webs produced on the first series of cards put in were badly clouded, but by setting in the cover, so that the fibres were not able to be influenced, the defect was

FIG. 90.

quite remedied. It may be taken as the first thing to look for if cloudy webs are found, whether there is any possibility of transverse air currents.

(133) The same cause, probably, accounts for thick and thin places, or rather contributes to their formation. It has been previously said that an uneven lap is a fruitful source of uneven slivers, and there is little doubt that this element is the principal one, but it is clear that if the fibres can, before being placed on

the doffer, be moved across the cylinder so as to be aggregated, so to speak, there must be a thin place left in the web. To the existence of air currents may be attributed not only the ordinary position of the fibres in a well-formed web, but many of those abnormal features which are sometimes found in carding.

(134) Another point upon which a few additional words may be said is the action of the rollers and flats in removing short fibres and neps. With reference to rollers, their action, as was shown, is that of absolutely removing the fibres from the cylinder, and again transferring them to it by the intervention of a second roller. This involves the complete turning over the fibres, and as this cannot be so treated unless a considerable space is provided, the chances of the action of the air are considerably increased. But it is specially to be noted that the short fibres have a less tenacious hold on the cylinder or roller wire, and not being, after they are embedded in it, so long as those of full growth, are at once more easily removed from, and much more difficult to transfer to the cylinder. With reference to motes and neps, as they cannot penetrate deeply into the cylinder wire, they are easily picked up by the rollers, and are gradually forced into the interstices of the wire covering, from which they can be stripped.

(135) Making due allowance for the fact that the stripping surface is a stationary or nearly stationary one, the action of a flat, so far as the removal of impurities are concerned, is practically that of the roller. But where flats are used they are stripped more frequently, and there is therefore a chance of observing the quality of their work throughout the whole of the working period. As was pointed out, the flats are given a "heel"—that is to say, they are caused to assume an angular position relatively to the cylinder. It is thought by some spinners that the "heel" of the flat should vary with the length of staple carded. There might have been some force in this contention in the old days when flats were nearly double the width they are at present, but the difference which it would be possible to make with the present width of flat would be very

slight. The character of the strippings or "strips" which are taken from the flats as they leave the cylinder, is a very good indication of the setting and condition of the flats. If these strippings be observed it will be noticed that at the edge which receives the cotton first the "strip" is thinner than it is at the edge where the cotton leaves. This is what would be expected from the setting and construction of the flat, and it affords a perpetual means of ascertaining the condition of the flats while they are working. If the "strip" from one flat is heavier than that from another, the former is either doing too much or the latter too little work. If the thickness of the strip at the receiving end of the flat varies with different flats, it is a proof that the distance between the wire is not the same in both cases—that is, the "heel" varies. Thus a close observation of the strips enables two important points to be decided, and gives a guide to the carder which is invaluable. The examination of the strips carefully is a very profitable exercise, and the revelations of a strong magnifying glass are sometimes startling.

(136) The undercasings are of great importance in the working of a carding machine. These are grids placed as shown at R in Fig. 69, and are constructed as follows. Circular frames corresponding practically to the curvature of the cylinder are connected by transverse bars, and are so mounted that they can be easily and accurately adjusted in a short time. They are preferably made of tinned iron, and the bars are of a shape which permits the ready transmission of the fly without leading to any adhesion. Reference has already been made to the mode of setting the licker-in casing, and Messrs. Dobson and Barlow, Limited, whose arrangement is illustrated in Fig. 86, now attach one-half of the cylinder undercasing to that of the licker-in, so that they are set simultaneously. It is perhaps as well to say here that the licker-in pedestal and the casings are usually coupled, so as to move together. The cylinder undercasing is in the arrangement named in two pieces, one attached to the licker-in and the other separately adjustable. Special guides are formed at their adjacent extremities, so that they

maintain, when set, the correct relative position to the cylinder. The undercasings made by Messrs. Platt Brothers and Co., Limited, are specially constructed, the bars being secured to segmental wrought iron rings turned to the correct size. As the purpose of these casings is the provision of means by which the emission of "fly" and other impurities is possible, it is necessary in setting them, as in setting other parts of the machine, that special care should be taken. Full liberty should be given to the short fibre to be ejected through the grids, but damage to the cotton must be sedulously guarded against. No empirical rule can be given by which this can be made, and only close observation will enable the best distance to be fixed. A distance of about $\frac{3}{100}$ inch is a good one for most varieties of cotton, but this is a point which is always open to variation according to the necessities of the case. It is requisite to say, however, that this is a matter of great importance and should be closely watched, as otherwise a considerable increase of waste results.

(137) The flats have, as has been indicated, to be set very closely to the cylinder surface, and this is a matter which involves the consideration of one or two points. There are several machines made, for which it is claimed that they are so constructed, mechanically, that the wire surface on the flats can be brought within $\frac{1}{1000}$ inch of that on the cylinder. Now, it is not necessary to do more than point to the fact that this is a setting which closely approximates to the diameter of the fibre, and that if, therefore, these lie upon the surface of the cylinder as described, a very slight elevation of their free ends will draw them through the teeth on the flats. It is not, however, by any means a universal practice to make these close settings, and, as a matter of fact, in the majority of cases the two surfaces are much wider apart. It is customary to furnish the carder with several carefully ground slips of steel, called "gauges," which vary respectively, from ·005 inch to ·016 inch thick. In setting, the carder preferably chooses a time when the mill is quiet, and there is not the vibration existing which is always found during working hours. By means of his setting screws,

in the case of a flexible bend, and of the adjusting mechanism, when other forms of the machine are used, he lowers the flats until, by slowly turning the cylinder, a slight click, caused by the contact of the wire, can be heard. When, by this means, it has been ascertained that the two surfaces are in contact over the whole of the working face of the flats, the screws are reversed, and the contact destroyed. In setting by gauge this removal is carried on until the gauge can be slipped in between the faces without undue pressure, and it depends, of course, upon which of the gauges are employed, how great the distance is between the two surfaces. A similar procedure is pursued in setting rollers and clearers, the bearing brackets of which are provided with screws for this purpose. In setting flats by the special arrangements of mechanism previously named, the reverse movement is regulated by means of an indicator, dial, and finger, the dial being graduated by divisions, each representing $\frac{1}{1000}$ inch. After the operation is completed, the various screws are securely locked by means of nuts or some other similar or equivalent device, and the machine is ready for work. The real basis upon which this operation rests is the audible click made when the wire surfaces are in contact, and in endeavouring to obtain this great care should be taken to see that the contact is of the slightest character. The gauges used are of two kinds. For setting the doffer, licker-in, feed roller or feed plate, doffer comb, and flat stripping cone to their respective positions, a slip of steel ground to the required thickness, and about 2 inches wide, is used. Of these, six or seven are supplied to the carder, ranging, as was said, from ·005 to ·016. When the machine is standing, the gauge of the required thickness is pushed between the parts at several points across their width, which have to be set to each other until it has the " feel " of fitting. Some practice is required to be certain of the proper distance existing, but the skill is soon acquired if a little pains be taken. In setting the flats the gauges used are short and are turned up at right angles at one end to enable the operator to handle them. A particular flat is selected, and two of those

adjoining it are removed, so that the gauge can be easily slipped into the space between the flat and cylinder. The flat is then tested at five points in its movement over the whole length of the bend, the chain of flats being moved by hand and the adjustments made at each point. As all the flats are ground from one surface, it is assumed they are all uniform, so that setting one will imply the accuracy of the others; but care should be taken to see that there is no undue wear of the ends of any of the flats over that of their fellows. The following will give approximately correct settings for the various parts for American cotton :—Feed plate to licker-in, ·013 inch ; licker-in to cylinder, ·011 inch ; flats to cylinder, ·007 inch ; doffer to cylinder, ·005 inch ; doffer comb to doffer, ·005 inch ; flat stripping comb to flat, ·007 inch ; under casings to cylinder, ·01 inch ; mote knives to licker-in, ·015 inch. The setting of the doffer is very important, as if too closely set it will act partially as a stripping roller ; while if too widely set it will take off the cotton intermittently, and so produce an uneven or cloudy web.

(138) The coiler, as was shown, has within it two revolving parts, viz., the coiler-plate and the can disc. These rotate in opposite directions, and their velocity is duly regulated by the train of wheels shown. Assuming the doffer to be delivering 900 inches of web per minute, and the peripheral speed of the calender rolls to be the same, it will follow that there will be 900 inches per minute delivered into the can ; but, as a rule, there is a slight draft between the calender rolls and the coils. If the laying of this sliver in the can depended upon the rotation of the coiler solely, it would be placed in a series of ascending coils, as at one time it was. The result of this is that nothing like the same length is laid as should be, in addition to which the coils become entangled, and are liable to be broken in drawing out. By giving to the can a slow rotation in the opposite direction to the coiler-plate, the coils are laid in various positions and the centre of each succeeding coil is a little removed from that of the one preceding it. The result is that a much greater length is deposited, and

the coils are quite free from one another, and can be withdrawn with
ease. Referring now to Figs. 70 and 91, the coiler can is 9 inches
diameter, and is driven from the shaft B which, we will assume,
revolves at a speed of 100 revolutions per minute. The can disc
J is driven by the wheel train shown, of which D has 16 teeth,
E 48, F 16, G 48, H 14, and J 84. The speed of J is there-
fore $\frac{16 \times 16 \times 14}{48 \times 48 \times 84} \times 100 = 1\cdot85$. The coiler plate M is driven by
the engagement of the wheel K with the annular rack L. K

FIG. 91.

has 42 teeth and L 108, the velocity of the coiler plate being
therefore $\frac{42}{108} \times 100 = 39$. The coiler will, therefore, lay a com-
plete coil in the can in $\frac{1}{39}$th of a minute, in which time the
can will make ·0475 of a revolution. Thus in a complete
revolution of the can 21 coils will be laid, and the sliver will
receive 21 turns in the length of sliver delivered by the calender
rollers during that period. Thus, if the calender rollers are $2\frac{1}{2}$
inches diameter, they, being driven at an equal speed to the
upright shaft, will deliver 785·4 inches per minute, and during
one revolution of the coiler 424 inches. As 21 coils are laid in

that time, the length in which one twist is introduced is $\frac{424}{21} = 20 \cdot 16$, which is about the ordinary amount. The illustration given in Fig. 91 shows graphically the method of laying the coils. It is seen that the successive coils touch the edge of the can at one point, and the distance traversed by the can before the next coil touches it is shown by the space between the successive points indicated by the figures 1 to 29. It will be understood that the size and number of coils depends upon the eccentricity of the tube, and the relative velocity of the coiler

FIG. 92.

plate and can, but the principle is illustrated by the sketch given. It is a good practice to use two discs connected with a spiral spring within the can, as in this way a good deal of the strain on the sliver, as it is deposited, is removed.

(139) It now only remains to show the method of driving the various parts, and in order to illustrate this, the two diagrams given in Figs. 92 and 93 have been furnished. These represent a revolving flat carding engine, and the mode of actuating the mechanism. The cylinder A is driven from the driving shaft by means of a pulley A¹. Adjoining this

there is a loose pulley on to which the belt is moved when the machine is stopped. Referring now more particularly to Fig. 93, which is a diagram of the opposite side of the machine to that shown in Fig. 92, it will be seen that the licker-in B is driven by a crossed band passing over the pulleys R on the cylinder shaft and R^1 on the licker-in. The doffer is driven on the other side of the machine from the licker-in, as shown in Fig. 92, by means of a crossed belt passing over the pulleys C and D. As shown in Fig. 92, the pulley D is compounded with a pinion E, which gears with the wheel F; but in

Fig. 93.

order to get more exactitude it is now the practice to gear it as shown in Fig. 94. In further references, therefore, regard must be paid to both figures. The pulley D rotates on a shaft or pin and from it is driven a wheel E by means of the pinion D^1 called the barrow wheel, which is compounded with the pulley D. A small pinion E^1 is compounded with the wheel E, and can be changed when necessary, and engages with the wheel F fixed on the doffer shaft. The wheel E is carried on the lever J, which is retained in position by the catch J^1, so that when desired the pinion E^1 can be taken

out of gear with F and the doffer stopped. From the wheel F, by the wheels I I^1 and K, the calender rollers L L^1 are driven. Again referring to Fig. 93, the feed roller W is driven by means of a bevel wheel Z fixed on its axis, with which is meshed a pinion V^1 fixed on one end of a horizontal shaft, on the other end of which is a bevel wheel V engaged with a similar one F^1 keyed on the doffer shaft. By the train of wheels W Y Y^1 W^1 the lap roller X upon which the lap X^1 rests is

FIG. 94.

driven. The driving of these parts does not greatly differ in carding engines generally, and a clear grasp of this arrangement will enable others slightly modified to be easily understood. The chain of flats is driven by a band or cord which passes over a pulley M fixed on the cylinder shaft, by which through the pulley O, worm P^1, worm wheel P, worm Q, and worm wheel Q^1 motion is given to the pitched chain wheel actuating the chain of flats. The doffing comb is driven from a grooved pulley T by a band passing over the pulley T^1, which is con-

pounded with a second pulley U. The latter drives a pulley U[1] fixed on the shaft on which is mounted the eccentric or cam giving motion to the doffer comb.

(140) The following rules will be sufficient to enable the necessary calculations to be made. It has been explained that the lap is reduced by the variation in the speed of the different parts to a thin web, and that the amount of this reduction gives the "draft" of the card. To find this, multiply together the number of teeth of the driven wheels and the diameter of the doffer, and divide the product by that of the driving wheels and diameter of feed roller. There is a slight draft between the doffer G and the calender rolls L, which is arrived at by dividing the product of the driven wheels and the diameter of the roller L by the product of the driving wheels and the diameter of the doffer.

(141) There are two ways in which changes can be made in the weight of the sliver produced on a carding engine, viz., either by changing the pinion V[1] on the side shaft, or by altering the speed of the doffer by changing the wheel E[1]. Of these the former is the more convenient and usual course, and it is a simple proportion sum to ascertain the correct pinion required to make a change. If, for instance, a change was wanted from a sliver 65 grains to the yard for one 75 grains, the pinion V[1], of whatever number of teeth it was, would be changed for one $\frac{75}{65}$ of V[1]. Thus, if V[1] had 20 teeth, it would be $\frac{15}{13}$ of 20 = 23 about. The speed of the doffer is, however, important, for although it is quite true that all necessary changes can be made by reducing or increasing the rate of feed, whenever it is desired to get a bigger production, the doffer must be speeded also. This matter is of some importance, and its *rationale* may be dealt with in a few words. If the feed-roller has its velocity increased or diminished the effect is that more or fewer fibres are beaten down by the licker-in, and that, therefore, the delivery of cotton to the cylinder is increased or diminished. This means that the sliver will be affected proportionately. Now, while it is possible to increase the quantity of

cotton so brought within the range of the cylinder teeth to an
extent which is only limited by the capacity of the latter
to receive them, it is obviously not so easy to diminish it beyond
a certain point.   If the delivery of the lap is too far reduced,
the effect would be that there would be a number of bare places,
and that a sliver very irregular in substance would be produced.
Further, any change made must be accompanied by an adjust-
ment of the speed of the doffer, if it is desired to produce merely
an additional quantity of a sliver of some specific weight.   If the
feed is increased while the doffer speed remains constant, a
heavier sliver will be produced, while by speeding the doffer in
the same ratio the quantity produced, but not the weight per
yard, is affected.   If the substance of the sliver is known it is
easy to ascertain the production of the machine by calculating
from this and the surface velocity of the doffer.   If a doffer
24 inches in diameter is used, its diameter when clothed would
be be 24¾ inches.   This would, when making 12 revolutions
per minute, have a surface speed of 25 yards.   This in 56 hours
will give 84,000 yards delivered, and by multiplying this by the
weight per yard of the sliver, say 50gr., we get a production of
600lbs. per week.   In the same way the production of any given
weight of sliver can be ascertained.

(142) It will be noticed, if the arrangements just described
are studied, that between the motion of the cylinder and that
of the feed and delivery mechanism a close connection exists.
Thus the doffer and licker-in are connected directly, so that a
change in the rotation of the former is followed by one in that
of the latter.   In like manner the feed roller is driven from the
doffer and a close connection is thus established between that
of the two parts.   By changing the pinion E^1, or pulley D, the
velocity of the doffer can be easily regulated, so that it
can be run quicker or slower as desired, giving a thinner
or thicker sliver.   All the calculations about this machine
are of a simple character and can be readily made.   If
a = the number of revolutions of the cylinder, then those of
the licker-in are $a \times \dfrac{R}{R^1}$.   In like manner the velocity of the

doffer G is $a \times \dfrac{R}{R^1} \times \dfrac{C}{D} \times 1\dfrac{D^1}{E} \times \dfrac{E^1}{F}$. Let this latter quantity be

called b, then the velocity of the feed roller is $b \times \dfrac{F^1}{V} \times \dfrac{V^1}{Z}$. If,

in place of the letters used, the diameter of the pulleys and the diameter or number of teeth of the wheels which are indicated by the letters are substituted, a ready calculation can be made of the relative velocities of the parts.

(143) There are one or two other rules which may be given, and which are likely to prove useful. To find the draft required to produce a given weight of sliver, when the weight per yard of lap is known, reduce the weight of one yard of lap to grains and divide by the number of grains in the same length of sliver. This gives the draft. It may be preferable to take two or three yards instead of one, but the rule remains the same. To find the hank of the sliver, take a few yards (3 to 6) of the sliver as delivered into the coiler, ascertain its weight in grains, and divide into the dividend for the number of yards taken.

(144) The dividend is obtained by dividing the number of grains in a pound by the fraction which the length taken forms to the whole length of a hank. This number is 7,000, and as there are seven leas in a full hank, each lea, if one hank weighs a pound, weighs 1,000 grains, and is 120 yards long. One yard, therefore, weighs $\frac{1}{120}$ of 1,000 grains, or 8·3, which is the dividend for one yard. By multiplying this number by the number of yards taken a constant dividend is obtained, thus—that for six yards is $8\cdot3 \times 6 = 50$.

(145) It will perhaps be convenient if the method of calculating the draft be illustrated by a few examples. Referring to paragraph 141, the method of calculating the speeds of the various parts was referred to. Using the letters in Figs. 92, 93, and 94, let—

X Lap roller ... ... =	6ins. diameter.
Feed roller... ... ... =	2¼	,,
L Calender roller... ... ... =	3	,,

R Licker-in driving pulley... ... ... = 20ins. diameter.

R^1 „ pulley... ... ... = 7 „

C Pulley driving barrow wheel... ... = 6 „

D Barrow wheel pulley ... ... = 9 „

G Doffer ... ... = 24 „

W^1 Lap roller wheel ... ... = 48 teeth.

W Feed roller „ ... ... = 15 „

Z Plate bevel „ ... ... = 120 „

V^1 Side shaft change pinion ... ... = 15 „

V „ bevel „ ... ... = 22 „

F^1 Doffer bevel wheel ... ... = 22 „

F „ spur wheel ... ... = 180 „

K Calender wheel... ... ... = 18 „

D^1 Barrow wheel ... ... = 26 „

E Doffer lever carrier ... ... = 104 „

E^1 „ change wheel ... ... = 26 „

a Speed of cylinder (revs. per min.) = 170 „

Then the speed of the licker-in is $a \times \dfrac{R}{R^1} = 170 \times \dfrac{20}{7} = 485\cdot7$.

The speed of the doffer is—

$$a \times \frac{R}{R^1} \times \frac{C}{D} \times \frac{D^1}{E} \times \frac{E^1}{F} = 170 \times \frac{20}{7} \times \frac{6}{9} \times \frac{26}{104} \times \frac{26}{180} = 11\cdot7.$$

To change the speed of the doffer the pinion E^1 must be changed. In order to calculate the velocity of the feed roller, which is driven by the interposition of the side shaft from the doffer, it is necessary to use the formula $b \times \dfrac{F^1}{V} \times \dfrac{V^1}{Z}$ or $11\cdot7 \times \dfrac{22}{22} \times \dfrac{15}{120} = 1\cdot462$. By changing the pinion V^1 the draft can be altered at will, and when it is desired to have a lighter or heavier sliver this is what is done. The calender rollers are driven from the doffer wheel F (see Fig. 92) through I and I^1, which finally drive a change pinion K on the end of the calender shaft. The speed of the latter is therefore arrived at by multiplying the speed of the doffer by $\dfrac{F}{K}$ or in actual

figures $11 \cdot 7 \times \frac{180}{18} = 117$. In like manner the lap roller X is driven from the feed roller by the train of wheels W, Y, Y¹, W¹. Of these, only W, W¹ need be considered, and as the speed of the feed roller was $1 \cdot 462$, that of the lap roller is $1 \cdot 462 \times \frac{15}{48} = \cdot 457$. The total draft is naturally the quotient of the surface speed of the lap roller divided into that of the calender roller, and can be arrived at in that way. Suppose that the speeds were as given. Then the surface of the calender roller is $3 \times 3 \cdot 1416 \times 117 = 1102 \cdot 7$ and of the lap roller $\cdot 457 \times 3 \cdot 1416 \times 6 = 8 \cdot 61$. The draft is, therefore, $\frac{1470 \cdot 26}{8 \cdot 61} = 128$. No higher draft is necessary than 130, and 120 is about an average. The draft can also be obtained by multiplying all the drivers together, and the product by the diameter of calender roller, and dividing the final product by that of the driven wheels and the diameter of the lap roller. The quotient is the draft. If in making such a calculation the change wheel V¹ be omitted from it, a quotient which is called a "constant number" is obtained. It is very usual to employ this method of simplifying calculations in textile work, and such a number is simply the quotient with the variable factor eliminated. In the present case, if the constant number is obtained, the draft wheel or draft can be indifferently arrived at. Thus $V¹ = \frac{constant}{draft}$, or draft $= \frac{constant}{V¹}$. It follows from what has been said that by stopping at any point the intermediate drafts between various parts can be easily made. It only now remains to be said that the speed of the calender rollers in the coiler can be arrived at in the same way, the method of driving being very clearly shown in Fig. 70.

(146) To ascertain the length of fillet required to cover a cylinder, multiply the circumference of the cylinder by its width and divide by the width of the fillet. It is advisable to add to this a length equal to one circumference, as a certain waste is made at the tail ends.

G

(147) The following table gives the hank of slivers of various weights and will be useful for reference :—

Number of grains per yard.	Decimal Hank Sliver.	Number of grains per yard.	Decimal Hank Sliver.	Number of grains per yard.	Decimal Hank Sliver.
40	·208	58	·144	72	·116
45	·185	60	·139	74	·113
50	·167	62	·134	76	·1095
52	·160	66	·126	78	·107
54	·154	68	·122	80	·104
56	·148	70	·119		

CHAPTER V.

CARD CLOTHING AND GRINDING.

(148) Having thus explained the several points connected with the operation of carding, it is now necessary to deal with the various problems which are subsidiary to it. It has been shown that the whole of the working surfaces of the cylinder, doffer, flats, and rollers are covered with wire points, by which the carding is effected. As this "card clothing" is of great importance in the working of a carding machine, it is desirable to give it a somewhat lengthy consideration. Card clothing consists of a "foundation" of cloth, in which are set wire teeth in certain numbers per square inch, these teeth being constructed and set as hereafter described. In all card clothing there are several points which affect the general result. Of these the principal are—

(1) The character of the matrix or foundation receiving the teeth.

(2) The character of the wire as to shape, material, and preparation.

(3) The angle at which the wire passes through the foundation.

(4) The angle of the forward inclination given to the tooth
from the bend or "knee."

(5) The relative height of the knee and point.

(6) The size or thickness of the wire used.

(7) The setting of the teeth in the foundation.

The foundation usually consists of four or five layers of cloth
securely cemented together.   When so formed the foundation
must provide a base which is strong enough to be tightly laid
upon the surface which it has to cover without unduly stretching
or disturbing the setting of the teeth, while giving an elastic but
firm support to them during work.   The foundation which is
the favourite in England consists of three or four plies of cotton
and wool, or cotton and linen, or union cloth, with a top facing
of natural indiarubber.   For cylinder and doffer fillets a
foundation of three plies of cotton and a ply of union, linen
warp and cotton weft, cemented together and faced with india-
rubber makes an excellent one when used for carding American
cotton.   The chief defect of the indiarubber face is that it
disintegrates with heat and even long use, while its principal
advantage is that it gives at the point where the tooth leaves the
foundation a support which is elastic enough to yield, under
pressure, and bring the tooth back again.   The clothing used
for the flats is never faced with rubber because of the disin-
tegration caused by the direct rays of the sun falling upon
it.   The number of separate layers or "plies" used in
any foundation depends upon the work to be done.   For ordi-
nary uses three plies are sufficient, but an excellent combination
is that of an upper and lower layer of twilled cotton cloth, with
a double woollen cloth between.   The twilled formation of the
cloth gives a special firmness, while the presence of the wool
gives a soft but all-round grip which holds the tooth excellently.
The woollen cloth used must be well made and compacted, the
latter being an essential condition in putting the various plies
together.   The importance of the matter lies in the fact that if
a tooth is too rigidly held it is liable to be bent back or

" cranked " at the point where it leaves the foundation, or it may, if hardened and tempered, " break out." The desideratum is a foundation which will fasten well on to the cylinder, doffer, rollers, or flats without distortion of the teeth or stretching during work. It must be strong and flexible and be able to grip the wire with sufficient firmness, while having the quality of recovery after the teeth have been moved during work or grinding. The strength of a cotton-wool-cotton foundation cloth is, for a strip 1 inch wide, from 800 to 900lbs., and the elongation under moderate stresses is very slight. For hardened and tempered teeth it is the best foundation to use, and is gradually becoming more widely adopted. A typical foundation for the doffers and cylinders of cards producing 800 to 1,000lbs. weight of carded web from middling American cotton in 56 hours consists of a back of twilled cotton, a second ply of cotton, a third ply of linen and cotton union, a fourth ply of cotton, and an indiarubber face. For the " tops," as the strips covering the flats are called, the cotton-wool-cotton combination is adopted, a double ply of wool being used if extra strength be required, and being very desirable. The thickness of the foundation, if four-ply, is about 0·1 inch, this thickness being common with three-ply cotton-wool-cotton, the wool fabric being made stout in order to give strength.

(149) With reference to the second point—the character of the wire used—this is now almost universally steel, and the chief distinctions in it relate to its temper and the method of grinding it. Although for certain purposes mild steel wire is preferred, the great bulk of card clothing is provided with wire which is subjected to a continuous hardening and tempering process which gives it great resilience. The systems of hardening and tempering have so greatly improved in the past few years that it is possible to produce wire even in temper and polished on its surface. The wire is made of various sections, those most used being round or oval, triangular wire being mostly used for raising machines. The sections are shown in Fig. 95. With reference to the method of grinding, there are several ways of

doing this.   In some cases the wire is " top ground," that is, the teeth are ground transversely of their axes.   When " needle-pointed "—a most misleading term—the wire is ground on its sides near the point, so as to reduce its thickness a little, this variety being also known as " side ground " wire.   " Plough-ground " wire is usually made from round wire reduced as low as the knee to a flat section by passing rotating emery discs between the rows of teeth, a plough guide going in advance of each disc.   In the first variety there is no reduction of the thickness of the wire at any point ; in the second the reduction is slight, and at the point only ; while in the third it is considerable, nearly half the original size, as shown in the left hand view in Fig. 95.   As a rule, plough grinding and hardened and tempered wire go together, although the latter is often used with top or side-ground wire.   In determin-

FIG. 95.

ing the class of wire to be used, regard must be had to the work which has to be done by it.   For instance, if 350lbs. only of Egyptian cotton is to be passed through the machine in 56 hours, it is obvious that other conditions will prevail than when 900lbs. of American, which is less uniform in staple and not so clean, are to be carded in the same time.   If it be true that the holding power of a tooth is determined by the area of its point, which in the course of grinding is scratched or serrated in accordance with the fineness of the emery, then it is clear that a top ground tooth made from round wire, with an area 35 per cent greater than one which is plough ground, would hold the fibres more tenaciously than the latter.   It follows from this that while a moderate weight of cotton could be got from the top ground wire with ease, it would be impossible to put through the card the heavier weight.   In this case the plough-ground wire would be undoubtedly the best.   Much has been made of

the roughness of the sides of plough-ground teeth, but this is a factor which is much reduced, as shown in Fig. 96, which is an enlarged photograph of a side-ground tooth above the knee, and, everything being equal, it is not proven that loss of strength in the yarn results from their employment. It is undesirable to overcard cotton, and the quicker it is got out of hand the better, provided it is properly cleansed. In the opinion of the author, side grinding is worse than useless. It does not materially diminish the area of the point, while roughening the sides and disturbing the regularity of the setting of the teeth. Plough grinding, which diminishes the area of the tooth by about 45 per cent, does so without disturbing the setting of the teeth, and increases the space between the teeth to the same extent. As has been said, the neps, short fibres, and other impurities are deposited in the interstices of the teeth, so that with any cotton which contains much of these the increased space is of high importance, alike as a repository and also by reason of the ease in stripping. As it is extremely improbable that every tooth carries a fibre, the decrease in the area of the point is not of great importance, as with average cotton there will be sufficient retention of the fibre

FIG. 96.

to insure its effective carding. With Egyptian cotton the matter is different, as in this case the fibres are finer, more uniform, and cleaner than in American; the weight carded is much less, so that every fibre can be subjected to a longer carding action with advantage. In this case the round top-ground wire is preferable, and generally gives the best results. Before leaving the question of the wire, it may be said that, on the whole, hardened and tempered wire is to be preferred. By subjecting it to this process, the resilience of the wire is increased rather than decreased, a statement which is confirmed by common experience. If the action of a card tooth be considered, it will at once be seen that it must in the course of its life be subjected to an enormous number of oscillations on its

FIG. 97.

fulcrum, and in resistance to permanent set, hardening and tempering plays an important part. Another feature is that the life of the wire teeth—that is, the time they wear—is increased by hardening and tempering, and this affects not only the quality of the carding but also the strain put upon the teeth by repeated grinding.

(150) Coming now to deal with the setting of the teeth, which includes all the points numbered 3, 4, and 5, it is necessary to give a brief description of the method of construction. All card clothing which is intended to be used on circular surfaces is made in long strips or "fillets," which are capable of covering the whole surface without piecing. The "tops," as the strips covering the flats are called, are made in sheets a little wider

than the length of the flats, the teeth being set in a sufficient number of rows to provide a carding surface of a width which varies from ⅞ inch to 1¼ inch. When the teeth for one flat have been inserted, the sheet is given a rapid forward movement so as to leave a space between the two tops, the setting of the next top being commenced at one end of it. The teeth are made from a continuous reel of wire, being bent up into the form of a two-pronged staple, as in Fig. 97, the cross bar coupling the prongs being called the "crown." When the tooth is formed it is pushed through holes in the foundation which have been previously made by a tool called a "pricker," the fillet being held

FIG. 98.

at an angle to the pricker while being pierced, so that the tooth when forced home leaves the foundation at a certain definite angle. As soon as the tooth is fixed its points are seized by a special tool which draws them forward to a definite extent, bending them over a sharp surface which is placed at the level of the "knee" of the tooth. The amount of angularity given is a matter of great importance. All these operations follow in sequence at a rapid rate, being effected automatically by a machine of great ingenuity which is capable of setting 300 pairs of teeth per minute. Referring now to Fig. 98, which is a

diagrammatic view of a card tooth, drawn to scale from actual
dimensions, the foundation F is penetrated by the tooth B C A
at an angle with the horizontal of 75°.   Drawing the vertical
line D G through the point E, where the tooth leaves the foun-
dation, the position assumed by the point A can be defined.
This should be about three degrees in advance of A, the
inclination being given from the " knee " C, and being
technically known as the " keen " of the tooth.   Having thus
defined the various parts, it is possible profitably to consider
the reasons for the construction indicated.   Substantially the
line D G may be considered to be, when the clothing is fixed
in position on the cylinder, a radial line from the centre of the
latter.   In order to enable the tooth to seize and carry the
fibres it is essential that it shall form what is, in its essence, a

FIG. 99.

hook.   If it were not given the forward inclination—while it
would, no doubt, engage with the fibres—its carrying capacity
would be materially diminished.   As, in addition to this, the
grinding of the point is effected by passing the emery wheel
across its face, its presentation in a truly vertical position would
result in the formation of a tip at right angles with the front of
the tooth, instead of at an angle with it, which is the correct
formation.   The two results are illustrated in Fig. 99.   If, on
the other hand, the forward inclination of the tooth was too
great, the angularity of the point would be injuriously great,
giving too great a retaining power to the tooth.

    (151) A card tooth is to all intents a lever which, when
subjected to pressure, oscillates upon its fulcrum which, in this
case, is theoretically the crown.   It is quite true that when the
pressure is slight or within reasonable limits, the foundation will
yield and permit the whole of the tooth within it—say from B
to E, in Fig. 98—to move back.   When the pressure applied is

excessive the resistance of the foundation increases, and becomes greater than that of the tooth.   The result is that the fulcrum of the tooth is moved to E, and flexure takes place at that point.   If the pressure is continued the tooth will bend at E— being then said to be "broken" or "cranked" back, and in some cases fracture or "breaking-out" takes place.   It follows, from what has been said, that any disturbance of the true conditions will facilitate the action named.   Thus, if the angle of the tooth with the foundation at E be too acute, if the height of the "knee" C be too great, or if the strength of the wire be insufficient, the tendency towards breaking back or out will be much increased.   Another fault arising from the existence of an angle at the base, which is too acute, is that it becomes neces-

Fig. 100.

sary to make the "keen" of the tooth greater, thus causing the point to be too sharp, and lessening the resistance of the tooth to collapse when—as in grinding—a pressure is put on it in a radial line towards the cylinder.   This is illustrated in Fig. 100, which shows in an exaggerated form a shape of tooth having the defects named.   The angle at Z is too acute, as is also the angle X Y Z.   Applying a weight in a vertical line at X would tend to cause the tooth to collapse at Y and Z alike, while the tooth A C B in Fig. 98 would stand up better to its work.   Again, the application of a pressure at X in a horizontal line would tend to push back the tooth at Z much more than a pressure at A would affect the angle at E in Fig. 98.   Further, as the space between the teeth becomes filled during work with

fly and motes, they require removing by a stripping brush,
which is made of light steel wire, and if the angle of the tooth
with the foundation is too acute, the removal from below the
knee becomes more difficult. Thus the tooth gradually gets
supported at a higher point, and its elasticity is considerably
lessened. With regard to the vertical position of the knee, this
affects the resistance of the tooth to breaking back and its
" keen." The rule is with clothing for carding cotton to make
the tooth so that a ratio of 3 to 4 represents approximately the
length of the tooth from crown to bend and bend to point
respectively. Cards which are made for cotton waste, and
sometimes for roller and clearer machines, have the bend mid-
way of the tooth, in which case it is said to be " middle bend,"
but in the majority of instances the proportion of 3 to 4 is

FIG. 101.

approximated to. The forward inclination of the tooth, which
was the fifth point detailed, plays an important part in the
proper working of the clothing. Card teeth invariably work in
opposition to each other, and, as the distance separating them
is slight and fixed, it is essential that there shall be no danger
of contact between them during work. If the point of the
tooth be too far in advance of the vertical line, and the tooth is
pushed back during work, there is great danger of it oscillating
on its centre, and rising above the plane in which it is supposed
to be working. In order to make this matter clear let reference
be made to Fig. 101. In this the tooth is assumed always to
leave the foundation at an angle of 75° from the horizontal,

but to be bent forward so that its point terminates 3, 10, 15, 20, 25° respectively to the right of the vertical line. If now, lines be drawn parallel with the base through these points respectively, it will be seen that they pass below the crown of the arc of the circle which the point of the wire describes when it is oscillated. If, therefore, the respective lines indicate the normal plane in which the point works in each position, it is at once apparent that if the tooth be caused to radiate about its fulcrum in the direction of the arrow, its point will rise above its normal plane, and will, if continued far enough, come in contact with any superposed surface. There is also a tendency for the tooth to straighten at the knee, which affects its action. An ingenious attempt has been made to show that no such

FIG. 102.

contact can take place, but experience demonstrates that it does, and not infrequently. There are many instances in which this action occurs, and in which the only explanation is that given. In Fig. 102 a view of a few teeth correctly set are shown, the illustration being taken from a photograph of an actual piece of clothing.

(152) It is now necessary to say a few words on the method of grading the wire used for various purposes. Before it became customary for card teeth to be set in fillets they were always set in sheets 4 inches wide and 10 crowns in each inch of length. The setting used was known as "plain," and is shown in Fig. 103, the points being indicated by spots, and the crowns by

the dotted lines. The fillets now used have the teeth set as in Fig. 104, this particular form being known as "ribbed" setting. The tops are always "twilled set," as shown in Fig. 105. If the back of a cylinder or doffer fillet be examined it will be seen that the teeth are set in rows or ribs, there being a clear space between each rib, which consist of successive groups of three crowns set so as to overlap each other. Under the old system the number of crowns per square inch gave the "counts" of the clothing. With the newer settings the matter is more complicated. Thus, a sheet 4 inches wide, with 100 crowns in that width, was 100's counts and there were $\dfrac{100 \times 10}{4} = 250$ crowns in a square inch.

FIG. 103.

In like manner, 110's had 275 crowns, and 120's 300 crowns per square inch. In other words, the number of crowns is counts × 2·5 and the number of teeth counts × 5. This remains as the basis of calculation, and can be used, no matter how widely the traditional setting is departed from. Thus, take a cylinder fillet 2 inches wide, with 8 ribs or 24 crowns in that width, and with 23 crowns in each inch of length measured on one row. There are thus 48 crowns in 4 inches. Care should be taken to count only those teeth or crowns which are on a straight line on each edge of a rib in ascertaining the number in each inch of length, as the triple combination is taken into

account in the width.   In the instance quoted there are, there-
fere, $48 \times 23 = 1,104$ crowns in 4 square inches, or 276 in one.
Dividing this by 2·5 we get 110's, which is the counts.   Again
let us assume we have a fillet with 7 ribs or 21 crowns in 2
inches, but 26 teeth in each inch of length, then the calculation
is $\dfrac{42 \times 26}{4 \times 2·5} = 109·2$.   In this case it will be noted that the counts
are not quite full, but the effect of getting 26 crowns in each
inch of length is to crowd the teeth, a procedure which is
inadvisable and necessitates the use of a finer wire.   If a doffer
fillet be taken with 6 ribs in 1 inch wide and 25 crowns per
inch long the calculation is $\dfrac{48 \times 25}{10} = 120$'s.   It is advisable in

FIG. 104.   FIG. 105.

every case to take the number of crowns in 4 inches wide,
because if 1 inch be taken it is sometimes necessary to break a
rib.   Thus, in the seven-ribbed cylinder fillet dealt with above
the number of crowns in 1 inch is only 10·5, but even from this
the calculation can be made thus $\dfrac{10·5 \times 26}{2·5} = 109·2$ as before
The rule may be thus formulated : Number of crowns per inch
wide × number of crowns per inch long $\div 2·5$.   As each crown
implies two teeth, the number of the latter per square inch is
double the number of crowns.

(153) With reference to the counts of wire used for the various organs these vary in accordance with the work to be performed. For carding American cotton, fillets of 110's counts are employed for the cylinders and 120's counts for the doffers and tops. Egyptian and fine staple cotton are best dealt with by clothing of finer counts. The exact counts used depends upon the work to be done, and where heavy weights are passed through flat cards 100's counts for the cylinder are preferable; the doffer and tops being reduced proportionately. For roller and clearer machines, the cylinders and rollers may have 100's wire on the cylinders, the clearers 110's, and the doffers 110's to 120's. For Indian cotton carded by the revolving flat machine nothing finer than 100's on the cylinder and 110's on tops and doffers should be used. Some people prefer to have the wire coarser on the flats and finer on the doffers, 80's for flats and 120's for doffers having been advocated. It depends on the amount of carding wanted, but generally speaking, it is not advisable to have the counts of wire on the flats coarser than that on the cylinder. The wire used in making card teeth is regulated as to size by a special gauge which is graded on a scale fixed by the clothing manufacturers. For 100's counts, the wire is made 31 gauge; for 110's, 32; for 120's, 33; and for 130's, 34. In carding fine cotton with top-ground wire, the thickness of the wire is sometimes made a gauge or half gauge lighter, but as plough grinding reduces the thickness of the wire above the knee it is advisable to keep it of the full strength below that point. The licker-in is clothed by teeth which are of much coarser pitch than the cylinder teeth, and are of the shape shown in Figs. 106 and 107. As shown in the end view, the part of the steel strip in which the teeth are cut is thinner than the portion forming the base, which is wide enough to fit tightly into the spiral grooves cut in the licker-in body. The pitch of the grooves varies, being from ·166 inch to ·1 inch, according to the class of work being done. It follows from this that when the strips are in position the teeth do not follow each other in circumferential lines, but overlap to an extent corre-

sponding with the pitch of the spiral. Thus each succeeding
tooth strikes the lap a little to one side of its predecessor, and
the removal of the fibres is much facilitated.   To a smaller
extent the teeth on the cylinders and doffers are also disposed
in spiral lines, as the clothing is necessarily wound on spirally.
The licker-in teeth, as shown, are made of two shapes, one
(Fig. 107) less angularly and more openly set than the other.
The finer tooth is used when no undercasings are employed
under the licker-in, but this is a practice to be deprecated, as it
leads to a considerable loss of fibre.   The clothing strips for
the licker-in are known technically as " Garnett " teeth.

(154) In covering cylinders, doffers, and rollers, it is necessary
to exercise great care.   The fillets, before being put on, should be
kept for some time in some place where the temperature is equal to,

FIG. 106.

FIG. 107.

or a little greater than, that of the card room.   If this is not done
they begin, when fixed, to expand and rise in particular places,
forming what are technically called " blisters." It was pointed out
that the cylinders and doffers are carefully prepared to receive the
clothing, and have what are practically smooth surfaces.
Opinion differs as to whether it is desirable to prepare these
by covering them with a thin coating of paint or thin calico.
If the latter practice is carried out, care must be taken to paste
it in position, so that it lies evenly over the whole area.   There
is, however, an increasing tendency to wrap the fillets on the
bare surface, and it is now believed that the fillet can be so
fixed as to avoid any danger of slipping, which is the only
motive for preparing the cylinder surface.   It will be at once

recognised as very important that, once the cylinder is covered, the clothing should be firm and immovable, as otherwise the setting of the various parts to the exactitude previously described would be impossible.   Assuming that the cylinder is left without special preparation, it is advisable to mark on it in chalk the date of covering it, so that the life of the clothing can be ascertained.   The method of covering the cylinder is as follows : The fillet is fastened at one end by means of a tack driven into one of the wooden pegs which fill the holes drilled in the periphery, and is then wound on by the rotation of the cylinder.   The fillet may be put on manually, or by a specially constructed machine which exerts a definite but adjustable tension upon it as it is being wound.   The latter plan is, by far, the better one, as the machine is so constructed that a very regular drag is exerted, and the fillet is, therefore, stretched equally throughout.   The tension at which the fillets are wound on the various parts is as follows :—For cylinders, mild steel wire 230lbs., hardened wire 270lbs. ; for doffers, mild steel wire 160lbs., hardened and tempered 175lbs.   As soon as the whole surface is covered the other end of the fillet is secured in the manner as described, and the cylinder is allowed to stand for a few hours to permit the elasticity of the foundation to adjust it over the whole surface.   The clothing is then tacked down by means of a special tool, which drives a tack into the various wooden plugs referred to.   Before covering the cylinder it is advisable to mark on a staff the position of the plugs transversely, so that the tacks may be driven without having to run the risk of damaging the clothing.   If this operation is properly conducted the fillets will lie close together, without gaps, and will be firmly and solidly bedded on the surface of the cylinder.   A similar procedure is followed with the doffers and rollers.   As the fillets are wound on spirally, it is obvious that at each end of the cylinder and doffer it is necessary to cut them away, so that they do not overlap.   There are two or three ways of shaping the fillets at the " tail ends," but the simplest is to cut it diagonally at the required angle to suit the pitch of the spiral

Flats are covered with strips made as indicated, which can be attached in several ways. Until recently the most common method was to drill a number of small holes near the edges of the flats, and to pass through these, and similar holes made in the top, lead rivets. One side of the top was first fastened by these rivets, care being taken that it was absolutely in contact with the under side of the flat throughout its length. The top was then stretched by a suitable instrument and the other edge riveted. Another method is to secure the strip by clasps which pierce it and the flat, and are clenched rapidly on the underside. This plan is an improvement on riveting, as it protects the strip from the action of the revolving brush which otherwise frays it. The edge of the top strip is necessarily acted on by the stripping brush, and was rapidly worn. All these methods are rapidly giving way to specially constructed clamp fasteners, of which there are now several varieties. The adoption of the clamp fasteners has led to a further important improvement. It is evident that any slackness of the top upon the flat would seriously affect the carding action, and would, in addition, prevent the teeth from being so firmly held. It is, in fact, imperative that the top shall lie quite close to the surface of the flat over its whole area, and to this end it is slightly stretched. In the operation of stretching it is imperative that no undue straining of the clothing shall take place, and more especially that it shall not be so stretched that any distortion takes place in the rows of the teeth near the edges. Some interest, therefore, attaches to the devices adopted. The first clamp, taken in chronological order, is the Tweedale, shown in Fig. 108. It will be noticed that the flat is formed at its underside with a semicircular bead, and that the edge of the top is enclosed within and gripped by a ⊃-shaped portion of the clamp. The operation of attaching the clamps to the top precedes the introduction of the flat, and the latter—which is specially formed—is made a little wider than the space between the two clamps when they are fixed on the top. Thus, when the flat is pushed between the clamps, it stretches the clothing, and when it is pressed down so as to be

firmly bedded, the free end of each clamp is, by a special machine, turned over the bead on the under side of the flat.   The stages are thus—attachment of clamps, introduction of flat and stretch ing of clothing, and final attachment of clamps to flats. Ashworth's fastener, which is a clamp of very ordinary construction, is shown in Fig. 109, and is differently applied.   One edge of the clothing is first fastened to the flat, the operation being completed at once, and, by means of a comb which first penetrates the clothing and then moves outwards, the clothing is stretched.   While in that condition the second clamp is attached.

FIG. 108.   FIG. 109.

(155) The foregoing description will have enabled a clear understanding to be obtained of the construction and method of attachment of the wire clothing, and it is now necessary to consider the most important question of grinding or sharpening the tooth.   It has been said that the clothing is sometimes called needle-pointed.   This is evidently an exaggeration, because the conditions under which the clothing is formed and applied

entirely prevent the construction of any such point. A needle point must of necessity be round and gradually tapering, and it is difficult to conceive of clothing being made in which this type of tooth was inserted. It certainly could only be done by machine with great difficulty, and would involve the manual setting of each pair of teeth. But suppose the teeth to be fixed, they could not be resharpened when the points were worn, because the pitch of the teeth is at most $\frac{1}{20}$ inch longitudinally, and from $\frac{1}{22}$ to $\frac{1}{37}$ inch transversely. A needle tooth being circular—although its original formation is easy—could not be ground at its point while in position, and unless this can be done its use is impracticable. If a true needle point could be practically adopted there is no doubt of its immense value, but as it cannot, the next best system must be taken. The usual solution of the difficulty is found in the formation of a tooth with a chisel or knife edge, which is presented to the action of the cotton. This is obtained by "plough grinding," and also by the employment of double convex wire. It does not require pointing out that when the machine has been working a short time the teeth become dulled at their points, and require to be sharpened. This is effected when the cylinder is dealt with, by removing the cover above the doffer, and bringing a grinding roller carried in bearings P (Fig. 72) into contact with the wire on the cylinder. By slowly rotating the cylinder and rapidly revolving the grinding roller the whole of the teeth on the former are ground. A similar procedure is pursued with the doffer. Rollers and clearers are removed from the carding machine, and are ground in a special machine constructed for the purpose. The flats of revolving flat carding engines are ground in position, the roller being placed in the bracket T shown in Fig. 72. There are two points connected with the operations thus briefly summarised about which something may be said.

(156) The cylinder is, as has been intimated, rotated at a slow velocity while being operated on by the grinding roller. At first sight it would appear that if the cylinder were revolved at its working speed during grinding the finished surface would

be consequently much truer. This is only partially true, as the experience gained in grinding all kinds of articles to a true cylindrical shape, shows that a slow velocity of the article operated on, and a quick one of the grinding wheel, give the best result. It is found that only in this way can a true cylinder be made, and what holds good in other cases is equally applicable to this. The cylinder is, therefore, reduced to a velocity of from $1\frac{1}{2}$ to 4 revolutions per minute by various arrangements of wheelwork or other gearing. Some of these necessitate the use of a separate and detachable piece of mechanism, in order to effect the reduction, while others are permanently attached to the machine, and can be thrown in or out of gear as desired. The general result of them all is, however, to give to the cylinder that reduction of motion named, and damage to the wires is thus reduced to a minimum. It is, however, customary to effect the major portion of the grinding in the method described, and to give a light grinding to finish, with the cylinder running at full speed. Where the clothing is well looked to, and repeated grinding given to it, it is often the practice to dispense with slow grinding altogether. Slow motions are applied, by which the speed of the cylinder is reduced during grinding, and they are also of value during the period when a new lap is being put in. If the cylinder and doffer during this time are allowed to run at their full speed, the doffer completely strips the cylinder and the web would be broken. By running at a slow speed the work of stripping is continuously carried on during the period of change, which is of great importance.

(157) The grinding rollers employed are of two types. In the first the roller is made of equal width to the cylinder, and is covered over its whole surface either with emery or emery filleting. In the second the grinding is effected by a narrow roller which is mounted upon a cylindrical roller or shaft on which it can slide. By means of an ingeniously arranged keybed at the bottom of the key groove, in which a fork fixed in the emery roller engages, a reciprocal sliding motion is given to the latter as the shaft is revolved. Thus not only does the rotation of the shaft drive the

roller, but it also gives this to and fro movement to the roller. It should also be stated that the continuous grinding roller receives a similar reciprocal motion, the object of which is to bring into operation the cutting edges of the various grains of emery, and so avoid excessive wear at fixed points. Either the broad or narrow roller may be covered with ordinary emery or by fillets or strips of emery cloth. The latter is the plan which is most preferred, and special arrangements are made for retaining the fillet in position. A grooved emery filleting, made by Messrs. Dronsfield Brothers Limited, in which the surface is formed of several raised parts or ridges, is in much request, and for the tempered steel wire now employed is found very serviceable.

(158) The flats, as has been said, are ground in position. In Fig. 72 brackets T are shown fixed to the framing at each side

FIG. 110.

of the cylinder, and act as bearings for the grinding roller, which rotates above the flats. At this point the latter have their wire surface upward, and they are held up by means of weighted levers which press upon their under sides and force their working faces against brackets placed for the purpose. There is involved in this operation a point which is of interest and importance. The flats are constructed, as previously shown, with their bearing surfaces parallel with the surface upon which the wire strip is fixed. This is shown diagrammatically in Fig. 110, where A B D C represents the end of the flat which ordinarily rests upon the " bend." The wire surface is represented by the line E F, and this it will be seen is parallel with the line C D which represents the bearing surface, but angularly disposed to the surface A B,

which is the back or upper edge of the flat. Now it is obvious
that if the flat is held on the surface A B while it is passing
under the grinding roller, the surfaces E F and A B will
become parallel with each other; and the heel, although remaining
in the surfaces C D, will, so far as practical purposes are con-
cerned, be entirely destroyed. It is, therefore, the practice to
sustain the flats, while being ground, in such a manner that their
surfaces C D are pressed against the guide-plate, and the parallel
relation of C D and E F is thus maintained. As was pointed
out at an earlier stage, while in theory this explanation is sufficient,
in practice it is necessary to take into account the curvature of

FIG. 111.

the cylinder and bend. If the diameter of the circle through the
points of the teeth be 51 inches, and the width of the carding
surface of the flat 1 inch, then the height of the arc, with a chord
1 inch long, is easily ascertainable by a well known rule, being
equal to the versed sine. It is the custom in some cases to grind
the wire surface of the flat to the radius of the circle formed
by it when in position, and strictly, this should be
maintained throughout the life of the flat. During the
whole period the flats are being ground they are moving on

wards, so that the provision of a properly constructed guiding surface is not so simple as it looks. There are several devices for doing this, of more or less merit. They are mainly based on one of two constructive principles, arrived at by practice. First, the provision of a plate with an angular surface so arranged as to give the requisite angularity to the wire surface, or maintain it in one plane during grinding ; or second, the provision of a surface of the required angle which moves with the flat until the latter is ground, when the bearing surface is released and returns to engage with the next of the series of flats. The object in all these devices is the same, although their mechanism differs, viz., to keep the surface E F in a plane which is coincident with that in which the grinding edge of the roller moves, while sustaining the flat on the face C D.

(159) One of the best known of these devices is Higginson and McConnel's, shown in Fig. 111. It consists of a bracket A fixed in a corresponding position to T in Fig. 72, and having at its upper portion C a slot in which the slide D is fitted. The slide has its under side shaped so as to give the necessary inclination to the flats when they are pressed on to it during grinding, and has a lip at one end of it. It is kept normally pressed to the left by the spring E. The flats G, of which only two are shown, move in the direction of the arrow, and when turned face up the chain lugs mount upon the nose of the short lever H, on the spindle of which a bell crank lever with a balance weight on is also fastened. The weight, which is not shown in the drawing, presses the end H upwards, the range of movement being determined by the set screw I. As the flats traverse, they mount upon the higher part of H, and are thus pressed into contact with the incline on the slide D, moving onward until they engage with the lip on D. When in this position the wire face of the flat is in the horizontal plane, and passes gradually under the guiding roller B. As the flat moves forward it carries the slide D with it until the whole of the wire is ground, when the chain lug passes over the nose of H and the flat falls. The slide D is thus released, and the spring E

pushes it back into the position necessary to receive another flat.
The effect of this arrangement is that the wire is kept in one
plane during grinding, being held in position by the contact of
its working face with the slide. Little friction is caused, so that

FIG. 112.

no extra stress is thrown upon the chain. Another form of
apparatus is Edge's (Fig. 112), which consists of a curved plate
B fixed to the grinding bracket. The flats C traverse over this
plate, and when they reach the centre the chain lugs pass on to
the raised portion B', which is long enough to permit each flat

to remain in contact with it while under the grinding roller. The grinding roller G is sustained and rotates in a bracket or bearing resting on a cylindrical stem E^1, fitting within a cup, and also in a similar recess or barrel E. The latter has a long boss, forming part of the plate D, the necessary adjustment of the under side of D being thus easily made, so as to give any desired pressure of the grinding roller. As the flats C traverse, they successively ride upon the projection B, forcing their working surfaces against the under side of D, which is shaped so that the traverse of each flat causes one side to become depressed and the other to be elevated. The change in the position of the plane of the flat face is sufficient to present the wires to the grinding roller in correct position, while the ease of adjustment enables an accurate pressure to be established and maintained.

(160) In these various arrangements, however, the flats are turned with their faces upward, and although they are strongly constructed with a strengthening longitudinal rib, there is a little deflection occurs between the sustaining points. Now it is obvious that, however little this deflection may be, the wire surface will be affected by it, and that, although it is very slight, not more than ·003 inch, yet the points of the wires will be arched to that extent. In other words, the centre will, while face up, have less ground off than the ends. The evil does not, however, stop here, because when the flat is again turned face downward, as it is when in working position, there will be a similar deflection in the opposite direction, so that the centre of the flat will be practically about ·005 to ·006 inch below its ends. When the setting is supposed to be made to ·001 inch it is clear this is a matter of importance. For this reason, therefore, mechanism has been designed by which the flat is ground with its face downward, while moving on a surface designed to preserve the heel. In one or two cases this involves the lengthening of the chain of flats, but by a recent arrangement, shown in Figs. 113, 114, 115, Messrs. Dobson and Barlow have overcome this difficulty in an ingenious manner, by so arranging the chain of flats that at the

point where the grinding bracket and roller are fixed, the chain is lengthened, and the flats pressed upon a surface corresponding to that on which they ordinarily travel. The grinding roller, which is placed just above the licker-in and between the working and idle flats, is pressed up to the wires, and is, as the flat

FIG. 113.

FIG. 114.

travels gradually, raised a little higher, to an extent equal to the heel required. After the flat is ground it is released and automatically resumes its normal position, all the parts of the apparatus assuming the necessary adjustment to recommence the arrangement. The cylindrical grinding rollers ordinarily

FIG. 115.

used to grind the flats are turned on their grinding surface to a curve supposed to correspond to that produced by the deflection so as to compensate for it.

(161) All the brackets carrying the grinding rollers are supplied with the necessary adjusting screws by which the

roller can be brought into contact with the wire surface. The greatest care should be taken in setting this roller. The procedure is similar to that of setting the flats to the cylinder, as described in par. 137, but in this case the gauges are preferably thin slips of paper, by pulling which the equality of the pressure upon the roller can be ascertained. It is essential, for reasons which will be presently detailed, that the contact should be a light one, but with ordinary care there need be no difficulty about this.

(162) It has already been intimated that the tooth is ground for the purpose of producing a chisel or knife edge, which is the nearest approach possible to a needle point. The purpose for which a needle point is required is to provide a carding surface which is of so delicate a character that it is able to deal with each fibre separately. It is easy to see that if the carding points were, say a $\frac{1}{4}$inch broad, the fibres would practically be scutched instead of carded, and any such construction would be fatal to efficiency. What is wanted is a point which will easily travel along a single fibre, or through a number, so as to scrape without injuring it, and thus complete the cleansing process. It is obvious that the finer and smoother the tooth the more likely it is to fulfil this important object. It is well established that the effect of any grinding process upon the material ground is to leave upon its surface grooves, scratches, or scores, the depth and pitch of which depends entirely upon the character of the material used in grinding. The material which it is neces-necessary to employ, or, at any rate, which is always employed, is emery, and even the finest grades which are commercially usable will have a considerable effect upon the surface to which it is applied. This has been very clearly shown by a number of experiments, and is very well established. By the aid of micro-photographs (like that in Fig. 95), the effect is fully demonstrated, but any reader, with the aid of a moderately strong magnifying glass, can see them sufficiently plainly without effort. Thus all plough-ground wires are more or less abraded and scratched on the side of the teeth, and, if left untouched, are

apt to produce an ill effect upon the cotton. It will be remembered that the cotton fibre is sheathed in a coating of wax, the preservation of this sheath being absolutely necessary for efficient working in the after processes. A rough tooth will present a saw-like surface to the fibre and will scrape off some of the wax from it. Whenever this happens a fine white powder will be found about the various parts of the machine, particularly about the trumpet guide and the mouth of the coiler. This is a certain sign that the fibre is being damaged, and whenever it is observed an examination of the wire should be made. It is a very much preferable practice to burnish the wire periodically by means of a wire brush, as in this way the roughened surface is made smooth and a much better carding tooth is obtained. The use of a brush of this character in which the bristles penetrate the teeth at intervals is very advantageous, and can be recommended to all who wish to get the very best effect.

(163) Having got a side ground tooth which has smooth sides, and having fixed it in position on the cylinder, the next thing is to grind it on the point. The mechanism for effecting this has been described, and it will have been noticed that the grinding roller can be set so as to exert any desired pressure. It is however extremely injudicious to grind heavily, as there is great danger of bending or barbing the wire teeth. If the emery roller is pressed too hardly down upon the tooth, the metal is made to flow over the front edge of the tooth and leave a barb or hook. The effect of this is that as the wire moves it gets hold of the fibres in such a way that they cannot easily be withdrawn, and they begin to collect until they are forcibly detached and many of them broken. Bad carding is the inevitable outcome of hooked wires, and nothing is more fatal to good work, the essential condition of which is the freedom of the passage of the tooth through the cotton. If this be not the case it is idle to look for an even web composed of fibres of full length and strength. In practice it is infinitely preferable to grind lightly and often than to wait for the card points to get dull and then grind them heavily. The diagrams given in Fig. 116, will illustrate this. A is the shape of the

upper part of a card tooth, the carding edge of which is sharp
and clean ; B is a tooth which is badly worn at the front, so as
to be quite rounded, and the dotted lines across the top shows
the amount which requires to be ground off ; C is the result of
heavy grinding, a hook or barb being found existing at the
front edge ; and D is a tooth only slightly worn, which, when
ground, will show a sharp clean carding point like E.   It must
be understood that these are merely diagrammatic representations
of what happens, but they illustrate the point being dealt with.
It is clear that if a barb is formed at all the chance of effective
carding is lessened, and it is also clear that if the wire is
allowed to become so far worn as to necessitate heavy grinding,
the chance of forming a barb is greatly increased.   It is, there-
fore, a preferable plan to grind the cylinder lightly once a month

FIG. 116.

than to grind heavily at longer intervals.   Very much more
depends upon attention to this matter than many carders appear
to think, and observation is the only guide to correct practice.
Two slivers, which shall be produced from laps formed of the
same mixing of cotton, made up at the same time, will yet be
entirely different in their appearance.   They may both be
perfectly well carded so far as motes and short fibres are con-
cerned, and yet one will be bright and lustrous, and the other
dull and dirty looking.   Many such slivers have been inspected,
and in almost every case it is found that it is from the setting
and condition of the wire that the difference in result arises.
Any roughness or want of sharpness of the wire speedily affects

the quality of the product. It is therefore essential for good work that the condition of the wire should be the very best it is possible to obtain.

(164) Not only is it essential for the proper conduct of carding that the wire teeth should be sharp and smooth, but they should periodically be thoroughly freed from the accumulation of short fibres, neps, and motes with which they become charged. Everything depends upon the maintenance of the freedom of the wire tooth, and it is obvious that if it is embedded in a mass of waste material it cannot be as effective as when quite free. The flats, in revolving flat carding engines, are stripped after every passage they make over the cylinder, so that they are always in the best and most cleanly condition. The cylinder wire, which does not do much more than act as a carrier for the fibre, will, of course, be in good working condition for a much longer time than the flats or rollers, because a little accumulation is not of so much importance as it is in wires which have actually to card. The proper period of stripping depends also upon the character of the cotton used, and this is a factor which varies from year to year, as was pointed out in Chapter II. In a season when the pod bursts open before many of the fibres it contains are fully matured, there will always be a large percentage of short fibre, so that a rule which holds good one year is of very little service the next. Cotton which, like Indian, contains a good deal of immature and short fibre, necessarily fills the wire much sooner than a cleaner variety, and stripping must be carried out oftener. It has already been pointed out that the character of the strippings is a fair indication of the quality of the work done, and they should be carefully looked to to see that good fibre is not being removed with the bad. For very fine work stripping is carried out several times a day; while with good, clean American, for ordinary work, once or twice a day is sufficient. It is very good practice to strip the cards in regular rotation, so that there is always a fair proportion of the machines with clean wire, and the carding throughout the room will be evener in

quality, as an average. The use of a wire roller for stripping cylinders and doffers is preferable, not only because it is more convenient, but also on account of the burnishing or polishing effect upon the wire. Before leaving this point it may be repeated that "good carding is absolutely essential to good work. With it a good even yarn can be made. Without it no such result need be looked for. It is impossible to lay too much stress upon this point, and the care bestowed upon the machine and its clothing will amply repay the spinner."

(165) The whole of the points which it is necessary to deal with at length have now been treated, and it only remains to be said that the attention of the carder should be especially given to the question of cleanliness. In an operation of this kind the prevention of the emission of fly is practically impossible, and it finds a lodgment on all parts of the machine. It is, therefore, of high importance to prevent choking of the parts and the collection of dirt, in places where it will be drawn into the lap, and that the utmost vigilance should be observed to keep everything free from any accumulation of fly. Especially is this the case with revolving flat machines, as the chain very speedily becomes stiff, unless great vigilance is exerted to keep it clear. Good carding requires vigilance, and the student of cotton spinning ought to be Argus-eyed in order to see every neglect of the small but essential duties required.

CHAPTER VI.

COMBING AND DRAWING.

(166) As shown in Chapter II., the process of combing is one which is only carried out when the finer qualities of yarn are to be spun. The manipulation of the material is so thorough that a large proportion of waste is made, so that, except when a high priced good yarn is to be spun, economic reasons forbid the combing of the cotton. It was briefly intimated in paragraph 61 that combing was a method of dealing in detail with the fibres, and that its result is to effect a much greater parallelisation of the fibres in the carded sliver. Not only so, but the setting of the mechanism leads to a species of sorting of the fibres by which all below a certain length are rigidly cast out. Thus, after cotton has been subjected to the action of a machine of this character, two of the essentials of perfect yarn are produced, viz., the presence within the thread

of a number of fibres laid in parallel order relatively to one another, and so selected as to be practically uniform in length. The cylindricality of the thread when twisted is therefore, if not absolutely obtained, much more nearly approached than is usually the case.

(167) In order to ensure the proper treatment of the material it is the usual practice to combine a number of slivers, and form them into narrow laps of $7\frac{1}{2}$ or $8\frac{1}{2}$ inches wide.   The carded slivers, in number from 12 to 16, are drawn from the cans, and after passing over spoon guides forming part of a stop motion, are passed between drawing rollers, by which they are consolidated and attenuated, after which they are rolled into a lap by means of suitable mechanism at the end of the machine.   The precise action of the stop motion and drawing rollers will be discussed at length when the operation of drawing is considered.   After the laps have been formed on the Sliver Lap Machine, as it is called, six of them are passed through a second machine called the Ribbon Lap Machine, also constructed with drawing rollers.   In this machine the laps are attenuated considerably, and are laid upon each other before being passed through calender rollers, and formed into a roll or lap for feeding the combing machine.   The advantage derived from this treatment is that the fibres in the laps are drawn into an approximately parallel order, so that the needles of the combing cylinder can very readily pass through them without any danger of damage, either to the needles or the fibres.   The method in which this parallel order is induced will be dealt with at length a little later on in this chapter.

(168) The lap having been obtained, the next thing is to feed it to the machine.   This is effected in the following way : Referring to Fig. 117, which is a transverse section of the machine, the lap is placed upon two wooden rollers A A which are given a definite rotative motion, the lap being slowly unrolled as required.   There are so many parts in a combing machine that it is impossible to have the same

letters referring to the same parts throughout, and care must be taken therefore to look at any special drawing dealt with at each point. The lap is taken down a tin trough B which terminates a little above the nip of two rollers C C¹, these being the feed rollers. The lower roller is held in suitable

FIG. 117.

bearings, and is in one line throughout the machine, being driven from the headstock placed at the end. It may be here explained that the description now being given is that of one head, but that there are usually six or eight heads in a complete machine, all the parts of which are driven from one point. It will therefore be understood that although dealing with one

head the construction of each is similar, and that the action of all is simultaneous. The plan of the gearing is given in Fig. 118, which is sketched from a single nip machine, made by Messrs. Dobson and Barlow. Although this varies to some extent from the ordinary machine, it resembles it sufficiently to enable the description to be followed. The lower roller C is driven from

FIG 118.

the wheel D by means of a star wheel G (Fig. 119), which is compounded with a pinion J. The pinion J gears into a wheel H fixed on the end of the lower roller. Thus any rotary motion of the star wheel G is communicated to the roller, and it is only necessary to see how this is obtained. On the driving shaft A is a pinion B which gears with a wheel D, to the inner face of which an adjustable boss is fastened, on which is fixed a

peg E gearing with the notches in the star wheel G every time
D makes one revolution, thus moving the wheel G forward one-
sixth of a revolution. It will be noticed that the partial rota-
tion of the feed roller only takes place once during the revolution
of the wheel D. As D is fixed on the shaft on which the circular
comb, afterwards referred to, is fastened, it follows that the
latter makes one revolution during each partial forward rotation
of the feed roller. The gapped disc F ensures that the star
wheel is only revolved when the gap in F permits the peg E to
rotate.

FIG. 119.

(169) The feed roller is 1 inch in diameter, or 3·1416 cir-
cumference, and according to the length of the fibres being
combed is given from one-eighth to one-tenth of a revolution.
As the number of recesses or pockets in the star wheel is fixed,
it is necessary to vary the relation between the wheels J H when
it is desired to alter the amount of forward motion of the feed
roller, and this can easily be done. Suppose that the roller is
required to move forward one-eighth of a revolution, any point

on its circumference will move $\dfrac{3\cdot1416}{8} = \cdot3927$ of an inch.

That is, the end of the lap is projected to that extent by this
action alone. The lower roller C (Fig. 117) is made of steel.

and is provided with a finely fluted boss of sufficient length to
receive the full width of the lap. Upon this the upper roller
C^1, which is sustained at its ends in slots, rests. C^1 is covered
with flannel and leather, and is weighted by hooks or stirrups
and weights suspended from the neck at each end. Thus a
complete nip is obtained which enables the feeding to be very
effectually performed.

FIG 120.

(170) The nippers and their attached levers are shown in detail
in Fig. 120, which should be referred to along with Fig. 121.
The end of the lap after leaving the feed rollers is passed through
the nipper jaws D H (Fig. 120). In the ordinary type of machine
the lower nipper H is made of steel with a rounded lip H^1. H
is fastened to the bracket or frame I, which is formed to receive
it, being long enough to extend across the head so that H is
capable of gripping the full width of the lap. I oscillates upon

the rod or pin J¹. The bracket I has two upwardly projecting
arms I¹ I², one of which I¹ has attached to it spiral springs, which
give it a downward pull so as constantly to draw the nipper
plate H up. The extent of the upward movement of H is
regulated by the screw I³ which is threaded through the arm I²,
and the point of which presses against the bracket F. The
latter is fixed to the framework, and constitutes a rest upon

FIG. 121.

which the bracket J carrying a bearing for the centre J¹ can
slide. It must, of course, be understood that in most cases the
mechanism is duplicated. This must necessarily be so, because
the various parts must be wide enough to deal with the lap, so
that it is essential that they should be borne at each side of the
head. The bracket J can be adjusted by the screw shown, and
afterwards locked in position by means of a bolt and nut. The
object of these various adjustments will be subsequently ex-

plained. The upper nipper D, which is also made of steel, is
fastened to the face of the bracket E, which rocks upon the
centre E^1 and has a backwardly projecting arm to which the
rod G is attached (see Fig. 121). The bearing for E^1 is formed
in the bracket F, and E can oscillate upon E^1 freely. The rod
G at its lower extremity is coupled to the lever G^1 (Fig. 121),
which rocks upon a shaft G^2. The other arm of G^1 carries an
anti-friction bowl engaging in a cam course formed in the
" cradle " cam K. This is fixed on a shaft parallel with the
cylinder shaft and driven by the wheel D which gears with a
pinion I on the cam shaft as shown in Fig. 118. Only the
outline of the cam course is shown in order to avoid confusion.
Thus a reciprocal oscillating movement is given to the bracket
E, which causes the nipper plate D to rise and fall, its position
when open and closed being indicated by the full and dotted
lines. A glance at Fig. 121 will show that the cam K is so
shaped that for a great portion of its revolution there is no
movement of D, the cam course being concentric. The whole
of the oscillation of the bracket E is effected while the bowl
carried by G^1 approaches or leaves that part of the cam course
which is eccentric to the centre of the shaft on which K is
fixed. Beyond noting this fact at this point nothing more need
be said. The cam shaft is driven from the wheel D shown in
Fig. 118 by means of its engagement with a wheel fixed on the
cam shaft. As was said, both the nipper plates H and D are
made of steel, and both are capable of being adjusted when
attached to the brackets carrying them. The lower nipper
plate is formed with a rounded nose which is covered with a
soft covering of smooth leather, and from this cause is usually
called the " cushion plate." The upper blade is formed with
longitudinal flutes and an overhanging lip, as clearly shown in
the drawings, so that when its lower edge is pressed against the
rounded edge of the cushion plate a firm grip is obtained of
any fibres interposed. In lieu of this construction, which is the
one ordinarily adopted, Messrs. Dobson and Barlow make the
lower plate D with an angular edge, and fix in the upper plate

a strip of indiarubber by which a good grip is obtained. It is obvious that the two nippers should be adjusted so that contact is established across their whole width at the same time, as otherwise the nipping of the cotton will be very ineffectively performed. The passage of the combs through the end of the lap tends to open or spread it, a tendency which is increased by the operation of the feed and detaching rollers. In order to avoid this risk Messrs. John Hetherington & Sons use the device shown in transverse section in Fig. 122, and in plan in Fig. 123. The lower nipper jaw, or cushion plate H, has

FIG. 122.

attached to it at each side a guide plate which has two projecting pieces C E, one at the front and the other at the back of the nipper. E is curved so as to allow the upper nipper D to descend without obstruction. The two pieces C and E are connected so as to form one piece. The plate D is cut away at F so as to clear the front guide C, which is arranged so as to be in contact with the front end of the cushion plate H. By this arrangement it is practically impossible for the lap to spread when nipped, while the fibres are prevented from lifting by the guide D. The cylinder is also formed with a flange. Wide laps can thus be used while the selvedge is straight.

(171) Having described the nipping mechanism of the Heil mann machine, we have next to deal with that which is employed for combing and detaching. The combing of the fibre is effected by means of a series of needles fixed in a cylinder, and a comb to which an upward and downward movement is given, but which is, during the operation of combing, retained in one position. The cylinder N (Fig. 117) consists of a central body or stock, shaped out at one point so as to receive a series of flat plates or matrices into which the needles N^1 are fixed. Of the latter there are usually seventeen rows, and they are made of round steel tapered to a fine point, and of

FIG. 123.

different diameters. In the various rows the pitch of the needles varies from one-thirtieth of an inch to one-ninetieth of an inch. They vary in diameter according to their pitch, and are usually disposed as follows :—

4	rows of	20's
3	,,	22's
2	,,	24's
2	,,	26's
2	,,	28's
2	,,	30's
2	,,	33's.

The matrices in which these needles are held is made of a metal into which they can easily be fixed, and they are planed and shaped so as to lie accurately in their proper position, and

give the needles their true angle when they are secured by the set screws attaching them to the comb stock. The object of this construction is to permit of the ready removal of any of the sets of needles which may be broken or damaged during work, and its replacement by a new one. It is essential that the several rows of needles should be in parallel lines, as otherwise

FIG. 124.

there will be an injurious action on the cotton. They must not be hooked too much, or their carrying power is increased, and too much waste is caused. The width over all of each row of needles is usually a little in excess of that of the lap, in order to allow for the spreading of the cotton caused by the nipping. The top comb is formed at the lower end of a flat plate L

(Fig. 124) which is fixed to the end of an arm or lever L^1, which rocks with the spindle L^2, carried by a bracket on the framing. The tail end of the lever L^1 comes in contact with the point of a stop screw L^3 which passes through an ear in the bracket, and which can be set so as to limit the range of movement of the lever L^1 and thus regulate the descent of the top comb L. On the same spindle as the lever L^1 is a lever M^1, having a bowl M^2 at one end which engages with the cam M secured upon the cylinder shaft. Beyond noting that the shape of the cam is such that the top comb is held out of contact with the cotton during part of the period occupied by the revolution of the cylinder, and allows it to remain embedded in it for the remaining portion, nothing more need now be said. The top comb is usually 28's, with almost all ranges of staple, and is sufficiently long to thoroughly penetrate the lap. The teeth on the cylinder are cleaned by a revolving brush placed below it and adjustable to it. The brush is cleaned by a small doffer which in turn is stripped by an oscillating comb, which is driven by a crank R (Fig. 118) actuating the rocking levers Q on which the comb is fixed. Special means of adjustment are given to the brush and doffer by setting screws so as to compensate for the wear of the bristles. The waste which is thus removed is valuable, and can be worked up for coarser yarns.

(172) At a point directly opposite that at which the needles are fastened to the cylinder, a segment is formed. This is finely fluted transversely, and is consequently known as the fluted segment. Between it and the needles there are two spaces or gaps in the cylinder, the object of which will be afterwards described. The surface of the segment is sufficiently distant from the centre as to come into contact with the underside of the combed end of the lap and sustain it during the revolution of the cylinder. The object of the fluted segment is to enable the detachment of a tuft of cotton to take place after it has been combed, and to aid in its attachment to the previously combed sliver. The last-named operation is the function of two rollers S and Q (Fig. 117), the former called the "detaching roller," and the latter the

"top detaching" or "leather" roller. These names are somewhat delusive, because, as a matter of fact, the actual operation of detachment is done by the latter, and the function of the former is really that of piecing or attaching. As these names, however, are those generally employed, it is better to retain them. The roller S is formed in a line extending along the machine, and revolves in bearings in the framework of each head, in such a position that it is always clear of the needle and fluted segment.

FIG. 125.

It is actuated from the headstock of the machine by special gearing, which is illustrated in Figs. 125, 126, and 127. This consists of a cam O (this cam being marked N in Fig. 118) fixed upon the shaft on which the "cradle" cam K is fastened. Engaging with the cam course in O is a bowl O^1 fastened at one end of a lever O^2 rocking upon a pivot borne by the framing, which is not shown in the drawing. The other end of the lever O^2 has hinged to it

a catch Q, which can be raised or lowered by means of a lever
Q^2, a bowl carried by which engages with the cam Q^1, fixed in a
position adjoining O. The catch Q is constantly drawn down
towards a " notched " wheel T, which is fastened on a spindle
carried by the framing. It will be noticed that the notches in T
are square, and that the end of the catch Q is correspondingly
shaped. The reason for this construction is to enable a movement
being given to the notched wheel with equal facility and without

FIG. 126.

any danger of slipping in each direction. On the same spindle or
arbor as the notched wheel is an internal disc wheel or annulus
T^1, with which engages a pinion fastened on the end of the
detaching roller S. Thus any motion which is given to the
notched wheel is at once communicated to the detaching roller,
and the extent to which the latter rotates in either direction is
regulated by the range of movement of the notched wheel and
the proportionate relation of the number of teeth in the internal

wheel and the pinion gearing into it.   A glance at Fig. 125 will
show that the course in the cam O is formed so that the lever
O² is rocked upon its centre in each direction alternately during
every revolution, but that the extent of the movement varies.
Thus if Fig. 125 be observed, it will be seen that the catch
Q is disengaged, being held out of gear by the cam Q¹.
As the bowl O begins to enter the curved part of the cam
course in O at 1, the catch Q is dropped into the notch

Fig. 127.

marked 1, and the continued rotation of O is followed by a
movement of the bowl O¹ to 2, so as to cause the notched
wheel T to take up the position indicated in Fig. 126.   It will
be seen that the notch 1 has moved forward, its position and
that of the lever being clearly shown in the drawing.   The
further rotation of O¹ from position 2 to position 3 causes the
lever O² to rock in the opposite direction, so that the notched
wheel is drawn backward until the bowl in O² passes into the

concentric part of the cam course and the catch is in position 3, as shown in Fig. 127. It remains in this position until released by the rotation of the cam Q^1. The extent of this backward, is greater than that of the forward, movement, and the proportion which they bear to each other will be referred to at a later stage. It will be sufficient at this point to mention that obviously

FIG. 128.

the same movement takes place of the detaching roller, which is first given a backward and then a forward rotation.

(173) The mechanism thus described is that which is employed in the Heilmann machine as usually constructed, but Messrs. Dobson and Barlow employ a special form of motion which has some points of interest. This is shown in Figs. 128 and 129. It consists of a clutch E, one half of

which is fixed upon the axis of the detaching roller and the
other half B slides upon it.   The latter is formed as a toothed
pinion, and has a ring groove formed in it with which the
forked end of a lever G engages.   The other end of G carries
a bowl A, which by the pull of a helical spring is constantly
pressed against the face of a cam M on the cam shaft.   (See also
Fig. 118.) A second cam F has a cam course somewhat similar
in shape to the one shown in Fig. 125, with which a bowl in the

FIG. 129.

rocking lever C engages.   The latter is formed with a toothed
quadrant D at its inner end, which gears with the pinion on the
loose-half-clutch B.   So long, therefore, as the clutch B E is in
gear the rotation of the cam F has precisely the same effect as
in the preceding case.   The detachment of the clutch is effected
by a cam operating the lever G, which is similar in effect to the
cam Q^1, which releases the catch Q in Fig. 125.   The distance
travelled during the backward movement of the detaching

roller is about $1\frac{3}{4}$ inch, which is a little less than one-third that of the complete forward motion. The total extent of the forward motion from one end of the motion of the catch to the other is about $4\frac{1}{8}$ inches, but this can, of course, be varied as desired by an alteration of the shape of the cam.

FIG. 130.

(174) It is now necessary to deal with the action of the top leather roller Q. This, it will be seen in Fig. 130, is in contact with the detaching roller, and is sustained by its arbors resting against the face of the block R. The latter is fixed on a lever called the " horse head," which is centred on a pin R^1. Its tail

end is oscillated by a cam Y, in which the bowl Y^1 engages. Y^1 is borne by a lever Y^2, which rocks on the same centre as the lever Y^3 coupled to the horse head by the connecting rod shown in the drawing. The effect is that as the face of the bracket R recedes from the centre of the detaching roller the distance between the centres of N and Q in like manner is increased, and the roller Q is able to fall so as to approach the cylinder N. The range of movement of R is regulated so that the roller Q can come in contact with the fluted segment N^2 at an earlier or later moment. At the same time this movement must not be of such a character that the rollers S and Q fall too far out of contact. This adjustment can be made by means of the sliding block R and by the coupling of the levers Y^2 and Y^3, which can be moved inwards and outwards by a screw and locked in position. The horse head lever is, of course, formed with two arms, so as to sustain the leather roller at each end. The effect of this mechanism is that the leather roller—always being in contact with the detaching roller—is alternately lowered into touch with, and removed from, the fluted segment. It is weighted by a stirrup lever and weight, or spring, so that when it touches the segment it is caused to revolve with the latter, and establishes a grip upon the cotton. The precise effect of this action will be fully described when the whole operation is dealt with. Fixed upon the rod R^1, which acts as a pivot for the lever R^2, is a small bracket U which carries a bracket U^1 having two slots formed in it which act as bearings for the roller T, known as the "piecing" roller, and a flannel covered clearing roller. The roller T is covered with brass, and is finely fluted longitudinally. It is of considerable weight, and presses upon the detaching roller so as to compress the cotton as it passes. These parts complete the list of those connected with the detachment and attachment of the combed tuft. After the cotton has been pieced by its passage between the rollers, as described, it is carried along a trough and collected by a trumpet-shaped guide into a sliver, after which it is carried to the end of the machine, where it passes through calender rolls prior to

being coiled in a can like a carded sliver. This part of the mechanism closely resembles that used in connection with the carding engine, and does not require special description.

(175) Having thus described the essential mechanism of the Heilmann machine, we have now to consider its operation. In order to make this clear, let it be supposed that the lap is held by the feed rollers and nippers, and that the circular combs are passed through its end. As there are in the lap fibres of various lengths, the comb needles, as they penetrate the end of the lap, will remove those which are not gripped by the nippers, so that the end of the lap will very speedily become thinned, and only the long fibres will be seized by the top leather detaching roller and segment. Every forward revolution of the feed rollers will thrust a fresh portion of the lap into the path of the combs, and in each case the short fibres will be removed, as described ; while the long ones, being freed from the nip of the rolls, will be drawn out by the detaching mechanism. To understand the action, it is important to remember that only a portion of the fibres contained in the whole width of a lap are removed at each nip, and that as the fibres lie irregularly in the length of the lap new sets are being continuously thrust out of contact of the nip of the rollers, so that they can be readily drawn away by the detaching mechanism. The small forward movement of the lap by the feed rollers, combined with the much greater forward movement of the detaching roller, makes it difficult to understand why the lap is not exhausted so that it does not protrude beyond the nipper. This would undoubtedly happen if the whole of the fibres in the width of the lap were removed at one operation, but as only a small portion of them are so removed the lap is always present.

(176) The action of these parts can now be fully explained, and in order to make the explanation clearer, four diagrammatic views of the positions of the various parts are given in Figs. 131 to 134. In the first of these, Fig. 131, the various parts are shown in their position during combing. The feed rollers C C^1 are stationary, and the lap is gripped by the nippers which

have closed upon it. By the action of the cam, as previously described, the cushion plate has been forced down until the lap is laid in the path of the advancing comb needles which enter and comb it. The top comb is raised so as to be out of the cotton and the detaching roller is stationary, with the top detaching or leather roller in its normal position. The circular comb needles enter the end of the lap very freely, and the gradually decreasing pitch of the successive rows causes them to remove all the fibres which are too short to be retained by the nippers, as well as the neps which have been left in the

FIG. 131.   FIG. 132.

cotton previously. After the combs have passed, the ends of the fibres fall into the gap left between the needles and the fluted segment, and the nipper begins to rise. At first the upward motion of the top nipper is accompanied by that of the cushion plate, the combined movement continuing until the screw I³, in the upwardly projecting arm of the nipper cradle I (Fig. 120), comes into contact with the bracket F. When this occurs any further motion of the nipper ceases, and this is the position which is illustrated in Fig. 132. The top nipper D is just leaving the cushion plate H, and the lap is being

released.   At the same time the top comb L is dropped into
the end of the lap, just in advance of the portion which has
been cleaned by the circular combs.   As the fluted segment
approaches the detaching rollers the roller S begins to make its
backward movement so as to bring the end of the combed
sliver into a position to give the necessary overlap.   The latter
is needed in order that the fibres of cotton about to be removed
shall be laid upon and joined to those which have previously
been combed and detached.   For this reason, therefore, the

FIG. 133.   FIG. 134.

sliver, of which these form a part, is moved backward by the
rotation of the detaching roller, which takes place during the
period that the first portion of the oscillation of the notched
wheel takes place, as previously described.   At the same
time the leather roller Q commences to roll round S, and
does so until it comes in contact with the fluted segment.
When this happens the position shown in Fig. 133 is assumed.
The movement of the detaching roller S is indicated in
the figures by the arrow which is marked *a*.   A glance at
Fig. 133 will show that the nipper is entirely open, in

which case the cushion plate should be about $\frac{1}{4}$ inch from the curve of the segment. The feed rollers receive their movement at this period and deliver the lap. The top comb is retained in the cotton, and the top leather roller comes into contact with the fluted segment. The combed fibres are held up by the forward movement of the segment, so that when the leather roller touches it their ends are gripped between the two. The weight on the leather roller is sufficient to establish a firm nip, and to ensure its rotation by the revolving segment. Thus the fibres are withdrawn from the lap, being forcibly pulled out. It is clear that only those which are of sufficient length to be held by the segment and leather rollers will be drawn away, while all the longer ones will be retained by the nip of the feed rollers. The rotation of the leather roller not only has the effect of detaching the fibres, but by reason of its simultaneous pressure upon the sliver laid between it and the detaching roller, it also attaches them to that portion of the combed sliver which is there retained. While the latter roller is thus being rotated the forward movement of the detaching roller occurs, and the result is that that end of the sliver which had been carried backward previously is again moved forward at the same time that the newly detached fibres are being carried forward. The result is that the latter are laid upon the former, and are pressed together by the nip of the leather upon the detaching roller. As the movement of the latter in a forward direction is about double that in a backward one, the fibres forming the end of the sliver, and which have been thus overlapped, are passed under the piecing roller T, which completes the operation of piecing. When the detaching roller finally comes to a rest, a tuft of fibres has been transferred bodily from the lap and attached to the sliver. In the operation their ends, which have been in the lap, are drawn through the top comb, any neps or other impurities attached to them are retained by it, and are left on the withdrawal of the top comb in the uncombed portion of the lap. The fibres, as they are detached, are also straightened, and are necessarily laid in a parallel relation to

each other, so that when they pass between the nip of the detaching rollers they are retained in this position. The forward motion of the detaching roller must be sufficient to ensure a complete attachment of the tuft of the sliver, but must be limited so as to leave the end drawn from the lap protruding a short distance beyond the nip of the detaching and leather rollers. The usual overlap of the sliver is about ¾ inch. Something will be said hereafter of the setting of the leather roller when dealing with the whole question of setting the various parts. As soon as detachment and attachment are completed the leather roller is moved back to its normal position, and the end of the lap falls into the space between the segment and comb. The top nipper descends and presses upon the cushion plate, the parts being then in the position shown in Fig. 134. The continued motion of the top nipper takes place, and the cushion plate is pushed down until it again assumes the position shown in Fig. 131, when combing recommences. The shape and setting of the cam actuating the top comb, as shown, is such that the latter is raised out of the cotton as the circular combs enter the end of the lap, and is dropped into it as soon as the combs have passed.

(177) Having described the operation of the Heilmann combing machine, it is now possible to deal with the method of setting the various parts. There are several considerations which have an effect upon this subject. The principal of these are the length of the staple of cotton which is used, the weight of lap to be produced, the quality of work required, and, as a consequence of the last, the amount of waste which is to be combed out. Each of these has an influence upon the setting, and within limits it is possible to produce widely different results on the same machine. It is obvious, for instance, that if a cotton, the staple of which is only one inch, is to be combed, a different manipulation will be required than is necessary if the staple is 1¾ inch. Further, if, as is now the case to some extent in American mills, combing is resorted to in the preparation of medium counts for the sake of getting an evener

and stronger yarn, then the percentage of waste taken out can be less than is necessary with the higher grades and finer numbers. This need for the absolute removal of all fibres which are shorter than those of full length, which exists when the better and finer yarns are to be produced, has hitherto stood in the way of the construction of the Heilmann combing machine with a duplex combing cylinder. To obtain the best effect, it is necessary to provide a full set of needles, and the removal of one or two rows has a great effect upon the cleaning property of the machine. Some of the leading makers of this machine in this country have constructed combers in which a cylinder containing two sets of combs and two fluted segments is used. The result is that a double nip and detachment is required during each revolution of the comb cylinder. This is not a difficult thing to do, but in order to retain the cylinder of the diameter as before, one or two rows of needles have been removed. The result has not been entirely satisfactory, for while many of the counts of yarn can be thus prepared, for the very highest and best the cleaning power has not been sufficient. It may, however, be said that this mode of construction is not without merit, and that it will lend itself very well to the construction of a machine which will produce good work and a greater quantity simultaneously. An enlargement of the diameter of the cylinder and a general rearrangement of the parts will probably take place with advantageous results, so far as the profitable use of the machine is concerned. This is, however, a digression, and we can now return to the subject of setting the various parts.

(178) To begin with, it is necessary to see that the axes of all the operating parts are parallel. Taking the cylinder axis as a base, it is obvious that the points of the combs will be parallel to it as well as concentric. In like manner the surface of the fluted segment must be also parallel to it. Now, if the axes of the feed rollers are not quite parallel to that of the cylinder it is clear that the end of the lap will not be presented to the needles properly, but that it will be combed more at one side than at

the other. It is, therefore, necessary to attend to this point. In setting the cushion and top nipper plates due regard must also be had to this fact, and by means of the various setting screws this can easily be done. The cushion plate must be quite parallel with the axes of the cylinder and feed rollers, and must be so set that it lays the cotton evenly upon the needles of the comb. If this plate is twisted, the same effect will occur as if the feed rollers and cylinder were not parallel. Care must be taken that the nose of the cushion plate is evenly and properly covered so as to present a perfectly smooth surface throughout. It is set to the $1\frac{1}{4}$ gauge from the steel rollers. The extent of the downward movement of the cushion plate is, of course, regulated by the pressure of the top nipper upon it, which can be regulated by the alteration of the length of the connecting rod G (Fig. 121). The absolute extent of the oscillation of the top nipper is, of course, dependent on the throw of the cam, but the period of its contact with the cushion plate is determined by the length of the connecting rod. If this is shortened the top nipper is raised so that it does not come into contact with the cushion plate so soon, and *vice versâ*. The result is that the oscillation of the latter and the nearness of its approach to the comb cylinder can be regulated at will. This should be arranged so that a gauge numbered 20 will pass between the cylinder and nipper. The ascent of the cushion plate is regulated by the screw I^3 (Fig. 120). The cushion must now be set so that when in contact with the top plate it touches it evenly along its entire width at the same time. This is quite readily done by means of the setting screws behind the cushion, but it is a delicate operation and requires care. The fact of equal contact can be ascertained by the employment of thin strips of paper used as gauges, an attempt to extract any of which will show if it is firmly held. Upon the care exercised in this respect the efficiency of the working of the comb needles largely depends. A stepped gauge is provided, and the nipper pins should be set to the first step on it. In the machine as made by Messrs. Dobson and Barlow, in which the lower plate

is the knife and the upper one the cushion, the procedure is naturally reversed, but the principle remains the same, although the shape of the nose of the lower nipper and the use of an india-rubber cushion gives greater latitude in this respect. The setting of the detaching rollers and segments is a very important part of the work. It is obvious that upon the relative setting of these two parts to each other and to the feed roller much or the efficiency of the machine depends. It will be further clear that the relative distance of the feed rollers from the detaching roller will depend upon the length of staple to be combed, and gauges are provided to set them in accordance with this. The bearings carrying the detaching roller having been fixed in position the latter is put in. Assuming that Sea Island cotton is being combed, a gauge of $1\frac{13}{16}$ or $1\frac{7}{8}$ inch is employed, and the detaching roller is set to that distance from the feed roller. It is necessary to see that this gauge accurately measures the distance between the two rollers at each end, and the feed rollers must be adjusted to ensure this. The importance of this can be seen by the fact that as it is the rotation of the detaching roller and its superincumbent rollers which draws away the fibres, if it were not parallel with the feed rollers there would be a straining of the fibres at one side of the lap and only a partial detachment at the other. Thus the resultant sliver would be unevenly delivered, and would be cloudy. Unless this point is carefully looked to the fibres will be cut, and the same fault will happen if the brass attaching roller is not parallel with the detaching roller. The segments must be so set that they are perfectly parallel to the detaching rollers, and care must be taken to adjust the bearings for this purpose. A gauge is provided to set the detaching roller to the segment, and a No. 21 or 22 will in most cases give ample space between the two.

(179) The next operation is the setting of the segment so that its front edge will be parallel to the detaching roller. The machine is turned until the index finger is opposite No. 5 point on the wheel D in which the peg is fixed (Fig. 118), when a $1\frac{7}{8}$ inch gauge

should pass in between the roller and the face of the segment. The wheel D is divided into 20 equal parts, which are marked and numbered on the rim, so as to be easily set to a pointer finger. If this does not take place all along, the segment must be adjusted until the proper position is attained, as upon this factor depends the appearance of the sliver when delivered. If there is too great a lack of parallelism the fibre will be cut, while even with a little it will be curled instead of straight. The order of setting these parts is not quite that of the description, but is really as follows : The placing of the detaching rollers, their adjustment and that of the feed rollers relatively to each other, the adjustment of the segment, and finally that of the nipper. From what has been said it will have been seen that the setting of the cams is a most important feature, and no empirical rule can be given for this. The proper fixing of the cams is rather a matter for the machine maker than the mill manager, and there are so many points of adjustment that any error can be easily rectified. The cam which operates the top nipper should be so set that the nipper is pressed down to the proper point to lay the cotton in the path of the needles. It may, however, be noted that the nipper should not close upon the lap at too early a moment, as if it does the forward movement of the feed roller will cause the cotton to fall into a loop, which it may be difficult to straighten out again. The detaching cam requires setting so as to give the exact stroke forward and backward at the right moment. Thus the backward stroke requires to be made when the needles have passed and during the time when the gap between the needles and the segment is beneath the detaching roller. In like manner the traverse of the leather detaching roller must take place so as to bring the latter into contact with the segment at the right moment, and the cam must be timed to accomplish this. The cam regulating the top comb is simple to set, and hardly needs explanation. The whole of these settings are regulated by means of the index wheel. The detaching cam is set, when Egyptian cotton is used, so that when the index is at 1 the roller is moving back, and makes its for-

ward movement when it is at $6\frac{1}{4}$. The leather or top detaching roller must be set so that when the segment has passed under the detaching roller the leather roller is down at $6\frac{3}{4}$. The peg is set so as to gear with the star wheel when the index is at $4\frac{3}{4}$ and the nippers close when it is at $9\frac{1}{4}$. In setting the top comb cam it is capable of variation within limits, being arranged to be down at anything from 5 to $7\frac{1}{2}$ on the index. In most cases, however, from $5\frac{1}{2}$ to 6 will be found to be the correct setting, but much depends upon the quantity of nep and short fibre which it is desired to remove. The settings given can be varied for Sea Island cotton, the adjustments being made so that the parts operate at a little later period. If the machine is making too much waste, the feeding and nipping should be made earlier; if the waste is not enough the reverse procedure is followed. As this matter is somewhat important, a few words may be spent upon it.

(180) It is necessary that the top comb should be put into the cotton before the leather rollers commence to move forward. Not only does the comb require carefully setting so far as its vertical traverse, but in addition to this it also requires setting at a proper angle. Unless care is taken, the nippers, in their ascent, will catch the comb, with deleterious effects, in addition to which the amount of fibre which is removed will probably be excessive. It is, resolved into its elements, a question of the relative angle of the comb with the sliver. On the other hand, the setting screws about the machine, especially those about the nipper mechanism, must be thoroughly watched to see that they are quite tight. The machine should be well oiled throughout, but it may be remarked on this head that all the parts do not require the same attention. All the chief working parts want frequently and regularly lubricating, and it is a good plan to reduce this operation to a system. The machine should be kept carefully clean throughout, and loose fly should never be allowed to collect about the machine, as it is apt to form into knots or balls and pass into the sliver. The bowls working in the various cams must be attended to, and it

should be carefully seen that they are neither too loose or too tight. In either event bad work is inevitable. All the leather coverings must be carefully seen to, and the leather roller must be kept cylindrical and well varnished. The needles in the cylinders should be carefully looked to, as if they are broken or bent, especially if hooked, bad work results. It is a good plan to overhaul the comb cylinders periodically, and always once in three months. They should be kept quite clean and free from dirt, cleaning taking place twice a week. The top combs should also be attended to, as if any of the teeth are broken out they produce a stringy lap. We may say, in brief, that constant vigilance and care is required to ensure truly satisfactory work, but it is certain that if given much will be gained.

(181) In proceeding to deal with the draft in the combing machine, it may be explained that after leaving the calender rollers the slivers are conveyed to a coiler which is similar to that used for a carding engine. The draft occurs in a comber (1) from the feed to the calender rollers; (2) from the calender rollers to the draw box; and (3) from the draw box to the coiler head. These three drafts, which are easily calculable, multiplied give the total draft of the machine, which is always very considerable. The principal draft is, of course, between the feed and first calender roller, and the least is that between the draw box and coiler. The production of the comber depends on the number of nips. From 80 to 90 nips per minute are made with a single comber, and 120 with the duplex. The production depends upon the amount of waste made, and the weight of the lap. With a single nip comber of eight heads the production varies from 170 to 350 lbs. per week of 56½ hours, this amount being proportionately increased with a double machine. The waste made is from 15 to 30 per cent, depending on the quality of yarn required.

(181a) There have been many attempts to construct combing machines which are capable of dealing with fibres of shorter staple than those ordinarily combed. The problem is one of some difficulty, owing to the fact that the fibres are not so

uniform in staple as they are in the better varieties. Further, it has always been difficult to detach and attach the fibres, owing to the limited space which exists between the nipping and attaching mechanisms. The Nasmith combing machine, which was introduced in 1901, is so constructed and manipulated that it will comb successfully laps made from American cotton with a staple of $\frac{7}{8}$ inch. The combing, detachment, and attachment is conducted with complete success, while the amount of waste can be regulated so as to enable the operation to be conducted on commercial lines. In the Heilmann machine the feeding of the cotton, the opening and closing of the upper nipper, the entrance and withdrawal of the top comb, and the operation of the detaching rollers are each the work of separate cams, which have to be individually adjusted relatively to each other. In the Nasmith machine the only cam which is used is one to give the alternate backward and forward rotation of the detatching rollers, all the remaining parts being operated simply and effectively through the reciprocal movement of the nipper frame given by a crank fixed on the cylinder shaft.

(181*b*) The nipper of the Heilmann machine has a very limited movement. The upper jaw is forced by the cam on to the lower one, and comes in contact with it at a comparatively high speed, from 85 to 95 times a minute, thus giving a kind of hammer blow (which is very destructive of the leather covering the lower plate), and instantly transfers the full force of the springs from the top screws to the nipper cam. In addition to this, the force required to oscillate the whole nipper in order to lay the fibres in the needles, is very considerable, each of the springs sustaining the nipper having a pull of about 20lbs. or 40lbs. per head. In a six-headed machine this is equal to 240lbs. thrown upon the cam suddenly, entailing a good deal of shock and wear. Unless care is taken, it often happens that the cushion plate is pushed on the comb needles, damaging both the covering and the needles, because the arc of oscillation, if continued beyond a certain point, intersects the path of the needles, a defect also present in other machines. Each cushion plate requires separate setting.

(181c) Beyond this slight oscillatory movement, the nipper of a Heilmann machine is stationary and plays no part in any other operation than that of combing, gripping the fibres while

FIG. 134A.

the needles are passing through the end of the Jap. In the Nasmith machine (Fig. 134A) it possesses many other functions, and is quite differently constructed and applied. Figs. 134A and 134B are sectional views of the nipper and attaching mechanisms in the combing and attaching positions respectively'

I

The top and bottom nipper plates, feed roller F, and top comb
are all borne on a double frame N, which is centred at a suitable
point N¹, and is given a reciprocal oscillatory motion by means

FIG. 134B.

of a disc crank fixed on the cylinder shaft, also acting as the
index wheel to facilitate setting, and which rocks the nipper
shaft W, and from which a connection to the nipper is made
by the connecting rod V. The pins N¹, on which this frame
is hinged, are of large size, and are fixed in such a position that

the arc followed by the nose of the nipper is a very flat one, and departs as little as possible, during the period of oscillation, from the periphery of the cylinder, which it never intersects. Consequently, when once set to the correct gauge, the nipper

FIG. 134C.   FIG. 134D.

FIG. 134E.

cannot be made to touch the needles, no matter how far it moves. The path of the nipper nose is nearly a direct one from the combing to the attaching point, as shown in the diagrammatic illustrations, Figs. 134C, 134D, and 134E. (Com

pare with Figs. 131 to 134.) It will be easily understood that, as the oscillation of the frame is derived from the rotation of a crank running at 100 revolutions per minute, it will be practically, if not theoretically, continuous, although the rate of movement will, of course, vary at different portions of the rotation of the crank. It has been found that this characteristic lends itself admirably to the working of the machine, the mechanism being smooth and ensuring easy running. There being two connecting rods V to each nipper, it can be adjusted exactly to the detaching roll, and when all the nippers are in line and parallel to the roller they can be simultaneously adjusted.

(181*d*) The bottom nipper plate is fastened to a transverse bridge piece S bolted to the arms N, and adjustable vertically by set screws I, enabling it to be easily and exactly set on the nipper frame to the needles. On this bridge ears are cast which carry the studs P¹ on which the top nipper frame is hinged. The top nipper frame is ordinarily acted on by springs, which tend to keep it closed, but it has a rearward arm carrying a small runner, which, during the forward oscillation of the nipper frame, engages with an adjustable bracket J, and thus opens the nipper. The position and shape of this bracket is such that the nipper closes easily and gently at the right moment with a sort of rolling contact, in marked contrast to the blow given by the Heilmann nipper, there being no weight on the springs when the nipper is in its most forward position. In effect, it is found that it is quite unnecessary to provide either the top or the bottom nipper jaw with a leather covering to form a cushion, the closing action being entirely free from hammering, and there being, moreover, no pressing of the bottom nipper down, as in the case of the Heilmann, so that, as already explained, once it is set there is no danger of its coming in contact with, while its position ensures that the fibres are well laid in, the comb needles. Again, a neglected roller lap cannot push down the plate into the needles. It will only raise the feed roller F.

(181e) The feed roller F revolves in bearings attached to the nipper frame, and rests on the bottom nipper plate, as shown, the lap being passed between it and the plate. The roller is spring weighted, and can be adjusted relatively to the point of nip, to suit the class of cotton combed, but, being once adjusted, is fixed in position. By means of a lever and ratchet feed arrangement, the forward oscillation of the nipper frame is caused to give the desired amount of feed, the quantity being

FIG. 134F.

regulated by the simple adjustment of a pin. The top comb frame (Fig. 134F) is hinged to the nipper frame at C^3. It can be adjusted angularly and horizontally independently, and its downward movement is fixed by stop screws C^4. The needles can be adjusted to penetrate the lap to any desired extent without coming in contact with the cylinder. The top comb C is carried on arms, which are pivoted to the rocking frame N, and carry a bowl engaging with a plate I when the nipper is retiring, thus raising the comb. The comb and arms can be taken out and replaced without altering the

setting.   Before passing on to notice the remainder of the operation, it will be as well to point out that the feed roller, the nipper, and the top comb are all oscillated without the use of a cam of any kind.

(181f) In the work of detaching in the Heilmann machine the tuft of cotton removed at each operation is confined to those fibres only which are gripped by the leather roller and fluted segment at the instant of contact, and the work of detachment and separation is performed solely by these two parts without any assistance from the motion of the nipper.   The time that the roller is drawing fibre through the top comb is only a small part of the period through which the rollers turn forward.   The top detaching roller must be running at the full surface speed of the fluted segment, and in consequence of this the grip is sudden, and there is a snatching action on the fibres as they are drawn out of the lap through the top comb, which very effectively limits the workable weight of the lap operated on a Heilmann machine.   Owing to the necessity of getting the leather detaching roller up to speed before contact with the fluted segment, it is found that at least a quarter of an inch of the sliver backed off is wound back again before the roller seizes the nipper tuft, so that all this length is lost for piecing, and it is this and the interposition of the top roller between the top comb and detaching roller which renders the treatment of short cotton difficult and impracticable on a Heilmann machine.

(181g) In the Nasmith machine this mechanism is altered. As was pointed out, the fluted segment is abolished, and there is therefore no need for the leather roller to be dropped on it, an operation which is very destructive of the covering of the leather rollers.   Instead of three rollers there are now only two used for piecing, D D¹, and the work of detaching or separation is principally thrown upon the nipper.   The detaching roller D (Figs. 134A and 134B) receives a similar backward and forward rotation as before, but it is caused to stop and start more gently, never attaining the speed of the Heilmann roller, although rotating through a much greater arc at each stroke.   The roller

is operated by a very smooth cam, which is a circle for the greater part of its working surface, and is much easier in action than the ordinary notch wheel cam. The top leather roller D^1 is mounted on the detaching roller, but simply rolls upon it backward and forward, being in its most backward position just before piecing begins, and in its most forward position near its completion. The method of communicating this rolling motion consists of coupling the lever X^5, by which the top roller is borne, to the lever L (fixed on a rocking shaft, operated by an

Fig. 134G.

eccentric O^1, adjustably attached to a wheel on the cylinder shaft, Fig. 134G), by the rod X and the levers X^1 and X^3, so that the reciprocal movement of the nipper is synchronous with the reciprocal rolling motion of the leather roller, the relative extent of the latter being regulated very simply. It is not necessary to adjust this roller as in the Heilmann machine (an operation of delicacy and frequency) as it can be set as easily as an ordinary drawing roller. The leather roller, of course, receives, by friction with the detaching roller, a reciprocal axial rotation of the usual kind in order to turn back the combed sliver preparatory to piecing and then deliver the newly drawn tuft. In front of the detaching roller a second pair of rollers (See Fig. 134A) are placed, which merely act as straighteners, and pass the combed web forward to the usual

calender rollers and draw box. The speed of the second pair of rollers is regulated by that of the detaching rollers with which they are geared.

(181*h*) The feature which forms the most radical change from the Heilmann procedure is the close relationship which now exists between the operation of the nipper and that of the detaching roller. As was pointed out, the Heilmann nipper, as a whole, has practically no movement except a slight oscillation through a short, almost vertical, arc, and the detachment of the tuft of cotton is controlled by mechanism having no connection with the nipper, which is stationary and inoperative during the piecing and separation periods. In the Nasmith machine the nipper and detaching mechanism are connected so as to operate synchronously, although the detaching roller proper is still given its backward and forward rotation. The oscillation of the nipper frame from the cylinder shaft controls, as has been pointed out, nearly every other motion, and this with the minimum of effort. Referring now to Figs. 134C and 134D and 134E, assuming that the nipper is moving towards and has nearly reached its rearward position, the first few needles of the comb are passing through the end of the lap, and, while this is still going on, the direction of the motion of the nipper is reversed, and it begins to travel with the needles, but at a slower pace. The effect is that the finer needles comb out the end with less exertion and less strain on the fibres, which are not so liable to be damaged. After the needles have passed, the nipper continues to advance, and the smooth filling-up piece on the cylinder sustains the fibres and keeps them horizontal. While the recession of the nipper is taking place the leather roller moves backward (in the direction of the nipper) on the detaching roller. The result is that the tips of the fibres in the lap are seized by the nip of the two rollers at the earliest possible moment.

(181*i*) It is at this point that the chief difference in the action of the new machine as compared with the Heilmann is found, and it is upon this that its effectiveness largely depends. As

was shown, when the combed fibres are seized by the leather roller and fluted segment of the Heilmann machine, the nipper is stationary, and the tuft is snatched out of the lap by their rotation, the length of the tuft and the amount of overlap being entirely limited. The result is that only a comparatively light lap can be used, as, if its mass is too great, the grip of the two rollers is not sufficient to pull a thick tuft suddenly through the top comb, and if extra weights are added they would deflect the roller and damage the comb as well. In the Nasmith machine, after the fibres are seized by the detaching rollers, the nipper and top comb continue to advance towards the nip of the detaching rollers, and at the same time the leather roller rolls forward on the detaching roller, which simultaneously makes its axial rotation to effect the piecing. The result is, that instead of gripping those fibres only in the lap head that are actually engaged by detaching roller at its moment of contact with the segment, as in the Heilmann, a much greater number are successively seized and gradually drawn through the top comb, to an extent depending upon the amount of forward movement of the nipper, a longer tuft being thus extracted. In addition to this, the overlap is a much longer one and is much better made. As a consequence of the successive seizure of fibres thus obtained a lap of greater substance is easily combed, one double the ordinary weight per yard being handled with perfect ease, because the tuft is not jerked instantly through the top comb but gradually drawn through it during a longer period, the period of the operation of the top comb being also much increased. As the path of the nipper during the operation is directly towards the detaching rollers the fibres are delivered in the very best way without any snatching or damage.

(181j) The top comb is put into the lap immediately before the fibres are gripped by the detaching roller. It is dropped in well in front of the nipper, and the result is that all the previously uncombed length of the tuft is drawn through it, as well as some of the combed part, and all the noil is held back by it. The actual separation of the tuft is done gently,

and it is principally the work of the recession of the nipper (which is the exact opposite of the Heilman method). The result is that all the short fibre, nep, etc., is left behind the top comb, which, when it lifts, leaves them at the end of the lap to be removed by the next passage of the cylinder needles. The separation of the tuft is accomplished before the nipper has made its full backward movement, and the end of the lap is presented to the needles of the cylinder while the nipper is still receding. The result is that the fibres are well embedded in the comb needles and all the waste is effectively removed.

(181k) A word or two may now be said about the simplicity of adjustment. It has already been pointed out that the nipper cannot be made to touch the needles when it has once been set to the gauge. The set screws at either end raise or lower the nipper on its frame, the pivots, unlike those of the Heilmann machine, being fixtures in the framing. The throw of the nipper is fixed by the crank, and, when at its most forward position, each nipper is set by its own screws to a given distance from the detaching roller. Once all have been set they may be moved simultaneously nearer to or further from the roller. The opening of the nipper is regulated by simply adjusting an incline, and is also independent and unaffected by alterations in the other settings.

(181l) The setting of the top comb is extremely simple, whilst the setting of the leather detaching roller consists in making it parallel with the under roller and in line with its fellows, and when this is done, in regulating them to a given distance from the nipper which can be done by a single screw. Thus, instead of the delicate setting of the detaching roller necessary in the Heilmann machine, we have no more difficulty than with a drawing frame roller. There are only two things to time, namely, the detaching roller cam, so as to determine the moment when the rollers begin to turn, after which it is fixed, and the crank pin driving the nipper. Neither of these timings in any way alters the previous settings. Finally, the quantity of waste made is determined not by an alteration of the combs,

for theoretically these must always be set to take out the actual dirt and short fibres, however low the percentage is, but by altering the distance of the nipper and top comb from the nip of the detaching roller, thus affecting not the taking out of the dirt but the length of fibre taken out as waste. A single screw is provided to alter this, and it is only a few minutes' work.

(181m) It may be stated that the production of this machine varies from 2lbs. per head per hour to 4lbs., when 100 beats per minute are made, and a lap 10½in. wide is used. A lap of that width should weigh not less than 20dwts. nor more than 32dwts. per yard. If production is the chief consideration the heavier lap may be used, and if the slivers have been drawn and then passed through sliver and ribbon lap machines a heavier lap can be used than is otherwise possible. The waste usually extracted is from 10 to 14 per cent with good cotton for medium work. American cotton of seven-eighths of an inch staple has been successfully combed, and waste taken out amounting to 5 per cent only. No machine previously made has been capable of doing this, especially when it is stated that the work was performed on a machine which, with slight adjustments, combed Sea Island and Egyptian cotton successfully. The profitable combing of American cotton is an object often sought, and the importance of which it is difficult to exaggerate. In brief, the writer has no hesitation in saying, with a full knowledge of all that has been done during recent years, that the machine constitutes the greatest step in advance which has been made in combing cotton since Heilmann's invention, and while retaining the essential features of the latter, in simplicity, ease, and accuracy of setting the various parts, in its wide range of usefulness and productive capacity, it possesses distinct advantages.

(182) We now come to deal with the process which is, in many respects, the most important in the whole range of spinning. We refer to the process of drawing. Upon the proper carrying out of this depends the fact whether the

resultant yarn is truly cylindrical or not, and whether its proper strength is obtained   It is, in addition, the first stage, in the proper sense, in the formation of a thread, because, although it is true that no twist is introduced into the sliver at this stage, it is so far reduced that it can be readily formed into a thread.   Further, the drawing process is the last one in

FIG. 135.

which any correction of the inequalities existing in the slivers can be made, so that when they leave the machine any irregularity of diameter or weight will thereafter be perpetuated. Finally, it is the treatment received by the cotton at this point which gives parallel order to the fibres in a sliver, especially if the slivers are collected from carding machines.   As the web is

produced on the latter, it consists of a thin sheet of fibres, disposed in all directions. The reduction of these to something approaching parallel order is one of the chief functions of the drawing machines.

FIG. 136.

(183) The drawing frame is, as shown in Figs. 135 and 136, which is a transverse section of the machine made by Messrs. Brooks and Doxey, a very simple machine, consisting of four pairs of rollers placed with their axes in one plane, but parallel to each other. The bottom rollers are made of a good quality of iron or steel, and are at intervals turned down to form the necks on which

they revolve, leaving bosses between them.   These bosses are longitudinally fluted with finely pitched flutes.   The roller necks revolve in brass steps, fixed in brackets B, called "roller stands," fixed to a longitudinal "roller beam" C, and the bearings are so arranged that they can be readily adjusted relatively to the respective lines of rollers as desired.   The lower rollers are made in sections, which are coupled by a special socket and spigot joint, so as to form a continuous "line" throughout the length of the machine.   The upper rollers are made of cast iron in short lengths, and are formed with bosses, to correspond with the lower lines.   They are placed above the lower rollers, against which they are kept pressed by weights E, suspended from hooks D, which pass over the arbors of the rollers.   The top rollers are made of cast iron, accurately turned, and are covered with a sheath of a specially woven cloth, surmounted with a cover of soft, smooth surfaced leather.   Roller leather is made from sheepskins, and is most carefully treated.   After preliminary preparation the skin is shaved so as to reduce it to a uniform thickness before tanning.   After the latter operation is complete the skins are glazed, and upon the perfection of the glaze depends the quality of the product in spinning.   Mr. A. Seymour-Jones, who is thoroughly conversant with the subject, in a brochure published in 1893, says : " A leather roller should possess a cushion effect.   .   .   .   To the feel the grain should be smooth, firm, yet pliable, compressible and expansible, the flesh side as fine in nap as broadcloth, and the whole skin mellow and glossy."   He gives the following rules for the selection of skins :—

For low or coarse counts select a cheap quality of skin.

For medium counts select a medium quality of skin.

For high or fine counts select only the best and finest skins.

For preparatory machines select large-sized skins of stout substance.

For intermediate machinery select medium sized skins of medium substance.

For roving and spinning frames select small sized skins of thin substance.

Great care is taken in preparing the rollers to make them truly cylindrical and smooth, any adhesiveness of their surface being absolutely fatal to success. The top rollers are almost universally made for the front line of a drawing frame of the Leigh loose boss type. This is called in America the "shell roll," and, as shown in Fig. 137, consists of a central roller of cast iron, formed with collars, the shanks of which are specially shaped to receive a cylindrical shell of cast iron, turned and covered as described. The shape of arbor shown is the best for this type of roller, as it ensures steadiness of the shell. The advantage of this class of roller is, that as the body or shank on which the weights are hung does not revolve, but only the shell, the friction set up in rotating the roller is much lessened, and this is still further reduced by the facility with which the roller can be regularly and continuously lubricated. There is an ingenious method of securing the shells on the shanks, which consists of a small split ring of steel, which can close as the shell is pushed on, afterwards opening out and securely holding it. The upper rollers are kept in position by means of grooves formed in "cap bars," in which their pivots rotate.

(184) A drawing frame is usually described as consisting of a certain number of "heads" with so many "deliveries." A

'delivery" is the term applied to each sliver delivered at the front of the machine, and in each head there is a certain number of deliveries; in other words, so many completed slivers are passed. The lower roller is formed with as many bosses in each section as there are deliveries, so that if there are three of the former there will be three of the latter. The upper rollers have,

FIG. 138.

of course, the same number of bosses as the lower rollers with which they are in contact. There may be a number of heads, but this is determined by several considerations to which special reference will be hereafter made.

(185) All the gearing of the drawing frame is placed at the end of the machine. A view of this is given in Fig. 138, and will enable the description to be followed. This view has been

sketched from the drawing frame in the Manchester Technical School. The frame is driven by a belt from the driving shaft, passing over a pulley on an intermediate shaft. By a second pulley fixed on the same shaft as the driven pulley the pulley T is driven. This is fixed on the arbor of the front roller A, on which also is a small spur pinion E, driving the crown wheel F, which is compounded with a pinion G, gearing with a wheel H on the back roller arbor D. Thus the front and back rollers are directly connected. The second line C is driven, as shown in a separate view 2, from the back line by means of the pinion I, carrier wheel J, and pinion K on the second line. The third line B is also driven from the back line D by the pinion L, carrier wheel M, and pinion N, on the arbor of the third line B. The coiler which is in this case employed is driven by the train of wheels O, P, R, and the bevel pinions shown.

(186) The four lines of rollers are driven, as will have been seen, at different speeds, and the statement of this fact at once brings us face to face with the very essence of the operation. The object of this variation in velocity is to procure a continuous attenuation of the sliver as it passes, and the amount of attenuation depends entirely upon the ratio of variation. Thus, if the surface speed of the back roller is 20 inches per minute, and that of the front one 120, the sliver would, as it emerged from the front roller, be six times as long and thin as it was when it entered the nip of the back rollers. Because the speed of the front roller is always the superior one, all the remainder are driven from it, the reason of this being very obvious, it requiring so much less power to reduce than to increase the speed of revolving bodies. It is the rule to effect the major part of the drawing by the front roller, and the draft between it and the third line is much greater than that between either of the others. The reason for this procedure is not far to seek. It is customary, as will be afterwards shown, for several carded slivers to be fed to each delivery at one time, and when they reach the rollers they consequently form a thick strand. An excessive draft put upon these slivers at this point would

probably be destructive. They are compressed and flattened out, and are only subjected to a slight attenuation between the first and second lines of rollers. Between the second and third they are drawn a little more, and this gradual acceleration results in the establishment of an approximately parallel order. By the time the combined sliver leaves the third line of rollers it has usually been reduced to a little over twice its length, and the gentle pull so exercised puts the fibres into good condition for receiving the greater draft of the front line.

(187) To make this clear an examination of the operation in detail can be profitably made. The first thing to determine is what drawing is intended to do. It has a two-fold object, but the second is really a consequent of the first. Drawing is intended to reduce the number of fibres in the cross section of the combined sliver fed to a defined extent, and as a corollary, to place these fibres in the resultant sliver in practically parallel order. To effect the first result the increasing velocity of the various lines of rollers is necessary, and when combined with a proper relative setting of the centres of the rollers is practically perfect. The last-named point is really the most important, and an improper setting of the rollers results either in broken or imperfectly drawn fibres. The theory underlying the whole process is that of exercising such a pull upon the fibres as will enable them to be straightened, and cause them to be disposed longitudinally in the finished sliver. It is obvious that, if the fibres were laid even partially crosswise in the sliver, the greater part of the advantage of drawing would be lost. For, as has already been pointed out, the strength of a thread depends upon the number of fibres existing in its cross-section relatively to its diameter, and it is therefore clear that, unless they are drawn so as to lie lengthwise of the sliver, the chances of a strong thread are materially reduced. It is therefore necessary to submit them to such a pull as will straighten but not break them.

(188) When cotton is first taken from the bale the length of the various fibres differs considerably. The shorter fibres are

removed during carding and combing, and the longer ones remain. They are not, however, so long when presented to the drawing frame as when passed into the opener, the reason of this being that many of them are broken at their points by the severity of the action of the scutcher. There is in almost every fibre near its point a part which is more brittle than the body, this being the result of the manner in which it is developed. This brittle portion easily breaks off, and the result is that when the fibre reaches the drawing frame it is ordinarily from 5 to 10 per cent shorter than as first presented to the spinner. This fact must be borne in mind in setting the rollers, and it is well to ascertain the average length of the staple in the carded sliver prior to adjusting them. When this has been done the rollers may be set, and in every case they should be arranged a little further apart than the length of the fibres. The proportion of excess varies with the character of the fibres. Harsh, wiry fibres which require a longer period of draft to pull them straight can have wider set rollers than the finer qualities, which are easily reduced. But in the former case the reduction of the cotton to proper order necessitates more repeated drawing than in the latter. The distance apart is also influenced by the class of sliver drawn. If a combed sliver is drawn the work of parallelisation is unnecessary, and only that of attenuation is required. This work is also considerably reduced by the mere fact of the parallel order of the fibres, because they slide easily alongside one another as the pull is exercised. It is desirable to take into account a large number of circumstances in setting the rollers, all of which influence the result. Thus the length of the roller bosses and the sharpness of the flutes affect their drawing power materially, and it is possible when this is large to pass the fibres from roller to roller in a shorter time than when it is smaller. As a rule, if the fibre be an inch long the distance between the centres of the front and third lines of rollers should be $1\frac{1}{8}$ inch, that between the second and third $1\frac{1}{8}$ inch, and between the second and back lines $1\frac{3}{16}$ inch, or $1\frac{1}{4}$ inch. It is customary to vary the diameter of the rollers

used with various staples of cotton, as well as their relative setting. This, it is obvious, is necessary, because a short stapled cotton demands close setting, which can only be got if the rollers are small enough in diameter. With Indian cotton, therefore, the rollers are made 1 inch or 1⅛ inch diameter, with American 1¼ inch, and with long stapled cottons 1½ inch. The top rollers are, as a rule, smaller than the fluted ones. The general rules may be stated thus : The diameter and the setting of the rollers is regulated by the staple of the cotton; high velocities of the rollers demand small drafts, and *vice versâ ;* easy or low drafts permit of close setting; heavy drafts demand open setting; the least draft and widest setting must accompany

FIG. 139.

the thickest sliver in each box, the setting getting closer and the draft greater as the sliver is reduced.

(189) The question may be asked why it should be necessary to set the rollers so that at one period during the passage of a fibre no pull is being exercised on it except that induced by the secondary traction of the surrounding fibres. To this there is an obvious answer, but the question opens up the whole subject of the treatment of the fibre as it passes through the machine. In order to illustrate this point the diagram given in Fig. 139 has been prepared. This represents, on a reduced scale, the passage of a fibre an inch long through four sets of rollers, the centres of which are indicated by the letters A, B, C D, A

being the front line. In order to condense the size of the diagram, the line marked E is repeated at the upper part of the diagram, and the remainder carried on in regular sequence. The fibre is supposed to have moved $\frac{1}{8}$ inch for each line drawn, and the spaces between the rollers are arranged as described in the last paragraph. That is, the distance between A and B is $1\frac{1}{16}$ inch, between B and C $1\frac{1}{8}$ inch, and between C and D $1\frac{1}{4}$ inch. Now, it will be noticed that as the fibre approaches the nip of the back line at the point D, it is subjected to the pull of that pair of rollers for a considerable time. There is a slight pull at this point, because the slivers are being drawn out of the cans, and the weight of the sliver acts as a slight check upon the drawing in of the cotton. Gradually, however, the fibre is carried forward until it reaches a point where it lies wholly between the rollers C and D, without there being any grip exercised on it by either of these rollers. At this point what is happening is that the fibres which are actually gripped at C are being drawn forward, and in so doing are, in consequence of their adhesion to those adjoining them, not only held back at their free ends, but exercise a certain pull upon their neighbours. Thus the fibres which are free from any grip by the rollers are not quite free from traction, although the extent of this is necessarily limited. The compression of the combined slivers, as they pass through the back rollers D, certainly creates an adhesion which is more or less effective for the purpose named, according to the quality of the cotton used. The fibres are gradually carried on until they pass into the nip of the rollers C, when the action just described begins to occur. We now come to a period when the fibre has passed partially through the nip of one pair of rollers, but has not yet come fully within the sphere of the next pair. Thus, assuming that the fourth fibre from the point E be taken as an example, about one-half having passed between the nip of the rollers C, what is the influence of the rollers B upon the end which has passed? There can be nothing more than an induced action created by the frictional or adhesive contact of contiguous

fibres, but this is very considerable. The fibre is therefore carried forward by the rollers C, while at the same time its free end is being pulled in the manner described. The resistance which it encounters is, paradoxical as it may seem, the resistance of the rotating rollers C, which practically act as a retaining nipper. Thus, until it finally passes out of the influence of C, there is a pull exercised on it which is practically a retarding one—that is, the frictional contact is sufficient to enable the fibre to be drawn against the resistance of the delivering nip of C. In like manner, when the fibre finally passes forward clear of C, and is laid hold of by the next pair of rollers, the adhesive contact named practically acts as a backward drag upon its free end. This is quite clear upon a little reflection, because the rollers B, revolving at a superior speed to C, naturally tend to draw all the fibres forward at the increased velocity, while the more slowly moving rollers tend to prevent this accelerated forward movement. Thus there is a draft exercised on the fibres embedded in the mass, by which they are straightened and caused to lie in the line of direction of the pull exercised on them. If this description has been followed, it will be seen that the contention is, that the fibres are in three conditions during their passage through the rollers—gripped at one end by the rollers of inferior and free from contact with those of superior velocity ; free from the contact of both ; or gripped at the other end by rollers of superior but free from contact with those of inferior velocity. In the gradual change of position which they assume the influence of the rollers of superior velocity is one tending to draw them forward, and that of the rollers of inferior velocity one tending to prevent them moving at a more rapid rate than the surface speed of the rollers. Thus the fibre is constantly being submitted to a strain in opposite directions, and the proportionate influence of each upon it will depend solely on the ratio of its total length within the sphere of the respective pairs of rollers. It is important to remember that unless this alternate draft upon each end of the fibre occurred there could be no straightening of it, and it is

this fact which renders the correct setting of the rollers a matter of importance. It will be noticed that in no period of its passage through the rollers, however close their setting may be, is the fibre actually in contact with two rollers at one time. If it were, the superior draft of one pair would immediately pull it into two pieces, which is a thing specially to be guarded against. The action, which has thus been explained, is that by which the fibres are drawn into parallel order, but it also results in an attenuation of the sliver, as will now be shown.

(190) It has been explained that the four rollers indicated by A, B, C, and D rotate at gradually accelerating speeds, and it has also been shown that one effect of the drag thus exercised is to pull the fibres apart from each other. This can readily be tested, and the action observed by anyone who will get a small piece of carded sliver, and hold it with the left hand, while, at a distance of say two inches, gripping it with the right and then gradually withdrawing the latter from the left hand. The actual sliding of the fibres over each other can be seen, and the resistance which is felt to the movement of the hand is solely that occasioned by the frictional contact or adhesion of the fibres with each other. True, it is not a large resistance in the aggregate, but proportionately to the strength and size of the fibres it is considerable. But an examination of the sliver, after this manual drawing has been made for some time, will show that its area has become contracted, if not throughout, at least in parts. In other words, it has been attenuated or drawn. If the process were continued sufficiently long, the sliver would rupture and be drawn into two parts. Now, if the two elements of a stationary and movable grip be exchanged for those of two revolving grips, we have, in the instance given, the true analogue of drawing. It is only necessary to arrange that the cotton shall be delivered by one of the nipping parts at a slower velocity than it is taken up by the other, to produce exactly the same kind of attenuation, but the degree, of course, varies in exact proportion with the difference in velocity. If the latter is made large enough the rupture of the sliver will occur,

but by regulating the proportionate velocities properly any
desired degree of attenuation can be obtained. It has thus
been shown that a two-fold
but connected action takes
place in a drawing machine,
and that, although the at-
tenuation of the sliver is
the main object, it is inevit-
ably accompanied by the
disposition of the fibres
parallelly and longitudinally
within it.

(191) It has been already
indicated that a number
of carded or combed slivers
are fed to the drawing frame
simultaneously. The num-
ber varies, but an average
is six, and they are com-
monly spoken of as so
many "ends" put up to
the machine. They are first
taken, as shown in Figs. 135
and 140, through the guide
plate F, which is formed
with a number of holes or
guides, and thus acts as a
separating plate. After pas-
sing through F, the sliver
is taken over the end of a
short, unevenly - balanced
lever G, which can oscillate
freely on a knife-edge bear
ing.   The end over which

the sliver passes is hollowed out and highly polished, being
named, from its shape, a spoon lever. The superior weight of

the other end of the lever causes the spoon to be ordinarily raised, and the tension of the sliver as it passes to some extent counteracts this tendency, and presses the spoon down. By means of an eccentric, fixed upon a shaft, and driven from the calender rollers by the train of gearing shown, a rod I receives a reciprocal movement, and communicates it by a bell crank J, rocking shaft K, and levers L, to a square bar fixed in the upper end of the latter. On the shaft K a bell crank lever V pivoted at V^1 is fixed, which can lift a lever M engaging with a stop on the stop rod N, on which a longitudinal pull is exerted by means of a helical spring. As the strap guide is fixed on the stop rod, the movement of it in either direction respectively pushes the driving belt on or off the fast pulley.

(192) The object of this arrangement is to prevent the formation of what is technically, but erroneously, called " single." This is the passage into the drawing rollers of one or two ends less than the number put up, and arises from the breakage or failure of an end as it is taken from the can. The object of putting up so many ends will be discussed at a later point, but it may be stated that it is absolutely necessary that the combined sliver shall consist of all of those put up, as otherwise unevenness will occur. If, therefore, an end fails or breaks, the pressure on the spoon end of its respective lever G is removed, and the weighted end falls and comes into the path of the bar fixed in the levers L. Thus, when the latter endeavour to make their forward reciprocation they are unable to do so, and the crank V is thus oscillated on V^1 so as to oscillate M and release the stop rod. The helical spring at once throws the belt on to the loose pulley and stops the machine. It may happen that after the sliver has emerged from the front roller it will break before it passes into the calender rolls Q. To stop the machine in this event a spoon lever O, of the same character as G, is used, which, when released, engages with a short arm of the lever P oscillated from K. The action is the same as in the former case. After passing the calender rolls, which it does in the shape of a loose rope, being collected by the trumpet guide shown, the sliver

in some cases is passed through a coiler head, by which it is
delivered into cans.   In order to prevent damage to the cotton
by overfilling of the cans, it is the practice to fit under-
neath the coiler head a loose plate R^1, which can be pressed
up, and brings into action a stop which also comes in
the path of the rod P, this having the same effect as the
oscillation of any of the spoon levers.   A stop motion, which
has had a large employment, is the electric arrangement

FIG. 141.

shown in Fig. 141. In this case the machine is practically
divided into two parts, insulating material being introduced
in joining them together.   One half of the machine thus
makes one pole, which is connected with the battery by
the rod K, while the other half constitutes the other pole,
being coupled to the battery by the rod O.   As the sliver
passes to the back roller it is taken between two rollers S T,
coupled respectively to the positive and negative poles.   The
lower roller S forms a line along the machine, while the roller T,

is only long enough for one sliver. If an end fails the rollers come into contact, the circuit is completed, which passes a current through an electro-magnet X, causing it to attract the catch Z, and draw it into the path of a cam which is constantly revolving. The arrest of the latter actuates a sliding clutch and releases the knocking-off lever, allowing it to move the strap on to the loose pulley. If a "roller lap" is caused, the top front roller H, which is coupled to one pole, is raised into contact with a pin L, connected to the other, thus completing the circuit. If the drawn sliver breaks before it passes through the calender rollers N K, they engage, or, if the can overfills, the tube plate in the coiler lifts, the circuit being completed and the machine stopped in either case.

(193) Before passing on to consider a few points in connection with the working of the machine, it should be stated that above the rollers are placed flannel-covered surfaces, the object of which is to collect the short fibres which are thrown off from the cotton in the form of "fly." These, unless carefully and systematically removed, gather into lumps or "slubs," and pass forward with the sliver into the cans. Whenever this happens, a thick place will be found in the subsequent yarn, which it is then difficult to remove. By placing above the roller the flannel surface named, the fly is taken up by the rougher surface from the rollers, and these "clearers," as they are called, can be easily and regularly cleansed. The clearers are of one of three types, viz., (1) a round roller, resting in the space between the two rollers, so as to engage with two of them, and free to rotate; (2) a flat flannel-covered board, lying on the top of all four rollers; or (3) an endless flannel band, constantly traversed, one side of it pressing on the rollers, and capable of being freed from the collected fly by an oscillating comb, the whole being covered, as shown in Fig. 135, with a metal cover. The last-named is the best form of clearer, and is known as "Ermen's revolving clearer." The clearers should be at once removed if their surfaces get roughened, as otherwise there will be a great risk of licking and roller laps.

(194) The policy underlying the combination of several slivers at the drawing frame is practically that referred to in connection with the scutching machine. It is well established, although the effect is often exaggerated, that a good deal of advantage is derived from the passage of several slivers at one time. It is by no means an incontrovertible fact that the inequalities of a sliver forming one of a series will fall in the convenient manner often imagined. It is generally believed that the thick place in one sliver will be presented at the same time as the thin one in its fellow, but this is not demonstrated, and is many times contrary to fact. But it is true that if six or seven slivers are put up together it will probably happen that the thick places in some of them will be counteracted by the thin places in the others. Further, the gradual parallelisation of the fibres as they are passed through the rollers induces a more even thickness of sliver, especially when the drawn slivers are themselves combined and passed through the machine once or twice. The mere attenuation of the sliver, if it does nothing else, reduces any existing irregularity, and when repeated two or three times practically corrects it. Thus if in one of six slivers put up, which should contain 9,000 fibres in their cross section, there was only 8,000, the total number of fibres in the six slivers would be 53,000 only instead of 54,000. When the combined sliver is reduced six times by a draft of 6, instead of containing 9,000 fibres it will only contain 8,826. It will be seen how rapidly the deficiency is reduced, and, if the attenuation is continued at a second head, as it always is, it practically disappears. But the most valuable features in this process of doubling are the reduction, by successive drafts, of the fibres to parallel order, and the gradual approximation of the sliver to a perfectly even condition, so that each foot contains more nearly the same number of fibres in its cross section, mainly in consequence of the parallelising operation. Doubling possesses many features of interest, but the observations of the author have confirmed the view that its chief merit lies in the establishment of parallel

order in the fibres included in the finished sliver. It is true that the gradual reduction of the thickness of the slivers also tends to lessen or remove any inequalities, as just shown, but the real secret of an even *drawn* sliver is the production of an even *carded* one. This, in turn, implies care in the formation of a lap, and so the genesis of a perfect drawing is removed to the earliest process within a mill. Every sliver possesses its distinctive defects—if any exist—at different points in its length, and these do not all pass into the rollers at the same point, so that the continuous attenuation is likely to be of advantage. Whatever may be the explanation of it, the fact remains that when doubling is resorted to the finished sliver is much better than when it is not. It is usual to pass the slivers through three heads, and it is a very common thing to put up six slivers to each head. In this case the aggregate doubling received by a sliver is $6 \times 6 \times 6 = 216$. The question of the effect of the draft of the rollers and doubling the slivers will be dealt with a little later.

(195) Among the more important detailed points which, in the manipulation of a drawing frame, require attention, that of the condition of the rollers is most important. The lower rollers, being made of steel or iron, and fluted, are, of course, much more durable than the covering of the upper ones. It is necessary to see that the flutes of the rollers are kept clean and smooth, and that the points are not too sharp. Any roughness, however slight, speedily results in licking, and the greatest care must be taken to avoid this. The upper rollers being covered, a series of points arise of more or less importance. In the first place the cloth with which they are covered requires to be selected carefully to suit the class of roller which it has to cover Roller cloth is a fine cloth made with great care and from a fine grade of wool. It is well milled so as to look almost like a felt, and it is essential that it shall be very level, and of even substance. In weight it runs from 12 to 30 ounces per yard of 27 inches wide. A good cloth must be at once pliable and firm with no more than the natural amount of

moisture in it.   If a solid roller is used, a lighter cloth is per-
missible than when a loose boss or shell roller of the same
length of boss is employed, and in like manner the shortening
of the boss of a roller has an effect upon the weight of
flannel used.   The reason of this is that a loose boss roller
requires a heavier weight applied than the solid roller, and the
pressure upon its surface being so much greater necessitates a
better bed for the leather.   It does not really matter whether
this careful grading of the weight of the flannel is made or not,
provided that the thickness of the cloth used is ample for the
pressure put upon the roller, as in most cases it will be.   The
point really aimed at is to provide a bed sufficiently firm to
accommodate itself to the weight applied, so that while
enabling the necessary pressure to be put on the roller there is
no danger of crushing the fibres which are being drawn.   Even
with the most perfect bed there is always a danger of this
crushing action, which is most objectionable and injurious.
The tendency is for weights to increase, but the student
will do well to bear in mind that no increased draw-
ing power is worth having if it endangers the fibres in
their passage.   The cloth being selected of a proper
thickness, should be carefully formed into a sheath, and fastened
on the roller boss.   The greatest care must be taken to see that
it is evenly stretched over the whole surface, and that there is no
thick place where the two ends are joined.   If this is not done,
cutting of the fibres will take place at every revolution.   The
roller, in fact, must be as nearly cylindrical as possible, and the
same remark applies to the leather covering, which must be
equally carefully prepared.   The skin-grinding machine of
Messrs. Dronsfield Bros., Limited, is especially valuable in this
respect, as it ensures the absolute evenness in thickness of the
skins.   The leather coverings are prepared by cutting the leather
into strips of the required length and width, and cementing them
together at the joints, which should be tapered so as not to
make a thick place.   After being drawn on by the aid of a
special tool the ends of the leather must be carefully closed over

the bosses, and the roller well calendered at a moderate heat. After the leather sheath is prepared and put upon the roller, it is a very good practice to subject the latter to a rolling pressure, so as to make it quite cylindrical. No care is too great with the leather-covered rollers, if good work is required, and the smoothness of their surface must be absolute. Any roughness induces licking of the fibres, and means waste, the amount of which in a drawing frame ought to be very trivial. Any roller which is not running true, or the leather of which has become fluted, should be at once overhauled and be re-covered, if that is found to be the fault, or straightened, if the roller itself is strained. Care should be taken that when rollers are ground after use the skins are varnished properly with a varnish that does not stick, and dries hard without cracks. The question of whether a loose boss or solid roller is the best is one which possesses some interest.

(196) There can be little doubt that in England, at least, there is a liking for the loose boss roller, and something may be said on this point. The weight of a roller has a certain influence upon the drawing power, and we shall see that in many of the spinning frames it is the custom to make the top rollers of some of the lines self-weighted. In a recently-introduced form of drawing roller, both the top and bottom lines are fluted, and made of steel, and the top rollers are, therefore, of greater weight than the usual form. These are known as "metallic" drawing rollers, a phrase adopted to distinguish between them and the ordinary covered rollers. Fig. 142 is a partial perspective and Fig. 143 an enlarged partial section of a pair of rollers made on this method. The upper and lower rollers are kept a definite distance apart by means of collars A A, which are fixed respectively at each end on the necks of the upper and lower rollers. These collars are hardened steel, and are ground to an exact size. The body of the rollers is fluted, as shown in B, and the flutes intermesh one with the other; but the point of one tooth is prevented from going to the bottom of its corresponding flute by the compulsory separation of the

rollers. It will, of course, be understood that all the dimensions
are greatly enlarged in Fig. 143. The sliver, which is forced
through the roller, is shown by the thick black line, and is
naturally caused to follow the formation of the teeth, and to be
partially crimped, just as in a combing machine. The depth of
contact of the teeth is ·044 inch, so that the crimping is slight.
The bottom roller being driven naturally drives the upper roller,
by means of the pressure exerted on it and the intervening
sliver, as shown in the figure. The space between the teeth is
ample for the sliver, and no crushing effect is produced. It is
claimed for this type of roller that the draft is a positive one,

FIG. 142.

and that there can be no damage to the fibre from such causes
as slip or friction, which is often found with leather-covered
rollers, especially when care is not taken to keep the top or
covered roller in good condition. It is found that a reduction
is wanted in the calculated draft when this type of metallic
roller is used; and further, that instead of the calculated draft
being in excess of the actual draft, the reverse is the case. The
explanation of this is not far to seek. The ordinary leather-
covered top roller is driven by the forward movement of the
sliver, which in turn receives its motion from the rotation of the
bottom roller. Thus there is, in the event of any inefficient

lubrication or similar cause, a resistance to the free rotation of
the top roller to overcome, which is in excess of the driving
force of the moving sliver. For this reason it is often the prac-
tice to weight the top rollers of drawing frames considerably,
especially if the material being drawn is harsh and wiry. The
result is that the pressure on the fibre is considerable, and even
then it is by no means easy to avoid slip. With the metallic
roll such a condition as this cannot arise, because, owing to the
absolute grip exercised upon the fibres, drawing is certain

FIG. 143.

Further, the divergence of the sliver from the straight line, which
as shown in Fig. 143, must occur, adds to the draft, and thus it
is found that there is a greater actual draft than that calculated.
Perhaps one of the most useful effects of this particular con-
struction will be found in countries where the leather tends to
become adhesive, owing to the various atmospheric changes.
In this country this cause does not often affect the result, but
in some places it is an important matter. The draft of the
K

metallic roll being positive and definite, and depending on a grip and not frictional contact, it is clear that there can be no adhesion. It is also found that there is no necessity to weight the top rollers so heavily, because, as it is only necessary to keep the collars in contact, only such weights as will do this are required. There is thus a decrease of friction. It the construction of a loose boss roller be considered it will be seen that the friction existing is that of its inner surface against the outer surface of the arbor. This friction is still further reduced by the efficient lubrication of a roller of this type, so that the shell can revolve with ease. This fact has a two fold bearing. It renders the rotation of the top roller easier, and at the same time it increases the necessity for weighting. An ordinary solid roller has to overcome the friction of the hooks on its arbor as well as the friction set up in its bearings. Both of these are absent in the loose boss, being replaced by the friction between the shell and arbor, which is much less than that of the hooks and rollers. The loose boss shell will therefore rotate more freely than a solid roll, and this fact renders it a little more difficult to get the nip required to obtain the draft. Thus the loose boss needs weighting, with due regard to the facts that it is more readily driven and is lighter than the solid roller, but this can be very easily arranged. With a loose boss roller one danger is practically removed. We refer to the abrasion of the fibres which occurs if there is any retardation of the rotation of the top rollers. For these reasons, although in some respects the solid roller is meritorious, the balance of advantage appears to the author to lie with the loose boss type, and by their use the durability of the leather is increased. On the other hand, it ought to be said that some spinners contend that a much better draft can be got with a solid than a loose boss roller, and that lighter weights can be used. With reference to the latter point it should be noted that the aggregate weight of roller and weights does not greatly differ in either case, and, with regard to the former, experience generally leads to the

opposite conclusion. Further, it might be pointed out when double bossed top rollers are employed it is of less importance to have the diameters of each boss, when covered, exactly the same size with loose boss than with solid rollers. Each shell in the former case revolves independently, while in the latter the surfaces of the bosses necessarily revolve at one speed, and if the surface speed is not the same there will be a certain amount of rubbing, which is detrimental. The lubrication of all the rollers is of importance, and should be specially looked after. Care should be taken to prevent oil getting on to the leathers, and the periodical cleaning of the rollers is an absolute necessity.

(197) The arrangement of the cans behind the frame is worth a little consideration. The usual practice is, as has been said, to place behind the machine a number of cans—five to eight—for each delivery at the first head. Subsequently a certain number of those produced at the first drawing head are fed to the second head, and the same practice is pursued at the third. Now, it is obviously a faulty procedure to feed a number of full cans simultaneously, because at each head these would all run empty at once, and the machines be stopped until the attendant had pieced up the ends throughout the series. To avoid this it is better to feed them in sections, one section being full, the next section three-quarters full, the next half full, and the next quarter full. In this way the piecing can be effected with a minimum of stoppage.

(198) The question whether the resultant sliver from the drawing frame is thinner or lighter than that from the carding or combing machine which is fed to it depends for its answer entirely upon the number of ends put up and the total draft of the rollers. Suppose, for instance, that six ends are put up to a drawing head, the draft of which is six, it is obvious that there would be no reduction in the weight of the sliver delivered compared with that of any *single* sliver put up. It is, of course, true that every one of the latter has been reduced to one-sixth its

original weight, but the combination of the six produces the full weight in the drawn sliver. If, therefore, it is desired to know what the weight of a drawn sliver will be, all that it is necessary to do is to multiply the weight of each by the total draft and divide by the number of ends put up. In order to establish a uniform method of calculation, it is customary to speak of a sliver as of such a number of hank, and this is arrived at as described in paragraph 162 in connection with carding. Thus, supposing the carded sliver is ·16 hank, six ends are put up, and the total draft of the draw box is 5, then the resultant drawn sliver will be $\dfrac{·16 \times 5}{6} = ·133.$ In this way the calculation can be made throughout, and, as will be shown at a much later stage in this book, the proper system is to plan the drafts from the opener to the spinning frame with strict relation to one another. The total draft of a frame is got by multiplying together the drafts—*i.e.*, the ratio of the velocities— of each pair. Thus, if the roller C (Fig. 138) travels at $1\frac{1}{4}$ time the velocity of D, the roller B $1\frac{3}{4}$ time as quick as C, and A 3 times as quick as B, then the total draft would be $1\frac{1}{4} \times 1\frac{3}{4} \times 3 = 6\frac{9}{16}$. Having determined what the drafts shall be, it is easy to make the necessary wheel changes required, and in doing so the velocity of the front roller is the determining factor. It is, for the reason previously detailed, the practice to put in the larger portion of the draft between the front and third line of rollers. It is, therefore, only usually necessary to alter the relations between the velocities of the front and back rollers, unless this change is excessive, because, as will be seen at 2 and 3 in Fig. 138, the relations between the velocities of C, B, and D are practically fixed, and are affected by any change in the relative velocities of A and D. The necessary wheel change is therefore ordinarily made at G, that being a pinion which can be easily altered. Now the draft of the machine is the ratio existing between the surface velocity of the front roller and that of the back roller. The ordinary rule for this purpose is as follows.

(199) Multiply all the driven wheels and the diameter of the front roller together for a dividend, then all the drivers and the diameter of back roller together for a divisor, and the quotient will be the draft required.

(200) This rule is really the reverse of the true way of putting the case, but produces the same result. The value of a wheel train is usually calculated in mechanics by multiplying all the drivers and dividing that product by one obtained by multiplying all the driven wheels. If the quotient so obtained is multiplied by the velocity of the first driver, the velocity of the last member of the train is obtained. Thus, in the case shown in Fig. 138, the wheel train consists of the wheels E, F, G, H, and its value is $\frac{E \times G}{F \times H}$. Now let us assume that the front roller is $1\frac{1}{8}$ inch diameter, and the back roller 1 inch, and the velocity of the front roller 220 revolutions. Let also E have 30 teeth, F 90 teeth, G 42 teeth, and H 60 teeth. Then, according to the formula, the velocity of the back roller will be $\frac{30 \times 42}{90 \times 60} \times 220 = 51\cdot3$. The draft therefore is, according to this computation, $\frac{220}{51\cdot3} = 4\cdot3$ nearly. If the front and back rollers were the same diameter, this would represent the draft, but as they are 9 to 8, the draft is $4\cdot3 \times \frac{9}{8} = 4\cdot8$. If the draft be worked out by the rule detailed above, it will be found to be as follows: $\frac{90 \times 60 \times 9}{30 \times 42 \times 8} = 4\cdot8$, which is identical. If the value of the wheel G be omitted from the calculations, we get a constant number. By dividing this by the draft, the size of the draft wheel G is obtained; or if it be divided by the draft wheel the quotient is the draft. Another method, and one that is the best, is to ascertain the surface velocities of the front and back rollers, and divide that of the former by that of the latter. The velocities can be arrived at either by calculating them in the manner described, and multiplying each by the respective circumferences, or by counting them. If, in the case named, the velocities are

220 of the front roller, the circumference of which is 3˙5343 inches, and 51⅓ of the back roller, which has a circumference of 3˙1416. then the relative surface velocities of each respectively are 777˙546 and 161˙268. Dividing the former by the latter we get 4˙8, as before. It does not therefore matter which of the three methods is adopted, the result obtained is identical, but the latter is the simpler way. The drafts of the lines B and C are calculated in a similar manner as described in connection with the front line, the wheel trains being shorter, and as in each case the centre wheel only acts as a carrier, the factor needed in the calculation being for C line $\dfrac{I}{K}$ and B line $\dfrac{L}{N}$.

(201) The calender rollers are driven by the carrier wheel T from a pinion on the front roller arbor, and revolve at a somewhat quicker surface speed than the front roller. This must be allowed for in arranging for the total draft. The coiler calculations need not now be dealt with, as they were fully gone into in connection with the carding engine. The length of sliver that the drawing frame will pass can easily be arrived at if the draft be known. Let it be assumed that the draft is 6, and that the front roller is 1¼ inch diameter and revolving 300 times per minute, the back roller being 1⅛ inch diameter. To give a draft of 6, the velocity of the back roller must be 55˙5. At this speed it will take in 196 inches per minute of each sliver, while the front roller will deliver 1178 inches of the drawn sliver. It follows, that if six ends be put up, the length of sliver taken up and delivered is practically the same. It was pointed out that the change is made in the drafts by means of the pinion G. If it is desired to change the hank drawing delivered, it is very easy to calculate the number of teeth in the new pinion. Thus, if a ˙15 hank drawing is produced by a pinion of 36 teeth, a ˙20 hank drawing would require a pinion $\frac{15}{20} \times 36 = 27$. This can also be arrived at by calculating from the weight of six yards of the drawing which is being made with any definite change wheel and that desired to be made. The rule is, that the coarser the drawing produced the larger the

change wheel required, and *vice versâ.* The hank of the final drawing made can be obtained, if the hank carding is known, by multiplying the latter by the drafts at each head and dividing by the number of ends up at each head. Thus, assuming the drafts in the three heads to be 4, 6, and 6, and six ends of ·15 hank carding to be fed at first, and six to each of the other two heads, the matter stands thus :—

$$\text{Drafts } \frac{4 \times 6 \times 6 = 144 \times \cdot 15}{6 \times 6 \times 6} = \frac{21 \cdot 6}{216} = \cdot 10 \text{ hank.}$$

CHAPTER VII.

SLUBBING AND ROVING.

(202) IN the scheme of operations which was given in paragraph 61, Chapter II., those of slubbing and roving are defined as drawing and twisting processes. They form practically the first stage in the formation of the twisted thread to which the name of "yarn" is given. As produced on the drawing frame the sliver is, as was shown, seldom much thinner than that obtained from the carding engine. It differs mainly in the important fact of the parallel order of the fibres within it, which is absolutely essential to the proper effecting of the twisting operation. The drawn fibre could be twisted into a yarn or thread, but its diameter would be too great for practical use. It is therefore essential to still further attenuate or draw the

sliver, and this is usually done in three stages, of which the first is "slubbing." In the slubbing frame the sliver is drawn to the utmost extent which is permissible without damage to its strength, and is, as it emerges from the drawing rollers, given a slight twist. The twist given is only sufficient to impart a certain cohesion and strength to the thread which will enable it to withstand the draft in the next of the series of machines. As the attenuation of the thread is continued until just before the final twist is put into it, it is highly desirable that up to this point it shall not be so "hardly" twisted—*i.e.*, have so many turns in each inch—as to present any obstacle in the way of the drawing action of the rollers. Accordingly it is the practice to put into the thread in each of the machines successively a definite amount of twist, but the amount put in in each case is not great. The final product of this stage is known by the generic name of "roving," and the machines themselves are sometimes known as "speed frames."

(203) Each of the machines of the series is practically the same in mechanical details, differing only in the size and strength of the parts. The slubbing frame is fed from the slivers in the drawing cans, and during the time the material is passing through the machine it is wound on to wooden tubes, being formed into a spool or "bobbin" with a cylindrical centre portion and truncated conical ends. The bobbins so produced are fed to the intermediate frame, being for the purpose fitted with round rods or "skewers" pointed at each end. By means of the skewers the bobbins are sustained in a nearly vertical position in a light frame known as a "creel," which is placed above the body of the machine. The creel consists of a number of light longitudinal rails, which have fixed in them at regular intervals small porcelain cups or steps in which the points of the skewers fit loosely, so that when the thread is drawn off the bobbins the latter can easily revolve. It may be perhaps as well to explain at this point that any frame which is used for the purpose of holding the bobbins or spools from which a machine is fed is known as a "creel."

The bobbins produced on the intermediate frame are smaller in size than those on the slubbing frame, and in consequence they can be placed nearer to each other in the roving frame creel. The same length of frame will therefore contain more bobbins. A creel may be one, two, or three in height, according to the number of rows of bobbins it holds. As at each operation the coarsely twisted thread produced is reduced in thickness, the bobbins on which it is wound are made less in size, and the pitch of the spindles is reduced.

(204) As the material passes from the cans or creel it is taken through the drawing rollers, which are in construction and mode of operation similar to those used in the drawing frame. There are ordinarily three lines employed; the top rollers for the back lines are of cast iron, and are made so much heavier than those for the front lines that they are not otherwise weighted. The rollers revolve in bearings of a similar character, and are fixed to the roller beam in a similar manner to those used in the drawing frames. Clearers are fitted above and also below the rollers; a revolving clearer being sustained in bearings formed in a spring fastened to the roller beam, the spring being sufficiently strong to ensure the constant contact of the clearer with the rollers. The method of arranging the cap bars which are used in roving frames to maintain the position of the top rollers is somewhat important. The practice is to cast on the front of the bar a projecting piece usually consisting of a square rod on which the adjustable " nebs " for supporting the ends of the top rollers are fixed by a screw. These are often thrown out of truth by the pressure of the screw, and, in order to obviate this, the arrangement shown in Fig. 144 is adopted by Messrs. Howard and Bullough. A rod F is fixed in the roller stand, and on it are fastened by means of cotters I, brackets B. The latter have fixed in them rods A of rectangular form on three sides, but V on the lower two sides. In the bracket B a hole of a similar shape is cut, so that the rod A when fastened by the screw C, is securely held. The shape of the hole is shown as cut in one of the

nebs D in a detached view. In the figure at the left-hand top
corner of Fig. 144, it will be seen that the necessary number of
nebs can be fixed in their proper positions, and, in the two
lower views, the application to a four roller box is very clearly
shown. The pentagonal shape of the rod ensures the fixture of
the nebs without twisting, so that the top rollers rest properly
on the lower line. In the sectional view at the left-hand lower
corner the method of fixing the cap bar is shown, and it will be
seen that the slides can be adjusted without interfering with the

FIG. 144.

cap bar bracket. The top clearer bracket is also hinged on the
cap bar shaft. The advantage of this arrangement is mainly
that arising from the easy and accurate adjustment of the cap
bars. The spindles are borne by two rails, one having bearings
formed which act as "footsteps" for the spindle and the other
rail carrying an upper bearing or "bolster." The spindles are
in two lines, placed one behind the other, and are disposed
rather peculiarly, the centres being arranged thus : ͏ ͏ ͏ ͏
It will be noticed that those in the back line are not placed
exactly midway between the others, but more to the left, and

foı this reason it is customary to describe the "gauge" of the
spindles—that is, the distance from centre to centre—as being
so many spindles in so many inches ; as, for instance, 4 in 17½
inches, 6 in 19½ inches, and so on.   The object of this

peculiar arrangement is to enable more
spindles to be fitted into any given length
of machine, and to give easy access to the
back line.   The spindle A, Fig. 146, is
made from steel carefully ground to an
even diameter, is reduced in size at the
lower end to form a foot, and at the
upper end is made with a taper spigot,
fitting into the flyer B.   The top end is
slotted across, so that a pin driven into
holes bored through each side of the
hollow central boss C, fits into the slot
and drives the flyer.   The spindle only
projects into the socket for a portıon of
its length, and the upper orifice of the
boss is carefully rounded and smoothed.
Near the top a hole C^1 is bored, which
is also well rounded and smoothed, and
through which the sliver or slubbing is
threaded during spinning.   The flyer has,
as shown, two downwardly projecting arms
B^1 B^2 connected to the boss by means of a
bridge or coupling piece.   One of these
arms B^2 carries two snugs or projections
D D^1 acting as bearings for a pressure finger
or "presser" E.   This is a round rod hooked
at its upper end, and bent to a right angle

FIG. 145.

at its lower end.   The presser is dropped into a socket, formed
in D, and, being also sustained by D^1, is capable of oscillating
freely on its upper pivot.   The inner end of the horizontal limb
of the presser E is flattened out into a "palm" and formed
with a guide eye, and is of such a length from the vertical

limb that it always lies about the centre of the empty bobbin F. The sliver or roving is passed through the boss C, out at the hole C^1, through the tubular arm B^2, then wrapped round the presser at E, taken through the guide eye, and so on to the bobbin. The effect of this construction is that the roving is conveyed to the bobbin, and the centrifugal force generated by the rotation of the flyer establishes a tendency in the presser arm to move towards the centre of the spindle, and thus exercise a certain pressure on the roving being wound. Although this action is apparently "centripetal," it is really the effect of "centrifugal" force acting upon a two-armed pivoted lever, the weight of one arm of which is in excess of the other. If this lever be hinged to a rapidly revolving arm, the result is to cause the weighted arm to tend to move outwards, and thus make the lighter arm approach the axis of rotation. In the present case the vertical limb of the presser is heavier than the horizontal or presser arm, so that the latter is caused to approach the axis during the rotation of the flyer, and thus exercise a pressure upon the bobbin. If only one presser is employed, the arm carrying it is made tubular, and the balance of the flyer is restored by making the other arm solid. If a double presser is used—which is now very seldom done—both arms are made tubular. In either case the flyer is very well finished, being made of close-grained material and highly polished. Unless this is the case, "fly" rapidly accumulates, and forms "slubs," which may possibly pass forward with the roving, and form a thick place in it.

(205) The spindle is, as shown, borne by a footstep and bolster, and in order to give it steadiness it is usual to make the latter a tube, which according to length is spoken of as a "short" or "long" collar. The latter is shown in Fig. 145 at I, and extends upwards from the bearing to a point within the flyer. The advantage of this arrangement is the freedom from vibration arising from the support within the flyer. The collar is shelled out, so as only to be in contact with the spindle at the bottom and top, thus giving the maximum of support with the

minimum of friction. The advantages of the long collar are so great that it is very widely adopted in preference to other forms. Another method of mounting the spindle is shown in Fig. 146. The spindle A is carried in a long tube I, extending downwards until it forms a footstep for the spindle toe. The tube is attached to the rails J K by means of swivel joints, so that it practically forms a sort of cradle, and allows the spindle to adjust itself in case any uneven balance exists in it. The latter is thus permitted to find its own centre of gravity, gyration being thus prevented and the friction on the bearings much reduced. There are many advantages in this construction over any other, and both the velocity and wear of the spindles and bearings are favourably affected.

(206) The spindles are positively driven by means of a bevel wheel F, fixed on the foot of each and fastened to the spindle by a set screw, or, as in Fig. 146, formed with a square hole, into which a similarly shaped part of the spindle fits. The wheel on the spindle engages with a larger wheel G, fixed on a shaft H, extending longitudinally of the frame. As there are two lines of spindles, two shafts H are used, one driven from the other, each line of spindles being driven by wheels of the same character. The wheels G G^1 are skew bevels, and the pinions F F^1 gear with them on their opposite sides respectively. As the shafts H H are driven one from the other they necessarily revolve in opposite directions, and the effect of this method of gearing the wheels is that the spindles are driven uniformly in one direction. The bobbins are driven by means of skew bevel pinions M and wheels N in the same way. The pinions M are borne in the bolster rail, and have a flange formed on their upper surfaces which sustains the bobbins L. The bobbins are provided with notches in their lower ends, which engage with projections or snugs on the flanges of the pinions M, so that the bobbin is positively driven. The rail K, bobbin wheel M, and bobbin are given a vertical traverse for a certain distance in each direction. This traverse is known as the "lift," and during its continuance the bobbin slides upon the spindle or collar, as the case may be.

The extent of the traverse is from 5 or 6 inches in a roving frame to 10 or 12 inches in a slubbing frame.   As the flyer eye continues to revolve in one plane during the lift of the bobbin, the spindle rail J being stationary, the roving is wound on the bobbin

FIG. 146.

in coils which vary in pitch according to the velocity of the vertical movement of the bobbin.   As the bobbin rails with their attached gearing are a considerable weight, they are balanced by suitable mechanism, consisting generally either of weights attached by chains or of levers pressing against the underside of

the bobbin rails and suitably weighted. The spindles and bobbins are, it will be seen, driven independently, and may therefore be rotated at different velocities, the sliver being in the meantime delivered at a uniform and regular rate. The parts thus described form what may be called the essentials of the machine, and a description of their action can now be given, in the course of which one or two points of interest and importance will be treated.

(207) It was shown in Chapter I. that whenever fibrous material is being twisted it is necessary to hold one or both ends while the twist is being introduced. In these frames the roving is held at one end by being wrapped on the bobbin, and at the other by the rollers. It is necessary to observe that the grip exercised is, in the two cases, of an entirely distinct character. The bobbin grip is one exercised by a rapidly revolving body, which rotates at a velocity slightly greater or less than that of the flyer. On the other hand, the delivery of the sliver by the rollers is made at a much slower rate than the rotation of the bobbin or flyer, so that between the latter and the roller a certain number of twists or turns are put in the roving. The number of these depends upon the ratio of the revolutions made by the flyer, which is the operative instrument in twisting, and the number of inches of sliver delivered by the rollers in any given time. If, for instance, the flyer makes 20 revolutions in the same time as the rollers deliver 5 inches of sliver, there will be four turns put into every inch of the latter. This delivery may be intermittent or constant, but the effect is not varied so long as the ratio of the velocities of the two parts remain unaltered. It is the practice in all spinning machines, however, except in special cases, to deliver the sliver at a steady and continuous rate, and thus both the delivery and twisting are regularly conducted. All twists therefore are obtained at a uniform rate, and are defined, as indicated, as so many turns per inch. Thus, the chief features of a machine of this character are a steady continuous delivery of a sliver which is drawn by the rollers, an equally uniform rate of

twisting it, and the winding of the twisted strand, at a regular speed, on to the bobbin. The last two of these three points include the chief mechanical problem of machines of this class, the proper understanding of which is most important alike to the spinner and mechanic.

(208) From the illustrations in Figs. 145 and 146 it will be seen that the bobbin and spindle, although independently driven, rotate round a common axis. It follows that upon the relation existing between the velocity of the flyer eye in its rotation and that of the surface of the bobbin will depend whether any yarn or roving will be wrapped on the latter. The rollers deliver, as was shown, a definite length of sliver or slubbing, which must be disposed of by being wound on the bobbin. There are three ways in which this can be done : (1) The flyer eye may revolve and the bobbin be stationary, so far as rotary movement is concerned ; in which case, if the necessary vertical traverse is given to it, the material would be wound on its surface in coils ; (2) the flyer eye may rotate at a speed so much superior to the bobbin that the roving will be wound on the surface of the latter—this is what happens when there is a " flyer lead "; (3) the bobbin may be revolved at a velocity so much in excess of that of the flyer that it will take up the roving and wind it upon the surface. This is the condition of things during a " bobbin lead." The first of these three conditions only holds good when one or two layers of yarn are to be laid, because if the bobbin remains stationary it is clear that the rapidly-increasing surface upon which the material is wound will stretch and ultimately rupture it. By so arranging the bobbin, however, that it can be sufficiently retarded by friction, this difficulty can be overcome, and this solution has been applied in the case of throstle spinning. In the roving frame, however, it is absolutely essential that the true relation of the velocities of the parts should be preserved, and a positive driving of the bobbin is therefore necessary.

(209) A few words may be expended in explaining the principle underlying the second and third methods of winding

the roving on the bobbins, and for this purpose the four diagrams given in Fig. 147 will be useful. In each of these the circle A represents the spindle, B the surface of the bobbin, and C the path of the flyer. The roving passes from the flyer eye at D on to the bobbin at E, as shown in the figure marked 1. Now, if the two surfaces B and C rotate at a constantly uniform speed, the relation of the positions of D and E remains the same, and therefore no roving can pass from one point to the other. If, however, the flyer moves in its orbit at a superior speed to the surface of the bobbin, then, as shown in the diagram No. 2, the point D having gained the distance from E to F during any given number of revolutions over the point E, it follows that on the surface of the bobbin B yarn will be wound for that distance. This is indicated by the thick line extending from E to F

FIG. 147.

This gain, if continued, will cause the roving to be wound on the whole of the peripheral surface of the bobbin, and the velocity with which the winding takes place depends upon the diameter of the bobbin B, upon its velocity, and upon the length of roving delivered by the rollers. This is the effect when the flyer leads. Now, if it be assumed that during any definite number of revolutions the point E on the bobbin has moved so much faster than the point D, representing the flyer eye in the third diagram, then the same result is produced by this excess of speed as shown in diagram 4, but in the opposite way to the former instance. In this case of a " bobbin lead," also, the amount of this excess of movement is limited by the three factors previously named. The explanation thus given holds absolutely so long as the diameter of the bobbin remains

constant, but as soon as this is departed from the conditions are at once changed.   Suppose, for instance, that the circumference of the front roller and of the bobbin alike is one inch.   Then, so long as the velocity of the bobbin is the same as that of the rollers, it will take up all the material delivered by the latter. If, now, it be assumed that the velocity of the bobbin and rollers and the circumference of the latter remain constant, while the circumference of the bobbin be increased to $1\frac{1}{2}$ inch, it will follow that for every inch of roving delivered by the rollers $1\frac{1}{2}$ inch can be taken up by the bobbin.   As the roving is gripped by the rollers this quantity cannot be obtained, and if such con-ditions arose the roving would be ruptured.   It is therefore absolutely necessary to provide some means whereby the velocity of the bobbin can be reduced as its diameter increases, so that its surface speed shall coincide exactly with that of the rollers.

(210) It is the practice at the present day to adopt the bobbin lead, and there are several reasons to commend this course.   It will be shown hereafter that the bobbins and flyers are driven by two trains of wheels.   Of these, the train driving the spindles contains the fewest members, and is directly con-nected with the driving shaft.   Thus there is more danger of delay in the commencement of the rotation of the bobbins than there is in that of the spindles.   When a frame is started, therefore, the spindles begin to revolve a little quicker than the bobbins, and the flyers tend to slightly stretch the roving before the bobbins have assumed their true relative velocity. If, on the other hand, the bobbin leads, the tardy commence-ment of its rotation only causes a little slack place to exist, which is rapidly taken up as the parts begin to revolve at their full working speed.   In addition to this fact there is another, which is, in view of the wear and tear of the frames, not unimportant— viz., that the velocity of the wheels, when the flyer leads, is much greater than when the bobbin leads, and accelerates as the latter fills with roving, which it does with every lift of the bobbin-rail.   If the bobbin has to lag behind the flyer, as is the case with the latter leading, it is easy to see that the retardation

must be greater when the bobbin is empty than when it is full, for it is clear that there is a smaller surface on which the roving is wound in the former case. As the bobbin fills, therefore, its surface velocity must be increased, in order that the relative position of the point where the yarn leaves the flyer and that where it passes on to the bobbin shall be preserved. Let it be assumed again that the bobbins and rollers are the same circumference, then the bobbin must lag behind the flyer one revolution for every revolution of the roller. If, however, the circumference of the bobbin is increased to double that of the roller, then it is clear that its periphery with the same amount of retardation would not be covered, but that such a drag would be put on the roving as to stretch and break it. Thus half the retardation is sufficient, and the bobbin must be quickened in order to attain that end. The reverse of this is the practice when the bobbin leads. In that case the bobbin requires to run at a velocity so much in excess of the flyer as will enable it to take up the roving delivered by the rollers. Now it will be at once apparent that the smaller the surface on which the roving is wound, the greater the number of revolutions needed to take it up as delivered by the rollers. Thus a gradual diminution of the speed of the bobbins takes place as they are filled. The action is not easy to describe, but may briefly be put thus. With the flyer leading, the roving is *wrapped* on a surface which is moving at a relatively slower pace than the flyer-eye. With the bobbin leading, the roving is *drawn* on to a surface travelling a relatively quicker pace than the flyer eye. Therefore, the larger the diameter on which the roving is wrapped— given a uniform delivery—the greater its velocity when the flyer leads, and the less when the bobbin leads. Now, it should be noticed especially that the increase in speed takes place, with the flyer leading, as the bobbins become heavier, and therefore more difficult to drive ; while with the bobbin leading the highest velocity is attained when the bobbins are lightest. From the point of view of the spinner this is a matter of some importance, as it diminishes the strain on some of the parts very considerably.

(211) Before proceeding further it is necessary to describe in detail the mechanism employed to drive the various parts, and in order to do this the diagram given in Fig. 148 can be referred to. The driving shaft A has on its outer end a pair of pulleys, fast and loose, by which the machine is driven from the counter shaft. The shaft A extends within the framing of the machine, and has fixed upon it the wheels B and O. From the wheel B the shaft C is driven by means of the carrier wheel shown and pinion B^1. On C is fixed the upper cone E and the pinion C^1. The latter gears with the wheel D on the front roller shaft, by which means the front roller D^1 is driven, and from it the second and third lines, as shown. The spindles are driven by the wheel O, communicating motion by a carrier wheel to O^1, fixed on the end of one of the spindle-driving shafts, the second spindle shaft being driven from the first, as was described, by a pair of spur wheels fixed upon each respectively. The bevel wheels W W^1, communicate the rotation of the shafts to the spindles. The bobbins K are driven by the bevel wheels M M^1 by means of a train of wheels N K^1. The carrier wheel between N and K^1, K^1 itself being fixed on one of the bobbin driving shafts, is sustained in a swing frame, which is centred upon the shaft A. The " swing," which will be presently described, is made double, so as to give a good bearing to the arbors of the wheels, and is secured to a box or frame, which extends along the machine, and within which the bobbin driving shafts and the wheels fixed on them are sustained in suitable bearings. The bobbin rails and box are attached to vertical racks or pokers V, which are suitably guided, and to which an alternate reciprocal motion is given by the rotation of pinions V^1, obtained in a manner to be afterwards described. Thus the bobbin rails receive a vertical motion up and down for a distance which is regulated by the period of rotation of V^1 in either direction. The swing being fastened to the bobbin rail is caused to oscillate on its centre, and the wheel K^1 and its carrier are made to roll round the wheel N. In this way the necessary constant driving of the bobbin K is obtained, while

at the same time it can receive the requisite vertical traverse to effect the operation of winding. The wheel N, known as the "bobbin wheel," is compounded with a wheel I^1, forming part of the differential or equating motion, to which a full treatment will be given presently. I^1 is driven by means of the intermediate carrier wheels $J J^1$, from the pinion I, which is fastened on and revolves with the driving shaft. The carriers $J J^1$ are borne in studs fixed in the arms of the plate or stud wheel L, which rotates on a sleeve surrounding the shaft A, and which is driven by a pinion L^1 fastened to a shaft H. On the end of H is a pinion G, driven by a carrier from a wheel G^1 fixed on the axis of the lower cone E^1, which receives its motion from the upper cone E by a strap F. On the shaft H is also a bevel pinion R engaging with a wheel R^1, fastened on the head of a vertical shaft, on the lower end of which a pinion S is secured, which can be engaged by either of the wheels $S^1 S^2$—called "striking wheels"—when they are thrust into gear with it. The pinions $S^1 S^2$ are fixed on a shaft which has a long pinion T fastened on it, T engaging with a pinion T^1 on a short shaft borne by the framework. This shaft is in front of the spindle shaft from the point of view in Fig. 148, and should not be confused with it. A pinion U keyed on it engages with a wheel U^1, fastened on a horizontal "lifter" shaft, on which the pinions V^1 are secured. Thus the latter receive rotation in a direction which is dependent entirely on the engagement of either S^1 or S^2 with the pinion S. The traverse of the strap F on the cones and the alternate engagement of S^1 and S^2 with S are both controlled from the motion Q, to which special reference will be hereafter made.

(212) Before doing so reference may be made to the method of communicating the motion of the bobbin wheel to the bobbin shaft. This is effected by a train of wheels consisting ordinarily of the bobbin wheel, a carrier, and the bobbin shaft wheel. In some cases two carriers are used, but the action is the same in either instance. The bobbin rail rises and falls as described, so that it is necessary that the connection between

FIG. 148.

the shaft and the bobbin wheel shall be of a flexible character. The carrier wheels are therefore sustained in a double frame, which is centred to the jack shaft and fastened to the bobbin rail. Thus as the latter rises and falls it carries the wheels with it, no break in the driving connection taking place. At one time the "swing" frame, as it is called, was single, but with modern speeds it is customary to make it double, so that the carriers are borne at each side, thus ensuring steadiness in work. The arrangement is shown in Fig. 149, and it will be noticed that as the axis of the bobbin wheel N is fixed, the

Fig. 149.

carrier wheel O engaging with it will receive, in addition to its rotary axial movement a similar rotation in consequence of its rolling contact with N. The direction of the rotation thus caused will vary with the direction of the traverse of the bobbin rail. Thus, if the rail is ascending, the wheel O will rotate in the direction of the arrow marked 1, while if the rail is descending it will tend to rotate in the direction of arrow 2. If wheel N be moving as indicated it will drive O in the direction of arrow 1, so that the effect of the rise and fall of the rail will be to accelerate the motion of O during the ascent and

retard it during the descent. As the bobbin shaft wheel S is
driven by the train of wheels named it follows that it and the
bobbins will be affected in the same way as O to a degree
which depends upon the extent of the bobbin traverse. It
follows, therefore, that during the ascent of the rail the
bobbin will be accelerated and during its descent retarded, thus
stretching or thickening the roving alternately. The divergence
from the normal speed takes place mainly in the last part of
the lift of the bobbin, although there is a certain amount
during the whole period. It is quite clear that any such action

FIG. 150.

will produce inequalities in the roving which it is very desirable
to avoid, because the alternations of acceleration and retarda-
tion take place during different periods in the process and
affect different parts of the roving. In order to overcome this
difficulty Messrs. Brooks and Shaw have devised the arrange-
ment shown in Fig. 150. In this case the four wheels are used
as shown, and are coupled by the links forming the swing. To
the spindle of the second carrier wheel P is attached an arm R
which is centred at a point R^1 behind and below the jack
shaft A. Upon the position of this centre depends the efficacy

of the mechanism, which has for its object the neutralisation of the rotation of the wheel O caused in the manner described. The movement of O is communicated to the carrier wheel P, which, under ordinary circumstances, would pass on the movement to the wheel S.   By reason of the rigid arm R the centre of P is made to travel in the arc described with the radius $R^1 P$. In the diagrammatic drawing, Fig. 151, the centre position of S is shown by the full line marked 1, its highest position by the line marked 2, and its lowest position by line 3.   Each of the parts are indicated by the same character of line when in any of the positions.   A glance will show that in the total traverse of the rail during which the wheel S moves from position S^1 to S^2 the centre of P is pushed outwards from the position indicated by the vertical line T^1 dropped from the centre of P in its lowest position to T^2, which is a similar line drawn when P is in its highest position.   In other words P is made to move laterally, and in doing so rolls round S to an extent exactly equal to its angular movement on its axis in consequence of the rotation of O.   The result is that the latter is neutralised and the rotation of the wheel S is unaffected by the vertical movement of the rail.   This can be easily seen by the removal of the arm R, which is followed, if the rail be moved, by a rotation of the wheel S in exact correspondence with the extent of motion.   It will be seen that in consequence of the relative positions of the centre of the wheel N and the carrier P, that the centres of O and P make a greater movement while S is rising from the middle to the top position than when it moves from the bottom to the middle position.   This is clearly shown by the letters P, P^1, and P^2, which represent respectively the middle, bottom, and top positions of P.   The distance $P^1 P$ is seen to be less than the distance $P P^2$, although the movement of S is equal in each.   This indicates that if left unchecked there would be a greater movement of S in the last portion of its ascent than in its first.   In like manner the vertical lines T, T^1, and T^2 show that there is a difference in the relative movement of the wheel P in an outward

direction, owing to the action of the arm R. The two movements are the complements of each other, and together the effect is to neutralise the angular movement of O round N. The whole matter turns upon the actual position of the centre R^1, because if this is not so placed as to give the

FIG. 151.

requisite lateral movement to the centre of P the latter communicates a certain rotation to the wheel S. Mechanically the result is very interesting, and to the student is an example of the effect of combining link-work and rolling contact.

(213) The general description thus given will enable the operation of the various parts to be understood. Assuming the speed of the driving or "jack" shaft A to be 300 revolutions per minute, the velocity of the spindles is obtained by multiplying together the driving wheels and dividing the product by that of the driven wheels multiplied together. The dimensions about to be given are all taken from a frame in actual work, which was producing a roving for a special purpose. They will, however, enable the relative influence of the various parts to be followed with ease, and will also show the mode of calculating the velocity of the various parts. We will first, therefore, ascertain the relative velocity of the spindles and rollers, so as to determine the twist put into the roving. The spindles are driven by the wheel O, with 60 teeth, driving, by means of a carrier wheel, O^1, which has 50 teeth. O^1 is on one end of a shaft having on the other end the bevel pinion W, with 50 teeth, gearing with the spindle wheel W^1, with 22 teeth. The velocity of the spindles is therefore $\frac{60 \times 50}{50 \times 22} \times 300 = 818$. The front roller is driven from the jack shaft A by a pinion B, known as the "twist" wheel. By changing this wheel the relation of the velocities of spindles and rollers is entirely changed, and, as will be afterwards shown, every motion in the frame is controlled by this wheel. B has 28 teeth, and drives, by the intervention of a carrier, the wheel B^1 fixed on the top cone shaft C. B^1 has 32 teeth, and on the outer end of the shaft C is a wheel C^1 with 34 teeth, which meshes with the wheel D on the front roller shaft having 120 teeth. The velocity of the front roller is therefore $\frac{28 \times 34}{32 \times 120} \times 300 = 74$. The front roller being 1⅛ inch diameter, it will deliver 261·5 inches of yarn per minute. The twist is therefore $\frac{818}{261 \cdot 5} = 3 \cdot 12$ per inch. The second and third lines of rollers are driven by means of a pinion with 20 teeth gearing into a crown wheel of 110 teeth, compounded with a pinion having 35 teeth, which gears with a

wheel of 57 teeth on the back roller. Thus the speed of the back roller is $\frac{20 \times 35}{110 \times 57} \times 74 = 8\cdot26$, and that of the centre line is the same, the driving being arranged for this purpose. The back roller is the same diameter as the front roller, and the draft is therefore $\frac{74}{8\cdot26} = 8\cdot97$, which is somewhat in excess of the usual draft, and, as will have been noticed, is put in entirely between the centre and front rollers.

(214) We now come to deal with the driving of the bobbins, and on the assumption that the bobbin is leading, we have to deal with a case in which it shall travel so much in excess of the velocity of the flyer as to take up in every minute the 261·5 inches of yarn delivered by the rollers. The upper cone shaft C rotates at $\frac{28}{32} \times 300 = 262\cdot5$ revolutions per minute, and drives the upper cone E at that velocity. Assuming that the strap was on equal diameters of each cone the lower cone E^1 would be rotated at the same velocity. In that case the pinion G^1, which is on the lower cone shaft and has 15 teeth, will drive the wheel G with 75 teeth at $\frac{15}{75} \times 262\cdot5 = 52\cdot5$ revolutions. G is fastened on the shaft H, on which is also the pinion L^1 with 20 teeth engaging with the " sun " or " stud " wheel L, having 125 teeth. L therefore is revolved $\frac{20}{125} \times 52\cdot25 = 8\cdot4$ times per minute. The wheel L forms part of the " differential " or " equating " motion, which requires a special explanation before proceeding further. This motion is sometimes called the " Jack in the box," and is perhaps more widely known by that name than by any other.

(215) The differential motion Fig. 152 belongs to that species of motions which are known in mechanics as epicyclic trains, and which consist of two wheels geared together by a carrier, the carrier and last member of the train being borne by an arm which revolves on the same axis as the driving wheel

during the rotation of the driving and driven wheels. It
is quite unnecessary to do more than explain the action of
the motion, as the theory upon which it is based belongs
to the domain of mechanics, and not that of cotton
spinning. It is fully treated in other text books, especially
in " Goodeve's Elements of Mechanism." The letters referred
to will be those in Fig. 151, but the necessary corresponding
references in Fig. 148 will also be given. In this special case
the wheel B fixed on the " jack " shaft drives by the interven-
tion of carrier wheels C E the wheel D loose upon the same

FIG. 152.

shaft, and compounded with the wheel N which is either
cast in one piece with it or fastened on its boss. It is
now customary to provide a tube surrounding the "jack"
shaft on which the wheels L and D N revolve. By shelling
out the tube and providing special means of lubrication
the friction on the shaft is much reduced. The carrier
wheels C E are borne by studs fixed in the arms of the
wheel L, and are free to revolve thereon. Thus they have
a rotatory motion upon their axes, and are simultaneously
carried round the orbit of the wheel L as it is revolved. The
motion of these parts produces a very remarkable result in

practice, and as it is often only imperfectly understood a full explanation is given. If the pinions C E were mounted on centres which were stationary, the rotation of the wheel B would cause D to revolve at the same speed in the contrary direction. If now the wheel L is revolved in the same direction as B, and at an equal velocity, the whole of the wheels will be locked, and D be carried round at the same speed as B. If, however, the wheel L rotates at a slower speed than B, but still in the same direction, then for every revolution of L the wheel D will lose two revolutions as compared with B. Thus in practice a curious result is produced. When the velocity of L is half that of B, and its direction of rotation the same, the motion of D entirely ceases. As the velocity of L still further decreases the velocity of D increases, but its *direction* of rotation is reversed. Thus what happens is, that if the velocity of L is either more or less than half that of B, its direction of rotation being the same, the velocity of D is increased, but the direction of its motion is altered—that is to say, the central point is a zero, and there is a gradual acceleration until either of the poles—as they may be called—are reached. Thus, if L revolves in the same direction as B, and makes more than half the number of revolutions of B, then the wheel D will move in the same direction as B, at a constantly accelerating velocity, as the speed of L and B approximate to one another. If, on the other hand, L rotates at less than half the speed of B, then there will be a constantly accelerated velocity as the speed of L is decreased, but the direction of the rotation of D will be reversed. It may be convenient to give the formula ordinarily employed to calculate the value of this class of wheel train. It is $n = 2a - m$, where $n =$ the number of revolutions of the last wheel D, $m =$ the number of revolutions of the first wheel B, and $a =$ the number of revolutions of the stud wheel L. Thus, if $m = 300$ and $a = 150$, then $n = 2(150) - 300 = 0$. If $m = 300$ and $a = 100$, then $n = 2(100) - 300 = -100$, indicating that D is revolving 100 times per minute in the opposite direction to B. If $m = 300$ and $a = 200$, then $n = 2(200) - 300 = 100$, or in other

words, D and B are revolving in the same direction at that speed. Now, if the wheel L revolves in the opposite direction to B, quite a different state of things arises, for the formula then becomes $n = -2a - m$, the quantity a having, by the reversal of the movement of L, become a minus quantity. Then the equations become as follows, when (1) the wheel L is stationary, (2) when it revolves at half the speed of B, and (3) when it revolves at the same speed as B, but all in the opposite direction : (1) $n = -2(0) - 300 = -300$; (2) $n = -2(150) - 300 = -600$; (3) $n = -2(300) - 300 = -900$. In other words, the velocity of the wheel D steadily increases with the increase in the speed of L, but the direction of its motion is in all cases the reverse of that of B. This fact has an important bearing upon the working of the motion, because it enables an equal velocity of the wheel D to be got with a slower speed of the wheel L. Further, when the bobbin leads, it is possible to commence the operation with a comparatively moderate speed of the wheel L, and to still further reduce it as the bobbin fills and requires a smaller circumferential speed. Thus we arrive at the conclusion that when the flyer leads it is better to run the wheel L in the same direction as B, and gradually accelerate the velocity of D, while with the bobbin leading it is necessary to rotate the wheel L in the opposite direction to B, and gradually diminish the velocity of D. From the point of view of wear and tear, there is no comparison in the merits of the two systems.

(216) Without pausing to consider the way in which the wheel L has its rotation diminished, we will take up the calculation where it was dropped in paragraph 213, merely premising that the wheel L is rotated in the opposite direction to the jack shaft, and consequently to I (Fig. 148 or B in Fig. 152). We saw that L was revolved 8·4 times per minute, therefore according to the formula $n = -2a - m$ we get the velocity of I^1 (Fig. 148 or D in 152) as $-2 (8·4) - 300 = 316·8$; that is, I^1 is revolving in the opposite direction to I at a speed of 316·8 revolutions. The wheel N has 60 teeth, and drives by the intervention of a carrier the wheel K^1, which has 50 teeth. On

the same shaft as K^1 is the bobbin wheel M with 50 teeth, which drives the bobbin by means of the pinion M^1 with 22 teeth. Thus the velocity of the bobbin is $\frac{60 \times 50}{50 \times 22} \times 316 \cdot 8 = 864$, which is 46 revolutions in excess of that of the spindles.

(217) In the differential motion constructed as described, it is necessary to use bevel wheels to transmit the motion of the driving pinion to the bobbin wheel. It is also requisite for the wheels to revolve in the opposite direction to the shaft, and when they are borne directly by the shaft this gives rise

FIG. 153.

to a good deal of friction. Accordingly, it has been thought desirable to design differential motions, by which the same effect is obtained without the evils ordinarily attaching to the motion. In one motion—Curtis and Rhodes'—the object has been to avoid the use of bevel wheels altogether and use spur wheels only. This motion is shown in Fig. 153, and consists essentially of a disc L, which carries studs, as shown at one part of it. One of these studs has fixed upon it the pinions D and E, and revolves with them. The pinion E engages with a pinion F, compounded with H, both of these revolving freely on the second stud. The pinion H is meshed with a pinion J,

L

formed on the end of the long collar K, on the other end of
which the wheel G is fastened.   Thus, the rotation of G from
the lower cone in like manner rotates the whole train of pinions
from H to D.   The latter is geared with an internal rack C,
formed in the flange of a long bush B, rotating on the jack
shaft A and having fastened on it the bobbin wheel N.   The
wheel G has 40 teeth ; the pinion J, 24; H, 28; F, 25; E, 23;
D, 14; and C 90.   The wheel G rotates at 316 revolutions
when the belt is on the small end of the cone E^1 (Fig. 148), a
special train of gearing being employed between E^1 and G.   The
disc L is fast on the shaft, and therefore revolves at 300 revolu-
tions ; or, in other words, the wheel G revolves at 16 revolutions
in excess of L.   Now, the pinion D is carried round with the
disc, so that it will cause the internal wheel to gain on the disc,
and the extent that it gains can be easily calculated by obtaining
the value of the train from J to C, and multiplying it by the
excess of revolutions made by the wheel G over the disc.   This
works out thus, $16 \times \dfrac{24}{28} \times \dfrac{25}{23} \times \dfrac{14}{90} = 2\cdot32$.   That is, the internal
wheel C revolves 302·32 times per minute, from which the
speed of the bobbins can be easily calculated.   It must be
clearly understood that the speeds and sizes of wheels, although
those actually used in some cases, are, so far as the present
instance is concerned, purely arbitrary, and are simply used to
illustrate the method of making the necessary calculations.

(218) Tweedale's motion is illustrated in Fig. 154, and
consists of a compound bell wheel C D revolving on the shaft
A, the direction of the motion of the wheels being indicated by
arrows.   The wheel B is connected with the cones, and is com-
pounded with the pinion E, both of these revolving freely upon
the shaft.   A double boss G is fixed on the latter, and carries a
short transverse shaft on each end of which respectively the
pinions F and H are fastened.   The shaft passes through a hole
in the shaft, but the horizontal boss of the arm G surrounds
the shaft at this point so as fully to maintain its strength.   The
pinion E engages with and rotates F, thus giving motion to the

pinion H, which drives the wheel D. There is one important
point in this motion, which is, that the wheels B, E, and D
revolve in one direction and at a slower speed than the jack
shaft, the speed being gradually diminished as the bobbins fill.
This motion deserves a full explanation. It belongs to the
epicyclic class, but has some points of difference to the ordinary
motions. It will be seen that the motion given to D is com-
pounded of two, that due to the rotation of the arm G and that
to the rotation of the pinion E. Let us assume that G—or the
jack shaft upon which it is fixed—makes m revolutions. The
pinions F and H in their revolution round the axis of A are

FIG. 154.

free to rotate on their common axis, and accordingly, as in the
Holdsworth motion, would give a rotation in the opposite
direction to the pinion E at a speed equal to $m \times \dfrac{E}{F} \dfrac{H}{D}$. The
latter factor represents the value of the train from E to D. It
now it be assumed that the arm G is fixed—that is to say, the
jack shaft is stationary—then if E makes n turns, the speed of
the wheel D is $n \dfrac{E}{F} \dfrac{H}{D}$. The ultimate velocity of the wheel D
when both the pinion and shaft revolve is equal either to the
sum or difference of the speed given in the two conditions

named. Obviously there is, if the jack shaft revolves in one direction and the pinion E in another, an added velocity given to the pinions F and H, which would affect the speed of the bobbin wheel; while as clearly, if the pinion E and the jack shaft revolve in the same direction, there is a reduced velocity of F and H. If, therefore, the value of the train E F H D be called r, then the velocity of the wheel D is

$$V = (m - m\ r) \pm (n\ r), \text{ or by transposition,}$$
$$V = m - r\ (m \mp n).$$

When the flyer leads, the factor in the brackets is $m + n$, for the reason stated; while when the bobbin leads, it is $m - n$. The speed of the pinion E is reduced as the bobbin fills when the latter leads, and its direction of rotation is the same as the jack shaft. When the flyer leads the speed of the pinion E is increased as the bobbin fills and its direction of motion is reversed. For a bobbin lead, therefore, the formula is :—

$$V = m - r\ (m - n),$$

and for a flyer lead—

$$V = m - r\ (m + n).$$

The pinion E is made with 18 teeth, H with 16, F with 30, and D with 48. The ratio r is, therefore, $\dfrac{18 \times 16}{30 \times 48} = \cdot 2$. If the revolutions of the jack shaft be assumed to be 300, and of E 260 revs., then the two formulæ work out as under—

$$V = 300 - \cdot 2\ (300 - 260) = 292.$$
$$V = 300 - \cdot 2\ (300 + 260) = 188.$$

The chief advantage derivable from the use of this motion is, that as all the wheels rotating on the jack shaft run in the same direction as that shaft, a considerable amount of friction is saved. This statement, of course, only applies to the bobbin leading frames, because, as was pointed out, there is a reversal of motion when the flyer leads. The cross-shaft and its attached pinions have an entirely independent motion, revolving in the direction of the upper arrow in bobbin leading frames, and their rotation does not affect the friction on the jack shaft, which is

an important point. The mechanism is very rigid and runs well, and, on the whole, this is one of the best of the newer appliances.

(219) Another differential apparatus is Brooks and Shaw's, which is illustrated in Figs. 155 and 156. The cone pinion is fastened on the boss C of the disc C¹, which has a flange C². The latter joins up to the flange G¹, forming part of the disc G. Both discs revolve freely on the bosses or sleeves shown surrounding the jack shaft, and carry pins

FIG. 155.

E which are secured by nuts. The discs and flanges form a cover for the gearing, in addition to acting as the revolving arm. Fixed on the jack shaft A is a pinion B, which engages with the pinions F freely rotating on the pivots E, and compounded with the pinions F¹. The latter, in turn, gear with the wheel D¹, running loose on the jack shaft, and having a long boss D on which the bobbin wheel is fastened. It will be seen that oil ducts are formed in the spindles E, oil being fed by specially contrived oil cups K, so as

to establish in the eyes of the pinions F F¹ continuous and
ample lubrication.   In this motion the chief features are, as in
the one preceding, a wheel train, of which the first member is B
and the last one D, and a rotating arm C¹.   The value of the
wheel train which forms the first essential feature is $\dfrac{B}{F} \times \dfrac{F^1}{D^1}$.   B
has uniformly 30 teeth, F and F¹ each have 18 teeth, while the
number of teeth in D¹ is, in the slubbing frame, 37; in the
intermediate, 35; and in the roving frame 33.   If, therefore,

FIG. 156.

the jack shaft makes m revolutions, the arm C¹ being stationary,
then D¹ would make $\dfrac{30}{37} m, \dfrac{30}{35} m$, or $\dfrac{30}{33} m$ revolutions re-
spectively.   The effect of rotating the arm C¹ is somewhat
peculiar.   The rotation of the arm once round the shaft A
causes the teeth in F to roll over 30 teeth of B.   As, during
the same time, the pinion F must roll round the wheel D¹, and
F F¹ are fastened together, it follows that unless the wheel D¹ is
moved, the whole train would be locked and would rotate at the
same speed as the jack shaft.   D¹ being free, can move, and

the effect is that if C^1 has a velocity in excess of that of the jack shaft A, the wheel D^1 must be carried forward during each revolution the number of teeth it has in excess of B. If, on the other hand, the arm C^1 moves more slowly than A, then, in like manner, it retards the movement of D^1. Putting this into a formula, let n = number of revolutions of D^1, m = number of revolutions of B, a = number of teeth D^1 has in excess of the teeth in wheel B, b = total number of teeth in D^1, and c = number of revolutions of C^1 more or less than those of B. If c be more than m, then $n = m + \left(\dfrac{a}{b}c\right)$, and if c be less than m, then $n = m - \left(\dfrac{a}{b}c\right)$. Putting this into figures, let $m = 250$, $a = 7$, $b = 37$, $c = 250$ (that is, 250 more than m), then $n = 250 + \left(\dfrac{7}{37}250\right)$ $= 297\cdot3$. Now, let $c = 158\cdot5$ (that is, C^1 is actually making $91\cdot5$ revolutions, then $n = 250 - \left(\dfrac{7}{37}158\cdot5\right) = 250 - 29\cdot993 = 220\cdot007$.

It is thus possible to get a wide range of regulation with a comparatively slight movement of the sleeve C, because it is never necessary to rotate it at a higher rate than the wheel B, its movement at an equal rate simply causing all the wheels to roll round together at an equal speed. Taking this point as the zero, the velocity of the bobbin is gradually decreased as it falls by diminishing the speed of the arm C^1. This is, of course, when the bobbin leads, the procedure being reversed when the flyer leads. The wheels all run in the same direction, and their speed is slow.

(220) Another form of motion is that shown in Fig. 157. On the jack shaft A are the spindle wheel C, the bobbin wheel N, and the cone wheel G. Also fastened on A is a bevel wheel B, which gears with one set of teeth on a double bevel wheel P. On the other face of P is a second set of teeth D, which gear with teeth on a wheel F, which has a long boss, and is fastened on a sleeve E, to which the bobbin wheel N is also fixed. At E^1 the sleeve is swelled out into a ball or sphere on

which the wheel P can revolve. The wheel P, as can be clearly seen, forms a sort of clutch between B and F, so that all the parts would rotate together. Working loosely on the shaft is a hollow sleeve N, the inner face of which is turned, and presses against the face of the wheel P. A glance at the illustration will show that the face of L is diagonal to the axis of the shaft A, and that consequently the position occupied by L determines the vertical position of the wheel P. On the sleeve of L the cone wheel G is fixed, so that L is rotated at a speed regulated by the velocity of the driven cone. If L makes a complete rotation, it will obviously rock P on its bearing E^1, and will cause all the teeth of P to engage with all the teeth of B and F in succession. As D is larger than B in the proportion of

FIG. 157.

$9 : 8$, the result is that D is retarded, or, in other words, its teeth do not all engage in one revolution. D thus loses a little speed, and instead of driving F at a velocity equal to that which one revolution of B would give, it drives it a slower speed. As N is compounded with F, it also—and by it the bobbins—have their speed reduced. By suitably speeding the wheel G, the necessary variation can be got. It is a peculiarity of this motion that the work of the cam L is confined to giving the retardation to the wheel D, the necessary excess of the bobbin speed over the spindles being in the first instance got by making N larger than D. By a duct K oil is admitted to the chamber R and finds its way into the inside of the outer casing in which it is flung about by the dashers shown.

It is most important in arranging the wheels in the differential motion, whatever may be its construction, that care should be taken to give the bobbin the correct surface velocity to begin with. That is to say, when the bobbin is empty its velocity must be equal to that of the flyers if the cone drum is stopped. In this case the only motion given to the bobbin is that derived from the rotation of the fixed wheel on the jack shaft, which transmits its motion through the train of wheels. The function of the cones is to give such a variation of speed to the bobbin as will wind the roving when delivered, and when the cone belt is in its initial position at one end of the cone the effect should be to give the bobbin such an amount of acceleration or retardation as will suffice to do this. In some differential motions this essential feature is absent, and cases have come under the notice of the author which demonstrate the importance of the subject. It is sometimes the practice, in order to meet the difficulty, to provide a larger driving pinion for the bobbins than is used for the spindles, but although this practice is permissible, it is, for many reasons, inadvisable. What is wanted is a re-adjustment of the gearing in the differential motion, in order that the proper driving is given to the bobbins. Any other procedure is likely to confuse the users of the machines, and more especially those whose duty it is to set and adjust them.

(221) An examination can now be made of the effect of the cones upon the motion of the "stud" or "sun" wheel L, and in doing so it will be necessary to explain why the cones are hyperbolic in outline. Their object is, as has been stated, to effect a reduction in the velocity of the wheel L, and owing to the fact that the surface which is finally operated on—that of the bobbin—is gradually increased, the reduction in the velocity of the wheel L must be also uniformly and gradually made. Of the two cones, E is the driving and E^1 the driven one, and the motion is communicated from one to the other by means of the belt F. In order to accelerate or diminish the velocity of E^1—that of E being constant—the

belt F is traversed along the cones from one end to the other.
From this it follows that if the bobbin is to lead the cones are
placed as in Fig. 148, while if the flyer leads they are reversed.
The diameters of the large and small ends of E and E¹ are
respectively 7 and 3½ inches, and they are placed with their
large and small ends opposite one another. Thus, if the strap
is on the large end of E and the small end of E¹, the latter
will be driven at double the speed of the former. When these
conditions are reversed the velocity of E¹ is only half that of
E. By this arrangement the belt is kept in even tension. If
the speed of the shaft C is 262·5, and the belt F is on the large

end of E, then E¹ will revolve at $\frac{7}{3\cdot5} \times 262\cdot5 = 525$ times per

minute. If, now, the belt be at the other end of the cones, E¹

will revolve $\frac{3\cdot5}{7} \times 262\cdot5 = 131\cdot25$ times per minute. Thus by

traversing the strap from the first-named position to the last,
there would be a diminution of the speed of E¹ from 525 to
131·25 revolutions per minute. Now it is not enough that the
total diminution must take place during the total traverse of the
strap from one end to the other, but it must exactly correspond
at any point with the required diminution of the speed of the
bobbin. If the cones have a straight profile—that is, if they
are right cones—this correct diminution will not occur. This
is a well-established fact, and the theory upon which the forma-
tion of the profile is based may be profitably explained.

(222) As was shown, the object of the increase or diminution
in speed of a roving bobbin is to enable it to wind upon its surface
during a given time precisely the same length of yarn. This
increase or decrease is, as has been made clear, on the uniform
speed of the spindles, but as this is a constant factor, it will be
disregarded in the demonstration which follows. The length of
yarn which can be wound on the bobbin at any time is fixed by
the uniform circumferential speed of the rollers, and it is this
which is the governing factor in the case. The number of revo-
lutions required to take up the yarn during each revolution is,

if l = roller delivery and c = circumference of bobbin $\dfrac{l}{c}$, a con-
tinually varying quantity. Now this factor is the reciprocal of
the diameter of the bobbin, and is the one which forms the
basis of the operation. In other words, it is the delivery which
determines the matter. If the factor l were not a constant one,
it would be difficult to determine the speed to be given to the
bobbins, but this uniformity makes all the difference to the
result. As the building proceeds by regular additions to the
diameter of the bobbins, it follows that the value of the
quantity $\dfrac{l}{c}$ will be affected by the increase in the factor c.
For instance, each ⅛ inch added to the diameter increases the
circumference by ·3927, and the reciprocal will necessarily be
diminished thereby. If it be assumed that the bobbin is 1 inch
diameter when bare, and that each layer increases it ⅛ inch
until it is 2 inches diameter, then if l = 1 inch, the value of $\dfrac{l}{c}$ in
each case would be as follows:—For 1 inch diameter, ·3183;
for 1⅛ inch, ·2829; for 1¼ inch, ·2546; for 1⅜ inch, ·2315.
for 1½ inch, ·2122; for 1⅝ inch, ·1958; for 1¾ inch, ·1819;
for 1⅞ inch, ·1697; and for 2 inches, ·1592. That is to say,
the bobbins must make to wind on 1 inch in each of the posi-
tions named respectively, the fraction of a revolution which is
stated in excess of the speed of the spindles when the bobbin
leads or less than it when the flyer leads. In other words, the
bobbin velocity is in inverse proportion to the diameter of the
bobbin, and in direct proportion to the reciprocals of its various
diameters. It will be seen that, in consequence of this undoubted
fact, the diminution or increase of the speed depends upon the
relation which exists between the diameter of the bobbin at any
particular point in building and the velocity of the driven cone
at the corresponding position of the cone strap. That this will
be so is evident from the fact that the length delivered by the
rollers being constant, the only variable quantity is the circum-
ference of the bobbin, which fixes its relative velocity. It is

better to deal with the problem mathematically, because it is necessary to establish ratios which it would be inconvenient to do by figures. In applying cone drums they are placed with their large ends in opposition to the small ends, so that it is necessary in order to keep the belt in even tension that the sum of the diameters of the cones at all points in their length shall be constant. Although this is practically true in roving frame cones, there is a slight correction needed when an open belt is used if the centre of the cones are near each other. Theoretically, this correction should be made, but practically, calculations on the basis about to be explained will be found to be sufficiently accurate. The strap is moved along the cones an equal distance every time a fresh layer is commenced.

Let d = diameter of the bobbin barrel

a = the uniform addition to the diameter for each layer.

n = the number of layers.

l = the constant length delivered by the rollers in any given time.

The various diameters will be expressed by the following arithmetical series :—

$$d, \ d + a, \ d + 2a \ldots\ldots d + n\ a \qquad (1)$$

Therefore, the reciprocals of these diameters will be a harmonic series, and will be —

$$\frac{1}{d}, \ \frac{1}{d + a}, \ \frac{1}{d + 2a}, \ \ldots\ldots \ \frac{1}{d + na} \qquad (2)$$

If the terms of (1) are multiplied by π the various circumferences of the bobbin in the following arithmetical series are obtained :—

$$\pi d, \ \pi(d + a), \ \pi(d + 2a)\ldots\ldots\pi(d + na) \qquad (3)$$

If l is divided by the term of series (3) the following series, which is also harmonic, is obtained, and represents the revolutions of the bobbin to wind the length l :—

$$\frac{l}{\pi d}, \ \frac{l}{\pi(d + a)}, \ \frac{l}{\pi(d + 2a)}, \ \ldots\ldots \ \frac{l}{\pi(d + na)} \qquad (4)$$

There are, therefore, two harmonic series—(2) and (4)—and it will be seen that the terms of the series (4) are those of (2)

multiplied by the constant $\frac{l}{\pi}$. It therefore follows that any term in series (2) is to the corresponding term in series (4) as any other term in (2) is to the corresponding term in (4). That is to say, the speed of the bobbin varies directly as the reciprocal of its diameter or inversely as its diameter. The speed of the driven cone must also vary directly as that of the bobbin, since, no matter what the intermediate train of wheels may be, any change in the speed of one produces a corresponding change in the velocity of the other. Therefore the speed of the driven cone also varies directly as the reciprocal of the diameter of the bobbin or inversely as its diameter.

Let R = the diameter of the large end of the driving cone.

Let r = the diameter of the small end of the driving cone. These will also represent the end diameters of the driven cone in inverse order. $R + r = T$, which is the constant sum of the diameter of the two cones. When the strap is at the large end of the driving, and at the small end of the driven, cone, the speed of the latter is $\frac{R}{r}$, and when at the other end of the cones, $\frac{r}{R}$. It has been seen that the speed of the driven cone varies directly as the reciprocal of the diameter of the bobbin. If therefore,

$$d = \text{diameter of the empty bobbin, and}$$
$$D = \text{diameter of the full bobbin,}$$

there is the proportion

$$\frac{R}{r} : \frac{1}{d} :: \frac{r}{R} : \frac{1}{D} \text{ or, } \frac{R}{rD} = \frac{r}{Rd}$$

Whence

$$R^2 d = r^2 D, \text{ or, } R^2 = r^2 \frac{D}{d}.$$

And

$$R = r \sqrt{\frac{D}{d}} \quad (1) \text{ and similarly } r = R \sqrt{\frac{d}{D}}. \quad (2)$$

Let it therefore be assumed that D = 4 : d = 1 ; and T = 10·5, then R = 10·5 − r ; and r = 10·5 − R. Substituting these values in the equation (1) we get $R = (10·5 - R) \times \sqrt{\frac{4}{1}} = 2$

$(10.5 - R) = 21 - 2R$, whence $3R = 21$ or $R = 7$. As $T - R = r$ we get $10.5 - 7 = 3.5$, which is the value of r. This demonstration shows that it is easy to arrive at the diameters of the cones at each end by simply determining what the diameters of the bobbins at the beginning and end of a set shall be. These are always arbitrarily fixed and are not a matter of calculation. The initial stage of the inquiry has thus been arrived at because the diameters of the cones at each end have been settled, these being in exact proportion to the sizes of the full and empty bobbins. In order to make the point quite clear, another instance, taking another set of values, will be given. Suppose that the diameter of the full bobbin D was 5.5 inches: the diameter of the empty bobbin d 1.25 inch: and the sum of the diameters of the cones T 10.5 inches: then the diameter of the small end of the cone r would be $10.5 - R$, the diameter of the large end. The equation (1) now works out

$$R = \sqrt{\frac{5.5}{1.25}(10.5 - R)}$$
$$= \sqrt{4.4}\,(10.5 - R)$$
$$= 2.0976\,(10.5 - R)$$
$$= 22.025 - 2.0976\,R,$$
$$\text{whence } 3.0976\,R = 22.025$$
$$\text{or } R = 7.11 \text{ and } r =$$

$10.5 - 7.11 = 3.39$. The last example shows that the diameters of the full and empty bobbins are not necessarily multiples, nor need that ratio exist between the diameters of the large and small ends of the cones. What it is especially wanted to point out is that there are three factors fixed in commencing to design the cones, namely, the size of the full and empty bobbin and the sum of the diameters of the cones, and that from these three factors it is possible to arrive at the various diameters of the individual cones.

(223) Up to this point the dimensions for the extreme conditions only have been obtained, and it is necessary to see how the diameters of the cones are obtained from any point of the

build. It is not difficult to understand that precisely the same relation exists between the diameter of the bobbin and the speed of the cone, in this as in the previously cited case, that relation being the determining factor in estimating the cone diameters, rendered necessary by reason of the varied diameter of the bobbin. If, therefore, it is assumed that R and r represent the large and small diameters of the cones as before, X and x the diameters of the two cones respectively at any points corresponding to each other in the length, d_o the diameter of the bobbin at that point in its build where the position X is the correct one for the strap, and d the diameter of empty bobbin as before, an equation can be worked out on the basis previously stated, which enables the true diameter of the cone at any point to be ascertained, beginning with a similar statement to that made in the preceding demonstration.

$$\frac{R}{r} \;:\; \frac{1}{d} \;::\; \frac{X}{x} \;:\; \frac{1}{d_o} \text{ and } X + x = T.$$

Then $$\frac{R}{rd_o} = \frac{X}{xd} \text{ or } \frac{Rd\,x}{rd_o} = X = T - x$$

whence $$Rdx + rd_o x = rd_o\,T \text{ or } x = \frac{rd_o\,T}{Rd + rd_o} \qquad (3),$$

and similarly $$X = \frac{TRd}{rd_o + Rd} \qquad (4).$$

Now assuming as was done in working out equation (1), that
$$d = 1, \; R = 7, \; r = 3\text{·}5, \text{ and } d_o = 2,$$

then $$x = \frac{3\text{·}5 \times 2 \times 10\text{·}5}{7 \times 1 + 3\text{·}5 \times 2} = \frac{73\text{·}5}{14} = 5\text{·}25$$

whence $$X = 10\text{·}5 - 5\text{·}25 = 5\text{·}25.$$

By proceeding in this way, for every increase in the bobbin diameter the correct diameter of the cone at the corresponding point can be got. Assuming now that a bobbin is to be built on a barrel 1 inch in diameter, increased to 4 inches when full, and that the cones have a combined diameter of 9 inches. Assuming also that ⅛ inch is added to the diameter of the bobbin, so that there will be for the 3 inches 24 sizes calculated. Let it also be supposed that the large and

small diameters of the cones have been found to be respectively 7 and 3½ inches, and that their length is also fixed at 36 inches, which gives a traverse for the belt of 1½ inch for each ⅛ inch increase in the diameter of the bobbin. From these data the diameter of the cones at each point will be calculated. There, will be, as said, the effect of 24 additions calculated, and this being done it is found that the relative diameters of the top and bottom cones are as follows:—

Position No. ....Starting	1	2	3	4	5	6
Diameter of top cone ... 7·0	6·72	6·46	6·23	6·0	5·8	5·6
Diameter of bottom cone 3·5	3·78	4·04	4·27	4·5	4·7	4·9
Diameter of bobbin ...... 1·000	1·125	1·250	1·375	1·500	1·625	1·750

Position No.	7	8	9	10	11	12
Diameter of top cone	5·41	5·25	5·09	4·94	4·8	4·67
Diameter of bottom cone ...	5·09	5·25	5·41	5·56	5·7	5·84
Diameter of bobbin	1·875	2·000	2·125	2·250	2·375	2·500

Position No.	13	14	15	16	17	18
Diameter of top cone	4·52	4·42	4·31	4·2	4·1	4·0
Diameter of bottom cone ...	5·98	6·08	6·19	6·3	6·4	6·5
Diameter of bobbin	2·625	2·750	2·875	3·000	3·125	3·250

Position No.	19	20	21	22	23	24
Diameter of top cone	3·9	3·81	3·73	3·65	3·58	3·5
Diameter of bottom cone ...	6·6	6·69	6·77	6·85	6·92	7·0
Diameter of bobbin	3·375	3·500	3·625	3·750	3·875	4·000

It will be noticed that both the cones, although having the same terminal diameters, do not increase and diminish exactly in the same degree at their large ends. If the figures given be looked at carefully it will be seen that the diminutions as each layer is wound are not equal, but tend perpetually to diminish in amount. The important feature, however, is that if tested by the formula representing their mathematical relations the diameters will be found to correspond. That formula was

$$\frac{R}{r} : \frac{1}{d} :: \frac{X}{x} : \frac{1}{d_0}.$$

Taking the eighth position this works out $\dfrac{7}{3.5} : \dfrac{1}{1} :: \dfrac{5.25}{5.25} : \dfrac{1}{2}$.

In the twelfth position it is $\dfrac{7}{3.5} : \dfrac{1}{1} :: \dfrac{4.67}{5.83} : \dfrac{1}{2.5}$.

In the sixteenth, $\dfrac{7}{3.5} : \dfrac{1}{1} :: \dfrac{4.2}{6.3} : \dfrac{1}{3}$.

And in the twentieth position it is $\dfrac{7}{3.5} : \dfrac{1}{1} :: \dfrac{3.81}{6.69} : \dfrac{1}{3.5}$.

All the figures given, if tested, will be found to be substantially correct, and would be more so if the figures were run out to more places of decimals. Further, when tested by the reciprocals of the diameters which are represented by the value of $\dfrac{l}{c}$ they will be found to agree. Thus the velocity ratio $\dfrac{R}{r}$ at starting is $2 : 1$; when the bobbin is 2 inches in diameter it is $1 : 1$, or half the initial ratio. In like manner the number of revolutions required at 1 and 2 inches diameter respectively to wind on 1 inch of yarn have the same ratio. Again, the ratio of the diameter of a bobbin $1\frac{1}{2}$ inches diameter to the empty bobbin is as $3 : 2$, as is that of the number of revolutions required to wind 1 inch in each case, and each will be found to correspond with the velocity obtained by the diameters of the cones shown at the fourth point. Thus, if the driving cone revolves 100 times at the beginning of the winding, the driven cone makes 200. To wind the same length on to a surface which is as $3 : 2$ of another the velocity must be as $2 : 3$, therefore, in the case supposed, will be $\dfrac{2}{3}$ 200 = 133.3. If the effect of the diameters of the cones given at the fourth position is calculated on this basis it will be found that the same result is obtained. Thus 100 $\dfrac{5.143}{3.857} = 133$. It is thus clear that the ratios are the same, which demonstrates the accuracy of this method of calculation, especially when tested by the required bobbin velocity at any point, which is the determining feature. It has therefore been shown that by taking due note of all

the fixed factors it is possible to calculate the diameters of the
cones by having regard to the mathematical relation which
exists between the increase of the bobbin diameter and the
diameter of the cones at the driving point for the time being.
It is not necessary to add anything to what has been said on
the matter beyond remarking that the relations thus established
fix the nature of the cones in all cases where a variable factor,
such as exists in this case, is found.   The cones calculated by
this method will have a profile which approximates to a hyper-
bola, and is theoretically of that character.   This portion of the
subject is really a mechanical demonstration, and is only intro-
duced in order to show the principles of construction.   It is not
often that a spinner wants new cones, and when the form is
once fixed by a machinist it may be taken as being settled.

(224) The demonstration thus given, although correctly stated,
may be somewhat too abstruse for some readers, but the argument
can be restated with sufficient clearness to make it quite intelli-
gible.   The form of the curve given to cone drums depends
absolutely upon the relation which exists between the surface
speed of the bobbin at any point and the velocity of the driven
cone.   The excess of the velocity of the bobbin over that of
the flyer must be such that its surface speed will be equal to
that of the rollers whatever the diameter of the bobbin at any
stage of building.   It is not a question of an increase in the
bobbin diameter or the proportion which each increase bears to
the whole diameter which determines the matter, although these
factors do influence the problem, but the effect which each
increase has upon the velocity of the bobbins as governed by
the uniform delivery of the sliver or roving.   As was shown
earlier, the decrease in the velocity gradually diminishes as each
layer is wound, and follows what is known mathematically as a
harmonic series.   It is clear, therefore, that the same result
must follow the movement of the strap along the cones.   As the
driving cone in every case runs at a uniform velocity the varia-
tion in speed is confined to the driven cone, and such variation
must be in exact proportion to the decrease or increase in the

velocity of the bobbin. The bobbin has two fixed diameters, when it is full and empty, and in like manner the cones have fixed complementary diameters at each end. From a calculation of the effect upon the driven cone of placing the strap upon the two extreme diameters we get a certain relative ratio, and this must be in accordance with the ratio existing between the speed of the bobbin when full and empty. Thus the highest velocity of the driven cone bears the same ratio to the greatest velocity of the bobbin as the lowest velocity of the driven cone does to the least velocity of the bobbin. That is to say, if the driven cone revolves 4 times when the velocity of the bobbin is also 4, then if the velocity of the bobbin is 1 that of the cone should also be 1. The same reasoning applies to the intermediate velocities and sizes. In this case the ratio between the highest velocity of the cone and that of the bobbin is the same as the ratio between the velocity of the bobbin at any point in building and that of the driven cone at the corresponding position. Thus if the velocity of the bobbin be reduced to 2 the velocity of the driven cone must also be reduced to 2, or half its initial velocity, which is equivalent to the alteration of the position of the belt to one where the diameter of the driven cone will give this result. As the ratio of the velocity of the driven to the driving cone at the beginning is as 2 to 1, a diminution of the speed of the driven cone to half its initial speed means that the ratio must be as 1 : 1, or in other words the strap must be on equal diameters on both cones. Again, if the bobbin velocity be four-fifths its original velocity the driven cone must rotate in the same ratio. Again, using the same figures, the velocity of the bobbin must be $\frac{4}{5} \times 4 = 3\frac{1}{5}$. It is this absolute relation of the factors named which forms the basis of the method of arriving at the true shape of the cones, and enables the reason for using the latter to be fully understood. In order to render the use of the formulæ given more easy they will be stated in words. First dealing with that employed to calculate the end diameters, the rule is large diameter of cone = small diameter of

$$\text{cone} \times \sqrt{\frac{\text{diameter of full bobbin}}{\text{diameter of empty bobbin}}},$$ while for the calculation of

the diameter of cones at intermediate points in the building the formula is—

$$\text{Diameter of driving cone at any point.} = \frac{\substack{\text{Sum of both diameters} \times \text{largest diameter of} \\ \text{driving cone} \times \text{diameter of empty bobbin}}}{\substack{\text{smallest diameter of driven cone} \times \text{diameter} \\ \text{of bobbin at any point} + \text{largest diameter of} \\ \text{driving cone} \times \text{diameter of empty bobbin.}}}$$

(225) In the explanation just given the assumption has been made that the bobbin was winding directly from the rollers without the intervention of the flyer, but, as is well known, the use of the flyer, which has the function of twisting the roving, introduces another element, for if the flyer eye and the bobbin moved at the same speed, no winding would take place. It is hardly necessary to remind readers that in the case of flyer leading frames it is the excess of speed of the flyer eye over that of the surface of the bobbin which winds on the yarn, whilst it is the reverse procedure which regulates the winding when the bobbin leads. The function of the gearing between the bottom cone and the bobbin is to adjust the velocity of the latter to suit the conditions prevailing, but, as the value of the wheel train is constant, it can, as was said, be neglected in calculating the diameters of the cones. It is the variation in the speed in excess of or less than that of the flyer which has to be reckoned, and in all calculations this must be borne in mind. While this is true, it does not affect the mode of calculation given, because that is a deduction which is entirely independent of any fixed velocity of the driving cone or other part. As the diameter is a variable one, the calculation can be made in other ways by taking the ratio which it bears at any time to some fixed quantity. Thus the proportion which the bobbin diameter at any period in the build bears to its empty diameter is employed to effect the calculation, and is a simple method of doing it. What has been desired to do in the preceding demonstration has been

to show that the governing factor is the roller delivery, because upon that depends the velocity of the bobbin. It is worth noticing that in any case where there is a variable circumference or diameter on which uniformly delivered material has to be wound, the reciprocals of the diameters always enable a curve to be described which is similar in form to that shown to be necessary for the cone drums. This will be reverted to when the problem of winding on the mules is dealt with. In setting out a cone from the calculated diameters an axial line is drawn a little longer than the proposed cones, and is cut by two verticals at the points representing the length of the cones. In a roving frame the length can be arbitrarily fixed and the traverse of the strap at each movement determined in accordance with it, or the number of layers could be ascertained, a given movement fixed for each, and the total length thus obtained. The former is the better procedure. In the scutching machine the range of movement is well defined, as the variation in thickness which is likely to occur is known. The length of the cones would therefore be arbitrarily fixed in accordance with the known conditions. Having in either case drawn the axial line, it is intersected by vertical ordinates drawn through points representing equal traverses of the belt, which may be as many as desired. The respective diameters at these points are then obtained as described, and are divided by two, the distances so derived being marked out on the respective verticals on each side of the axis. Through the points so obtained a line is drawn, and this will give the profile desired. After this has been carried into practice, and the cones prepared, it is necessary to make the adjustment previously named, which can be done either with wooden or iron cones, the former being preferable. The cones which are shown in Fig. 158 have been set out in this way, and enable the method to be clearly understood.

(226) As was said, the theoretical form of cones thus obtained requires modification in one or two points, owing to various factors arising in working. When the first layer is wound on

the bobbin, it is wrapped on a rigid surface, forming—if properly laid—a continuous spiral. When the next layer is wound, owing partially to the change in the initial point of the lift, the coils lie in the spaces between the previously wound spirals, so that the diameter is not increased by twice the diameter of the roving, as at first, but by one diameter only, and that is the extent of the increase afterwards throughout building. To some extent, this more compact winding is compensated for by the sponginess or elasticity of the mass on which the succeeding layers are wound, but it doubtless affects the problem to some

FIG. 158.

extent. It does not really matter in making the calculation, because it is known how many layers are wound on to a bobbin before it is filled, and that enables a simple calculation to be made as to the increase of diameter for each layer, and, as the belt makes a total lateral movement of so many inches, its traverse for each layer can be readily calculated. Perhaps of more importance is the tendency of the strap to assume an angular instead of a vertical position. It is well known that if a belt is stretched over two drums, one of which is conical, or has its axis placed angularly in relation to that of the other, it

will tend to run towards the larger diameter, or the point on the one drum further from the other. This is recognised in the common practice of rounding the faces of pulleys in order to keep the belt in a central position thereon. It is clear that if a belt is $3\frac{1}{2}$ inches wide and be assumed to drive when wrapped round complementary diameters on the two cones, the theoretical effect, at any rate, will be affected if it assumes another position on either cone from the reason named. In order to meet this difficulty, Messrs. Brooks and Doxey have added to the small end of each cone a short parallel piece equal in width to the strap. In this way the belt when starting and finishing a set is prevented from riding or assuming an angular position, and thus gives the correct speed to the bobbins at the beginning and end of a set. In addition to this, as each cone is moved endwise to a distance equal to the width of the belt, the belt will throughout grip the diameters on to which it tends to ride under ordinary circumstances, and will not assume an angular position. It is therefore possible to obtain an accurate adjustment. If the parallel ends are removed, the cones remaining represent the ordinary construction. Messrs. John Hetherington and Sons, Limited, minimise the tendency to ride by the employment of a divided belt, that is, two belts of half the width connected together, so that an adjustment to the contour of the cone is possible. One of the most fruitful sources of errors in regulation arises from the slip of the belt, and a few words may be expended on this. The function of the cone mechanism is, as has been clearly indicated, the regulation of the velocity of the "sun" or "stud" wheel, or its equivalent. This looks to be a simple thing and one which would not involve much stress on the strap. As a matter of fact there is thrown upon all the wheels of the train between the bottom cone and the bobbins a considerable stress. Students of mechanics know that wheels or pulleys are levers, and that the stress caused in lifting or moving the weight is thrown upon their fulcra. In this case the weight is represented by the resistance of the bobbins in rotating, or practically, their inertia. The

stress thus set up is transmitted from member to member of the train until it reaches a point where it is either entirely sustained or in some way removed.   Usually this point is represented by the point of contact of the belt and the lower cone, and if from any cause the adhesional friction of these is insufficient a certain amount of slip occurs.   This tendency is increased if there is any accumulation of dirt or grease on the belt.   Attempts have been made to overcome this difficulty by so sustaining the lower cone that its weight is always on the belt.   One or two firms have also increased the diameters of the cones, these being now made in some cases 10 inches and 5 inches diameter at their large and small ends respectively.   In another case a duplex system of cones is used, as Fig. 159, which is an illustration of Messrs. Ashworth and Moorhouse's patent, as made by Messrs. Platt Bros., and Co.   It will be seen there are two sets of cones used, each being duplicates, and the cone shafts are extended to receive two cones respectively.   The strap guides are in like manner attached to an extended traverse bar, but the belts are only 2 inches instead of $3\frac{1}{2}$ inches wide, and are only in moderate tension.   It is stated that the employment of this system has met with considerable success.   Referring now to Fig. 155, the motion therein shown meets this difficulty in another way.   It is substantially the same problem as the well-known Weston pulley block, which easily sustains heavy weights. In this case the stress is taken up within the motion and is not passed on to the same wheels between the cone and the arm C^1. The stress is taken by the jack shaft at the point where the wheel B is fastened to it.   It is found that if the bobbin driving shaft is rotated by suitable means its motion is transmitted through the intermediate wheels and " sun " wheel to the driven cone when the Holdsworth and other types of differential motions are used.   If this be tried with the motion shown in Fig. 156, it is found to be impossible to rotate the bobbins. Nor is there any motion of the arm C^1, which corresponds with the " sun " wheel.   The explanation of this phenomenon is found in the fact that the motion is transmitted through two

wheels of unequal size, so that the axis of the fixed wheel B becomes the fulcrum. The power is expended in the attempt to rotate the wheel B and shaft A, from which all the power flows, and cannot be communicated to the wheel D^1. The difference in action arises from the relative position of the parts, the wheel receiving the stress being a fixture, instead of, as usually, movable. By the removal of this factor the sole function of the cone strap is to rotate the regulating disc C^1 and the

FIG. 159.

pinions F F^1 in the same direction as the jack shaft A, which is a comparatively light duty. The importance of this factor lies in the ease with which a belt in moderate tension can be moved along the cones, a task which is very much more difficult when the tension is greater. Upon this rapid movement depends the immediate change of velocity of the driven cone when a new layer of roving is being begun. This is a most important factor in producing even rovings, and its value cannot be over-estimated.

(227) The strap F receives its longitudinal traverse along the cones by means of the forward movement of the toothed rack P, which is actuated by the rotation of the pinion P^1. The pitch of the teeth of the rack is $\frac{5}{16}$ inch, and the pinion has 45 teeth. One complete rotation of the latter, therefore, will move the rack $14\frac{1}{16}$ inch. It was shown in par. 221 that the extreme variation in the number of revolutions of the lower cone is 393, or, if the cone is 36 inches long, 10·9 for each inch of strap traverse. Thus, one revolution of the pinion P^1 will reduce the velocity of the lower cone 153 revolutions. The rotation of the pinion P^1 is obtained by means of the pull of a cord or chain passing round the pulley X^1 on the shaft X. The latter cannot, however, revolve freely, being held by the detent catches of the motion Q, of which a description will now be given. This motion is called sometimes the "box of tricks," but a much better name is the "building motion." It has a two-fold function. It regulates the movement of the belt along the cones, and it throws into gear alternately the wheels $S^1 S^2$ with the pinion S. By the first of these actions it regulates the velocity of the bobbin, and by the second the duration of its lift. It may be here explained that in the early period of the history of this machine it was customary to wind the roving on bobbins with flanges at each end. It was found, however, that the roving in being drawn off adhered to the flanges and was thus stretched and broken. It has therefore become the practice to shorten the lift of the bobbin after every layer is wound, and to wind the roving on to plain cylindrical wooden tubes without aids. Unless the lift was shortened the roving would be easily unravelled or fall off at the ends, but by the adoption of the system of shortening the traverse, the double conical bobbin is built, which can be handled with impunity.

(228) The illustrations in Figs. 160, 161, and 162 represent respectively a front and back view and plan of a building motion, which is in every respect like the one shown in Fig. 148, except that weights are substituted for the springs, and the rod R is differently coupled. Two cradles A and B are centred

on the pins A^1 and B^1. The upper cradle A has attached to it
at each side double hooks C C^1, which pass through holes in
the lower cradle, and have weights attached to them. In the
lower cradle B a pin E^1 is fixed, which engages with a slot in
the lever E, centred on the pin F, and jointed to the rod R,
coupled to the striking wheel. On the pin A^1 a ratchet or
"rack" wheel N is fixed, with which two catches G G^1 can
alternately engage. These catches are coupled by a spring, and

Fig. 160.

are of different shape, so as to engage with the teeth of the
rack wheel at each side of its centre. On the same pin as the
rack wheel the bevel pinion J is fastened, this gearing with a
similar one J^1 on the upright shaft X. Two detent levers L L^1
are pivoted to the frame, and have their inner ends connected
by a helical spring M, which passes round the centre B^1. The I
levers, from their action, are sometimes called "pigeons'
wings," and their inner extremities engage with shoulders I is
formed in the lower cradle B. The bobbin rail has attached to

it a double slide Q, which is slotted so that the pin O can move along it. On this pin one end of the "diminishing" rod S is centred, the rod passing through bearings formed in the cradle A. A toothed rack is formed on the underside of the rod S, with which a wheel T, fixed on the pin A^1, engages.

(229) The action of these parts is as follows : The slide Q rises and falls with the bobbin rail, and consequently communicates an oscillatory motion to the cradle A. It is properly

Fig. 161.

set when a line drawn through its centre passes through the centre of the pin A^1 when the bobbins are at the central point of their lift. The rod S can then be moved horizontally without producing any effect on the cradle A. The levers L L^1 are then engaged with the shoulders I I^1. If the bobbin rail now descends the cradle A is oscillated on its axis, and, as a consequence, the hook C^1 is raised while C is lowered. There is a shoulder or boss on the latter which prevents it falling too low, but causes the weight to come upon the arm of the cradle

B, and so exercise a pressure on the latter. As the oscillatory movement of the cradle A is continued the weight C^1 is entirely removed from B, and the point of contact of L^1 and I^1 becomes a fulcrum by which the motion of A is temporarily arrested. This is practically an anchor action, and when springs are used bears much more resemblance to it than in this case. The effect is that the point where the weight C^1 is ordinarily applied is quite free, while there is a proportionately heavier thrust on B. As A continues to oscillate the screw Z begins to press on the outer end of L^1, and finally causes it to oscillate so as to free it from contact with the shoulder I^1. The cradle B makes a sudden movement, which partakes both of a rotary and vertical character. The result is that the pin E^1 strikes the

FIG. 162.

slot in the lever E, and the latter turns upon the pin F. A blow is thus given to the detent catch G, releasing the rack wheel, which at once turns. As, however, G and G^1 are coupled by a spring, the lateral movement of one is accompanied by a similar movement of the other. Thus the rack wheel can only move half a tooth for each of the oscillations of the cradle in either direction. The partial rotary movement so made is communicated to the pinion P^1 by the gearing described. The oscillation of the lever E, or of the cradle in Fig. 148, communicates a longitudinal motion to the rod R, and causes it to throw the wheel S^2 into gear with S, thus reversing the motion of the lifter pinion. The rotation of the rack wheel is also accompanied by that of the pinion T engaging with the rack on the underside

of the bar S.   The latter is thus drawn inwards, and the relative
position of the pin O and the centre of the cradle A is altered,
with the result that at the next lift of the bobbins the escape-
ment motion is actuated a little earlier.   Thus the duration of
the lift is constantly shortened, and as a result each layer
occupies a little less vertical space than its predecessor.

Fig. 163.

(×30) The arrangement shown in Fig. 163 is an improvement
made by Messrs. Howard and Bullough, which has for its object
the removal of all the weight from the diminishing rod when the
oscillation of the cradle takes place.   It is not necessary to deal
with the motion generally, which resembles that just described.
To the slide B is attached a lever A, having at its lower end
two adjustable stop screws A^1 A^2.   Between these the free end

of the arm C passes.   C pivots on a stud in the centre of the
cradle bracket, and at D is curved as shown. The two extremities
of D are arranged so as to take into the two weight-hooks E E¹.
The effect is that, as the slide B ascends and descends, the lever
C D is rocked, and alternately lifts the weight-hooks E E¹, thus
freeing the catches F F¹ from the weights H H¹ respectively. In
this way all the weight is taken off one of the catches and all of
it removed from the hanger bar, thus permitting the latter to
make the change freely, the release of the catches being made
by means of a stop on the upper end of each of the weight-
hooks E E¹.

FIG. 164.

In lieu of the weights or springs applied directly to the cradle
Messrs. Asa Lees and Co. have adopted the device shown in Figs.
164 and 165. In this case the short sliding shaft upon which the
" striking " bevels S¹ S² are fastened is connected to the reversing
shaft F by the coupling F¹.   The shaft F is coupled at F² to the
cradle A, which receives its release in the same manner as
previously described.   On the shaft F are four stop hoops, one
pair G G¹ having between them a coiled spring L, and the other
pair H H¹ being without a similar spring L¹.   Attached to the
frame is a slotted bracket K (Fig. 165), in which one end
of a lever J, the lower end of which is forked, engages, the
forked end being fitted into the space between the hoops

G H.   As J is pivoted to the frame, and the bracket K is attached to the lifter rack, it is oscillated as the latter rises and falls.   In this way the springs L L¹ are alternately put into compression, thus acting on the cradle A precisely as the weights or springs do in the ordinary motion. The alternate release of the detent catches is preceded by the compression of its corresponding spring, and followed by its sudden extension, which changes the position of the striking

FIG. 165.

wheels.   The charging of the spring is done a little before the necessary change, so that much of the strain is taken off the reversing cradle, and all of it from the diminishing rod.   This modification has been extended by combining the motion with the knock-off motion.   In Fig. 166 the knocking-off lever D is shown, its upper end pressing against a stop on the setting-on rod U.   It is controlled by the weight D¹ when released,

which occurs at some predetermined point. The release is
effected by raising the latch P^1 attached to the knocking-off
lever, by means of a stop attached to the lifter, which acts

FIG. 166.

when the latch is brought into proper position when the
bobbin is full. A lever M (see also Fig. 167) is
hinged on the frame carrying the reversing bracket, and is
coupled to an arm on D by a pin. Thus the motion of D is

FIG. 167.

communicated to M. The horizontal arm of M has two stops
on it, M^1 M^2. When knocking off takes place, which, when this
motion is fitted, it always does on the downward traverse, the stop

M

M^1 engages with the engaged detent catch, and releases the reversing cradle. If permitted, the latter would oscillate sufficiently to reverse the gear of the striking wheels S^1 S^2, but by means or the second stop M^2 the cradle is prevented from moving a further distance than is sufficient to put the striking bevels entirely out of gear. They are therefore quite free, and in starting the next set of bobbins the bobbin rail can be wound down without difficulty, so as to commence rebuilding at the beginning of the lift, which is a desirable thing to do. Also coupled to the stop lever D is a link O which is connected to a bell crank lever R coupled to the rod V by means of which the bottom cone is lifted. The knocking off not only frees the striking wheels, but also lifts the cone so as to loosen the strap, thus allowing the whole of the parts to be wound back easily. When the frame is restarted the adjustment of the cone strap brings all the parts into position for commencing winding, taking the stop M^2 out of contact with the cradle and M^1 with the catch, thus allowing the striking wheels to again engage with the pinion, so that the movement of the setting-on handle re-starts the machine. The lever Q is so fixed that in winding back it is acted on by a stop bracket, so that its arm Q^1 operates the knocking-off lever and resets it. This combination has, therefore, the triple object of relieving the strain on the diminishing rod, freeing the strike wheels, and releasing the cone belt. It is entirely automatic, and is reset in the ordinary operation of restarting.

(231) Let it now be assumed that the strap is on the small end of E^1, the velocity of the shaft H will be 105, and of the wheel L 16·8. From this we deduce the speed of the bobbins as 909·27, or 91·27 in excess of that of the flyer. Now, if the bobbin be supposed to be 1⅛ diameter, it will, for every revolution, take up 3·53 inches of yarn. In other words, it will, during the 91·27 revolutions in excess, take up 322 inches of yarn. It was shown in paragraph 209 that the rollers delivered in a minute 261·5 inches; therefore the velocity of the feed cone is too great, and the strap must be moved towards the large end

of E^1 in commencing the set. The bobbin requires reducing to a velocity of 891·2 revolutions, or 75·2 revolutions in excess of that of the flyer. By means of the modes of calculating previously detailed, we find that the strap must be at a distance of nearly 6 inches from the smaller end of the cone E^1, when the velocity of the latter will be 406·25 revolutions, at which speed the bobbins will revolve 889·3 times, which is what is required. Suppose, at the end of a set, the bobbin is $2\frac{3}{4}$ diameter, at each revolution it will take up 8·5394 inches of yarn. Thus, to take up the 261·5 inches of yarn delivered by the rollers, it must revolve 30·62 in excess of the flyers, or 848·62. This means a reduction of the velocity of the cone E^1 to 167·2 revolutions, and the traverse of the strap nearly 26 inches. Although the strap is sometimes moved along the cones in beginning a set, in practice it is always endeavoured to arrange the gearing so that the belt can move along the entire length of the cones, and its traverse can be correspondingly arranged. The case which is here supposed would, therefore, not often arise, but it is sufficient to illustrate the general principle involved, the figures given being not actual but suppositious.

(232) We now come to deal with the method of obtaining this traverse. The rack P is $\frac{5}{16}$ pitch, and the pinion P^1 has the same pitch and 45 teeth. Therefore, as shown in paragraph 217, one rotation of the pinion P^1 moves the rack P inwards $14\frac{1}{16}$ inches, so that to obtain a total traverse of 26 inches the pinion P^1 must make 1·84 revolutions. Now the bevel wheels J and J^1 (Fig. 161), having each 25 teeth, it follows that every time the rack wheel N makes a complete revolution the shaft X and the pinion P^1 do so also. Thus as the rack wheel has 32 teeth and moves a half tooth every lift, a complete revolution means the winding of 64 layers on the bobbin. Thus to attain the full diameter of $2\frac{3}{4}$ inches 64 × 1·84 layers must be wound, or 118·06 in all. The successive series of coils are not laid over each other, but as the roving is wound, each alternate layer falls into the spaces between each of the pre-

viously laid coils, so that only half the diameter is added at each layer. As the difference between the diameters of the full and empty bobbin is $1\frac{5}{8}$ inches, the thickness of each layer is approximately $\dfrac{1\cdot625}{\frac{1}{2}\ (118\cdot06)} = \cdot0275.$

(233) On the shaft H is a bevel wheel R with 22 teeth, driving a wheel R^1 with 51 teeth. R^1 is on the same shaft as the striking wheel S, which has 16 teeth, and gears with the wheels S^1 S^2 with 51 teeth. On the same shaft as S^1 is the pinion T with 14 teeth, driving T^1 with 70. T^1 is on the same arbor as U, which has 16 teeth, and gears with U^1 with 80 teeth. U^1 is fixed on the lifter shaft, on which at intervals are pinions V^1 gearing with the rack V. The pitch of the teeth on the rack V and pinion V^1 is $\frac{3}{8}$ inch, and V^1 has 16 teeth. Now on the assumption that the cone E^1 is making $406\cdot25$ revolutions, and the shaft H $81\cdot25$ revolutions per minute, then the pinion V^1 will make $\dfrac{22 \times 16 \times 14 \times 16}{51 \times 51 \times 70 \times 80} \times 81\cdot25 = \cdot44$ revolutions in the same time. At this velocity the bobbin rail will be raised $2\cdot64$ inches per minute, and to complete the full lift of 7 inches the pinion V^1 will require to make $1\frac{1}{6}$ revolution, and will take $2\cdot65$ minutes to do so. In that time the rollers will deliver 693 inches of roving, which is the length of the first layer. By making a similar calculation for each layer it is possible to complete its length.

(234) On the same spindle as the rack wheel is a pinion 'I', which has 20 teeth $\frac{3}{16}$ inch pitch, and gears into the rack on the underside of the diminishing rod, which is, of course, the same pitch. Thus one revolution of the rack wheel moves the diminishing rod S inwards $3\frac{3}{4}$ inches, and during the period of the full movement of the rack P the diminishing rod will be moved in $5\cdot85$ inches. Thus the pin O will be moved towards the cradle A (Fig. 161), and if the lift of the bobbins remained constant, the velocity of the oscillation of A would be increased; but this increased velocity leads to the release of the detent catches G G^1 respectively at an earlier moment, so that the

reversal of the lift is made a little earlier every time it is completed. Thus the striking wheels S^1 S^2 are thrown into gear at an earlier period respectively, and the lifter pinion has its direction reversed at a proportionately early moment. The extent of the traverse is therefore shortened after each layer is wound, and the bobbin is thus formed into the double conical shape to which reference has been made. There is no definite ratio between the length of the lift and that of each layer, and the only object of the decrease in the lift is that of forming a bobbin which can be easily handled, and which will not ravel off at the ends. A few words may be expended on the action of the diminishing rod or hanger bar. As the slide Q is fixed to the lifter rail it follows that it will rise and fall with it. It was shown that when the bobbin is at the middle of its lift the hanger

FIG. 168.

bar S should be horizontal—that is, the centre of the pin O should be exactly midway of its vertical movement. At the beginning of building, as shown in the diagram in Fig. 168, the diminishing rod pin O is at its greatest distance from the centre T, on which it is virtually pivoted. It, therefore, moves a distance equal to the left of the bobbin from the position O to O^1, and in doing so the pin O passes through the arc shown being free to move in the slide. As soon as it reaches that point the cradle A is in the correct angular position relatively to B to release the detent catch, the screws in the cradle A being correctly set for that purpose. As was shown, the release of the detent catch effects three objects: 1st, the movement of the cone strap; 2nd, the simultaneous inward motion of the diminishing rod

itself; and 3rd, the sliding of the striking wheels, so as to reverse the motion of the lifter shaft. It follows from what has been said that whenever the centre of the pin O coincides with the axial lines OT, O¹T, whatever the relative position of O and T may be, the correct angular position of the cradle A is assumed, and the change will take place. Thus, if the pin O is in any of the positions O¹, O², O³ or O⁴, the reversal will take place, and as the diagram shows, these positions correspond with different points in the total length of the bobbin. It is thus clear that by an acceleration of the rotation of the pinion on the axis T the shortening of the lift takes place more rapidly, while by retarding it the change occurs more slowly. By a regulation of this movement it is possible to give more or less taper to the ends of the bobbin. A reference to Fig. 148 shows that the wheel S being driven from the shaft H is necessarily subject to the changes which take place in the velocity of H from the movement of the strap along the cone drums. This, in the case supposed, varies from 105 to 26·25 revolutions. The velocity of the pinion V¹ engaging with the lifting rack would, therefore, be in each case respectively ·56 and ·142 revolutions per minute. Thus the extreme speed of the lift of the rail is 3·16 inches per minute, and its lowest velocity ·852 inch. It will, therefore, be seen that as the cone strap moves along the cone, not only is the bobbin velocity increased or diminished, but the speed of the lifting rail also, but the latter is in inverse ratio to the diameter of the bottom. The coils of roving are wound, therefore, in spirals, the pitch of which is substantially uniform as the bobbin increases in diameter and shortens in lift. In other words, these factors are reciprocals of each other. An increased diameter implies a decreased velocity and slower lift in exact proportion, and a decreased diameter the reverse. The taper of the bobbins can be regulated within certain limits by setting the screws Y Z in the cradle A (Fig. 161), so that the levers L L¹ are tripped at an earlier moment. If the required change cannot be got by this, it may be necessary to alter the wheel T, by which means the traverse

of the rod S can be made at a quicker rate. The coils of roving should be properly laid, neither too far away nor too near, because it must be remembered that the gradual shortening of the lift varies the pitch of the coils. What is wanted is that the largest possible number of coils shall be laid, so as to get the greatest length of roving on each bobin which is possible. In this connection Table IV. may be referred to. If the bobbin rail traverses either too fast or too slow, the coils will be badly laid, and the surface of the bobbin will be rough and uneven instead of fairly smooth. To remedy this defect the builder wheel S (Fig. 148) should be altered so as to give the necessary acceleration or retardation to the lifter shaft.

(235) The detailed examination into the roving frame just made is intended to enable the principles upon which it works to be understood, and a reference can now be made to one or two practical matters of detail which will be of service to the student. As after the slubbing has been formed it partakes more or less of the nature of a thread, it is found that its passage through the rollers leads to the formation of grooves or hollows in the leather covering of the top roller. This is obviated by the use of a traverse motion by which the thread is guided from end to end of the roller boss in each direction alternately. In this movement there are one or two points of interest, especially when double or treble bossed rollers are employed. If the rovings make their sideward movement simultaneously there is a period when one of them is well within the range of action of the weights, while the other is so near the centre of the roller as to be less acted upon. The problem is purely one of leverage, and if it be calculated out by the ordinary rule of mechanics it will be found that the pressure on one of the slivers is greater than that on the other by a ratio of 2 : 1. It has been made abundantly clear that the drawing power of rollers depends largely upon the pressure which is induced by weighting, and if the effect of the latter is at any period so unequal it is certain to have an effect upon the roving being produced. Unless the draft exercised upon the sliver or

slubbing is constant the tendency towards thick and thin places
in the resultant roving is much increased, and anything which
detracts from the uniformity of the action of the rollers is
necessarily hurtful.   Towards the production of this uniform
action many things contribute, among which the two elements
of effective lubrication and equal pressure upon the slivers are
perhaps the most important.   The ordinary traverse motion
does not fulfil the latter condition for the reasons stated.   There
are several traverse motions designed with a view of minimising
the wear of the rollers by giving a differential traverse, but they
retain the principle of moving all the threads in the same direc-
tion simultaneously.   Whatever objections therefore exist in the
case of the ordinary type of rollers, have equal force in the case
of the differential traverse motion so far as the variation in
weight is concerned.   By adopting a double traverse rail with
guides on each, so that the guide for one boss is on one rail and
that for the other on the second rail, the difficulty can be over-
come by moving the rails in opposite directions at the same time.
Such an arrangement has been patented by Mr. William
Tatham, of Rochdale, and is made by Messrs. Platt Bros.
In Figs. 169 and 170 the old and new form of traverse guide is
shown.   In the first case the guides are fixed on one rail,
which is given an alternate traverse in each direction for a
distance nearly equal to the length of the boss of the roller.
It will be seen that one of the slivers will be at the nearest point
to the centre of the roller, which it reaches while the other is at
the extreme end.   As the weight is applied to the roller at its
centre, it follows that under these conditions the sliver nearest
to the weight will receive a pressure much in excess of that upon
the other sliver.   The exact amount of this excess is easily
determinable, and it only requires a measurement to be made
from the point of the application of the weight to the
nearest position of the sliver.   Adopting this as the unit,
when the pressure is greatest, the relative pressure on the
sliver can be easily ascertained.   When the guides are
in the position shown in Fig. 169, the pressure upon A

is only half that upon B, and a load of 24lbs. applied to the
centre of the roller would give a weight of 8lbs. on A and 16lbs.
on B. In other words, the effective drawing force exerted on A
is half that on B, and it is quite obvious that evenness of
drawing would not be secured, it being necessary to overload B
to get 8lbs. pressure on A.   In the new construction shown in
Fig. 170 the two guides used in connection with each roller are
respectively attached to separate traverse bars A^1, B^1.   These

Fig. 169.

Fig. 170.

move in opposite directions simultaneously, so that the slivers A
and B move towards, and recede from, the centre of the roller
during the same periods.   The effect is that they are always
evenly weighted throughout their movement, and that the
variation arising from uneven drawing cannot occur.   Further, a
load of 16lbs. applied at the centre of the roller would always
give 8lbs. on each sliver, and so ensure even drawing, so far
as equal weighting can do.

(236) The explanation so given is intended not so much to give an absolute instance of the operation of a machine of this character as to illustrate the principle upon which it works, and to define the connection between the whole of the parts. It has been shown that the spindles, rollers, bobbins, and cones alike derive the whole of their motion from the jack shaft, and that of these the only parts which constantly maintain the same relation during the twisting of a set of bobbins are the spindles and rollers. They rotate at a definite and regular rate, so that it is possible to easily calculate their effect. When it is desired to change the hank of the roving it is necessary that the velocity of the rollers shall be increased or diminished. If the wheel B be changed for one larger or smaller, the rollers will revolve at a slower or quicker rate accordingly, and the twist can thus be altered. The alteration of the twist wheel B not only affects the rollers but also the velocity of the bobbins and the speed of the lift, for it will have been seen that the whole of these motions are driven from B. Thus if a larger wheel is substituted at B, giving a quicker velocity to the rollers, the roving delivered will have less twist, and will be coarser. Any one who has carefully read the foregoing explanation must see that a coarser roving will increase the diameter of the bobbin at a quicker rate, and thus necessitate a more rapid diminution of its velocity. Accordingly the change in the wheel B causes the cones to run at a quicker speed, thus accelerating the lifter shaft, and consequently causing the change of the building motion to take place at an earlier moment. This in itself would bring about a quicker longitudinal traverse of the strap, but when the roving is made coarser it is the custom to change the rack wheel for one of fewer teeth, in order that the traverse of the rack P shall be made more rapidly. When the change is to a finer roving a larger rack wheel is used. The strike pinion S can also be changed if desired, as can also L^1, and where there is an increase of any great extent this is probably the best course. Ordinarily, however, the changes necessary can be effected by the substitution of the wheel B, the rack wheel, and the change

pinion in the roller train, by others of the required size. It is of course, necessary to alter the draft to suit the roving made. The changes which can be made are, therefore—

First. Twist wheel B when altering twist. This affects the speed of the bobbins and of the lifting shaft. A larger wheel gives less and a smaller one more twist.

Second. The "ratchet," or "rack" wheel N, which regulates the movement of the strap guide rack P. A smaller wheel increases the speed of P, a larger one decreases it.

Third. The "draft" wheel, which, as in the drawing frame, alters the hank of the roving delivered.

Fourth. The "sun wheel," or jack pinion L^1, which can be changed when absolutely necessary to secure correct winding.

Fifth. The bottom cone pinion G^1, only to be changed when winding is too slack.

Sixth. The "diminishing," "tapering," or "coning" pinion T when desired to alter the taper of the ends of the bobbins. The screws Y and Z can be set so as to give an equal taper at each end of the bobbin.

(237) The following are the rules for calculating the speeds and effects of the various parts. The rules are those which are in ordinary use, but to make them clear references are inserted to the letters in Fig. 148 :—

1. To find the velocity of the spindles—

Speed of jack shaft A × spur wheel O × pinion W ÷ by spur wheel O^1 × bevel pinion W^1.

2. To find the velocity of front roller—

Speed of jack shaft A × spur wheel B × spur wheel C^1 ÷ spur wheel B^1 × spur wheel D.

3. To find the length of roving delivered by the front roller per minute—

Speed of front roller × circumference of front roller.

4. To find the twist per inch—

Revolutions of spindles ÷ length delivered per minute.

5. To find the draft of rollers—

Multiply all the driven wheels together and the product by the diameter of front roller in eighths of an inch, and divide the number obtained by the product of all the driving wheels multiplied together, multiplied by the diameter of the back roller in eighths of an inch.

6. To ascertain the correct change pinion to obtain a given draft—

Draft × wheel **D** × diameter (in eighths) of back **roller** ÷ crown wheel × back roller wheel × diameter of front roller.

7. To calculate turns per inch by the wheels—

Wheel **D** × wheel B^1 × wheel **O** on jack shaft × wheel **W** ÷ circumference of front roller × wheel C^1 × twist wheel **B** × wheel O^1 × pinion W^1 on spindle.

8. To calculate number of teeth in the twist wheel to be substituted when changing from one counts hank to another—

Twist wheel squared × hank roving spun ÷ hank required. The square root of quotient so obtained gives number of teeth required in twist wheel.

A second method of obtaining the same result is—

Hank made × present twist wheel ÷ hank required. The quotient of this + twist wheel ÷ 2 equals twist wheel required.

9. To calculate the number of teeth in rack wheel when changing hank being made—

Hank required × present rack wheel ÷ hank being made. The quotient thus obtained + rack wheel ÷ 2 gives rack wheel required.

Another method is to square present rack wheel and multiply it by hank required, then divide this product by hank made. The square root of the quotient thus obtained gives the number of teeth required.

10. To ascertain what hank a roving is—

Constant dividend (see Table II.) ÷ weight of any number of yards.

Another form of this rule is—

Constant dividend ÷ given hank = weight of any length in grains.

In working out rules 6 and 7 a constant number can be used. This is obtained in the same way as detailed in the rules named, but leaving out the draft in rule 6 and the twist pinion B in rule 7. If the constant number be divided by draft required as in 6, or the turns per inch as in 7, the correct pinion in each case can be calculated. The ordinary method of finding the necessary turns per inch for slubbing and roving is as follows :—Slubbing $\sqrt{\text{hank}}$ = turns per inch ; intermediate $\sqrt{\text{hank}} \times 1\cdot1$ = turns per inch, and roving $\sqrt{\text{hank}} \times 1\cdot2$ = turns per inch. These are the usual twists, but different cottons require special treatment. In this connection refer to Tables III., IV.

TABLE I.

Measurement of cotton yarn (English) :—

1 thread on a wrap reel =	1½ yards.
80 threads	= 1 lea = 120 yards.
560 threads	= 7 leas = 840 yards = 1 HANK.

Weights used for cotton yarn (English) :—

24 grains =	1dwt.
437½ grains =	18·225dwts. = 1oz.
7,000 grains =	291·6dwts. = 16oz. = 1lb.

NOTE.—The counts of yarn are calculated by ascertaining the number of hanks in one pound weight. If one hank weighs one pound, the yarn is No. 1 count; or, if one lea of 120 yards weighs $\frac{1}{7}$th the weight of a pound (1,000 grains), it is No. 1 count. By ascertaining the accurate weight of a lea the counts can be easily calculated. The rule is, number of grains in $\frac{1}{7}$th of a pound ÷ weight in grains of one lea = counts. Thus, if one lea weighed 40 grains, the counts are $\frac{1000}{40} = 25$.

TABLE II.—Dividends.

The numbers in this table are arrived at by the following rule: Take 12 for a divisor, and divide as many hundreds as yards are weighed. This is based upon the fact that 10 yards are $\frac{1}{12}$th of a lea, and that 100 is a multiple of 10.

120 yards	=	1	lea	=	1,000	grains	dividend.
60 ,,	=	$\frac{1}{2}$	,,	=	500	,,	,,
40 ,,	=	$\frac{1}{3}$	,,	=	333·3	,,	,,
30 ,,	=	$\frac{1}{4}$	,,	=	250	,,	,,
20 ,,	=	$\frac{1}{6}$	,,	=	166·6	,,	,,
15 ,,	=	$\frac{1}{8}$	,,	=	125	,,	,,
10 ,,	=	$\frac{1}{12}$	,,	=	83·3	,,	,,
8 ,,	=	$\frac{1}{15}$	,,	=	66 6	,,	,,
6 ,,	=	$\frac{1}{20}$	,,	=	50	,,	,,
5 ,,	=	$\frac{1}{24}$	,,	=	41·66	,,	,,
4 ,,	=	$\frac{1}{30}$	,,	=	33·3	,,	,,
3 ,,	=	$\frac{1}{40}$	,,	=	25	,,	,,
2 ,,	=	$\frac{1}{60}$	,,	=	16·6	,,	,,
1 ,,	=	$\frac{1}{120}$	,,	=	8·3	,,	,,

In using this table to find the counts the rule is to divide the dividends given above by the weight in grains of the respective number of yards taken. Thus, 20 yards weighing 80 grains is $\frac{166\cdot6}{80} = 2\cdot08$ counts. In arriving at the hank of the roving it is customary to use a small machine known as a "wrap block." This consists of a light drum exactly one yard in circumference which can be turned by hand, and on the spindle of which is fixed at one end a handle and on the other a worm. The worm gears with a wheel having 60 teeth, so that a complete revolution of the wheels implies that 60 yards have passed. Four pegs, however, are fixed in the wheel at equal distances, so that every 15 revolutions of the wheel causes a bell to sound, thus indicating that 15 yards have passed. The roving is kept in contact with the drum by a small roller which rests on it, and it is guided to and from the drum by suitable guides. When the 15 yards have passed it is detached from the roving and weighed. thus enabling its hank to be readily ascertained.

TABLE III.

No. of Hank Roving.	Grains per Yard.	Twists per Inch.		
		Slubbing.	Intermediate.	Roving.
˙10	83˙33	˙316	˙347	˙379
˙15	55˙56	˙387	˙425	˙461
˙20	41˙66	˙44	˙484	˙528
˙30	27˙77	˙548	˙602	˙657
˙40	20˙83	˙63	˙693	˙756
˙50	16˙66	˙707	˙777	˙848
˙60	13˙88	˙778	˙855	˙933
˙70	11˙90	˙89	˙979	1˙068
˙80	10˙41	˙94	1˙034	1˙128
˙90	9˙25	˙99	1˙089	1˙188
1˙00	8˙33	˙1˙0	1˙1	1˙2
1˙25	6˙66	1˙118	1˙22	1˙341
1˙5	5˙55	1˙224	1˙347	1˙469
1˙75	4˙7	1˙328	1˙455	1˙587
2˙0	4˙16	1˙414	1˙555	1˙697
2˙25	3˙7	1˙5	1˙65	1˙8
2˙5	3˙33	1˙581	1˙739	1˙897
2˙75	3˙03	1˙658	1˙823	1˙989
3˙0	2˙77	1˙732	1˙9	2˙078
3˙25	2˙56	1˙8	1˙982	2˙163
3˙5	2˙38	1˙87	2˙057	2˙244
3˙75	2˙22	1˙936	2˙13	2˙323
4˙0	2˙08	2˙0	2˙2	2˙4
4˙25	1˙96	2˙061	2˙267	2˙473
4˙5	1˙85	2˙121	2˙333	2˙545
4˙75	1˙75	2˙179	2˙397	2˙615
5˙0	1˙66	2˙236	2˙459	2˙683
5˙5	1˙51	2˙345	2˙579	2˙814
6˙0	1˙38	2˙449	2˙693	2˙939˙
6˙5	1˙28	2˙549	2˙803	3˙059
7˙0	1˙19	2˙645	2˙909	3˙174
7˙5	1˙111	2˙738	3˙011	3˙286
8˙0	1˙041	2˙828	3˙11	3˙394
8˙5	˙980	2˙915	3˙2	3˙498
9˙0	˙925	3˙0	3˙3	3˙6

TABLE IV.

Hank Roving.	Square Root.	Coils per Inch.	Hank Roving.	Square. Root.	Coils per Inch.
½	·707	6·57	4	2·000	18 6
¾	·866	8 05	4¼	2·061	19·165
1	1·000	9·3	4½	2·121	19·723
1¼	1·118	10·397	4¾	2·179	20·268
1½	1·224	11·389	5	2·236	20·793
1¾	1·322	12·302	5½	2·345	21 81
2	1·414	13·152	6	2·449	22·78
2¼	1·5	13·95	6½	2·549	23·710
2½	1·581	14·704	7	2 645	24·605
2¾	1·658	15·422	7½	2·738	25·468
3	1·732	16·107	8	2·828	26·304
3¼	1·802	16·765	8½	2·954	27·113
3½	1·87	17·391	9	3·000	27·9
3¾	1·936	18·203			

(238) There are a large number of small points of more or less importance in working a frame of this sort. The strap should be carefully looked to, and kept sufficiently tight on the cones to avoid slippage. If the strap slips there will be either slack or uneven winding, both being evils to be avoided. So many of the motions of the machine depend for their success upon the proper driving of the bottom cone, and the maintenance of a uniform velocity of it and the parts connected by it, that it is of the utmost importance that the strap is kept in absolutely perfect working condition. Vigilance should be observed to see that the minder does not move the strap along the cone by hand, as otherwise the variation in the roving so produced will be detrimental to the yarn spun. The object of all the carefully designed and constructed mechanism which has been described is to render the action of the machine automatic, and any interference with its operation is therefore

to be carefully guarded against. The cones and strap should be kept clear from dirt and grease, the risk of slippage being thus increased. There are, of course, several points in the earlier processes which have an influence in the regularity of the roving, but these have been referred to in their own place. The bobbins in the creels should be free from contact with each other, and all undue friction which would in any way retard their free rotation must be avoided. It is not advisable to keep the rovings in the creels too long, as they are more or less affected by atmospheric changes. In making the necessary wheel changes, practice will enable allowance to be made for several small matters which cannot be strictly defined, but which all have an influence upon the successful operation of the machine. All these points are comprehensively summed up in the word slippage, the allowance for which covers most of the loss in transmission, which is inevitable. It is perhaps necessary to say in conclusion that, in making any changes, care should be taken to see that they are accurately carried out, as otherwise there will be some defect in the roving which will be difficult to trace to its source. It often happens that a defect in the finished yarn has its origin in one of the earliest processes, and the obscurity of the cause leads to a considerable amount of trouble before it is finally traced. In a machine which depends so largely as the roving machine upon the accurate adjustment of its mechanism, no care can be considered too great to attain this result. It is true that the setting points ordinarily used are few in number and the changes easily calculated, but a slight error in these may be of great consequence subsequently. The establishment of a correct surface velocity for the bobbin has been shown to be of great importance, and unless this is preserved uniformly even roving is impossible. It is sometimes found that there is a draft between the top of the spindle and the front roller. Whenever this condition exists the roving is in constant danger of being stretched or "ratched," with the result that thin places are found in it when wound, which in turn produce inequalities in the yarn. Care should

be taken and vigilance continually observed with reference to this matter, as otherwise good work is impossible. The condition of the wheel trains driving the bobbins and spindles should be carefully looked to, as otherwise back lash may exist, which results in an earlier start of the flyers relatively to the bobbins. This arises from the greater number of wheels in the train which drives the latter, back lash or wear being more pronounced in consequence. If the acceleration of the revolution of the flyer is excessive the roving will be stretched at first, with the usual consequences. It is often the practice to double the slubbing and intermediate in feeding it to the next machine. The justification for this is, of course, that the resultant roving is rendered more even than it would otherwise be. If this practice is pursued it is essential to see that the tension on both threads is equal, as otherwise there will be a tendency for one to be wound round the other in the action of twisting. Another point which it is desirable to mention is, that although twist is introduced into the slubbing or roving, it is not preserved in its passage through the drawing rollers of the succeeding machines, but is, in each case, when the roving leaves the bite of the front roller, practically removed. It is, therefore, quite accurate to calculate the twists in each case as if an untwisted strand were being dealt with.

CHAPTER VIII.

THE THEORY OF SPINNING.

(239) WE have now reached the terminal stage in the formation of yarn, viz., that in which the sufficiently attenuated strand of cotton receives its twist. The method of carrying this process into effect is uniformly the same, although the mechanism employed is different. It is not, however, the operation of twisting itself which gives rise to the variation in the character of the mechanism, but the necessity for winding the twisted strand or yarn into a cop, spool, or on to a bobbin, as the case may be. Twisting is effected by giving the roving a rotary movement on its axis at a velocity which bears a definite relation to the length delivered by the feed rollers. This remark is, however, subject to one important qualification. If an untwisted strand was wound on a cylindrical surface in successive coils, and was drawn off the cylinder by pulling it steadily in the direction of the axis, it would, every time a coil came off, receive one twist. This is practically the reverse of the action taking place in the coiler. There the laying of the sliver in the open coils while one end is free results in the introduction of a twist, but when the coils are subsequently drawn from the can this action is reversed and the twist removed. The effect, however, is a real one, and explains why, without the employment of any eye or its equivalent, twist can be put into yarn.

All twisting machines consist essentially of means whereby the delivery of the material to be twisted is accomplished at a definite rate, while it is turned or twined by the rotation of a spindle or other similar part. The further attenuation of the roving or strand, and its formation into a spool or cop, are additions which are rendered necessary by manipulative considerations, and are accessory to the principal object of this process. In proceeding to deal with spinning, therefore, we shall in the first place endeavour to discover what the principles are upon which it proceeds, before describing the various means and methods adopted to effect it.

(240) The cotton thread, like all those which are produced by modern methods, consists of a series of fibres laid successively, and which can be twisted round the axis of the thread or round one another, but are not possessed of any felting or milling properties. That is, the fibres being pliable and having been reduced approximately to the same length and laid serially, as described, can only be incorporated into a thread by the action of twisting, and not by any other pressure, which interlocks fibres of different construction. From this factor it follows that it is necessary to provide throughout the whole length of a cotton thread successively fibres so arranged as to be present in equal numbers at every point. To illustrate this let a reference be made to the three diagrams given in Fig. 171, marked respectively A, B, and C. In A the fibres are assumed to be laid in successive lengths, the ends of which adjoin each other without overlapping. The effect is that, assuming the fibres shown to be multiplied, when they are twisted they would form a number of short strands or cords entirely unconnected one with another. In the second diagram B the successive layers are overlapped, and no break is therefore left in their continuity, but the overlap is slight and there will exist only a partial coherence between the successive sets of fibres. Further, the thread will be affected so far as its diameter is concerned, which is a matter of some importance, to which reference will be hereafter made. Now let it be assumed that the fibres are laid

as shown at C, where each alternate set overlaps its predecessor
and successor to the same extent.   It is clear that when a strand
so formed is compressed and twisted the chance of any rupture
of the yarn is largely avoided, and that a much stronger yarn will
result.   Roughly speaking, the three diagrams given accurately
illustrate what it is desirable to aim at and avoid in preparing
cotton for spinning.   If it be assumed that at any point in C
there is the same number of fibres, which were each of the same
diameter, it is clear that a yarn twisted up from a sliver so
constructed would be practically even.   Of course this is a large
assumption, but it is the true statement of the conditions
necessary to obtain the perfect thread.   At any rate it enables
the nature of the problem to be understood.

(241) This method of laying the fibres is what is aimed at
by combing.   There an arbitrary selection of fibres of a certain
length is made, and they are so laid in the resultant sliver and
are joined to one another in such a way that practically the
order shown at C in Fig. 171 is established.   It is clear that in
the succeeding drawing processes the effect upon each set of
fibres will be practically uniform, and that there will be—if the
drawing is properly conducted—no creation of places of variable
thickness in the twisted yarn.   It is far otherwise with a sliver
constructed as shown at B.   There the fibres do not fall within
the influence of the drawing rollers in the same regular manner
as do those shown at C.   There are periods when the fibres are
being strongly drawn, and other periods when they are only
partially subjected to the draft.   As was pointed out in
Chapter VI., the fibres in drawing are slid over one another
by the action of the rollers.   If, therefore, the overlap is slight,
or all the fibres are not equally drawn, weak—that is, thin—
places develop in the yarn with all the ill effects consequent
thereon.   It does not follow that, even when established, the
proper order is maintained throughout the various stages, but
if anything approaching an even draft exists there is not so
great a chance of any irregularity occurring.   It is, however,
obvious that if the fibres are so laid that their adhesion is con-

siderably weakened, they can be more easily drawn into the position represented in diagram A in Fig. 171. Thus, if the sliver is constructed like B, it is much more liable to the danger thus indicated than when it is laid as at C, and this is a factor of the highest importance. The construction of such a sliver in any case where a selection of the fibres does not occur is very difficult, and it is doubtful when carded slivers are used whether it is ever attained.

(242) There are, therefore, a number of considerations of more or less value which it is necessary to remember in selecting a cotton for spinning, and a few remarks may be made on some of the features of the earlier stages. It is necessary to go over some of the ground already covered, and to amplify somewhat a few of the points made. It was shown in Chapter IV. that the fibres when delivered from the carding engine were laid in a tangled or crossed condition, and in Chapter VI. that the draft exercised upon them in the drawing frame gradually laid them in parallel order. It does not need pointing out that the fibres which possess the greatest length are brought earlier within the range of influence of the drawing rollers, and remain longer under it. Thus they are subjected to a greater draft, and are consequently laid longitudinally in the yarn earlier than the fibres which are shorter. In consequence, the latter tend to move towards the outside of the sliver, and are thus placed in a position in which they can be twisted round the core of longer fibres as soon as the first twist is introduced. But owing to their imperfect development and consequent shorter length, they do not fully twist in, and the result is a hairy or oozy appearance on the surface of the yarn. The extent to which this exists varies with the cotton employed, but it is present in all yarns to a greater or less degree. This is one of the points requiring attention in making up a mixing. In all the preparatory processes it is necessary to proceed upon the assumption that a definite length of fibre is being treated. That is, of course, an arbitrary assumption, but it is necessary, as otherwise there cannot be any successful commercial work. The result is that

to a large extent the fibres are broken, until in the yarn, as finally produced, there is much more uniformity in length than existed in the cotton to begin with. It may, however, be fairly laid down as a dictum—subject, of course, to all the limitations necessarily attaching to the knowledge existing—that in an ordinary yarn not specially prepared by combing, the sequence of the successive series of fibres is more or less like diagram B, and only partially approximates to diagram C. This is one of the reasons for uneven yarn, because each of the spaces between the termination of the fibres in B is a source of weakness and unevenness. It is, of course, quite impossible to say with any certainty what the disposition of the fibres will be, because the different lengths will cause them to lie relatively to each other

FIG. 171.

in anything but the orderly manner shown in Fig. 171. At the same time, a consideration of the manipulative machinery employed will show that so far as a designed arrangement is obtained, the best is that illustrated at C. No better disposition is possible with the machinery at disposal.

(243) As has been said more than once, the object of the spinner is to produce the nearest approach to a perfectly cylindrical thread of equal diameter throughout its length, and containing at any point the same number of fibres in its cross section as at any other point. This is a task of enormous difficulty, and is one which it is doubtful will ever be solved. There are so many considerations which influence the result that even the most unceasing vigilance will scarcely suffice to

accomplish it. It has been shown that the utmost efforts are made to obtain an evenly weighted sliver from the earliest stage, but it is obvious that these efforts can only at best be partially successful. Even when cotton is combed and a selection is made of the fibres, it is only a choice of length and not one of diameter. Now it is known that the fibres even of the best variety of cotton differ considerably in diameter, so that it is only necessary for a clump or group of the larger or smaller diameters to be formed to make a sensible variation in the diameter of the resultant yarn. Thus, assume that in the varieties of cotton used the fibres vary in diameter from $\frac{1}{1320}$ inch to $\frac{1}{1260}$ inch. Suppose that at two points a foot apart in a strand containing 40 fibres in its cross section throughout its entire length the fibres were all of the largest and smallest diameters respectively named. In that case the strand would have a thickness at one point of $\frac{1}{33}$ inch, and at the other of $\frac{2}{63}$ inch, a difference of $\frac{1}{693}$ inch. The result would be that when twisted up, instead of being cylindrical, the yarn would be uneven in diameter. Of course, this is only an example, but it serves to illustrate the principle. Further, although the measurement of the thread when twisted will be diminished from its untwisted size, the relative variation is likely to be greater owing to the increased difficulty in twisting the thicker fibres. If a number of fibres, say like rhea or ramie, each possessing the same diameter, were laid alongside one another and twisted, it would be possible to produce a cylindrical thread equal to the length of the fibres, which is considerable, although the spinning properties of ramie are not good ; but when it is necessary to deal with a material which exists in short lengths only, and which must be practically treated in mass and not in detail, the difficulties are largely increased.

(244) It has been shown how greatly the diameters of fibres of the same growth vary. Now, even where the disposition, shown at C in Fig. 171, exists, it does not follow that the yarn will be of the same thickness, because it may happen that a lot of fibres of the larger diameter may fall together, and *vice versâ*.

Thus, in spite of the compression existing in the calender and drawing rollers, nothing but a change of disposition of the fibres would remedy this fault.   This is only a minor point, but the measurements made by careful observers show that even with fine cottons it exists.   The selection of the cotton, so far as the length of the fibres is concerned is, it has been shown, successfully accomplished, but it is a much more difficult task to select them relatively to diameter, even if it were desirable.   If some procedure could be adopted by which the fibres could be mixed, so that an equal proportion of those of large and small diameters could be given in each part of the sliver, the problem would be solved, but this is wellnigh impossible, and the only solution of it appears to be the provision of a staple naturally even in length and diameter, and its treatment so as to lay it in the sliver in the manner indicated.

(245) Another matter, which depends very largely upon the evenness of the diameter of the thread, is the strength of the yarn.   All things being equal, the strongest thread has the greatest number of fibres in its cross section.   Strength is, of course, a relative term.   The strength of 100's yarn spun from Sea Island cotton is less than that of 30's spun from Orleans, but relatively to its diameter it is greater.   Therefore, in speaking of the strength of yarn, it must be clearly understood that this refers to that quality in true relation to others.   It follows, therefore, that the strength of a single thread of yarn will vary with the number of fibres in its cross section, and if these vary considerably there will be corresponding differences in the strength of the yarn.   This is easily ascertainable if single threads are tested ; but as it is the custom to test 80 threads at one time, it is the average strength which is ascertained, and which influences the record.   The point which it is desired to make is that the existence of uneven places in the yarn detracts from its strength, and on this account they should be avoided.   There is an element of strength in the fibres which is sometimes lost sight of, and that is the resistance to rupture which is caused by the friction of contiguous fibres upon

each other. This has been admirably treated by Dr. F. H. Bowman in "The Structure of the Cotton Fibre," and is a similar action to that which was remarked on in connection with drawing in Chapter VI.

(246) There arises from the various circumstances which have thus been detailed an unevenness in the yarn which has an influence upon the operation of twisting. It is obvious that if three hundred fibres are to be twisted in any strand of yarn they will be turned with more difficulty than 200 fibres of the same diameter. It is probably true that the extreme variation in the number of fibres in the cross sections of any yarn does not reach so high a percentage as the assumed case just given, but a much less percentage is ample to produce the same effect. Thus it is found that the tendency of twist is to run into the thin places existing first, and afterwards to affect the thicker parts of the strand. The observations of the author— which have not, however, been sufficiently extensive to warrant a dogmatic statement—tend to prove that the presence of thick places in the yarn is coincident with the existence of thicker fibres, but this is a point which is by no means settled. That even in the best yarns, made in the most careful manner by combing and repeated doublings, great variation exists is certain, and this matter can be determined in two ways, namely, by comparing the weight of several leas of the same yarn, or by microscopic measurement. The former is the most convenient method, but is of necessity much less exact than the latter. The student may be referred to Dr. Bowman's book for a number of tests of the weight of leas, which will illustrate this point. In an interesting paper, communicated to the Manchester Microscopical Society by Mr. E. H. Turner, the following measurements of mule yarns were given (see page 367). These results are very remarkable, but it is evident that the 70's, 76's, and 80's yarn are by no means the correct counts, as otherwise the diameters would not vary as they do; as, instead of the latter being the thickest, it should be the thinnest of the three. Making all allowance for the defects in the yarn, how-

ever the results confirm the common experience. The table is only given in order to show the variations existing in the same spinnings, and does not by any means deal with all the points requiring elucidation. With these may be compared the results given by Dr. Bowman, on p. 149 of his work, when dealing with the twist per inch in two folds 60's yarn spun from Egyptian cotton. Here the variation in the twists per inch is

Description of Cotton.	Counts.	Average Diameter.		Largest and Smallest Diameter in 1000ths of an Inch.			Maximum Variation.	
		In 1000ths of an Inch.	Decimal of an Inch.	Highest.	Lowest.	Percentage of Lowest to Highest.	Maximum Variation 1000ths in.	Percentage to Average Diameter.
Egyptian	24	48	·0096	65	30	46	35	73
American	36	42·5	·0085	55	30	55	25	59
″	46	30·6	·0061	40	20	50	20	65
″	56	26·5	·0053	40	15	37·5	25	93·5
Egyptian	60	25	·0050	40	10	25	30	120
″	70	23	·0046	40	11	27·5	29	126
″	76	23	·0046	31	17	55	14	61
″	80	23·75	·00475	36	15	41·5	21	88·5
″	86	19·2	·00385	25	14	56	11	56·5
″	100	18·4	·003675	26	12	46	14	76
°	110	18·2	·003625	28	12	42·75	16	88
″	120	17·7	·00354	25	10	40	15	85
Sea Island	140	13·4	·00267	20	9	45	11	82

shown to be 12 per cent, which is quite sufficient to account for a considerable difference in the diameters, especially when it is stated that Mr. Turner's measurements were made with yarn wound on slips one inch wide, so that the variations would be easily observed.

(247) It was mentioned in Chapter II. that cotton fibres are naturally possessed of good spinning qualities—that is, they are possessed of a natural twist which induces that intertwining one with another which is so necessary in spinning. There is, however, a fact which, in this connection, is not always kept in view—viz., that the twists in the natural fibre are neither regular in pitch nor are they always in the same direction. It is not uncommon to see a fibre with twists of widely different characteristics in various parts of it, while in some grades the convolutions, spirals, or twists are extremely irregular. These facts somewhat detract from the absolute reliance sometimes placed upon this natural twist, although in the main it is a feature not to be lost sight of. There is, however, one point which is affected to some extent by this convolute formation. It is customary when twisting rovings up into yarn, which is to be employed for warp or "twist," to rotate the spindles from right to left—that is, give them a "right-handed" twist—the reverse being the practice when "weft" yarn is spun. It has often been supposed that this difference in procedure had an effect upon the finished yarn by reason of the untwisting of the natural twist in spinning "weft" yarns, the direction of rotation being in that case opposite to that existing naturally. Weft yarn presents a more hairy or "oozy" condition than twist, and an explanation which has been offered is that the untwisting of the fibre led to it being thrown out from the surface of the yarn. There does not appear to be any justification of this theory, especially if it be true that the fibres possess twist in both directions. The more open appearance of weft yarn is rather to be attributed, in the author's opinion, to the smaller twist put into it in spinning, and to the fact that the fibres employed in the manufacture of weft are generally of a softer nature than

those used for twist. It is desirable always to keep in mind the purpose for which cotton is to be used, and to manipulate it throughout the whole series of processes, so that it will eventually be in the best condition for spinning the class of yarn for which it is employed.

(248) The strength of the yarn is affected by the twist introduced into it in a twofold way. The cohesion of the fibres and the consequent resistance to rupture of the sliver is much increased, while in one system of spinning the thin places are hardened so that more strain is thrown upon the thick ones in drawing. Two principal factors have an influence upon the strength of a thread—the parallel disposition of the fibres, their arrangement in equal numbers throughout the whole length of the yarn, their diameter and the twist given to the thread. It has been found that only a percentage of the sum of the strength of all the fibres in any yarn is utilised. The exact amount of this has not been determined, but does not exceed in any case 40 per cent. The pull exercised upon a thread is ordinarily in the direction of its length, and the loss in its strength as compared with the sum of the individual strength of the fibres composing it, is partially the result of the divergence of the fibres from straight lines, which is the effect of twisting them. Unless the whole of the fibres composing a thread are equally twisted—that is, unless throughout the yarn there is a spiral disposition of the fibres—if, in other words, the fibres laid on the outside of the yarn receive more twist than the inner ones, they must be proportionately less able to resist a longitudinal strain than those forming the centre or core. Thus the existence of twist is at once a source of weakness and of strength. The yarn is weakened by the divergence from the parallel longitudinal disposition of the fibres, and is strengthened by the additional cohesion thus obtained. Of these two the latter factor has the most powerful influence, and, in consequence, weft and hosiery yarns, which are more slackly twisted than warp yarn, are, even when of the same counts, relatively weaker. Although the strength of a yarn may be practically ascertained

by the test of one lea, it is quite clear that within that length there will be considerable variations, and that, as the strength of a chain is practically that of its weakest link, the existence of thinner and weaker places in a strand of yarn limits its power of use in the same ratio.

(249) Having thus dealt with the question of the structure of the cotton thread generally, without any consideration of the way in which the twisting is conducted, we are naturally brought to deal with the different methods of twisting. Of these, as was intimated in Chapter I., there are two, the intermittent and continuous. The earliest method was, as was shown, of necessity the intermittent, if the phrase be employed to indicate the fact that the operation was conducted with successive lengths of material. Relatively to the amount of material prepared the operation was a continuous one, and the difficulty was rather one of preparing the material for spinning fast enough than of twisting it. As soon as the preparation could be made continuously, spinning also became a similar operation. At the present day there are two methods adopted, which are indicated in the classification in Chapter II., viz., mule and ring spinning. The third mode named—flyer spinning—is now practically extinct, except for special ranges of counts, but has some points of interest. Its rationale was described in paragraph 207 in the last chapter, and need not now be dealt with. Between mule and ring spinning there is a wide difference existing in the mode of procedure and the result upon the yarn In the former the yarn is twisted in successive lengths of from 60 to 66 inches each, while in the latter it is continuously spun. At first sight there does not appear to be much in this, but without going into a number of points bearing upon each operation, there is a wide distinction. As the roving is delivered from the rollers in the mule it is conveyed to a nearly upright spindle, which gradually recedes during the time twisting is going on, from the roller beam. The velocity at which the spindle recedes from the rollers is such that a draft is exercised upon the yarn as it is being twisted. There is a

distinct difference in the effect of this draft and that of the rollers. In the latter case the fibres are in a sense compressed or bound by the nip of the roller, which to a certain extent prevents them from assuming a different disposition in the cross section of the sliver. That is, the fibres are not so free to move from the centre of the sliver to the outside, although where they vary in length considerably this action unmistakably takes place. But when the roving is finally freed from the bite of the rollers, when it is stretched between two points, then the longer fibres having more cohesion, and offering proportionately great resistance to the draft exercised, gradually approach the centre of the yarn as the attenuation of each length takes place. The shorter fibres consequently move outwards, and are placed on the outside of the yarn, where by the rotation of the latter upon its axis they are wrapped round the inner core. The latter is also twisted, but by reason of the superior length of the fibres composing it, is not so easily ruptured as its outer covering of short fibres. The ends of the latter project from the thread at all points, thus giving it the distinctive hairy or oozy appearance named.

(250) The effect thus described has no correspondant in the second of the two methods of spinning. In mule spinning the successive treatment of definite lengths of yarn in the manner described is followed by the winding of each length as a separate operation before the subsequent length is twisted and drawn. In ring spinning the only draft which is put upon the roving is that exercised by the rollers, and immediately it leaves the latter the roving is twisted up and wound on to the bobbin. All these operations are continuous and without break. There is therefore no possible chance of any further attenuation of the roving after passing the rollers, and the drawing of the fibres into the order which occurs in the mule is absent in this case. Whatever the disposition of the fibres may be in the roving after the final roller draft, remains the disposition in the twisted yarn plus the effect of the twist itself, which is considerable. It is quite easy to understand that under such different con-

ditions the structure of the thread will vary considerably, and
that the effect of the final draft upon a defined length of yarn
will be greater than the draft of rollers applied to the same
length continuously.   In the first-named case the older forms
of spinning, when conducted by hand, are approached, while in
the latter the more modern method of continuous drawing is
relied upon.   The importance of this fact is made manifest
when it is remembered that twist is being put into the yarn
simultaneously with the additional draft in one case, and sub-
sequently to the final draft in the other.   This has an important
bearing on the subject.   In continuous spinning operations the
moment the roving leaves the rollers it receives twist, so that
whatever may be the disposition of the fibres, it is at once fixed.
Thus, if the shorter and longer fibres are intermingled throughout
the cross section, they are twisted up together and are formed
into a thread at once.   If, moreover, there exists any variation
in the thickness of the roving as it leaves the rollers, the twist
fixes itself first in the thinner places, but is not so soon put
into those which are thicker.   In paragraph 243 this point was
illustrated, and it is obvious that the twist will be much more
readily introduced into the thinner than into the thicker parts
of the roving.   The velocity at which, in continuous spinning,
the roving is delivered, and the speed at which it is wound is
so great, that before any adjustment of the twist in various
parts of the yarn can take place, it is attached to and fixed on the
spool or bobbin. This is not the case with intermittently spun or
mule yarn.   Here each successive length receives the twist as it
emerges from the rollers, and, as in the preceding case, it runs
at once into the thinner places.   This increases the cohesion of
the fibres; in other words, it causes them to resist the draft
put upon them, and, as a result, the latter exerts more power
upon the thicker untwisted places in which, despite their larger
diameter, the cohesion of the fibres is less.   Thus the thicker
places are drawn out, and as they decrease in size the twist
gradually runs into them.   There is, further, a slight pause of
the spindles at the termination of their recession from the

rollers, which is generally a little in advance of the cessation
of their rotation, so that, during this period, the twist can
gradually pass into every part of the length of yarn, and thus
become equal throughout.   Two distinct features thus charac-
terise the intermittent system of spinning, namely the draft
upon the thread after leaving the rollers, and the subsequent
equalisation of the twist.   Both of these are, by the necessities
of the case, absent in yarn spun continuously, and in conse-
quence the structure of the resultant yarn is much affected.

(251) The essential properties of a good yarn are elasticity,
evenness, strength, and colour of the thread.   The former
quality is very important.   If a strand of yarn is strained until
it approaches the point of rupture it is very clear that its
strength will be materially diminished.   Even if the draft
exercised falls short of this point, as it always does when
spinning is properly conducted, the method and period of
winding has an effect upon the yarn.   It is obvious that
if yarn is kept in tension while being twisted, and is there-
upon wound so that the tension is maintained subsequently,
it has no chance to recover its elastic strength.   The amount
of this property which it retains is made to depend solely upon
the question of the treatment accorded to the fibres in the
preparatory stages.   If they have been overstrained the defects
consequent thereon will be fixed, but if reasonable care
is exercised in this respect, a yarn possessing a fair amount of
elasticity can be produced even by continuous spinning.   In
the intermittent process, however, after the full tenuity of the
yarn is obtained and the twist introduced, the spindles are
rotated a little in the reverse direction prior to the commence-
ment of winding, and the strain upon the length of yarn is con-
siderably reduced.   Further, during the operation of winding,
the spindles again gradually approach the rollers, so that the
yarn is slowly relieved from tension.   Every condition which
can favourably influence the preservation of the elastic strength
of the yarn is present in the intermittent system of spinning.
Among these must not be forgotten the tendency towards the

N

formation of a core of longer fibres, to which reference has already been made. The hardness imparted by extra twist naturally decreases the elasticity of the yarn, and, as will be shown, it is customary to give continuously twisted threads—at any rate when formed on the ring frame—a harder twist than mule yarn. Care should be taken not to confound the strength and elasticity of yarn, as these are absolutely distinct characteristics, although each affects the other. We have already dealt with the evenness and strength of the yarn and their causes, and need not again treat this part of the subject. With regard to the colour of the yarn, this depends largely upon the twist imparted to it, as was mentioned in paragraph 66, Chapter III. There is, as was there shown, a difference in colour between yarns spun from the same cotton, the degree of which depends upon the amount of twist put in. This effect arises from the incidence of the light upon the fibres, as they lie upon the surface of the yarn. This naturally varies with the angle at which the fibres are disposed, which in turn is determined by the pitch and direction of the spirals. The latter depends upon the number of turns per inch, as can be clearly understood.

(252) It is not pretended that the foregoing explanation exhausts the subject of the structure of the cotton thread, but it is sufficient to enable the chief features in connection with it to be comprehended. It must also be understood that the remarks made with reference to continuous spinning are more especially directed towards ring spinning, and are not so true of throstle or flyer yarn. There is the difference between ring and flyer yarn which exists between yarn spun by means which ensures an absolute regularity of twist and those where the regular motion is absent. The winding of flyer yarn also differs from that of ring yarn, by the fact that in the former case the bobbin is frictionally retarded, while in the latter it is positively driven. In the flyer frame the yarn is wrapped on a bobbin, the motion of which is retarded as described, while in the ring frame it is drawn on to a bobbin positively driven. It is quite clear that the conditions existing in the first case are more favourable to

the production of an elastic yarn than those in the latter. It is also true that flyer yarn, probably owing to the method of putting in the twist, is very even and cylindrical, but the slow velocity of the spindles has at present put this method of production out of the field. It is, perhaps, necessary to caution the student against the supposition that ring yarn is necessarily deficient in the qualities named. This is not so, as it possesses considerable strength and elasticity, but these properties are necessarily comparatively greater in some classes of yarn than in others. All that has been attempted to show is that the method of constructing the thread by the intermittent process is more favourable to the creation of a perfect thread than the continuous system. Looking at the matter from the commercial point of view, the relative values of the various properties of yarn, of course, assume a different aspect, and on this matter something will be said at the conclusion of the consideration of the two systems of spinning.

CHAPTER IX.

MULE SPINNING.

(253) HAVING explained the theory and some of the reasons for the adoption of the special construction of the thread, and having intimated the differences naturally arising in it according

to the method of producing it, we can now profitably proceed
to describe the special mechanism employed and its manipula-
tion. As the intermittent system has, on the whole, the larger
employment, and as the machine employed in effecting it is the
more complex and interesting, it will be perhaps the better
course to deal with it first. The machine used is known as the
" mule "— the origin of the name being given in Chapter I.—-and
on account of its practically automatic action, the " self-acting
mule " or " self-actor." It has been previously indicated that
the various operations of twisting and winding, which together

form the complete cycle which is understood by the term spin-
ning, are in this machine performed separately. It will be better
therefore to describe the elementary or essential parts of the
machine before proceeding to show how it is operated in detail.
To enable the description to be understood the diagrammatic
illustration given in Fig. 172 is used. In this the roving bobbins
R are shown fixed in the creel, and the roving is passed
through three lines of rollers E, by which it is drawn and
emitted from the front pair. From thence it is taken directly to
the spindle S to which it is attached, and on which it is wound
in the form of a spool or "cop" C of the shape shown. The

spindle S is borne by two rails, one carrying a footstep and the other an upper bearing or "bolster." It will be noticed that the spindle is not absolutely vertical in position, but is slightly diverged from a perpendicular line. The amount of angularity varies with the class of work being done to an extent which will be defined a little later. Between the bolster and footstep the spindle has fixed upon it a small grooved pulley V^1 called a "warve" or "whirl" which has an endless band V passed round it. V is also taken round a cylindrical roller T^2, revolving with a shaft T, and called the "tin roller." The tin roller is so named because it is constructed of short cylindrical lengths made from tinned iron sheets which are coupled together by a specially arranged coupling shaft. It is, of course, the full length of the carriage, the rollers in each carriage being coupled by a transverse shaft on which the whole of the driving pulleys are fitted. The spindles and tin roller are borne in a frame or "carriage" O, which is carried by transverse bearers, at the ends of which are journals for the axes of disc rollers O^1. The latter are formed on their peripheries with square grooves, which fit on to narrow iron bars or "slips" U secured to the floor of the room. Thus, if traction is applied to the carriage it can readily be moved to or from the rollers E in a horizontal direction. It will be noticed that the roving passes under a wire N fixed in the sickle shaped bar shown, which oscillates with the centre shaft or pivot B, and which is known as the "faller wire," or shortly, the "faller." The object of this is to guide the yarn on to the spindle in suitable coils during the operation of winding. The yarn also passes above the wire M—known as the "counter faller"—fastened in the arm or bar shown, this being oscillated with the rod B^1.

(254) Yarn is produced by this mechanism as follows : When twisting is beginning, the carriage O, with the parts which it bears, is brought to a point near the rollers E. As the latter begin to deliver the roving the carriage simultaneously commences to recede from the rollers, and the spindles S begin to revolve. In doing so they take up the slack yarn and coil it on

the spindle between its point and the nose of the cop. Thus there are three things taking place : The roving is being drawn and delivered ; it is, as it is delivered, twisted ; and it is kept in a stretched condition by reason of the recession of the carriage. The latter moves away from the rollers—or makes its "outward run" or "stretch"—for a distance of 63 or 64 inches, during the whole of which period the triple operation named is going on. When the carriage reaches the end of its stretch—that is, when it has made its utmost recession from the rollers—it is stopped, and is held for a brief period at that point. While so held, the spindles are sometimes rotated for a short time, so that a little additional twist is put into the length of the yarn. It is perhaps necessary to say here, that although the singular number is occasionally used in speaking of the various parts, mules contain a large number of spindles, sometimes as many as 1,500, so that the processes described are equally applicable to all of these. After the completion of the twisting the motion of the spindles is arrested and at once reversed, so that a few coils of yarn which are wrapped on each spindle between its point and the nose of the cop C are uncoiled. As this takes place the faller N descends and the counter faller M ascends, so as at once to maintain approximately the tension of the stretch of yarn and to guide the latter on to the cop. This operation of reversal of the spindles is technically known as "backing-off." Immediately it is completed the drawing in of the carriage begins, and the spindles are revolved in their normal direction, so as to wind the yarn on to the cop as it is released by the inward run. As this takes place the faller N first descends quickly and then rises slowly, the yarn being thus guided on to the cop in descending and ascending coils. When the inward run is complete the whole of the winding operations cease, the faller and counter faller wires assume their normal position clear of the yarn, and the parts are again adjusted to begin the work of drawing and twisting. The complete outward and inward run of the carriage is technically called a "draw," and the speed of the mule is indicated by the

number of "draws" per minute.   Generally speaking, the finer
the yarn the fewer the draws, but this is subject to some
exceptions.

(255) The brief description just given enables a classification
of the various stages to be made.   They are, 1st, twisting and
drawing; 2nd, arrestation; 3rd, backing-off; 4th, winding; and
5th, re-engagement.   The operations of the various parts during
each of these periods will be dealt with in detail as they arise.
The difficulty which occurs when an attempt is made to master
and comprehend the movement of the various parts at different
periods arises from the fact that at one time a certain portion of
the mechanism is performing one function and at another quite
a different one, both the direction and velocity of its movement

FIG. 173.

being changed.   In order to save space and trouble the whole
of the mechanism which forms the operative portion is contained
in a central frame, called the headstock, from which diverge to
the right and left the two carriages, roller beams, and bearing
pieces.   This arrangement is shown diagrammatically in Fig. 173,
which is a representation of two mules set in the positions which
they occupy in the mill.   H in each case represents the head-
stock, which is a double longitudinal frame securely tied together
by transverse beams or rails.   The carriages O extend at right
angles to the right and left, and in each case the carriage is
shorter on the right hand side of the headstock.   The roller
beams marked E also extend the whole length of the mule, and
are borne at suitable intervals by light frames or spring pieces.

and at the ends by frames F as shown.   The number of spindles
in a mule varies with the work it has to do, the gauge—that is,
the distance from centre to centre—being less with the fineness
of the yarn produced.   Weft cops, being smaller in size than
those used for warp purposes, are spun upon smaller spindles,
and the gauge of the spindles is less.   Mules are made with
gauges varying from 1⅛ inch to 1¾ inch.   There is an advan-
tage in the disposition of each pair of mules in the manner
shown, which is that as the minder works between the headstock
he is able to attend to each alternately.   The bulk of the piecing
of broken ends is done during the early part of each stretch, so
that it is possible to be piecing the ends which may be broken
on one machine while the other carriage is running up.   This
relative movement is always maintained if possible, and greatly
facilitates the conduct of the work.   The bobbins R from the
roving frame are mounted on pointed rods or skewers, which
rest in porcelain or wooden footsteps, and can, with the bobbin,
rotate freely.   The creel is shown in Fig. 174, which is used to
show in more detail the general arrangement of the headstock.
In this figure the creel is what is known as a "three-banked"
one.   The disposition of the creel varies, in some cases only two
heights of bobbins being used.   These are arranged so as to
give a good direction to the roving, and when yarn is spun from
"double" roving the two ends of the latter must be guided so
as to pass through the same roller boss together.   Guide rods
are provided to make the passage of the upper roving easier, but
in the case of the lower bobbins it is taken directly to the rollers.
A three-height creel is also shown in Fig. 178.   A creel is some-
times duplex, that is to say, instead of there being one row of
bobbins there are two in each height, one behind the other, the
bobbins being arranged so that those in the back row have their
centres between those in the front.

(256) There are usually three lines of rollers in a mule, the
lower line being fluted, the upper front line sometimes loose
boss, the back top rollers being self-weighted.   The practice in
this respect varies, some people preferring to weight all the three

lines by stirrup and weight, while others only fit the front
line in this manner. The loose boss roller is unsuitable for
mules of a fine pitch. The rollers are, of course, in two sets
in each machine, one on each side of the headstock, but the two

Fig. 174.

front lines are coupled by a short shaft extending across the
headstock. This shaft is fitted with a clutch, the engage-
ment or disengagement of which gives motion to or stops the
rollers. The period of the engagement of the clutch is regu-
lated in a manner to be afterwards described. The carriage

of the mule is a strong frame, built partially of wood, the longitudinal beams being of that material. These are secured to each other by transverse cast-iron stays, or "muntins," which also act as bearings for the tin roller shafts. It is also advisable, especially in long mules, to provide diagonal stays. Each of the carriages in a mule is firmly secured to a strong iron frame, which is known as the "square." The square carries the driving mechanism for the tin roller and also a great part of that connected with the fallers. The rollers in each carriage are coupled by a shaft extending across the square, on which is fixed the pulley by which they are driven. The spindle is made of steel, is from $13\frac{1}{2}$ to 18 inches long, and of a diameter varying from $\frac{3}{8}$ to $\frac{1}{8}$ inch, terminating in a sharp conical tip. For that part of its length between the footstep and bolster it is of the same diameter, and on this part—called the haft—the warve is secured. Above the bolster the "blade" of the spindle is made taper, and on this the spool or cop of cotton is wound. The spindles are, as has been indicated, not carried vertically but angularly in their bearings, the degree of angularity depending on the material to be spun. In some cases special provision is made to enable the spindle rails to be easily adjusted, and by means of stay rods fixed to the rails the proper inclination can be readily given. In setting the spindles a special gauge is used, with arms projecting from a plumb level. One of the arms has a small hole to drop on to a spindle point, and the other arm presses upon the haft just above the foot. The arms are attached to the level, and can be adjusted so as to give any desired bevel. When so set they are pressed against the spindle, and the rails are adjusted until the plumb bob hangs vertically as indicated by the line on the frame of the level. The rule generally pursued is to give the point of the spindle a forward inclination from a vertical line drawn from the centre of the footstep of about $\frac{1}{4}$ inch for each inch of its length. Thus a 16-inch spindle would have 4 inches of incli nation. It is, however, the practice to vary this slightly

according to the counts of yarn being spun, coarse counts being spun on spindles having less inclination, the amount of which is increased as the yarns spun become finer. It is also the custom to give weft spindles a relatively greater inclination than those used in spinning warp yarn, the reason being that weft is more slackly twisted, and will not stand so great a stress. The average, however, is as stated. The purpose of this inclination is to permit of the ready passage of the yarn over the point of the spindle, for it is evident that as the point of the spindle is below the rollers, the angle formed by the yarn when the carriage is out, and it is held between the spindle point and the rollers, will be more acute than when the carriage is in. It is, therefore, necessary to give the spindle such an angular disposition as will enable the yarn to bend over the point at all parts of the carriage traverse without undue strain or any slip. The spindles are driven by bands in the manner previously named, the direction of rotation being dependent on whether weft or warp is spun, as mentioned in the last chapter.

(257) It was said in the last chapter that twist is introduced by turning the roving upon its axis, and while it is quite clear that this will happen if the material is treated by a flyer and spindle as in the case of roving, it is not so obvious on the mule. The angular position of the spindles relatively to the line of thread renders it difficult to understand how the twist is introduced into the yarn. If, however, the spindles be revolved at a slow pace the action is easily seen. The yarn being held in tension between the nose of the cop and the rollers is coiled spirally on the spindle in coils of decreasing pitch, the latter being caused by the taper of the spindle. As during the period of twisting the spindles are running the direction required to wind on the yarn, it is obvious that unless some relief is given it would snap. Owing to the pull upon the yarn the tendency is to draw off the coils, and it will be noticed if the spindles are slowly revolved that the top coil slips off, and as it does so the yarn is twisted right round. If a length of yarn be selected with a snarl or curl in it in this operation of twisting it is very easily

noticed. As soon as the top coil has slipped off, the rotation of the spindles restores it, and this process goes on during the whole period of twisting. The angular position of the spindle aids this drawing-off process by rendering the slip of the yarn more easy, and it is probable that but for this position breakage would occur. Owing to this rapidly repeated slipping of the top coil the yarn is given that peculiar vibratory movement which is observable.

(258) This very general review of the essential portions of a mule is sufficient to enable a clear idea to be obtained of the mechanism, and a detailed description can now be given. In doing so, it may be stated at the outset that it is intended to

FIG. 175.

deal with the various motions, less from the mechanical than from the spinning point of view, and although it will be necessary to treat largely the mechanical construction, it will be done with a view of elucidating the actual operation of the machine. Referring then to Figs. 175, 176, and 177, which are representations of the method of driving the mule of Messrs. Platt Brothers and Co. Limited, the machine is driven from a countershaft by means of a belt, which passes over a pulley A, fixed on a shaft C, known as the "rim shaft." The pulley A is 16 inches diameter and is 5 inches wide. Alongside the pulley A, which is fast on the shaft, is a loose pulley B of the same diameter, but 5¼ inches wide. The strap is only partially put upon the

fast pulley, a certain portion of it, sufficient to drive the loose pulley, being always on the latter. In some cases the driving pulleys A B are arranged transversely of the mule, as in the arrangement shown in Fig. 178. This is often a convenient arrangement, and suits the direction in which the line shaft runs. In this illustration the arrangement of the counter-shaft is shown, and it will be noticed that on it are fixed

FIG. 176.

a fast and loose pulley for the driving shaft belt, a broad fast pulley for the belt driving the rim shaft, and the grooved pulley by which, as afterwards described, the side shaft is driven. The fast pulley is provided at one side with a part of a cone A^2, engaging with a similarly shaped, but female cone on the wheel A^1. Leather strips are used on the conical part of A^1 for two reasons, to prevent any danger of fire, and to enable repairs to

be easily effected. It is important that these cones are truly shaped, and that, alike in diameter and width, they are as large as they can be conveniently. The great size of modern mules renders this imperative, and it is also of great importance that the leather covering of A^1 is as truly applied as is possible. The conical shape causes a jamming or wedging action to take

FIG. 177.

place, which creates a tight grip. It is obvious that as the clutch must be rapidly engaged and disengaged the angle of inclination must not be too obtuse, it being well known that the grip of slightly tapered surfaces is greater than that where the inclination is larger. This is a matter of some importance, but is a point which is one for the machinist rather than the

spinner.   The cone A^1 is called the "backing-off friction," and is utilised as afterwards described.   The spindles are driven, as shown in Fig. 175, from the pulley C^1, which, although, for simplicity, shown as a single grooved pulley, is generally made

FIG. 178.

with two and sometimes with three grooves.   The pulley C^1 is called the "rim pulley," or shortly, the "rim."   The course of the endless band or rope C^2 is clearly indicated, and it will be seen that it passes first over a carrier pulley O^1, thence over a

pulley T^1 on the tin roller shaft T, being then conveyed to a carrier pulley X, and back to the rim pulley. The course of the rope is, naturally, doubled or triplicated, when a double or treble grooved rim is used, but to show the course of the rope, under these circumstances, would complicate the drawings and render them obscure. When this factor is taken into account, however, the effective driving of the tin roller will be easily understood. The rollers are driven from the pinion G, fixed on the rim shaft. By means of a carrier wheel, G drives the pinion G^1, fastened on the side shaft J, on the other end of which is a bevel pinion J^1, engaging with a bevel wheel F on the roller shaft E. In order to give a clear idea of the operation of most of these parts, it is intended to show the effect of the various trains of wheels, but it must be clearly understood that, in doing so, the number of teeth given are not actual, but only such as will illustrate the subject. So long as the principle is demonstrated the assumed size of the wheels is immaterial, and fictitious dimensions can be employed with equal effect to actual ones. Let it therefore be assumed that the rim pulley C^1 is 22 inches, the pulley T^1 on the tin roller shaft T 12 inches, the tin roller T^2 6 inches, and the warve V^1 on the spindle ¾ inch diameter respectively. Let it also be assumed that the rim shaft is running at 600 revolutions per minute. Then the velocity of the spindles would be $\frac{22 \times 6}{12 \times \cdot 75} \times 600 = 8{,}800$. In like manner, if the pinion G be assumed to have 18 teeth, the wheel G^1 39, the pinion J^1 19, and the front roller clutch wheel F 40, then the speed of the latter would be $\frac{18 \times 19}{39 \times 40} \times 600 = 131\cdot5$ revolutions per minute. Now, if the front roller be assumed to be 1 inch diameter, it will deliver 413·2 inches of yarn. The twist is therefore $\frac{8800}{413\cdot2} = 21\cdot5$ turns per inch, which is practically equal to that required for 32's twist. The back shaft is driven by the train of wheels shown in Figs. 176 and 177, of which Q is fixed on the roller

shaft and is assumed to have 21 teeth. It drives, by the inter-
vention of a carrier wheel, the wheel Q^1, which is fixed on a short
shaft, on which is also a pinion R, called the "gain wheel,"
gearing with a wheel P^1, which forms part of a clutch on the
back shaft H. The teeth of the clutch are also shaped so as
to permit the half clutch P to move outwards when required.
The half clutch P is ordinarily pressed into gear with the wheel
P^1 by the spring P^2, which is, however, sufficiently weak to yield
if any obstruction is presented to the rotation of the shaft H.
On the back shaft H are fixed several small drums H^1, which
are known as "scrolls." They have rounded grooves cut
spirally in their surfaces, and are for the greater part of their
length cylindrical, but at one end terminate in a smaller

FIG. 179.

diameter. Thus any given speed of rotation when the rope
is on the smaller part of the groove will give a slower velocity
than will be given when it is on the larger diameter. This
condition of things arises when the carriage is beginning to
run outwards, the drawing out band H^3 being then on the small
diameter winds on slowly, thus enabling the inertia of the
carriage to be overcome before the full speed is attained. There
are four operative bands wound on a similar number of scrolls
on the back shaft. Two of these are fixed to the end frames of
the carriage, as shown in Fig. 179, and two others to the carriage
at points between the end of each carriage and the headstock. A
greater number can be used if rendered necessary by the length of
the mule. A fifth scroll H^2 is also fixed on the back shaft. The

ropes H³ (Fig. 175) are taken round carrier pulleys Z fixed at the end of the headstock, and are fastened to the carriage in the manner shown. From H² a band is taken to the scroll L³, the function of which will be afterwards described. Q¹ is supposed to have 50 teeth, R 23, and P¹ 56. The velocity of the back shaft is therefore $\frac{21 \times 23}{50 \times 50} \times 131\cdot5 = 22\cdot6$. The scrolls H¹ are assumed to be 6 inches diameter; 22·6 revolutions of the scrolls will therefore give a traverse to the rope of $6 \times 3\cdot1416 \times 22\cdot6 = 426$ inches, and the carriage is traversed at the same velocity. It would therefore take for a full stretch of 64 inches 9 seconds, and in this time the rollers would deliver $\frac{9}{60} \times 413\cdot2 = 62$ inches of yarn nearly. The carriage thus gains upon the roller delivery 2 inches in each stretch, and draws the yarn out as described. The effect of this " gain " of the carriage is to elongate or sub-ject the roving to a further draft, and thus decrease the inequali-ties in diameter. As was described in the last chapter, twist runs into the thinner places in the roving, and thus hardens them. It follows therefore that this supplementary drawing action elongates the untwisted—*i.e.*, the thicker—places, and aids in the production of an even thread. The amount of gain which is permissible depends entirely upon the quality and staple of the cotton which is being treated. Very short stapled cotton will not permit of the introduction of any draft subse-quent to the roller draft, while long stapled cotton allows it to be introduced to a considerable extent. The practice in the former case often is to allow the rollers to deliver yarn at a quicker speed than the rate of traverse of the carriage, the rollers thus gaining on the carriage. This is principally the case when very coarse counts are being spun from short stapled cotton. The total draft depends entirely upon the quality of the cotton, and in arranging it, it must be properly divided between the rollers and carriage.

(259) No special description need be given of the method of obtaining the differential velocity of the three lines of rollers in

order to put in the draft. This is similar in principle and practically in detail to that in the roving frame. In setting the rollers, however, some care should be exercised, as the draft in the mule is considerable, as will be seen when the question of drafts comes to be dealt with. This subject will be reverted to in a short time. It will be better at this point to give the various rules for working out the speeds and drafts, in so far as they relate to the operation of the parts described up to the present point. Practically the different portions of the mechanism with which we have dealt comprise the whole of those necessary for spinning, the remaining operations being connected with winding, and having no relation to spinning. The ordinary rules employed are as follows :—

To find the draft required in the rollers when the gain of the carriage, the counts to be spun, and the hank roving are known—

Subtract the amount of gain from the total length of stretch. Thus, if gain is 2 inches, and length of stretch 64, net length of yarn delivered is 62 inches.

$$\frac{\text{Counts required} \times \text{length delivered}}{\text{Full length of stretch} \times \text{hank roving}} = \text{draft.}$$

To find the draft required in the rollers when the carriage does not gain—

$$\frac{\text{Crown wheel} \times \text{back roller wheel} \times \text{diameter of front rollers (in eighths)}.}{\text{Front roller wheel} \times \text{change pinion} \times \text{diameter of back rollers (in eighths)}.}$$

A constant number can be got by making the above calculation, and omitting the change wheel.

To calculate number of teeth in change pinion, to obtain any given draft—

$$\frac{\text{Crown wheel} \times \text{back roller wheel} \times \text{diameter of front roller (in eighths)}.}{\text{Front roller wheel} \times \text{draft required} \times \text{diameter of back roller (in eighths)}.}$$

To find the counts being spun when carriage gains—

$$\frac{\text{Hank roving} \times \text{total draft} \times \text{total stretch}.}{\text{Length delivered by rollers}.}$$

To find change pinion required to spin any counts when present counts are known—

$$\frac{\text{Present counts} \times \text{present change pinions}.}{\text{Counts required}.}$$

To find back roller wheel for any draft—

$$\frac{\text{Front roller wheel} \times \text{change pinion} \times \text{diameter of back roller} \times \text{draft required.}}{\text{Crown wheel} \times \text{diameter of front roller.}}$$

To find the correct wheel on middle roller—

First determine the ratio of draft which exists between the back roller and the middle roller. Say this is as $y : x$, representing the relative velocity of the middle and back rollers. Then—

$$\frac{\text{Back roller wheel} \times \text{diameter of middle roller} \times x.}{\text{Diameter of back roller} \times y.}$$

Two courses are open in changing the twist in yarn. The one is to take off the rim pulley and substitute a larger or smaller one. In this way the velocity of the spindles is altered without changing that of the rollers. The second plan is to change the twist wheel, by means of which the velocity of the rollers is changed, and that of the spindles remains constant. For many reasons the latter is the better course, but rules are given by which either can be taken.

To find the number of turns per inch in the yarn, velocity of spindles and rollers being known—

$$\frac{\text{Number of revolutions of spindles.}}{\text{Revolution of front roller} \times \text{circumference of front roller.}}$$

To find the required size of rim pulley, to obtain any counts when present counts are known, without altering front roller speed—

$$\frac{\text{Diameter present rim pulley squared} \times \text{counts required.}}{\text{Counts spun.}}$$

The square root of quotient = diameter of pulley required.

Or, $\dfrac{\text{Counts required} \times \text{diameter present rim pulley}}{\text{Present counts.}} = a.$

Then $\dfrac{a + \text{present size of pulley}}{2}$ = diameter pulley required.

It is much preferable to change the twist wheel rather than the rim pulley, except in extreme cases of variation. To do this, if the size or number of teeth of the twist wheel is substituted for the rim pulley in the last rule given the size of the twist wheel can be ascertained when changing counts.

To find the amount of gain in the carriage—

There are three ways of doing this. The first is indicated in the last paragraph, this giving the total gain. By dividing this by the roller delivery the gain per inch is given. Thus, in the case supposed the gain is $\frac{2}{62}$ = ·032 per inch. The next method is as follows :—

$$\frac{\text{Number of inches carriage travels.}}{\text{Number of inches of roving delivered by front roller.}}$$

The third method is (refer to Fig. 177)—

$$\frac{\text{Wheel Q} \times \text{pinion R} \times \text{diameter of scroll H.}}{\text{Wheel Q}^1 \times \text{wheel P}^1.}$$

The quotient in either case will be the roller delivery plus the gain, and will be the distance travelled by the carriage during the delivery of one inch by the rollers. The rules thus given are those which relate to the spinning or twisting mechanism and a brief description of what happens during this period, together with a few detailed remarks about the care required, may not be out of place. The strap being on the fast pulley A, which is free to revolve and entirely out of contact with the friction clutch A^1, the rim pulley C^1 is rapidly rotated. By means of the rim band this movement is communicated to the spindles, which are revolving at their normal velocity. During the same period the rollers are delivering roving, which is being twisted as it emerges. The two faller wires are out of contact with the yarn, and the carriage O is traversed as described by reason of the forward movement of the drawing-out band. During all this period the work of spinning and drawing is going steadily on, and continues to do so until the carriage arrives at the end of its outward stretch. It is obvious that in starting a mule containing a large number of spindles the inertia of the carriage and spindles, and the friction of the bearings, will offer a considerable resistance to the driving force, and although it is assumed that the transfer of the belt to the driving pulley is immediately followed by the rotation of the spindles at full speed, in practice this is not so. The rollers, being driven by gear wheels, begin to rotate at once, as does the back shaft, but the

rim band slips at first, so that the spindles only get up full speed after a few inches of roving have been delivered. The result is that twist is only partially introduced, and there is some danger of broken ends and uneven yarn. In order to obviate this difficulty, Messrs. Asa Lees and Co. have recently introduced the system of driving which is shown in Fig. 180. The rim shaft has mounted on it a long sleeve on which the driving and rim pulleys A and C^1 are fixed. The rim shaft C revolves within the sleeve B^1, and has fixed on at its tail end a grooved pulley D, and at its front end the wheel F from which the roller is driven.

When the outward run commences the rim pulley C^1 will be driven by the rotation of the sleeve, and the tin roller and bands will be similarly driven. The rim band C^2, however, instead of being returned to the rim pulley, is carried round the grooved pulley D adjoining C^1 on the rim shaft. The latter is therefore driven at the same speed—neglecting slip—as the rim pulley C^1 and the front rollers are driven through the wheel F. The object of this arrangement, which is working very successfully, is to ensure the spindles beginning work before any roller delivery or movement of the carriage can take place. As the tension in the bands, however, is considerable, the whole of the parts

apparently start at one time, and it is incorrect to suppose that
there is any pause between the operation of one motion and
another. It is, however, obvious that, as the power for driving
the rollers and back shaft is transmitted through the rim band,
they cannot attain their full motion while the spindles are only
rotating at part of their full velocity. It is obvious that the use
of two rims increases the power of regulating the speed of the
rollers and spindle.

(260) As will afterwards be specially described, when
very fine yarns are spun the rollers cease to deliver roving a
little before the carriage terminates its traverse, and an extra
draft is given to it. The operation is called "jacking." It is
also the practice for twisting to be continued after the carriage
has arrived at the end of its stretch, this being known as
"twisting at the head." The determination of the amount of
each of these operations is made by the peculiar setting of the
mechanism, which will be dealt with presently. The condition
of the various bands used in connection with twisting is an
important matter. It has become the very praiseworthy
practice of machinists to make all the rope pulleys used as large
as possible, the rim, carrier, and tin roller pulleys being alike
made of large diameter. In this way the operation of twisting
is improved, and the life of the rope increased. All change
wheels are also made of as large a diameter as possible ; the
reason of this being that if they have only a small number of
teeth, one tooth more or less makes a large proportionate
difference in the velocity of the part driven, and thus renders
the exact variation which is required difficult to obtain.
Thus, if the regulation of the roller speed depended upon
the changing of the pinion J^1, which has been assumed to have
19 teeth, it is obvious that a change of one tooth would have
an effect upon the velocity of the rollers much greater than
would happen if J^1 had 50 teeth. It is customary to change
the wheel G^1 when it is desired to accelerate or diminish the
rate of delivery of the rollers. The tin roller bearings require
to be kept constantly lubricated, and it is most important to

attend to the tension of the spindle bands. These, if too tight, so speedily add to the power required to drive the machine, that it is highly important they should be of absolutely the correct tension. If the pull of the bands is excessive, an increase of friction on the bearings immediately follows, while if they are too slack slipping occurs, and the correct twist is not introduced. The tension of all the bands in a mule is more or less affected by atmospheric conditions, and this is a point which ought not to be forgotten. The lubrication of mule spindles is a difficult matter and requires careful attention. Unless they are properly looked to, friction arises, and loss of power ensues. The oil has a tendency to rise up the spindle and be flung off by centrifugal action. Not only is there a loss arising from this cause, but there is a danger of oil getting on the cops. There are one or two patented devices in the way of shields which overcome this difficulty to a large extent, and which are meritorious in that respect. The setting of the rollers has been previously referred to, and it may be here said that, as in the drawing-frame, the diameter of the rollers used depends to a large extent upon the length of staple treated. Thus, Indian cotton can best be drawn by rollers $\frac{7}{8}$ inch diameter, while most other varieties can be drawn by a front roller 1 inch diameter. In setting the rollers a space should be left between the back and middle lines of from $\frac{1}{4}$ inch to $\frac{3}{16}$ inch greater than the average length of staple, and between the front and middle lines a space of from $\frac{1}{16}$ inch to $\frac{1}{8}$ inch. The reason for this procedure is obvious. The roller draft in the mule is large, taking place usually entirely between the front and middle lines, but is only used for the purpose of attenuation, and not for parallelising purposes. Thus the absolute work required can be easily carried out with the rollers set as described. The covering of the rollers should be carefully looked to, and the leather sheaths kept in as nearly perfect a condition as possible. All the remarks which were made in dealing with this point in drawing should be carefully borne in mind, and unless they are, the evils produced in drawing will be reproduced at this point.

The leather should never be permitted to become too dry, as if so, slip occurs, and the yarn will be too coarse. This matter is one of the most important details in connection with a mule, and uneven yarn is largely the result of inattention to this point. Lubrication should, therefore, be strictly looked to, so as to ensure the preservation of a uniform surface velocity between the top and bottom lines. The bottom rollers should be kept cylindrical, and, if strained, must be at once attended to. If traverse motions are fitted, they must be kept clean, as otherwise they are liable to set up such a friction on the roving as to stretch it considerably. It is easy to see that this is an attenuation not provided for in any system of drafts, and one which will only be perceptible when wrapping the yarn. The remarks made about cleanliness in the traverse guides and motion apply equally to all parts of the mule. The creel pegs and their bearings should be arranged in such a manner and kept in such a condition that the bobbins can easily and freely revolve. Cleanliness in this part is essential, and any collection of fly or dust must be avoided. Attention to a number of little points is, in brief, essential if the best work is to be produced, and although a good workman will look after these himself, they should always be borne in mind by those in authority.

(261) The points thus detailed have especial reference to the operation of spinning or twisting. As soon as the carriage arrives at, or near, the end of its stretch, or outward run, it is necessary to stop it, so as to permit of the readjustment of the parts for performing the operation of winding. It becomes, therefore, requisite to provide means whereby the motion of the rollers, spindles, and carriage can be stopped, and this is accomplished in the following manner. The driving strap is transferred to the loose pulley, so that when the roller motion is driven from the rim shaft, as shown in the preceding figures, the rollers and back shaft would be stopped. It is the practice, however, to afford facilities for the detachment of the clutches actuating the rollers and back shaft independently of each other and of the strap guide. Accordingly, on the roller shaft

a toothed clutch is fitted, one-half being formed on the wheel F
and the other half sliding on a feather key on the shaft. By
means of a ring groove the necessary lateral motion of the sliding
half-clutch is obtained, a claw fitting in the groove. This claw is
at the end of a lever which is actuated as presently described.
In some cases the clutch is arranged so that after it is in gear
a little movement of the driving half is necessary before the
roller begins to revolve, this being effected by making the
driving depend upon the engagement of pins in one half
with slots in the opposing half clutch. In other cases a
ratchet motion is employed, the pawl coming into action
a little after the carriage has started. The object of this
arrangement is to put the yarn into tension so as to avoid
"snarls," which are curls or loops caused by slack yarn.
The back shaft clutch P P¹ is also connected and disconnected
by means of a claw ended lever. It only remains to be seen how
these various levers are actuated. This is mainly the work of a
shaft M, shown in Fig. 181, with its connections, which is known
as the "cam shaft," owing to the fact that it carries several cams,
by means of which the necessary changes are made. It is be-
coming the fashion to do without the cam shaft, and to rely,
at least partially, for the operation of the parts on levers suitably
arranged and actuated. That all the requisite changes can be
made without the aid of the cam shaft is true, but, on the whole,
the latter is a convenient method of effecting them ; and, at
any rate, in principle, is not dissimilar to the other arrangements
named. The principle underlying them all is to produce the
requisite movements of the various parts by means of leverage,
so as to cause the transferral of the strap and the detachment
or attachment of the clutches at the proper moment. In some
cases the cam shaft is employed as an aid to other mechanism,
which is thus relieved from a good deal of strain. Whatever
may be the manner of its application, the object is the same in
every case. Hinged to one side of the headstock framing is a
lever T, known as the "long lever." It is by this or from a
corresponding lever that the changes are made when the cam

FIG. 181.

shaft is not used. The latter is actuated in the example shown by two adjustable brackets S and S¹, which are affixed to the carriage, and which, when the latter runs out or in, come in contact with the two bowls R R¹, placed on studs fixed in the lever. In some makes of mule, as in Fig. 182, the lever T is straight, and has affixed to it at each end brackets with angular faces which project above the top of the lever, so as to come into contact with the counter faller rod. These also are adjustable so that the lever may be oscillated a little earlier or later. This adjustment is of importance, as snarls result if the oscillation is too late, and broken ends if too soon. The effect is the same, as the lever T is in either case depressed alternately at each end, as the engagement of the bowls R and brackets

Fig. 182.

takes place. After each alternate movement the long lever is locked by the lever Q, which is constantly pressed against it by the spring O. When either movement occurs, a lever U¹, coupled to T by the rod U, is rocked so that (as shown in detached views in Fig. 181 at the left hand corner) one end of it is oscillated towards or from the cam shaft M. The cam V, against which the lever T¹ abuts, is formed with two raised surfaces, V¹ V², one being part of an outer ring, and the other part of an inner ring. So long as the lever T¹ is pressing on either of the raised parts of the cam V, the half-friction clutch W is kept out of contact with the other half X. As the latter has a toothed annulus formed on it, which engages with the teeth in the friction clutch A¹, it is constantly revolving, because, as

will be shown presently, A^1 is also in constant rotation. When the lever U^1 is oscillated, however, its end is removed from the high part of the cam surface with which it is engaged, and is brought into the lower space of the other ring or surface. The coiled spring V^3 is thus able to push the clutch W into gear with X, and the cam shaft is revolved. As the end of the lever U^1 is, however, held up to the face of one of the cam courses, and as the raised part in each is opposite that in the other— that is, at the other side of the cam shaft centre—the cam shaft can only make half a revolution before its motion is arrested by the detachment of the clutch W X. In the form of cam shaft, as in Fig. 182, where it is placed alongside the framing

FIG. 183.　　　　　　　FIG. 184.

and below the long lever, the detachment is obtained by means of a pendant plate L (Figs. 183 and 184) surrounding the shaft M, on which revolves a tubular cam shaft K. The plate L is jointed to the long lever, and is formed with a slot in it to permit of its rise and fall. It is constructed with two cam courses, O and S, against which the pin T is kept constantly pressed, by reason of the pressure of the spring U acting through the half clutch R. The clutch shown in Fig. 183 is a toothed one, but it is now customary to make it as a friction clutch, the part P being formed with an internal cone, and the other half R with a corresponding taper. The surface of R is covered with leather. The action is precisely that of the preceding case.

When the cam plate L is lifted, the pin T moves on to the lower part of the adjoining cam course, and the clutch P R is engaged. The cam shaft makes its half revolution, and the clutch is again detached.

(262) The effect of this movement is threefold. Referring again to Fig. 181, there are three cams on the cam shaft. One of them, Z, operates the back shaft clutch P P^1 by means of the lever Z^1, as shown in the detached view. The clutch, as was previously named, is usually kept in gear by a coiled spring H^2, threaded on the shaft H, and the half rotation of the cam Z presses the clutch open. Thus the back shaft is stopped and the carriage is brought to rest. A second cam course formed in the half clutch W actuates by means of a rocking lever W^1 the roller clutch F^1, which is also shown in a separate view. A third cam Y engages with a pin in the strap guide lever, which is pivoted at its lower end, and the rotation of Y—as separately illustrated—causes the strap lever G to be moved. The position of the bowl on the strap guide lever when the strap is on the loose and fast pulley is shown separately in the detached view at the lower right hand corner. In some cases the movement of the strap lever G is made by means of a separate motion, known as the "strap relieving motion," on which a few words will be said. Before dealing with this part of the subject, however, a brief description of the method of moving the strap in the mule illustrated may be dealt with. The strap guide is fixed as indicated at the upper end of the lever G, which is free to oscillate. By means of a spring attachment a second hinged lever is constantly drawn towards the strap guide lever. The second lever is fixed upon a short shaft, and has an arm on it which receives a pull from a second spring. The cam Y engages with a pin in the latter, and the spring constantly keeps them engaged. A horizontal hinged lever H, shown in Fig. 185, is attached to the headstock framing, and is drawn upwards by means of a spring P, so that a shoulder H^1 formed on it engages with a catch L fixed to the frame. Thus, when the catch is engaged any oscillation of the strap guide is impossible. The

worm C^3 formed on the end of the rim shaft gears with a
worm wheel G, which, being compounded with a spur wheel
G^1, rotates, by means of the wheel J, a small crank arm K,
the pin in the outer end of which is caused during its rotation
to press on the end of the horizontal arm H. When this

FIG. 185.

happens the latter is depressed, and the catch L is disengaged.
The strap guide lever is thus unlocked, and the springs attached
to it are free to draw it over so as to move the strap from the
fast to the loose pulley when freed by the cam. The period at
which this detachment can take place is easily regulated by
means of the gearing named, and it is obvious that by duly

proportioning the various levers the extent of the movement can be accurately regulated. It is also clear that the roller and back shaft clutches may be disengaged, while the strap, owing to the engagement of the catch with the horizontal lever, is held on the fast pulley. The cam shaft having made its half revolution the strap guide lever would, of course, be free, but could not make its traverse until the catch is released. Thus, drawing out would have ceased, the rollers would not be delivering yarn, while the spindles would be revolving for a period controlled by the detachment of the catch and lever. "Twisting at the head" can thus be effected, and its extent is entirely dependent on the difference between the time when the cam shaft moves and the catch is released. The spur wheel J on the crank arbor is practically the twist wheel when this arrangement is fitted, because its diameter determines the period of termination of the spindle rotation, but the change is more conveniently made by altering the pinion G^1 driving it. Where twisting at the head does not take place, and this contrivance is not fitted, the necessary change can be made by controlling the roller speed, which is effected by changing the pinion. For the reasons given it is desirable to make these wheels as large as possible, and thus enable slight variations to be effected. It may perhaps be stated that the cam shaft is technically said to "make the changes" when it rotates in the manner described.

(263) Instead of employing a clutch like P P^1 on the back shaft, as described in paragraph 258, it is in some makes of mule the practice to drive the back shaft by a train of wheels from the roller shaft, and to mount these in a lever having an oscillatory movement round the roller as a centre. This lever M, which is shown in Fig. 186, is known as the Mendoza lever, is centred on the roller shaft, and is oscillated by suitable means from the cam shaft or long lever. The wheel Q is fixed on the roller shaft, and drives through the intervention of a carrier wheel the wheel Q^1 compounded with which is the pinion R. R in turn drives the wheel P on the back shaft H. The communication of the motion from the roller to the

o

back shaft only takes place when the pinion R engages with the wheel P. The exact period when this occurs is, as will be understood, the same as that when the back shaft clutch is engaged—that is, immediately after the carriage has finished its inward run. During the periods of backing off and winding the lever M is raised so that the pinion R is out of gear with the wheel P. It often happens, therefore, that, as the back shaft immediately commences to revolve and draw out the carriage, a considerable strain is put upon the wheels P R, which some-

FIG. 186.

times jump out of gear in consequence. In engaging again, there is a danger of broken teeth, and this is one of the parts of a mule where there is considerable risk of damage. It is not an unusual thing to see the pinion R dance in and out of gear with P until the inertia of the carriage is overcome, and this is one of the chief objections to the Mendoza lever. There is always a difficulty in engaging a revolving and a stationary wheel, and it very often results in breakage, especially if the power to be transmitted through the stationary wheel is great. It is true that the weight of the Mendoza lever and

its attached parts is considerable, but that does not prevent this slip or failure to engage taking place. It is accordingly desirable to make some provision for ensuring that the moment the Mendoza lever falls and the pinion R engages with the wheel P it shall be locked and prevented from rising. In the arrangement made by Messrs. John Hetherington and Sons this trouble is avoided. Fixed in the Mendoza lever M is a pin M^1 which is long enough to take into an open mouthed slot S^1 in a counter-balanced lever S. S is hinged to the framing, and when left entirely free, its horizontal arm being heavier than the vertical, causes it to overbalance the latter. The result is that a shoulder formed in the slot S^1 at the point shown falls over the pin and firmly secures the lever M. As the carriage O runs in, a bowl O^1 fixed on it engages with the angular portion of the lever U and raises it, thus freeing the lever S from the sustaining effect of the tail end U^1 of the lever U. It will be noticed that a small ear S^2 on S has a screw fitted, the point of which bears on U^1. So long, therefore, as the lever U can freely move on its centre the lever S is held in position to allow the free passage of the pin M^1 into the slot S^1; but when it is raised as described the lever S is allowed to oscillate and thus lock the Mendoza. A glance at the illustration will show that it is not until the bowl O^1 passes from the angular to the straight part of U that the absolute locking of S^1 and M^1 can take place, and this is simultaneous, or practically so, with the engagement of the pinion R with the wheel P, which, as explained, occurs as the strap is transferred to the fast pulley. After the carriage has made a small portion of its outward run, the lever U is released by the bowl O^1, and the locking lever S is thus oscillated so as to free the pin M^1. By this time the carriage has gained its full momentum, and the chances of disengagement of P and R are very slight. It occasionally happens that in cleaning, the minder will run out the mule a little and then change the cam without freeing the lever U. The result is that both the back shaft and taking-in shaft are in gear, and the two sets of bands are pulling against each other, there being in this case a great danger of serious

straining of the carriage. Breakages thus occur, and to avoid these there is attached to the long lever T an arm T^1 engaging with a relieving lever V, the tail V^1 of which presses upon a small projecting piece S^4 formed on the lever S. Any elevation of the inward end of the long lever T—which is what takes place under the circumstances named—is followed by the arbitrary release of the pin M^1 and the slot S^1. Thus the chance of a breakage is practically avoided. With a contrivance of this character many of the evils usually existing with this type of gear are entirely removed. The Mendoza is raised by means of a lever X operated from the cam shaft, and can be locked in position by the small catch Y which is employed to hold it up when desired. This is very useful at times, when it is desired to clean or make adjustments of the parts. Although the Mendoza lever is perhaps more widely employed by makers than the clutch, the latter is on the whole less liable to induce breakages, and can be more certainly and smoothly put into gear. In another make of mule a very similar catch is employed to prevent the engagement of the taking-in friction, even after the cam has been changed, and in this way breakage is avoided.

(264) Before describing the operation of a strap relieving motion, it is necessary to deal with the method of operating the friction cone A^1, shown in Figs. 176 and 185. As will be seen in those illustrations, A^1 has a ring groove formed on its boss, by means of a lever engaging with which it can be moved along the rim shaft towards or away from the pulley A. Without stopping at present to enquire how this is done, it may be stated that the friction cone is always revolving, being driven (as shown in Fig. 176) by the train of wheels B^1 on the boss of the loose pulley, D^2 on the side shaft D, and pinion D^1, also on that shaft, and engaging with wheel A^1. The loose pulley is always revolving, owing to the overlap of the strap previously referred to, or, in some cases, is separately driven by a grooved pulley fixed on D. In either case, the friction cone A^1 is always revolving. B^1 having 23 teeth and D^2 55, the velocity of the side shaft D is $\frac{23}{55} \times 600 = 251$. D^1 having 14 teeth and A^1

112 teeth, the speed of A^1 is $\frac{14}{112} \times 251 = 31 \cdot 37$ revolutions—

that is, when the strap is transferred from the fast to the loose pulley, as indicated by the dotted lines in Fig. 176, and the engagement of A and A^1 takes place, A is revolved, as in the rim shaft C, at a speed of $31 \cdot 37$ revolutions. The spindles are therefore revolved at a velocity of $\frac{22 \times 6}{12 \times \cdot 75} \times 31 \cdot 37 = 460$. Their

direction of motion is, however, reversed, and is utilised for a purpose to be shortly described. The point it is desired to make is, that the engagement of the friction clutch A^1 with A, when the rim shaft is running at its normal velocity, entails the expenditure of a good deal of power to arrest the motion of the rim shaft and spindles prior to the direction of that motion being reversed. So great is that power that many spinners prefer to begin to transfer the strap from the fast to the loose pulley at a time a few inches before the carriage reaches the end of its outward run. It is also a common practice to fix on the end of the shaft D a grooved rope pulley, which is driven by a separate band from the counter shaft, thus relieving the gearing driving the backing-off friction considerably. This practice is becoming common, and the back view of a mule so fitted is shown in Fig. 187. In order to avoid confusion the same letters of reference are used for the same parts. There are many advantages in this arrangement, as there is a greater command both of the "backing-off" and "taking-in" friction clutches, and less strain is thrown upon the rim shaft. As mules are now very long the inertia of the parts is considerable, so that a reduction of the power transmitted through the belt is very advantageous. Of course when this additional driving is provided, the velocity of the side shaft D can be regulated with ease by the provision of a suitably sized pulley. Special arrangements are made to keep the bands in tension. The premature transferral of the strap involves the diminution of the velocity of the spindles, and also necessitates the abolition of the strap lever cam Y, as the work of moving the strap in

either direction is performed by the pull of springs which are brought into action by the release of catches or detents by means of levers. The result of such a transfer of the strap is to reduce the friction named to a considerable extent because the momentum of the carriage decreases more gradually, as can easily be understood. Thus, when it arrives at the end of the

FIG. 187.

stretch the power required to arrest the movement of the spindles and reverse its direction is much less than it otherwise would be. The construction of strap relieving motions is very simple, consisting of a hinged lever, which is coupled to a connecting-rod, which, in tuin, is jointed to the strap lever. The first-named lever is arranged to have one end of it so disposed as to

come into contact with a stud fixed on the carriage. The stud
is capable of adjustment, and should be set so that it will have
depressed the hinged lever sufficiently to move the strap, and
cause it to be leaving the fast pulley when the carriage finally
arrives in its outermost position, and is locked. Means of
adjustment are provided at various points in the series of levers,
so as to give them a greater or less range of action. The chief
merit of a motion of this character is the saving of wear caused
by the reduced friction of the parts. In addition, when required,
it undoubtedly relieves the cam of much of its work. It also
enables the minder to have a better control of the mule, which,
owing to the fact that the strap fork is not moved by the cam,
but by springs, is more easily stopped at any point. On the
other hand there is the undoubted fact that the amount of twist
is reduced during the time that the carriage is gradually coming
to rest. The strap being ordinarily traversed by this motion
when the carriage is from 7 inches to 9 inches from its outermost
point, the velocity of the spindles is of necessity reduced. It is
true that the velocity of the rollers is also reduced, but the effect
of the reduction in the latter case is not so great as the loss of
speed in the spindles themselves. If the relieving motion is
used, this factor should not be lost sight of. More important than
this, however, is the fact that, when it is employed, " twisting at
the head " is impossible. It is doubtful whether this alone does
not outweigh all the advantages obtained from a relieving
motion. When the final twist is put in with the carriage out,
the yarn has been drawn by the gain of the carriage, and is in
the best condition for receiving twist. Therefore, the practice
of twisting at the head—although not permissible with some
classes of cotton—possesses real advantages which cannot be
overlooked. For these reasons, although the relieving motion
undoubtedly has advantages, it possesses other disadvantages,
which should be borne in mind. Its profitable employment or
otherwise depends upon circumstances, and can be best deter-
mined by every spinner for himself. It will probably be found
most advantageous when the coarser counts are being spun,

especially when short stapled cotton is used. Before passing on to consider the next branch of the subject, it may be stated that a duplex system of driving has found extensive employment. In this case there are (see Fig. 188) two fast and two loose pulleys on the rim shaft, two belts of less width than those ordinarily used being also employed. There is thus a less range of movement required in the strap guide, and consequently less power required to move the straps, while the bite upon the pulleys is increased. On the other hand, there is the

FIG. 188

difficulty which arises when it is necessary to keep two straps uniformly of one tension. This factor is a most powerful one, and all kind of schemes have been devised to overcome it. Straps have been specially constructed from the same hide in order to get a similar strength and structure, but the trouble of unequal tension is only partly overcome. From this cause there is a loss of power, which has an important bearing on this matter from the commercial point of view. It is also alleged that the starting of the mule is made too rapidly, thus giving

too great a shock. There is, however, the fact that the strap is moved more quickly, and in beginning to "back off" this is a matter of great advantage.

(265) The cessation of the whole of the motion of the parts having been accomplished it is now necessary to obtain the backward movement of the spindles which has been referred to, this being known as "backing off." The reason of this procedure is as follows : A cop is built or wound on to the spindle in gradually ascending coils which, as will be hereafter fully explained, are at first laid only upon a certain part of the length of the spindle, and are subsequently wound on the further portion of it so as to cover the greater part of the blade. As the yarn passes over the point of the spindle it is coiled round it in coarsely-pitched spirals until it finally reaches the nose of the cop, whatever may be the position of the latter. Reference may be made to Fig. 189 to elucidate this point. It has already been explained that the coils are put on the spindle by its revolution when twisting the yarn. It is obvious that if the yarn be held at both ends and the spindle is revolved it will wind itself tightly on the latter in coils which will have a pitch controlled by the length of yarn and diameter of the spindles. It is quite clear that if the yarn so wound on was drawn upwards, or if the motion of the spindle was reversed, the coils would be unwound and the yarn freed. It is not possible in the mule to take the first of the two courses named, and it is accordingly the practice to take the second. Thus the coils shown in Fig. 189, while formed by the rotation of the spindle in one direction, are released by its revolution in the other. As it is necessary to commence winding at a point a little below the upper end of the cop, the yarn must be depressed from the line it forms between the rollers and spindle during spinning to a line drawn from a little below the nose of the cop to the rollers. It is clear that if the yarn remained coiled on the spindle blade between its point and the nose of the cop it could not be forced down in the manner described. Thus it is essential that between the moment when the movement of the various parts ceases

and winding begins, the length of yarn which, as described, is on the spindle blade, must be released. It is obvious that the length to be unwound is never very great, and is gradually reduced, so that the operation only lasts for a very short period, which renders the shape of the friction cones a matter of impor-

FIG. 189.

tance as affecting its easy engagement and disengagement. Backing-off is effected by the engagement of the friction clutch A¹ with the pulley A when the strap is on the loose pulley B. In order to make this movement clear, reference can be made to the diagrammatic illustration given in Fig. 190 (p. 427). It may be explained that this diagram represents the

mechanism opened out, that which adjoins one side of the framing being shown at one end of the drawing, and that which adjoins the other side at the other end, although in actual practice they are parallel to each other, as shown in the diagram of positions on the right hand top corner in which the carriage O is shown at right angles to the headstock as it really is. The contact between the two parts of the clutch A A¹ is established by means of a movement given to a vertical lever D, which is fixed, as shown in Fig. 185, on a short arbor placed above the groove in the boss of A¹. On the same arbor, which is free to oscillate, is a claw lever engaging

FIG. 190.

with the ring groove, so that the oscillation of D in either direction engages or detaches the clutch A¹. The lower end of D is arranged so that it passes over a rod X. which is guided by suitable brackets attached to the longitudinal framework of the headstock. On the rod X are two stop hoops X¹ X², and between X² and the end of the lever D a spiral spring is threaded on the rod, Fig. 190. The backing-off lever D has a pin fixed in it which engages in a slot formed in the horizontal catch lever controlling the movement of the strap. It is essential that the transferral of the strap to the loose pulley shall be nearly simultaneous with the backing-off, but it is equally essential that the

latter operation shall not possibly precede the former. In order to give the requisite power to push over the lever, the spring on X is put into compression a little before the strap is moved. This is effected by means of the lever V, which is hinged on the carriage O, and has a constant pull exercised on it by the spring V^1, so that it presents its open mouth to the end of one arm of the lever L pivoted on a stud attached to the headstock. The lever V is, from its shape, called the "shark's jaw" or "fish jaw" bracket. The upper end of L is jointed to the backing-off rod X. When the carriage runs out the bowl at the end of the horizontal arm on L engages with the angular portion of the mouth of V, and the lever L is thus oscillated so as to compress the spring on X. As soon, therefore, as the horizontal strap catch lever is released, as described in paragraph 262, the spring, which has previously pushed over the backing-off lever D as far as it can move, continues the forward motion, and so brings the backing-off friction A^1 into contact with A^2. It is important to note that the backing-off lever must be actuated so as to gradually establish the contact between the backing-off friction cones. Two objects are served by this. In the first place, the friction is considerably reduced, and the heat arising from it is to a great extent avoided. It should, however, be stated that, owing to the large diameter of the backing-off friction which is now adopted, the power exerted is better applied and the spindles are gradually but rapidly brought to rest prior to their reversal. This is the second object aimed at. As soon as backing-off commences and the yarn wrapped between the nose of the cop, and the point of the spindle is being released it becomes necessary to take up this portion of it so as to preserve the tension existing in each length. If this object is not attained the twist in the yarn would cause it to run into little kinks or loops, known technically as "snarls." The manner by which this is effected will now be described, reference being made to Fig. 191.

(266) The thread is guided by means of a wire N fixed in the ends of sickle-shaped arms, which are fixed, at intervals, on

a longitudinal rod B, which can be freely oscillated.   As de-
scribed in paragraph 253 this wire is known briefly as the
" faller." The arms are, from their shape, spoken of as
" sickles," and the rod as the " faller rod." There is also a
second set of sickles which sustain the " counter faller " wire M ;
the former being fixed on the " counter faller " rod B¹. It is,
perhaps, necessary to say that the winding and counter fallers
extend along the whole length of the carriage, and should be kept

FIG. 191.

straight throughout their entire length. It will be noticed that the
counter faller presses against the underside of the yarn so as to
divert it from the direct line between the rollers and the cop.
The winding and counter faller rods are set quite parallel with the
centre of the tin rollers, and when the carriage is at its innermost
point the same parallel relation should exist between them and the
rollers. It was stated in the last chapter that the object of the
counter faller wire was to take up the yarn as it is delivered from
the spindle during the process of backing-off. The maintenance

of the required pressure to sustain the whole of the threads in
the manner described, entails the freedom of oscillation of the
counter faller rod, and also necessitates the balancing of the
counter fallers so that they will easily yield when anything above
the normal pressure is put upon them. The action of the
counter faller is in brief a negative one, and is practically that
of a compensating motion. The object of the winding faller,
on the other hand, is to press down the yarn to the required
point for the commencement of winding, and subsequently to
guide it in such a way as to enable it to be wound on the cop.
It becomes therefore essential that the motion of the winding
faller shall be rigidly controlled, and for that reason it is
attached to suitable mechanism. There is, however, a co-
relation between the two fallers, and it is necessary to use
such means as preserves this. On the counter faller rod
B^1, Fig. 191, a curved sector E is fastened, which has
attached to and passing over it a chain E^1. This is fixed at its
lower end to a weighted lever J, which is hinged to the under
side of the carriage O. The weight of J is sufficient, when the
counter faller rod is free, to oscillate it, but ordinarily the weight
of J is taken by a second chain or band I, which is attached to J
at a point nearer its fulcrum. I is fixed to a hook attached to
a bracket S fastened on the winding faller rod B. This bracket
is formed with a stop resting on the counter faller rod, and is
normally pulled in that direction by the spring V. The result
is that the extent of the upward movement of the winding faller
is regulated. As "backing-off" proceeds the winding faller
slowly descends, and the chain I is thus by the oscillation of
the bracket gradually slackened until a point is reached when
the lever J is free to exercise a pull on the chain E^1, and thus
cause the counter faller to press on the underside of the threads.
By means of the angular slide Q, the weight lever J is lifted
just before backing-off when the carriage is at the end of its
stretch, and the bowl W can be similarly adjusted, if desired,
at the other end of the stretch. The regulation of the weight
of the lever J is very important, and it is arranged to be readily

increased by the addition of small balance weights. The state
of equilibrium established depends entirely upon the yarn being
spun, and must be carefully regulated for that purpose. For
fine or delicate yarns the counterpoise must, of course, be more
exact than when stronger yarns are being spun, and a little
practice will speedily enable the correct results to be attained.
It is easily possible to adjust the balance so that a few threads
in extra tension will depress the counter faller, and this is one
of the small points which require constant attention.

FIG. 192.

(267) We now come to deal with the method of actuating
the winding faller, and this brings us to the consideration of a
very important portion of the whole operation. The winding
faller rod B has pivoted to it an arm D (see Fig. 192), which is
curved at one end so as to pass over the counter faller rod B^1,
and thus forms a sector C, which is jointed at C^1 to the
"locking" lever A—or "boot-leg," as it is sometimes called.
A chain D^1 is fastened to the outer end of D and passes over
the pulley F, borne by the lever F^1, being attached to a snail or
scroll K mounted in the tin roller shaft. The snail is geared
by means of a ratchet clutch in such a manner that it is only
revolved when the tin roller is reversed during backing off. The

effect of this arrangement is that the moment the tin roller
shaft begins to run backward, the chain D^1 is wound on the
snail K, and thus draws down the backing off finger D.
This raises the locking lever A, and at the same time
necessarily depresses the winding faller. As soon as the latter
reaches the point which it should occupy at the commencement
of winding, the shoulder A^1 is pulled over the bowl carried
at the end of the lever L, called the "trail" lever, which
is hinged to the carriage, as shown. In some cases a small
slide or bracket is used instead of the trail lever, but
the effect is the same. L carries a small bowl L^1, which
rests on the top of a longitudinal rail P, along which it
is traversed by the movement of the carriage. As soon as
the engagement of R and the bowl in L takes place, the
"locking" lever and winding faller are said to be "locked,"
and the commencement of winding is possible. It should be
noticed that during the time the locking lever is being raised
the counter faller balance weight is being released, so that
simultaneously with the descent of the winding faller, the
counter faller is raised by the action of the lever J. In many
mules this is all the mechanism which is provided, but in the
special arrangement which is illustrated in Fig. 192, there is
provision made for an adjustment of the position of the faller
wires. It can be readily understood that the number of revolu-
tions to be made in a backward direction by the spindles during
backing off will vary with the position which the winding faller
must assume at the beginning of winding. Further, backing
off commences a little in advance of the full depression of the
faller, so that there is a short length of yarn unwound before
the faller presses on it. The ratio of this prematurely released
yarn to the whole is greatest near the termination of the cop,
and gradually increases as the cop is built. For these reasons
it is necessary to expedite the movement of the faller so as to
cause its engagement with the yarn at the earliest moment. At
the commencement of a cop the distance traversed by the
winding faller is greater than at its termination, and it is locked

at an earlier moment, because the subsequent descent of the copping rail raises the initial position of the faller. The amount of lagging in the winding faller which is permissible when a cop is being commenced is absolutely detrimental when it approaches its conclusion, because the ratio of this retardation to the total traverse is much greater in the latter case. It is, therefore, absolutely necessary to draw the winding faller down at an earlier moment and at a quicker velocity. In order to effect this, a lever H is pivoted to the carriage, and can oscillate within the limits shown by the dotted lines in Fig. 192 on a stud fixed to it, having its range of motion controlled by a claw, the two horns of which engage with a stop H¹, fastened to the carriage. The vertical arm of this lever carries a bowl N¹ which engages with the top of a bracket N, which is gradually pushed under it, as afterwards described. The horizontal arm has attached to it a rope or chain which gradually winds on to the snail the backing-off chain. Thus the latter is gradually tightened, and from being quite slack at the commencement of a set of cops, is drawn into complete tension at the termination. In this way the required expedition and acceleration of the descent of the faller are obtained.

(268) As soon as the faller is locked, the period of backing-off is at an end, and the parts want adjusting for winding, but it should be stated that the carriage is locked while at its outermost point, and must be released prior to the beginning of its inward run during winding. In order to illustrate this, the diagram in Fig. 190 may again be referred to. On the carriage O is a bracket O¹ in which a stud O² is fixed, with which the end of the horizontal arm S¹ of the bell crank lever S can engage. As will be seen by referring for a moment to Fig. 197 the catch O¹ is a pin capable of adjustment by the screw shown. The lever is jointed to the horizontal rod R, which is coupled to a second lever U¹, also free to oscillate. U¹ is attached by the connecting rod U with the lever W, and the latter is connected to the horizontal arm of Z¹ by the rod M. Thus a connection is set up between the cam Z, which controls the back shaft

clutch P, and the "holding-out catch-rod" R.   When the carriage is running out, and has nearly arrived at the termination of its outward run, the movement of the rod X, obtained in the manner described in paragraph 265, causes the lever Y to be oscillated on its pivot.   There is a short arm Y^1 formed on Y, which is pushed under the end of W^1 of the lever W, and acts as a support for it and the top conical dish I^1. W^1 is forked, and has pins fixed in the fork which project into the ring groove in the dish I^1, thus controlling and sustaining it.   When the carriage arrives at the end of its outward run, the cam Z makes a change and detaches the clutch P on the back shaft H. Previously to that period the rod R is free, so that the catch on S easily rises and falls over the pin in O^1, thus locking the carriage securely.   It will be seen that at the moment of locking three things happen : the carriage is locked, the dish I^1 is locked so that it cannot fall into gear with K, and the backing-off friction is being pushed over by the spring on X, as previously described.   The carriage can be locked at the end of any stretch by the pedal lever fixed to the floor.

(269) We have now reached the fourth period—that of winding, in which the nicest mechanical problems existing in the mule are found.   At the moment when backing-off is finished, the parts are in the following position : The strap is on the loose pulley ; the backing-off clutch is in gear ; the spindles are revolving in a backward direction ; the winding faller is locked in a position a little below the nose of the cop ; the counter faller is held just out of contact with the threads, but is released as soon as the carriage moves in ; the roller and back shaft clutches are disengaged, and the upper half of the friction clutch I^1 K is out of gear with the lower, but is revolving with the shaft on which it slides.   It is, therefore, necessary, in order to commence winding, for the following things to be done : the backing-off clutch must be disengaged, the carriage must be unlocked, the friction clutch I^1 K engaged so as to give motion to the bands which draw in the carriage, the counter faller released, and the spindles revolved at a velocity sufficient to

take up the length of yarn as it is freed by the run in of the carriage. These different steps will be treated in the order named, and in doing so we shall deal with several problems arising.

(270) It should be noted that when the whole of the yarn has been unwound from the spindles and taken up by the faller the function of the backing-off clutch is finished and it may be detached. As the backing-off chain draws down the backing-off finger D it can freely move, but as soon as the locking lever is ready for locking, the continued movement of the backing-off finger ceases, and the chain draws in the upper end of the lever V, and by means of the connecting lever F^1, also pulls in the lever A and thus locks it. This same movement withdraws the mouth of the lever V from the end of the lever L, and when the sudden inward motion of the locking lever is made, the pressure of the lower jaw of V causes the lever L to be moved in the direction of the arrow. The result is the disengagement of the backing-off clutch by reason of the pressure of the stop X^1 against the lever D; the motion of the rod X being aided by the extension of the spiral spring threaded on it. The movement of the rod oscillates the lever Y and takes away the supporting arm Y^1 from under the end W^1 of the lever W. In this way the dish I^1 can fall into contact with the lower clutch K. It is imperative that the dish I^1 shall fall into gear with K as soon as backing-off is completed, and for this reason it is always so held that the release of a stop is all that requires to be done. There are many modifications of the mechanisms which is used for this purpose, but they all proceed upon the same principle. The dish is held in suspension by a suitable lever and stop, upon the removal of which the engagement takes place. In one instance an attempt has been made to do away with the dish clutch, and use a movable strap on two pulleys fixed on the side shaft, but in this arrangement there is not the element of sudden contact, which is of great value. The fall of the end W^1 of the lever W is aided by the pull of a spring Q, which is attached to the arm of the backing-off

clutch lever T, which rests on a stop fixed in the horizontal arm of the lever Z^1. In order to permit of this movement of the lever W on its centre there is a slot in one end of the connecting rod M, which is sufficient to allow of this motion without affecting that of Z^1. By means of the connecting rod U, lever U^1, and holding-out catch rod R, the motion of W is communicated to the holding-out catch S, and thus unlocks the carriage. It is obvious that the backing-off friction and the holding-out catch must be nearly simultaneously released, and that they must be quite free before the taking-in friction engages, as otherwise there would be breakage. Thus there are many points of adjustment provided. The stops X^1 X^2 can be set as required, the connecting rod M, coupling Z^1 and W, can be also adjusted, and the holding-out rod is also arranged to be regulated. The effect is that immediately after the release of the carriage and the detachment of the backing-off clutch, the taking-in clutch I^1 K is engaged, and the carriage begins to run in.

(271) The shaft I (Figs. 176, 177, 187), on which is mounted the friction clutch I^1, is driven from the side shaft D by means of the bevel wheels S S^1. The lower part of the half clutch K is formed as a pinion K^2, which engages with the wheel K^1 fixed on the shaft L, called the "scroll shaft." At one time it was the custom to make this clutch with teeth (as shown in Fig. 174), and there are still some mules working with this type. The advantages of the newer form, however, are so manifest that it may be fairly said that toothed clutches are becoming obsolete. On the latter are several scrolls L^1, which vary in diameter from 9 inches in the largest to 3 inches in the smallest portion. To these scrolls are fastened ropes or bands, attached to the carriage, so as to draw it in when the shaft L is suitably revolved, which it is when the "taking-in" clutch I^1 K is in gear. Assuming the wheels S S^1 to have 28 and 31 teeth respectively, and the pinion on K to have 20 teeth, while K^1 has 80, then the speed of the shaft D being 251 revolutions (paragraph 264),

L revolves $\frac{28}{31} \times \frac{20}{80} \times 251 = 56 \cdot 6$ revolutions. Thus it will com-

municate to the drawing-in bands when they are on the largest diameter a speed of 1,600 inches per minute, and when on the smallest diameter a velocity of 532 inches per minute. The carriage is, of course, started at its slowest speed, and also finishes at about the same velocity, attaining its highest rate of traverse at about the middle of its course. It is thus brought evenly and easily to rest. The curve of the scrolls is carefully formed, in order that the acceleration and diminution of the the carriage speed may be obtained without any jerkiness or irregularity, it being important that these should be avoided. The formation of the scrolls is a problem of some nicety, looked at from a mechanical point of view, but, as they are usually fixed by the machinist, the method of making them does not belong to the operation of spinning. There is fixed on the scroll shaft an extra scroll L^2, which is set at an angle of 180° to the others, and which, being fitted with an extra band, which is naturally diametrically opposite that of the remaining " scroll bands," is wound on when they are unwound, and *vice versâ*. The object of this " check band " is to exercise a drag and avoid over-running of the carriage, which it can be easily understood may readily occur owing to the high and varying velocity of the carriage traverse. The scroll shaft only extends across the head-stock, and the pull exerted by it is consequently confined to a limited space. It is therefore the custom to fit an extra scroll L^3, which is connected by a band to the scroll H^3 on the back shaft H, on which it is wound, as the latter is revolving to draw out the carriage. When the scroll shaft is rotated—at which time the back shaft is free—the latter, which extends behind the carriage for its whole length, having scrolls at intervals, is converted into a taking-in shaft, and powerfully aids in drawing in the carriage without deflection. It will be noticed in Fig. 187 that the end bands have means of adjustment. These are provided in order to enable the carriage to be "squared," as it is called—that is, drawn into such a position that the centre line through the points of the spindles is parallel with the rollers. As this is a most important matter, it is proposed to spend a few

words on it. The bands, being made of cotton, are, of course, liable to stretch, and if one of them elongates more than the others, it will follow that the carriage will have a varying pull exercised on it at different points. The effect of this is, that when it is being drawn in its great weight causes it to deflect from a truly straight line, and the result is that the yarn is neither so evenly drawn or wound as it ought to be, the tension on the different ends not being the same. It is absolutely necessary for good work that this departure from perfect alignment should be obviated, and it is essential that minders and overlookers should keep a sharp eye on this defect. The check bands require considerable adjustment to make them work smoothly, so that the carriage when it comes against the back stops, will come up gently, and not with a bang. There is, towards the end of the inward run, owing to the greater pull of the winding chain, more resistance to the inward movement of the carriage, and this tends to stretch the check bands. There are two principal faults arising from an imperfect adjustment of the check band. The carriage either comes against the back stops violently, or pauses a little before doing so. The result is that in the first case the threads will be snarled or broken, in the second case winding takes place at such a tension that the ends are broken. This matter of the stretching of the scroll bands is a most material one if good work is wanted, as it will be shown hereafter how very important it is to have the tension on every thread equal, which cannot happen if the carriage is out of alignment. The length of mules is now so great that difficulty is sometimes experienced, and the longer the mule the greater the trouble. An increase in the diameter of the end bands shown in Fig. 179 would probably be attended with good results in the case of very long mules.

(272) It is now possible to deal with the problems underlying winding. It has been shown that the carriage is drawn in at a variable speed, and that in so doing it releases the yarn held in tension between the spindle point and the rollers. This it is necessary to wind on the spindles, and in order to make quite

clear the nature of the problem thus stated, the construction of
the cop must be understood. For this purpose a reference to
Figs. 193 and 194 may be made. The cop is shown as a
cylindrical body or spool, formed with conical ends of different
tapers. The part indicated by the letters B, G, J, E, is nearly,
if not quite, cylindrical; while to the bottom and top of these
are cones A, B, E, F, and G, H, I, J, respectively. The cop is

FIG. 193.   FIG. 194.

wound into this shape by wind-
ing upon the spindle successive
ascending layers of yarn. At
first the yarn is only traversed
along a short part of the spindle
in closely pitched coils, the whole
of the first stretch being wound
within a vertical space of about
an inch. The next length of
yarn is wound upon that pre-
viously laid, and the initial point
at which winding begins is
gradually raised. It has been
previously pointed out that the
winding faller, when locked in
position ready to begin the
guidance of the yarn on to the
cop, is a little below the "nose"
or uppermost point of the latter.
As soon as winding begins, the
first movement of the faller is
rapidly downwards, so as to
lay the yarn upon the nose of the cop in widely pitched spirals,
as illustrated by the coarsely broken and rapidly descending
lines shown in Fig. 194. As soon as the winding faller reaches
the base of the top cone for the time being, it begins to rise at
a more gradual rate, and so allows the yarn to be wound in the
finely pitched spirals also shown in the same figure. The full
length of each stretch of yarn is wound by the time the winding

faller reaches the uppermost point at the nose of the cop. After the first layer or two have been wound, the initial position of the faller wire is gradually raised, and its traverse slowly increased until at last that portion of the full cop, as shown by the letters A, B, C, D, E, F, is formed. This is known as the "cop bottom," and some idea of the actual method of altering its shape is shown by the angular lines. After the cop bottom is fully formed, the traverse of the faller wire is gradually shortened until the angle of the nose C, H, I, J is a little more acute than that of the cone B, C, D, E. The length of the traverse of the winding faller is called the "chase" of the cop.

(273) It is evident that we are at once confronted with a problem similar in principle, although varying in character, to that which was dealt with in connection with the roving frame. We have to provide for winding each length of yarn spun on to a surface of varying diameter while the delivery of it remains constant, because even if the speed of the carriage varies at different times during winding the velocity of the spindles experiences a corresponding variation. It will, on the whole, be better to deal with the actual mechanism employed to perform the winding and the principles on which it rests before dealing with the method of traversing the winding faller. The mechanism employed in winding is shown in Figs. 195 and 196, to which reference may be made. The winding chain or band C is attached, at one end, to the scroll X^1, and at the other is attached to a small barrel E. The latter is carried by a slide A, which is fitted to the face of the oscillating arm or "quadrant" M, and has fastened to it a nut threaded upon the screw P. It is clear that if the latter is revolved in either direction the nut will be correspondingly traversed along the arm M. At the lower end of A a pulley D is carried, which serves to act as a guide for the "winding chain" C. The arm M has formed on it a quadrant rack M^1, with which a pinion Z engages, Z receiving its rotation from the back shaft H, as the carriage moves, by means of the band shown. Thus the motion of the arm M in either direction is entirely controlled by that of the

FIGS. 195 AND 196.

carriage O.   On the lower end of the screw P a bevel pinion is
fixed, gearing with a similar pinion on the arbor or spindle on
which the grooved pulley P^1 is fastened.   On the scroll shaft X,
which is carried by suitable bearings, a wheel X^2 is fixed, gearing
with a pinion V^2 on the tin roller shaft T (see Figs. 195, 197,
and 198).   The pinion V^2 is in one piece with a disc V loose
upon the shaft T, so that any rotation of the disc has direct
driving power on the shaft.   The disc V has fixed on it at one
point a pin on which a small catch or " click " V^1 is hinged.
The " click-catch " is formed with a forked end, against one side
of which the end of a bent " click-spring " W^1 ordinarily presses.
W^1 is formed so as to surround and clip the boss of the disc V,

FIG. 197.

and the pressure of its free end is ordinarily employed to
hold the " click-catch " out of gear with the " click-wheel " T^1.
When, however, a slight oscillation of the " click-spring " in the
backward direction occurs it causes it to engage with the
wheel T^1, and so rotates it. T^1 being fixed on the tin roller
shaft T, the latter is also rotated, and so communicates motion
to the spindle.   The action of these parts is as follows : As the
carriage O is drawn in, the quadrant arm M begins to move
forward, and a pull is at once exercised on the winding chain.
A rotatory movement is at once given to X^1, and the disc V is
moved a little forward, thus engaging the click-catch with the
wheel.   The subsequent pull upon the chain continues to rotate

the scroll X^1 and wheel X^2, and consequently the tin roller shaft T. The spindles are thus revolved, and by the arrangements previously named, run at such a velocity as just to take up the yarn as it is released. The arrangement just described is the ordinary one, but the method of engaging the click-catch is somewhat defective. It will have been seen that only when the disc V is being rotated in the manner described is the click-catch in gear. As soon as the completion of winding takes place, the spring W^1 acts upon the catch, and takes it out of gear. The tin roller shaft can then be rotated entirely independently

FIG. 198.

of the winding scroll X^1, from which the chain is withdrawn during the forward movement of the quadrant arm M. It may happen that when backing off is complete, the nose of the click-catch may at one time be in close contact with the face of the tooth in the click-wheel with which it must next engage, or it may be only just over the point of the preceding tooth. In the first case, the rotation of the tin roller would take place immediately the scroll X^1 began to move, and in the other it would not begin until the catch had time to fully engage with the next tooth. In the mean time the traverse of the carriage

would release a little of the yarn, and in hard twisted yarns the result is the production of "snarls" which are drawn on to the cop. In order to avoid this difficulty a lever W is placed on the tin roller shaft, and the spring W^1 fits on the boss of this lever. A spring W^2 exercises a pull on W when the latter is pushed back. If the lever W is oscillated, it causes the spring to press the click-catch into gear, aud this movement is obtained by means of a stop R^1 on the holding out rod R. When the catch is released the movement of the rod R causes the oscillation of W, as shown by the full lines, and thus ensures the engagement of the click-catch. As soon as winding is finished, and the holding-out rod assumes its normal position in consequence of the movement of the cam, the weight of the tail end of W causes it to again assume a perpendicular position, and so disengage the click-catch. It is obvious that the stop R^1 can be easily set so as to cause the full engagement of the click-catch prior to the commencement of winding, so that there is an equal celerity in commencing winding at every stretch. The arrangement just described varies from the preceding one in the fact that the click-catch is put in by an actual movement prior to the commencement of the run in of the carriage, while in the older method it was engaged in consequence of that movement.

(274) There are two additional points to consider in relation to this part of the subject. The first is the manner of rotating the screw P, and the second the method of obtaining the required terminal velocity of the spindles. The small pulley P^1 (in Fig. 195) is, as shown, traversed by an endless cord or band Q, which is taken over small carrier pulleys, and a large carrier fixed, as shown, and also over two pulleys S S^1 sustained in bearings attached to the carriage. If the whole of these pulleys are free to revolve, the motion of the carriage in either direction has no effect upon the cord Q, but if any one of these is held, then the cord is locked and will receive motion. The pulley S has affixed to it a winged wiper or detent, which is formed with three teeth with straight faces. If, therefore, a

catch is presented in the path of these teeth during their rotation, and the pulley S prevented from rotating, the cord Q will receive a longitudinal motion which will be communicated to the pulley P¹. In order to effect this, a lever Y, with a downwardly projecting arm Y², is hinged to the carriage O, and is sustained by a chain Y¹, one end of which is attached to an arm U, on the faller shaft B, and the other to an arm U¹, on the counter faller shaft B¹. The position of these arms is, of course, controlled by the oscillation of the faller shafts, as previously described. It is clear that if the two arms be depressed sufficiently, the downward arm Y² on the lever Y will engage with the winged detent on S. And it is equally obvious that the engagement or non-engagement of the detent depends solely upon the relative position of the arms U U¹. The outward movement of the nut only takes place during the time the cop bottom is being formed. After every layer of yarn has been wound, the nut remains in the same position until the next layer has been begun. The alteration in the diameter of the cop, consequent upon the winding of the last layer, increases the speed at which the yarn is taken up, and consequently puts it in considerable tension. The degree at which the diameter increases varies, of course, with the yarn being produced, coarse yarns necessarily giving a more rapid increase. The result is, however, that the initial velocity of the spindles becomes too great after a certain thickness of yarn has been laid, and establishes the tension spoken of. In consequence of the manner in which the counter faller is balanced, it yields to this tension, and thus slackens the chain Y. The result is that the arm Y² falls into contact with the catch on S, and prevents the pulley from turning. Thus the cord Q is held between S and S¹, and is traversed. The pulley P¹ᵣ, at the foot of the arm M, is rotated, and in consequence the screw P is turned by means of the bevel wheels shown. The bevel wheel on the spindle of the pulley P¹ is held by a brake spring P², which clips its boss and prevents it from rotating with the forward motion of the quadrant, causing the pinion on the screw to roll round it. When the cord Q is moved,

as described, it overcomes the resistance of the clip, and rotates the pulley and bevel wheel. When the winding faller is depressed at the commencement of a set of cops its position is lower than at subsequent periods, and consequently it requires a greater elevation of the counter faller to disengage the catch Y^2 than at later stages. In either case the effect is the same. The advance of the nut from the centre gives it a little greater movement horizontally, and so decreases during the early portion of the carriage traverse the velocity of the spindles. The tension on the yarn is thus released ; the counter faller rises, and draws the catch Y^2 out of contact with S, thus causing a cessation of the traverse of the nut. When the locking point of the winding faller has been raised to that necessary when the cop bottom is finished, the elevation of the arm U is sufficient to prevent any further engagement of the catch Y^2 with S. This it will be seen is simultaneous with the arrival of the nut at its outermost point. From the fact that this motion is intended to regulate the velocity of the spindles during winding it is called the " governing " motion, or, on account of the use of a band or strap to give rotation to the screw, a " strapping " motion. Although on the whole this motion is an effective one it is not without fault, and it is often found that the traverse of the nut is not quick enough to preserve the correct tension. It will have been observed that the motion of the nut takes place when the winding is actually in operation, and that the tension must be put upon the yarn before governing occurs. It has been accordingly attempted by various devices to obtain the required motion of the nut during the time that the quadrant is making its backward stroke. In either case the regulation is made from the fallers, and the relative elevation of these regulates the period during which the nut is traversed. It is essential that the yarn shall neither be stretched too tightly or be too slackly wound, and this is a point which requires care and watchfulness on the part of the minder. It is questionable whether any automatic motion will ever be an entirely efficient substitute for this vigilance, and a good minder is able

to keep his yarn in very even tension throughout a set of cops by occasionally regulating the position of the nut, by means of the handle shown. It is, of course, much to be preferred if an efficient automatic motion can be substituted for a manual operation, but there is generally some difficulty about this, and it is troublesome to obtain. The skill of the minder is, in mule spinning, at least, of great value, and will probably always remain so. If Fig. 196 be observed, it will be seen that the screw P has a rapidly decreasing pitch. Thus, one revolution of the screw, when the nut is near the centre, will move it more rapidly outwards, and this enables the relatively rapid increase in the diameter of the cop at this point to be compensated for, the regulation of the initial velocity being thus accurately accomplished. As a consequence of this construction, the nut is made with a finger which enters the thread, so as to give it perfect freedom when the screw rotates.

(275) Every layer of yarn wound is necessarily of uniform length, and, as shown in Fig. 194, is distributed in ascending coils on the cop for the greater part, and in descending coils of coarser pitch for the lesser portion. It is also wound throughout on varying diameters, except so far as the first layer is concerned. For the present the taper of the spindle blade will be disregarded. The yarn is supposed to be of uniform diameter, and as the successive beds upon which it is wound, after the cop bottom is fully formed, are uniform, it follows that alike in the ascending and descending coils the pitch is respectively similar. The speed of the cop ought, therefore, to be in inverse ratio to the diameter both in the upward and downward movement of the yarn, and the ratio remains substantially uniform during the building of the body of the cop. In other words, throughout the winding of the several layers there is a uniform acceleration of the speed of the cop during the ascent of the faller. During the descent of the faller this variation is not so noticeable, for the rapid motion given to the faller makes the spirals of a very coarse pitch, thus giving a tight winding of the threads which causes

them to act as binders. The variations in the velocity during the upward motion of the faller can be graphically shown by hyperbolic curves, constructed by means of ordinates representing the number of turns which, for any given length of yarn wound, are the reciprocals of the circumferences—that is to say, the quotient of any given unit divided by the circumference of the cop at various points. When the first layer is wound on the spindle little variation of speed occurs, but with each fresh

Fig. 199.

layer the differential action takes place, increasing until the cop bottom is fully formed, after which it remains uniform. There is an easy method of discovering the relative diameters of the cop at any part of the cone. This is illustrated in Fig. 199, and consists in producing the sides of the cone until the lines meet at its apex. Then if X equals the length of the truncated cone, and Y that from the point of truncation to the apex, the full length is X + Y. If a equals the diameter at the large end or base, and b that of the truncated

point, then $Y = \dfrac{b}{a}(X + Y)$.   A cop is, of course, a truncated
cone at that part where winding takes place, as shown in Fig.
193.   If the full diameter be assumed to be 1 inch, the diameter
of the spindle $\frac{3}{16}$ inch, and the length of the conical portion
2 inches, then the length of the part Y of the cone is $Y = \frac{3}{16}$
$(2 + Y) = \cdot4615$, and of the whole cone $2 + \cdot4615 = 2\cdot4615$.
If any distance be selected from the apex or from the point of
the cop, it is easy to calculate the diameter of the cop at that
point.   Thus if a point $\frac{3}{4}$ inch from the nose of the cop be
selected, the distance from the apex is $\cdot75 + \cdot4615 = 1\cdot2115$
inch.   If x be the required diameter at any point, at say y
distance from the nose, then by the formula $Yx (Y + y) b$ the
diameter can be obtained.   If in this way the diameter be
calculated at the various positions, a curve can be described
which will graphically indicate the relation of the velocity
required to the diameter.

Let it be assumed that the cone of the cop is of the dimensions
given, 1 inch at its largest diameter, $\frac{3}{16}$ inch at the nose, and
2 inches long.   Its diameter at a point midway between the
base and nose would be $\cdot5922$ inch.   If it be also assumed
that the stretch is 64 inches the number of revolutions at that
point to wind that length will be $\dfrac{64}{1\cdot86} = 34\cdot4$.   Where the cop
is 1 inch diameter the number of turns required would be only
$20\cdot4$, while at the point they would be as nearly as possible
$108\cdot55$.   It has been shown that the yarn is first wound in
quickly descending and part in more slowly ascending spirals.
In the whole stretch of 64 inches suppose that one-eighth
or 8 inches is laid during the downward movement, and
seven-eighths or 56 inches during the upward motion.   The
downward layers are neglected in the demonstration which
follows, because they are not wound under the same con-
ditions as the upward coils ; but in Fig. 200 the nose of
a cop of the dimensions given is represented.   This is
divided into 10 parts, and the required number of turns cal-

P

culated to wind on at any of these points the same length of yarn. The points are numbered 1 to 10, and on the horizontal line A B ten equal divisions are also made. On each point or division ordinates are erected. By cutting these ordinates to any scale by the reciprocals of the circumferences, or by a length representing the number of turns required, a curve can be drawn which represents the variation in the bobbin velocity. It is clear that the acceleration ought to take place at a quicker rate during the downward winding when much fewer coils are laid, but owing to the rapid descent, which crosses the yarn on the

FIG. 200.

nose and thus avoids the necessity for a variation in speed, the speed of the spindle is not at this point varied.

There are two points which principally affect this problem. These are—(1) the variation in the speed of the spindle and cop necessary to wind the yarn properly on different parts of the cone; (2) the proper regulation of the movement of the guide or faller wire. The first point involves the action of the winding quadrant throughout the period of building, which, however, can be considered along with it. As was said, the cop is a cylindrical-conical body, which is built up of successive layers of yarn wound on the conical surface. In order that the cop bottom

A, B, C, D, E, F, may be properly formed, it is necessary that more yarn should be wound on the base than on the summit of the cop. In this way the full diameter of the cop is slowly reached, after which the elevation of the base remains uniform. In other words, in building the cop bottom the enlargement of the diameter of the point of the cone is slow, and that of the base is greater, so that the height of the cone grows more quickly. This is shown by the lines in Fig. 193, which illustrate the growth of the cop bottom. For the formation of the body, on the contrary, it is necessary to elevate the base and point uniformly, so that the length of the cone remains the same, and each fresh addition is substantially laid parallel to its predecessor. This remark is subject to a slight reservation. If the yarn were wound upon a cylinder, the elevation of the base and summit would be uniform, but, as the surface on which winding takes place is conical, it is found that the elevation of the point is lessened by reason of the conicity. The amount of correction needed is not large, and amounts to less than three per cent.

(276) Before proceeding to show the principle underlying the action of the quadrant, reference may be made to Fig. 201. Let it be assumed that the three sets of circles, B to G, H^1 to N^1, and O^1 to T^1, represent the winding drum to which the chain is attached, and that while it can be moved horizontally in the direction of the arrows, it is quite free to rotate on its centre. Let it first be supposed that the point A is a stationary one, having no motion whatever, and that the winding drum is moved equal distances—B, C, D, E, F, and G—in a horizontal plane. It is obvious, and is shown clearly in the upper series of circles, that every such movement of the drum will cause a portion of the chain to unwind from it, and, as a consequence, will rotate the drum, as shown by the curved arrows. The result is, that when the drum finally arrives at its last position, G, the chain is entirely unwound from it, and has thus caused it to rotate a little over two revolutions. This is very clearly shown by the series of small diagrams given below the circles, where the amount which the chain is wrapped on it, at each position, is

indicated by the diagonal lines.   In each of these diagrams the
centre of the drum is indicated by a vertical line, and its
diameter by the space between the two dotted vertical lines.
Thus in each of the positions, it will be seen that the chain is
gradually uncoiled, but it can also be noticed that as each hori-
zontal movement is assumed to be equal, the same length of
chain is unwound in consequence of each, and the rotation of
the drum would be uniform.   Now, let a reference be made to
the lower set of diagrams.   In this case the point of attachment
of the chain, at its free end, is supposed to be a nut which can
slide out from the centre I, and which is carried by an arm H I,
to which, simultaneously with the movement of the drum hori-
zontally, a forward oscillating motion in the direction of the
arrow is given.   In order to illustrate the point more fully, the
travel of the arm H I is divided into six equal parts, each or
which is assumed to be traversed during the period occupied by
the motion of the drum from one position to the next.   In the
lower set of diagrams the nut is at a point only a little removed
from the centre.   It will be noticed that as the arm H I
approaches the horizontal, the traverse of the nut, although
equal in a circular direction, becomes smaller horizontally.
This is clearly illustrated by the dotted vertical lines which
are drawn from each of the six positions of the nut, and
which cut the horizontal line given.   The result is, that
while the drum is travelling the same distance as in the
upper diagram, the chain is *delivered to it* to the extent indi-
cated by the distance W X between the first and last of the
vertical dotted lines.   The result is that when the drum reaches
its sixth position—N^1 or T^1—the chain, instead of being
drawn from it to the full extent, as illustrated in the first series
of diagrams referred to, remains wrapped on it for a portion of
its circumference, as clearly shown.   In other words, the drum
has made fewer rotations.   But this is not the only difference.
If the small diagrams illustrating the wrapping of the chain on
the drum in the diagrams B to G and O^1 to T^1 be compared, it
will be seen that the chain, instead of being unwound to an

FIG. 201.

equal extent as in the former case, is unwound in the latter unequally during each stage. A comparison of the terminal points of the line indicating the position of the end of the chain when on the drum will show this very clearly, and this is the salient feature to which attention should be specially directed. A close inspection should be made of these drawings, as it enables the precise action which occurs in winding to be fully comprehended. Now, if the point at which the nut is placed on the arm be assumed to be moved outwards until it occupies the position shown by the outer curve H N, then a still greater variation arises. Again, the extent of each forward movement of the nut is assumed to be equal, as is also each made by the drum, and, as in the former case, lines indicating the chain are drawn to the drums from the various points, H to N. The chain, instead of being unwound entirely as indicated at G, or to the extent shown at T^1, is now only unwound as indicated on the last of the circles, N^1, in the centre set of diagrams. It has, in fact, been *delivered* to the drum to the extent indicated by the space U V between the first and last of the vertical dotted lines drawn from each of the six assumed positions of the nut, H to N. In addition to this, if the diagrams illustrating the winding of the chain be examined it will be seen that there is a great variation in the amount unwound at each motion of the drum, and, if actual measurements are made, this variation will be found to be considerable.

(277) In order to make this action clear, and enable the amount of chain unrolled to be calculated, let it be assumed that the winding barrel is 6 inches and the outermost position of the nut 30 inches from the centre C, Fig. 201. If the barrel is cylindrical, as for the time is assumed, the movement of the carriage during its inward run of 64 inches will unwind the chain in uniform quantities for equal portions of that movement. The full traverse will, of course, unwind 64 inches if the nut be fixed, which would give a total revolution of 3·39 turns to the drum. By reason ot the gearing between the drum and the spindles, which, it is assumed, multiplies the rotation of the former by 19, this implies

the rotation of the latter 64·4 revolutions during the inward run. As was seen, however, the forward movement of the quadrant diminishes the number of turns of the drum, and all that is necessary is to determine the amount. The quadrant arm is in effect a crank, and the horizontal advance of the pin or of any part corresponding to a pin along a straight line is determined by the rules relating to the crank. All circular motion is a compound of two movements, a vertical and a horizontal. Not only does a crank pin rise vertically, but it also makes a horizontal movement which can be set off on the line representing the diameter. Let, in Fig. 202, A B represent the diameter of the

circle described by the quadrant nut when at its outermost position. Two quadrants of the complete circle are only shown, as the movement of the nut takes place within these. Let C 1 represent the most backward position which the arm assumes. By dropping a vertical line from 1 till it cuts the line A B a point marked E is got, which indicates the amount the pin has moved in a horizontal direction, and this is calculated as follows :—Calling the angle E C 1, a, the radius A C, b, and the distance A E, c, then $c = b\,(1 - \cos.\ a)$. Under the conditions named A C = 30 inches and the angle $a = 77°$. The cosine of $77° = ·22495$, and the equation works out $c = 30$

$(1 - \cdot2249) = 30 = 6\cdot747 = 23\cdot253$, which is the distance the point 1, when described on the diameter, has moved from A towards C. In completing its traverse from the position 1 to 2 the point will approach and be finally coincident with the vertical radius line C 2, at the same time advancing horizontally $6\cdot747$ inches. Let it now be assumed that the arm makes a further forward motion of $70°$, which will take place in the second quadrant. It is only necessary to deal with the motion in the same way as previously to obtain the relative horizontal movement of the nut and calculate each advance. This can be done by multiplying the sine of the angle measured from the vertical by the radius of the circle described by the nut. Dividing the segment of the circle traversed by the nut from the point 2 into 10 parts, the advance in inches of the point representing the nut on the diametrical line is found to be as follows, calling the various positions 3 to 12: (3) $3\cdot654$, (4) $3\cdot6$, (5) $3\cdot49$, (6) $3\cdot33$, (7) $3\cdot113$, (8) $2\cdot86$, (9) $2\cdot56$, (10) $2\cdot23$, (11) $1\cdot86$, (12) $1\cdot46$. It is thus shown that as the arm approaches the horizontal, the forward motion of the nut thus described on the diameter decreases, so that it gradually appproximates to a fixed point, which it would practically become when the lines C 12 and C B coincide. It is only necessary therefore to deduct at any of the points the amount of horizontal advance of the nut from the length of the carriage traverse, to obtain the actual angular movement of the drum at any position, or, in other words, the length of chain unrolled. Thus, if it be assumed that the position of $70°$ from the vertical line be reached when the carriage is at its innermost position, the amount of chain unrolled is 64 inches, minus the total amount of the forward motion of the chain nut, or $64 - 35\cdot056 = 28\cdot944$. This would give to the drum $\dfrac{28\cdot944}{6 \times 3\cdot1416} = 1\cdot535$ and to the spindle a total of $29\cdot165$ revolutions. By making a calculation of the amount of chain unwound at each point the relative velocity of the spindles can be arrived at, and this will be seen follows a similar curve to that obtained as necessary for the proper wind-

ing of the cops. Thus assuming that the carriage in moving
from its initial to its final position is accompanied by a motion
of the arm through an arc of 83°, of this 13° takes place in
the first quadrant prior to the vertical position being reached,
so that the proportionate amount the carriage must move is
$\frac{13}{83} \times 64 = 10$ inches, leaving the remaining 54 inches to be
traversed during the rest of the quadrant stroke, or 5·4 inches
during each of the fractional movements named. The rotation
of the drum during a forward motion of 5·4 inches is,
if the nut be fixed, ·35 revolutions, giving to the spindles a
motion of 6·65 revolutions. In the first part of the movement
of the arm from 2 to 3 the unwinding would only be 5·4—3·655
= 1·745 inches, and the number of revolutions of the drum and
spindles respectively ·0936 and 1·759. The revolutions of the
spindles at the various positions would be as in the following
statement, beginning at the point 1 :—

Position	2	3	4	5	6	7
Revolutions of spindles	3·23	1·75	1·81	1·92	2·07	2·29
Position	8	9	10	11	12	Total
Revolutions of spindles	2·54	2·85	3·19	3·55	3·97	29·17

From the data thus obtained a curve can be described which
will give the rotation of the spindles as regulated by the winding
quadrant. This is shown in the upper curve, given as a broken
line in Fig. 201, and is substantially the same as the lower curve,
but is drawn to a rather larger scale. The base is divided into
ten equal parts, assuming the curve to start from the vertical
line C D, the portion of the traverse of the arm behind C D
being neglected. It will be easily understood that the horizontal
movement of the nut in the quadrant A C D is the same as that
in B C D, so that the rules hold good in each case.

The description thus given shows that the radius of the circle
described by it has a controlling influence on the value of the
horizontal movement of the nut. All the other factors remain
similar, so that the reduction of the radius diminishes alike the

forward movement and its effect upon winding. If the centre of the nut were coincident with the centre C of the arm it would be practically a fixed point, and the unwinding would follow the law laid down at an earlier stage. With the dimensions given, this means that the value of the factor b in the equation $c = b$ ($1 - \cos. a$) increases from 0 to 30. As a matter of fact, in actual construction this is not so, because the nut at its innermost position is always about 3 inches above the centre. The effect is that, as the carriage moves in, equal distances travelled by it give nearly equal numbers of revolutions to the drum and spindles. As the nut moves out along the quadrant arm the value of b increases, so that whenever it is used to calculate the advance of the nut horizontally it gives a greater variation in the relative rotation of the spindles at each movement of the nut. This, it will be seen, is what is required, because during the building of the cop bottom the growth of the diameter of the cop at the base is, as was shown, rapid, so that the acceleration of the velocity of the spindles at the end of winding, or conversely, its retardation at the beginning of winding each stretch becomes more necessary. When the cop bottom is fully formed the nut is in its outermost position, and nothing more is needed in the way of regulation. It is desirable to say that the effect of setting the quadrant arm behind the vertical line at the beginning of its movement is to give for a longer period the rapid horizontal advance of the nut, so as to diminish the velocity of winding while the yarn is on the larger diameters.

(278) We have now to consider the second of the two points which were named as essential to winding, viz., the method of guiding the yarn on to the nose of the cop so that it shall be in the right position throughout to suit the velocity of the spindles. The manner in which this object is attained is as follows. Referring again to Fig. 205, it will be seen that the bowl L^1 in the trail lever or slide rests upon the upper edge of the rail P, which is known as the copping rail, and is drawn over it by the carriage in its movement. As the latter travels during its traverse along the slips, in the same plane, it follows

that if the profile of P is arranged to be angularly disposed rela-
tively to the edges of the slips, there will be a certain amount of
vertical movement of the bowl L^1 and its slide L. As during
the inward run of the carriage the boot leg or locking lever A
rests on the upper edge of the slide L, it follows that any motion
of the latter is communicated to the former. The locking lever
A being jointed by means of the sector C to the winding faller
shaft, the vertical motion of A is necessarily communicated to
the latter, which is, in consequence, oscillated in its bearings.
The winding faller sickles being fastened on the shaft B, any
oscillation of the latter necessarily affects the former. Thus
when the locking lever A is raised by the action of the backing-
off chain, as described in paragraph 257, the winding faller is
lowered into winding position. After it is locked, the vertical
motion of the lever A in either direction is communicated to the
winding faller, but the direction of the latter is in every case the
contrary to that of the locking lever. That is to say, the ascent
of A implies the descent of N, and *vice versâ*. All that is
therefore requisite to obtain the necessary guidance of the yarn,
as described in the last paragraph, is, that the profile, or upper
edge of P, shall be so shaped that, as the bowl L^1 runs along it,
it shall first rapidly ascend, and then slowly descend.

In order to make this clear, Fig. 203 may be referred to. The
profile of the copping rail is indicated by the line Q, Q^1, P, the
pendant or locking lever by the line A, the sector by C B, and
the faller sickles by B N. The point B indicates the position
of the faller rod on which the sector and sickles are fixed, C
being that where the locking lever is jointed to the sector. If,
therefore, A receives any vertical movement, the arm C N will
be rocked on B and the point N will receive a movement in the
reverse direction, within a range regulated by the ratio of C B
and B N. This ratio is assumed to be 1 : 2, so that 1 inch of
the vertical movement of A will give one of 2 inches to N in
the opposite direction. To effect the upward and downward
movement of N, which has been shown to be necessary, means
must be provided by which, as A is drawn forward with the

carriage, the trail lever will first rise rapidly, and then fall more gradually. The trail lever bowl runs on the copping rail, the profile of which is indicated in Fig. 203 by the line Q Q¹ P, and it will be readily seen that if the point Q—called the "ridge"— be raised relatively to the terminal points of the lines Q Q¹ and Q¹ T, a corrrespouding greater movement of the lever A and faller N will be obtained.

The actual method of building the cop was shown in Fig. 193, but in order to make it more clear, the diagram may again be referred to. It should be premised that there are two distinct stages in building a cop, the first the formation of the cop bottom, and the second the formation of the body. In the

FIG. 203.

first the action of the building motion, like that of the winding motion, is continually varying, while in the second the conditions are fixed, and only a vertical advance of the winding points is necessary. Thus the only movement of the copping rail, which is required in the latter period, is a uniform vertical one, while in the earlier stage it is necessary to enlarge the chase gradually, and at the same time to raise the initial point of winding. In Fig. 193, let the length of the chase at the beginning of winding be 1 inch, and indicated by the vertical distance A B. Assume that when the chase is fully formed that it is 1¾ inch, as shown by the dimension B C. It will be noticed, first that the terminal point of winding must rise from the position marked B on the spindle to that marked C, a distance of 1¾ inch. In the same period

the rise of the initial point of winding must take place
from the base A to the point B. In other words, while
the length of the chase is increased from 1 inch to 1¾ inch, the
height of the initial point of winding must be raised 1 inch. The
lengthening of the chase is the work of that part of the rail
which extends from the point Q^1 towards the roller beam, while
the elevation of the initial point of winding is the work of the
front part of the rail. It follows from this that the declination
of the long part of the rail must, in the inception of winding, be
rapid, while that of the front part must be less so. It has been
shown that when the faller locks, it is opposite the nose of the
cop, and is then pushed down so as to reach its base.
Remembering the multiplication of the movement of the locking
lever, and that the motion of the latter is the reverse of that of
the rail, let the point F represent that occupied by the bowl of

FIG. 204.

the trail lever when at its initial point. When it arrives at its
highest position the bowl ought to be raised sufficiently to have
given the faller a movement of 1 inch and the pendent ½ inch.
Assuming that the proportion of the traverse of the carriage
during the winding of the downward coils is one-eighth of the
whole, that would mean that the bowl must move 8 inches while
the locking lever rose 1. Drawing a diagram, Fig. 204, in which
the fall is shown on an exaggerated scale, we are able to illus-
trate the necessary alteration in the shape of the profile required.
For the front part of the rail this is initially the line F G.
Having arrived at the base of the cop, the faller must rise to
the same height, and the line assumed by the long part of the
rail is indicated by the line G H. The fall of the point H,
to ensure the enlargement of the chase so as to make it full size,
must be to the point K, and the line G K then represents the

position assumed by the long portion of the copping rail. In the same period the front rail must also fall, and the position it assumes is shown by the line G L. It will be noticed that the declination of L is less than that of K, and the effect of the fall from F to L is to cause the faller N to take a higher position as every stretch is wound, but as the rise of the initial point of winding is slower than that of its terminal, it follows that the beginning of the various layers is wound partially on that preceding it, but is carried beyond it at the end of the chase. Thus the cop is thickened at the base, and the cone slowly formed.

(279) There is another point which it is now necessary to deal with, and in order to make it clear it will be desirable to consider the construction of the copping rail and its attached parts, these being shown in Fig. 205. The copping rail consists of two

FIG. 206.

parts, but as originally made was in one piece, approximately of the shape shown separately in Fig. 206. The disadvantage of this arrangement was that, as not only the ascent but the descent of the faller had to be provided for, while the range of the two varied, it was difficult to get a movement which was accurate enough to permit of the faller locking at the right place and being pushed down to its true position at the base of the cop during each stretch. This is overcome by the application to the copping rail of a loosely hinged front rail separately regulated. Thus in Fig. 207 P is the copping rail proper and Q is the loose rail which is hinged to P at Q^1, so that its upper edge does not project above P at that point. In this way the bowl does not meet with any obstruction as it passes over Q^1. At the front of the rail P a head is formed, in which is a slot for the reception of a pin

projecting at each side of P. On the pin bowls are placed which rest upon the edges of two plates Y, one at each side of the rail, and thus sustain it. The position of the pin is

FIG. 205.

FIG. 207.

regulated by a screw, which is not shown, but which is used to give a certain vertical adjustment of the front end of P. At the other end of P another pin is fixed, also carrying bowls, each of which rests on a plate X. The copping rail is thus sustained between two sets of plates. The loose rail Q is in the form of a shell which fits over the front end of P, and in each of its sides is fixed a pin, the bowl on which rests on the edge of a plate Z. The effect of this arrangement is to give steadiness and solidity. A frame is fixed to the floor in a level position, and has within it planed surfaces upon which the feet of the copping plates— which are also planed—rest and can slide. A similar frame carries the copping plates X. On one side of the "copping plate" Y is an ear S^1, which forms a nut into which the "shaper" or "builder" screw S is fitted. S is borne so that it has only a rotary but no longitudinal motion, and on its inner end has fixed a hanging pawl S^2, which engages with a "shaping" or "building" wheel fixed on S. The pawl is controlled from the quadrant when it makes its backward stroke. The rotation of the screw S by the action of the pawl draws the plate Y inwards, and by reason of the connection of Y and X by the connecting rod W also gives the plate X a corresponding movement in the same direction. The plates Z and Y are coupled, so that the latter when moved carries Z along with it.

(280) Having thus described the various parts used, it is now possible to make their action clear. It has been previously shown that in building the cop bottom it is necessary to drop the inner end of P at a more rapid rate than its outer end. It will be convenient to neglect for a time the action of the loose copping rail Q, because that requires specially dealing with. Consider the rail P first, because it is the descent of the locking lever from Q^1 to the inner end of the rail which determines the chase. Assuming that the length of the bottom of the cop is 1 inch, and of the cylindrical part or body 4 inches, then during the building of 1 inch the inner end of the copping rail must fall sufficiently to permit the chase to increase to 1¾ inch,

while during the building of the remaining 4 inches both ends must fall at the same rate unless it is desired to shorten the chase. Now it is obvious that if a rigid bar is supported on surfaces receiving a horizontal movement which is not communicated to it, that in accordance with the shape of the supporting surfaces and the rate of their motion, the position of the bar relatively to the horizontal will be determined. As in the case under consideration all the surfaces move at a fixed rate this element can be neglected, and only their shape be treated. It is necessary, therefore, to provide a surface by

FIG. 208.

which the required fall of the end of the rail is obtained. In Fig. 208 an illustration is given of three plates, which are superimposed so as to facilitate comparison. These are drawn from actual examples, and correspond to the plate Y carrying the front end of the copping rail, the plate X carrying the back end, and the plate Z which sustains the front loose rail. The thick vertical and horizontal lines represent inches and the thinner lines quarter inches on the original full-sized drawing, so that the effect of any movement of the plates can be ascertained. If now it be supposed that the bowl at the front end of the

rail rests on the highest point of Y, and that the latter is moved
in the direction of the arrow 1 inch, the fall of the bowl will
only be $\frac{1}{16}$ inch. Assuming that the plate X is also moved
simultaneously, as in practice we have seen is the case, then the
fall of the bowl resting on its surface beginning at the highest
point will be $\frac{7}{8}$ inch. In other words, while the front end is
practically fixed, the back end has fallen $\frac{7}{8}$ inch, and the pen-
dant or locking lever receives an additional vertical movement to
that extent. The next inch of motion of the two plates results in
no fall of the front end, but a further fall of $\frac{1}{4}$ inch of the back
end. In all, therefore, to this point the rail is $1\frac{1}{8}$ inch lower
at the back end than at the front, in addition to the inclination
previously existing. When the second position is reached the
bowl is entering upon the straight part of the plates, and the
rail thereafter falls in accordance with the inclination given at
both ends. It will be noticed that the fall of the front end over
the entire length given from the beginning of the straight part
of the plate is $2\frac{5}{8}$ inches, while that of the back end is only $1\frac{1}{4}$
inch, leaving a net fall of $1\frac{3}{8}$ inch over that existing initially
In other words, during this part of the traverse, the chase is
gradually shortened as building proceeds. From this descrip-
tion it will be seen that the higher portion of the plates is
that concerned with the enlargement of the chase, while the
remaining portion is that which completes the building of the
cylindrical part of the cop. There is one correction to make.
As the highest part of plate Y is nearly straight, it follows that
during the descent of the bowl on X, the bowl at the front end
of the rail substantially forms a fulcrum on which the copping
rail hinges. If, therefore, the upper portion of X was quite
straight, a thrust would be put on the rail which would tend to
make it move forward. This is neutralised by giving the plate a
curve such as is produced when its inward traverse, the vertical
descent of the rail, and the curve followed by the end of the latter
are graphically drawn. This is really a draughtsman's point, and a
demonstration of the method of drawing the curve would not
aid in the comprehension of the principle, which is all that is

needed in a book of this kind. It may also be said at this point that a bracket P^1, Fig. 207, is fixed alongside the rail P, being formed with a slot into which a pin fixed in the rail takes. The slot in the bracket is formed at such an angle relatively to the horizontal that the rail always falls in a directly vertical line. There is a slight correction due to the radial movement of the rail. The ascending motion of the faller is caused by the descent of the locking lever from G to K, Fig. 204, and its range depends on the amount of that descent. As the rail radiates about the point F, it follows that G will also move a little in a circle, and the amount of the descent of the ridge so caused must, of course, be deducted from the total fall of the point H. The correction needed is not great, as will be easily understood when the relative lengths F G and G H are considered.

(281) Coming now to deal with the front copping rail, it rests on the plate Z, and following the same course with it as with the plates X Y, the fall of the bowl in the front of the loose rail is for the first inch $1\frac{1}{8}$ inch, and for the second inch $\frac{1}{2}$ inch, together $1\frac{5}{8}$ inch. But the trail lever bowl only runs along one half of the length of the loose rail, and thus begins its inward traverse half way between the point of support of the plate Z and the ridge where the rail is fulcrumed. Thus the motion at the initial point is only half the total fall given to the end of the rail, or $\frac{13}{16}$ inch. After the cop bottom is formed the inclination of the rail Z is substantially that of the rail Y carrying the front end of the long rail. It will also be noticed that the plate Z is $\frac{1}{2}$ inch lower at its head than the plate Y, which gives the necessary inclination to the loose rail at the beginning of winding. The loose copping rail is a valuable adjunct to the mechanism, as it ensures the locking of the pendant A always in the right place, owing to the ease of independent adjustment. When it was not applied, the faller often locked at a point 1 inch or $1\frac{1}{2}$ inch below the nose of the cop, and the ends became lashed, thus leading to breakage. This is entirely avoided by the use of the loose rail. It will be quite

clear, after the demonstration given, that the motion of the cop-
ping rail can be varied in two ways—first, by accelerating or
retarding the speed of the horizontal movement of the plates;
and, secondly, by increasing or diminishing their inclination.
Some remarks are made on this point at a little later stage, but
the facts should be borne in mind, as they form the basis of the
construction and manipulation of the plates.

(282) It is obvious that the relative position of the winding
and counter fallers will have an influence upon the yarn. For
instance, the angle formed by the yarn when it passes over the
counter faller to the winding faller when the latter is in the
second position, shown in Fig. 203, must of necessity be greater
than it is when it is in the position illustrated at the right hand of
that drawing. In the one case it is more acute than it is at the
other, owing to two factors. There is also the increased acute-
ness of the angle formed by the relative position of the winding
faller and the nip of the front rollers when the carriage is out, as
compared with the angle formed when the carriage is in. The
variation in the angle at which the thread is bent over the
two fallers, however, remains, and forms a consideration
which cannot be neglected. The yarn always passes round
the winding faller at a sharp angle, and the drag thus induced
is not without influence upon it. The second factor which
affects this portion of the subject is found in the variation in
the paths of the faller and counter fallers. The former travels
round a circle with a smaller radius than the latter, and its
traverse relatively to a vertical line drawn through the centre
B shows a greater inward and outward movement than that of
the counter faller. This variation is, of course, also affected by
the extent of the depression of the faller at various points, as it
is clear that the further the winding faller travels, the greater
will be its distance from the circle described by the counter
faller. There is also the fact that in the commencement of
winding, the counter faller will rise to a much higher point than
at other times, and the angle formed by the thread is made
more acute. The extent of the rise of the counter faller is

naturally determined by the amount of yarn released during backing-off. Thus, throughout the building of the cop the yarn is bent at a constantly differing angle round the counter faller. In other words, there will be at different periods considerable variations in the strain put upon it between the counter and winding fallers. This point has a bearing upon the weighting of the balance lever which controls the counter faller, and involves the consideration, that if this is too great, the strain upon the yarn may be caused to vary considerably during a stretch, and throughout building, with a necessarily detrimental effect upon it. Another feature in connection with this part of the subject is the character of the surface upon which the yarn is spun. If it has to be wound upon a hard surface like a steel spindle, it is quite evident that the strain on it will be greater than when wound on to the cushion-like surface of the cotton when the cop is partially filled. Although a small matter, this has some bearing on the character of the winding and the diameter of the yarn.

(283) As was shown in paragraph 272, the cop is built upon the taper blade of the spindle, which varies in diameter from $\frac{5}{16}$ to $\frac{1}{8}$ inch. At first, and more especially when a short paper tube is employed, the yarn is wound on a practically cylindrical surface, so that every revolution takes up about the same quantity. Thus, if this be $\frac{5}{16}$ inch diameter, or ·98 circumference, every revolution will take up the latter length of yarn. Thus, to wind on 64 inches, 65·3 revolutions of the spindle are wanted. Every layer of yarn, as shown in Fig. 193, increases the diameter of the cop until the full size is reached, so that if it be assumed that the cop is finally 1 inch diameter, every revolution of the spindle will take up 3·1416 inches of yarn, and only 20·5 revolutions of the spindle are required to take up the full length of yarn. But, as was made obvious when the method of building the cop was dealt with, the yarn is not always being wound either on the smaller or larger of the diameters named, but is during each stretch wound on a variable diameter. Thus, when the cop bottom is formed, the

next layer is wound on the surface B C (Fig. 193), and is consequently taken up at a continually varying velocity. Now, if the carriage had a uniform speed, and the tin roller also received a similar rotation during the period of winding, it would follow that the yarn would either be taken up at the point B too quickly or too slowly at the point C. In the first case it would be strained and broken, and in the latter case would be wound too slackly on the spindle. Either of these difficulties are detrimental to the production of a perfect cop, and must be avoided. It is a natural consequence of these factors that there must be means provided by which the velocity of the spindle is accelerated as the yarn is wound on the constantly decreasing circumference of the nose. Until the cop bottom is finished this acceleration is calculable and easily provided for, but after that period an entirely new set of conditions arise. If it be assumed that the correct initial and terminal velocities of the spindle which are needed to wind the yarn on the spindle blade have been obtained when the cop bottom is finally formed, every rise of the initial point of winding brings into play a new set of conditions. The spindle S (Fig. 193) is, as shown, tapered, and the result is that the yarn is being wound at the nose on a perpetually decreasing diameter. Suppose, for instance, that at the termination of the cop bottom the yarn is wound at the nose on the spindle, which at this point has a diameter of $\frac{5}{16}$ inch. In this case its circumference would be ·9817, and to take up the last 5 inches of yarn it would require to rotate 5·09 times. Now, let it be assumed that the winding is being conducted higher up the spindle, and that the diameter of the spindle at the nose is ⅛ inch. In this case the circumference of the spindle will only be ·3927, and to wind 5 inches of yarn will require 12·72 revolutions. It is quite obvious that the same terminal velocity of the spindles being maintained in each case, if the yarn is wound with sufficient tension on the larger diameter of the blade, it will be slackly wound on the smaller diameter. In other words, a "spongy" nose will be formed. As yarn is

often wound off a cop by drawing it upwards, as shown in Fig. 194, any such condition of the cop nose results in a number of coils being drawn off simultaneously in an entangled condition. In this case the cop is said to be "halched," and a good deal of waste is produced when the unwinding takes place. From the foregoing remarks it will be seen that in addition to an increase in the variation of the velocity of the spindles as the full diameter of the cop is approached, an acceleration of the terminal velocity as the cop nose is wound on a higher point on the spindle is also required. It is sometimes the practice to give the copping rail such a profile that the faller rises more rapidly as it approaches the nose of the cop, the idea being to lay it in spirals of increasing pitch, and thus keep it tight.

(284) When the gradual outward traverse of the nut, which is made during the time the cop bottom has been formed, has been completed, the relative initial and terminal velocities of the spindle remain fixed, so that any further acceleration of the spindle must be obtained by other means. This supplementary acceleration is requisite, as shown, on account of the diminishing diameter of the spindle blade, and the consequent inability of the spindle to take up exactly the same length of yarn at the nose throughout the whole of the building, as previously explained. It has been pointed out that the length of the conical surface upon which the yarn is wound remains practically the same, so that if the diameter of the spindle blade was thereafter uniform, the establishment of the true conditions for successful winding at this point would be all that is necessary. As, however, this is not the case, but the spindle blade decreases · in diameter, it follows that a new set of conditions arises, which, however, does not affect the operation, except at the point where the yarn is being wound at the nose. It, therefore, becomes necessary, as was said, to communicate to the spindle, as the yarn approaches the nose, a greater velocity, and the amount of the acceleration at this point must increase in exact proportion to the diminution of the diameter of the spindle. There are two

ways of doing this. One is to deflect the chain attached to the drum from a straight line while it is in tension, and the other is to gradually shorten it by taking it up. In the first method, the chain is either pressed or pulled down as the arm H I approaches the horizontal, so as to be suddenly shortened. For instance, if it be assumed that the line from A to F in Fig. 201 represents the chain in tension, and the drum F be supposed to be stationary, it is clear that if the chain be pressed down between those two points so as to be deflected from a straight line, the drum F would, if free to rotate, revolve for a distance commensurate to the deflection of the chain. It is easily understood that the deflection of the chain is practically equivalent to shortening it, so that in addition to the rotation of F, caused by the ordinary pull on the chain, it would receive an additional amount because of the extra pull put on it by the deflection of the chain. If, on the other hand, the chain is shortened, then the effect upon a truly cylindrical surface, such as that shown in Fig. 201, would be practically nothing. All that would happen would be, that the chain would be earlier unwound from the drum. If, however, in lieu of a cylindrical surface on which the chain is wound, a spiral surface, such as that found in a scroll, is used, then the shortening of the chain has an important consequence. For instance, if the largest and smallest diameters of the scroll were 6 inches and 3 inches respectively, their circumferences would be 18·84 inches and 9·42 inches respectively. Thus, to cause the drum to rotate once, lengths of chain equal to the cirference must be unwound. In other words, if 18·84 inches of chain is unwound from the large part of the scroll, so producing one revolution, the same length taken from the small diameter of the scroll would cause the drum to revolve twice. Thus, there is not only the acceleration caused by the increased pull upon the chain referred to, but also that caused by the unwinding of the chain from a surface of less length. Shortening or taking up the chain when used in conjunction with a scroll is, therefore, very effective as a means of getting a high terminal velocity, from the fact that it is taken off a smaller circumference as the

shortening proceeds, and that the pull of the chain itself draws it from a circumference which is continually decreasing. If a scroll were used with a fixed point of attachment of the nut there would be a terminal acceleration, but when it is employed in conjunction with a greater pull on the chain as the nut moves forward, and the gradual removal of the chain from the larger diameter as the chain is shortened, the acceleration is considerably decreased. It is, of course, necessary to give a correct velocity to the chain nut in its forward movement to compensate for the diminishing diameter of the scroll, because it is essential that the conditions illustrated in Fig. 200 should be as nearly as possible approximated to.

(285) It is now possible to deal with the method of actuating the chain to obtain the desired terminal acceleration. This is done in most cases by a device known as a " nose peg," which is a pin or stud fixed in an arm fastened to the upper end of the quadrant. As the nut is gradually moved outwards, the nose peg begins to press upon the chain, and depresses it more and more as the nut is raised. At first, while the cop bottom is being formed, and is in its early stages, the pressure of the nose peg is slight, but as the building proceeds it gradually increases. It is worth while noticing, however, that with the plain nose peg, the chain, after the nut has arrived at its outermost point, and the cop bottom is finished, is always deflected to the same extent, so that unless the terminal velocity of the spindles is too great at first, it is too little at the termination of building. Accordingly, it is sometimes the practice to fit an automatic arrangement by which the peg is gradually moved downwards, and thus presses upon the chain with increasing force, communicating to it a greater deflection each time the quadrant makes its forward stroke. In many respects this arrangement has been satisfactory in actual practice, and has found extensive use. Another method of obtaining the same result is one, in which, instead of pushing the chain down, it is pulled out of a straight line by means of a second chain which is being continually shortened.

In taking the faller mechanism as a base from which to carry out the operation the method is noteworthy and meritorious. One good point in this procedure is that an alteration in the deflection of the chain only takes place when the elevation of

FIG. 209.

the faller really necessitates it, which is a matter of some importance. The arrangement shown in Fig. 209 is based upon the idea of shortening the chain, and is controlled from the shaper screw, which may be said to be the other extremity of the

mechanism of which the winding faller is the last member. The ratchet wheel E, fixed on the slide A carrying a small barrel to which the winding chain C is fastened, is held by pawls E¹. On the spindle of the barrel is an arm F receiving a pull from the chain G fastened to it, the latter being guided, as shown, until it is attached to the bracket I, moved inwards by the shaper screw S, by the finger I¹. In its course the chain is passed over a hinged or pendulum bracket K, a short arm of which K¹ comes into contact with a finger or bracket K² on the quadrant during the backward movement of the latter. The extent to which the pendulum K is pushed back by this action depends entirely upon the extent to which its lower end is drawn forward by the travel of the bracket I, and varies as winding proceeds. When winding is beginning, the chain G is slack, and F is in the position shown in the view at the top right hand corner of Fig. 209. As the slide A rises and the bracket I is moved inwards there is a pull upon the chain G, which draws down the arm F and thus rotates the barrel, causing the chain C to be wound on it. The amount of the movement of E is very slight until the cop bottom is completed, when it begins to increase. The result is that the chain C is gradually wound on the barrel in the slide A and wound off the large diameter of the scroll X¹ (Fig. 195), so that there is the combined effect of the slower horizontal movement of the nut and the unwinding of the chain from a smaller diameter. The actual position which these parts occupy, at the beginning and end of a set, is shown in Figs. 210 and 211.

(286) In commencing to build a set of cops it is the practice to attach the first few layers to the spindle by means of a starchy mixture. This practice is supposed to strengthen the cop bottom, and to enable it to be more readily placed upon a skewer when it has to be wound. The initial position of the nut in the quadrant depends upon whether the cop is formed on the bare spindle or upon a paper tube. If the latter, it is not wound down so far as it is when winding begins on the spindle. In commencing a set of cops the copping plates are

wound back to the stops, adjusted as described, and the nut is wound down to its initial position. The extent to which the copping plates are drawn back and their setting is determined by the fact whether a short or long cop bottom is wanted. Some spinners prefer the former, alleging that they can be better made, especially when starching takes place. In this case the bottom cone is made short, and the lengthening of

FIG. 210.

FIG. 211.

the chase takes place with a very slow elevation of the locking point. The regulation of this is effected as afterwards described, but it is worth noting that by skilful manipulation of the shaper or copping mechanism cops of any shape can be easily obtained.

(287) The proper building of a cop is seen, from the foregoing explanations, to depend upon two operations. viz., the elevation and traverse of the faller and the differential rotation of

the spindles. These two factors have a close connection and each has an influence upon the other. It is quite clear that the inaccurate adjustment of either of the two portions of the building mechanism would entirely destroy the normal relation of one to the other, and it is this absolute interdependence which renders this part of the operation of a mule of high importance. It will, therefore, be profitable to consider some or the defects usually found in cops, and explain the causes which produce them. If the explanation given has been followed it will be seen that during every run-in of the carriage a uniform length of yarn is wound on the spindle. If the traverse of the winding faller is not correctly adjusted, or if the velocity of the spindles is not differentiated properly, then some of the yarn will be wound upon a part of the cop which is not the right one. In this case the cop will be wrongly built, and, unless great care is taken, the readjustment is likely to lead to mischief in other directions. Cops are often badly shaped—that is, instead of maintaining the cylindrical shape in the body, which is the characteristic of a true cop, they vary in thickness at different points. In other cases the nose of a cop will be spongy and soft, so that when the yarn is being unwound it unravels, and thus causes a great deal of waste. Occasionally, cops will vary in weight, one from another, although they may be produced on the same mule. Now, all these defects arise from causes which are ascertainable, although, in some cases, a long search is required before the cause can be found. It is always necessary to ascertain the part of the cop in which the defect exists, because, by so doing, a guide is given to the parts which require adjustment or alteration. For instance, if it were found that the cop suddenly became thicker at a point about midway of its length, this would enable the observer to determine the place where the defect arose. It would be evident to him that for some reason or other the gradual elevation of the initial position of the faller during winding was not, at this particular point, taking place at the proper velocity. Suppose, on the other hand, that the cop became gradually thinner as building proceeded, then it would

be easily inferred that the elevation of the faller was taking place too rapidly, and that, instead of the cone being properly formed, the first coil of each stretch was being laid upon a portion of cop where the diameter was too small. If the cop thickened, as building proceeded, the cause could be ascertained, by the same reasoning, to be the too tardy elevation of the winding faller and the consequent winding of the earliest coils on a diameter of excessive size. In this way, by exercising a little thought, much time and labour will be saved, and there will be a chance of the actual defect being cured in the most effective manner.

(288) It will be better to deal with the defects in cops as they are produced, by treating first, those which are due to the improper setting of the carriage or driving mechanism; second, those which can be attributed to the wrong shaping or manipulation of the copping rail; and third, those arising from imperfect winding. In the first instance named the faults which are created are mainly those of imperfect drawing. If a carriage is not perfectly squared—that is, if the centre line of the spindles is not parallel to the rollers—then, during the outward run, some of the threads will be subjected to a greater draft than others, and will be, when spun, thinner, and of course lighter. The tension upon the drawing out bands is so great that it is only natural that they will stretch. The result is that one part of the carriage is drawn out quicker than the other, and the draft put upon the yarn is proportionately increased. Thus on the same mule there will be cops produced which vary in weight considerably. It is, in practice, necessary, especially with long mules, to make some allowance for the inevitable vibration caused when dealing with so large a body as the carriage, but the amount necessary is not great, and will not practically affect the general principle. If the rollers are not carefully attended to, and the lubrication of the top rollers properly effected, the drawing will be imperfect, and the result will be variable threads. There is another consequence of the imperfect squaring of the carriage, which rather comes under the third division, but which can be conveniently dealt with

here. If the tension is not even, the spinner, in attending to the governing of the quadrant nut, will be almost certain to regulate the winding by the tightest threads, with the result that snarls will—especially with hard twisted yarn—be liable to form in the ends which are slackest. When soft twisted yarn, such as hosiery or weft yarn, is wanted, the extra tension induced by a badly squared carriage is very prejudicial, and is apt to produce uneven yarn, which in the first case named is most undesirable. It is, of course, not intended to be implied that the bands are always stretching and requiring adjustment, only that this is a point which requires periodical attention and care. Sometimes it happens in very long mules that the scrolls on the back shaft will work loose, and that the carriage is thrown out of the square. This is not a frequent occurrence, but if it takes place the scrolls should be set and re-fastened on the back shaft.

(289) Coming now to deal with the question of bad copping caused by the incorrectness of the shaping mechanism, it is necessary to point out one or two features in the latter which bear upon the subject. The copping plates are formed as was shown, with curved portions at their upper ends. These are indicated in Fig. 207 by the letters $Y^1 Z^1$ and X^1. When the copping rail P is in position for commencing a set of cops, the studs fixed in each of its ends rest on these curved portions of the plates, and the first result of the inward traverse of the latter is to rapidly alter the position of the profile of the copping rail. It was pointed out that the curve X^1 is much steeper than Y^1, the result being that the back end of the rail P falls more quickly than the front, and the traverse of the faller is in consequence rapidly lengthened. This action is intended, as was shown, to form the bottom cone properly, and it will be an obvious corollary to this fact that the special formation or setting of the plates will enable a shorter or longer cone to be formed. This can be done in one or two ways. If the back plate X be moved towards the plates Y Z by an alteration in the point of attachment of the rod W the studs will rest on a higher part of the curve X^1, and will thus

fall more rapidly as X is pushed back. In ordinary cases the same effect can be produced by winding back all the plates. It is quite clear that the length of the cop bottom can be varied at will by the simple adjustment of the parts in such a way that, when the inward motion of the plates takes place, the back of the copping rail P will fall more rapidly forward than the front. It is extremely desirable that the position of the rail shall not be such as to cause the yarn to be wound below the lower coils cf the bottom cone. If this occurs the yarn is liable to be broken either when being unwound in warping or when in the shuttle. We have referred to the variation in the diameters of cops which is sometimes found, and have indicated its cause, which is that the elevation of the point of locking takes place too early or too late. In other words, the descent of the copping rail is, at the particular point where the defect occurs, not properly accomplished. If the cop is thickened, then the elevation of the locking point is made too slowly, and the copping plates require adjustment to permit the rail to fall. In the case of a thin cop the opposite of this procedure is necessary. These points are so obvious, if the principles of copping are understood, that it would be hardly worth while spending time in explanation, were it not that the matter is one of some importance and occasional perplexity. What it is desired to do is to endeavour to make clear the reasons which regulate the adjustments rather than give a specific for every imaginable case. The yarn should, if the rail is correctly shaped, produce a cop the upper cone of which is straight and neither convex nor concave, and unless this is the case the rail should be straightened. In some cases spinners prefer to have the cop bottom curved in its outline, and a slight alteration in the profile of the plates will do this. It is a common practice, when these defects are found and are attributed to the formation of the copping plates or rails, to file or plane the plates or rail, and there are cases in which this is the only procedure which will remedy the evil. It is desirable, however, to give a warning against undue interference with the shape of the

copping plates or rails, as, unless the alteration is skilfully made, evils worse than those it is intended to cure will be produced. In addition to this it may happen that the variation thus produced will so affect the working of the machine as to render it difficult for any one who is not familiar with the alterations made to put on the required ratchet or "shaper" wheel S. This point may be illustrated thus. Suppose the shaper or copping plate Y was shaped so that its edge was at an angle from the vertical of 45°, then the rail P would fall at a definite rate. Let this angle be now altered to one of 20°, it is obvious that for each inch of inward traverse of the plate the end of the rail would fall proportionately quicker. If, therefore, it is desired to maintain a uniform rate of descent, it follows that the velocity of the inward movement of the copping plates must be decreased or increased according to the amount of angularity in the plates. In other words, the speed at which the screw is rotated must be varied, and if its pitch remains the same, this implies the adoption of a shaper or builder wheel S of greater or smaller size. The evils which arise from worn or loose pins need not be dilated on, as these are well known to be very great in machines of all classes, and when the accuracy and delicacy of the settings of this part of the mechanism are remembered, it is not too much to say that this feature is of prime importance.

(290) We have now to deal with the defects which arise from imperfect winding. These may be caused in the cop bottom by the governing of the traverse of the quadrant nut being imperfectly performed, and this is a point which requires careful attention. The initial point of the quadrant traverse is a matter to which some care should be devoted, and there can be no empirical rule given to guide the student. In most cases the quadrant arm should be, as shown in Fig. 201, set well behind the vertical line through its centre at the commencement of winding, and a common practice is for the quadrant to be set quite vertically when the bowl L^1 is at the point Q^1 (Fig. 203), and the full diameter of the cop has been reached. It is not, however, possible to say that in all cases such an adjustment

Q

will succeed, and the best practice is to leave the setting to be determined by careful observation, coupled with experience. The exact delivery of chain to the carriage by the quadrant during its forward stroke cannot be other than a variable quantity, and the amount of variation necessarily depends on the whole circumstances of the case. The setting of the scrolls on the scroll and back shafts is also a matter which affects winding, because the quadrant is driven by a band from the back shaft, and its forward motion should be in unison with that of the carriage. If this is not so, and if any antagonism of the two parts exists, it is impossible for winding to be effected properly. The regulation of the nosing motion is a matter of the greatest importance, as has been previously pointed out, and should have constant attention paid to it. Most of the points which affect the formation of the cop have now been touched on, and without giving dogmatic and inflexible rules for adjusting the various parts, the points which require special attention have been sufficiently indicated. It is altogether undesirable, in dealing with a subject of this kind, to do more than point out the direction in which the efforts of the student should be made ; but a careful study of the explanations given will enable most ordinary defects to be grappled with. It may, however, be said that the following procedure can be followed in adjusting the various parts. The carriage being out and locked, an inspection can be made of the position of the scrolls to see that all the bands are in the proper position. If the scrolls want adjusting, in order that the correct speed of winding shall be obtained, this should be done, and the scrolls fixed. Examine the backing-off, see that the backing-off friction is always free during twisting and winding, and ascertain that the chain is just tight enough to draw down the faller to its proper position and no further, and that immediately the faller is down the click-catch gears. Next, adjust the quadrant in the manner described, after which the squaring of the carriage can be carried out. Care should be taken to see that no slip is taking place in the rim band, as, although this is an unusual occurrence, it does

sometimes happen, and is difficult to discover. All the rollers must be kept very clean, and any imperfect ends ought to be broken, if seen, and not allowed to run on to the cop. These are a few of a large number of points which should be looked to, and it is this multiplication of detail which makes the mule a comparatively difficult machine to tend.

(291) In paragraph 259 the various rules used for calculating the effect of the parts actuating the rollers and carriage were given, and we can now give those which relate to the various portions of the mechanism subsequently described.

To find the correct twist wheel to put in any defined number of turns per inch—

$$\frac{\text{Number of inches in a stretch} \times \text{ turns per inch.}}{\text{Number of revolutions of spindles for each revolution of rim pulley.}}$$

To calculate number of teeth required in twist wheel in altering counts—

$$\frac{\text{Present twist wheel squared} \times \text{counts required}}{\text{Counts being spun.}} = x$$

$$\sqrt{x} = \text{twist wheel required.}$$

NOTE.—It may be found more convenient to have a twist wheel which makes two complete revolutions, in which case the number of teeth in present wheel would require multiplying by 2, and the number equalling $\sqrt{x}$ divided by 2.

To find the builder or shaper wheel required to spin any counts when counts being spun are known—

$$\frac{\text{Present wheel squared} \times \text{counts required}}{\text{Present counts spun.}} = x.$$

$$\sqrt{x} = \text{wheel required.}$$

NOTE.—The above rule should be read in the light of the last paragraph, especially those remarks which are made regarding the alteration of the profile of the shaper plates.

To find turns per inch during the outward run of carriage, by means of the wheels (refer to Figs. 176 and 177), when relative number of turns of spindles to rim shaft is known—

(1) $\dfrac{\text{Pinion G} \times \text{pinion J}^1 \times \text{wheel Q} \times \text{pinion R}}{\text{Wheel G}^1 \times \text{wheel F} \times \text{wheel Q}^1 \times \text{wheel P}^1} = x.$

(2) $\dfrac{\text{Relative turns per minute of spindle to rim}}{x \times \text{circumference of scrolls H}^1} = \text{turns per inch.}$

The method of arriving at the number of turns per inch which should be in yarn is, for the different varieties, as follows—

Hosiery yarn	$\sqrt{\text{counts}} \times 2.50.$
Yarn for doubling	$\sqrt{\text{counts}} \times 2.75.$
Weft (medium numbers)	$\sqrt{\text{counts}} \times 3.25.$
Weft (fine numbers)	$\sqrt{\text{counts}} \times 3.183.$
Twist (medium numbers)	$\sqrt{\text{counts}} \times 3.75.$
Twist (fine numbers)	$\sqrt{\text{counts}} \times 3.606.$
Twist (extra hard and ring)	$\sqrt{\text{counts}} \times 4.0.$

Although the numbers given form the usual multipliers employed in arriving at this result, it must not be understood that the amount of twist is inflexible. It may happen that a change of cotton, or many other causes, will enable the method of calculating the twist to be judiciously modified, and it is only possible, therefore, to give the above as a general rule for the purpose.

(292) Having now fully dealt with the question of winding and its accompanying problems, it only remains to describe the method by which the various parts are restored to the necessary position for recommencing the operation. As the carriage approaches the roller beam, the various parts are operated as follows :—The spindles are being revolved at a gradually accelerating speed by means of the winding chain; the carriage is being drawn up by means of the scrolls on the scroll and back shafts; the winding faller is locked and is gradually approaching the nose of the cop; the counter faller is sustaining the threads; the strap is on the loose pulley; and the rollers are disengaged. The whole of these portions of the mechanism want adjusting so that they shall occupy the places and perform the functions which were detailed as belonging to the first period of action. In doing this, the cam shaft plays a great part where it is used, or the changes may be made by other means, such as a series of levers, which are set in motion by stops or fingers on the carriage. In the case of the mule illustrated, the bracket S^1 (Fig. 181) engages with the bowl R^1

on the long lever, and so oscillates the latter. This leads to the cam shaft making a half revolution in a similar way to that described. The half rotation of the cam Z detaches the taking in friction clutch I^1 K, and at the same time, by reason of the connection between the lever Z^1 and the back shaft clutch lever T, engages the back shaft clutch P P^1 (see Fig. 177). The roller clutch is engaged by the cam W and the strap is transferred by the cam Y from the loose to the fast pulley. The horizontal catch lever, which is connected with the strap guide lever, is pushed forward and is engaged with the detent catch, thus firmly fixing the strap lever in driving position. At the completion of the half revolution of the cam shaft, the friction clutch W X is disengaged, and the cam shaft stops. The carriage is drawn by the scroll bands up against the back stops, and it is very desirable that it should be drawn up gently and without a hard blow. This has been previously touched upon, and depends upon the adjustment of the scroll and check bands. If the carriage is not parallel to the roller beam, it is very likely to thump against the back stops, and this is a matter to be avoided. When the carriage runs up to the beam the counter faller is relieved by means of a pendent arm which engages with a releasing bracket in the manner diagrammatically shown in Fig. 205, and the lever J is also released by means of a stop. The effect of this is to take the strain from the yarn before delivery by the rollers recommences. The lower end of the locking lever A in like manner comes in contact with one of the back stops, and the shoulder R is pushed off the bowl L^1 in the trail lever. The weight of the locking lever causes it to fall until its movement is checked by the stop bracket engaging with the counter faller shaft, the winding faller being in the meantime entirely removed out of contact with the yarn. It is obvious that the guiding action of the faller must be fixed, so far as its period is concerned, by the height at which the cop is being built, and it must terminate at such a point that sufficient yarn is left to coil on the spindles between the nose of the cop and the point of the

spindles. As this length of yarn varies throughout the formation of a cop, and is greatest at the commencement of building, it follows that the detachment is required at a little later period as building proceeds. For this reason the face of the stop bracket G (Fig. 205) is made curved, and is so shaped that the exact moment when the faller is unlocked is strictly regulated by the position of the winding faller at the termination of each stretch. The descent of the copping rail P has an influence upon this special operation. The whole of the parts are thus restored to their initial position and spinning recommences.

(293) It will have been noticed that the quadrant arm M is at the termination of winding in its most forward position, and that the winding chain is drawn off the scroll or drum. It has also been shown that the forward motion of the quadrant is obtained from the back shaft by means of a band driven by the latter. As the back shaft therefore rotates in the opposite direction in drawing out the carriage, it, by means of the pinion M^1, restores the quadrant arm to its original position. During this time the tin roller is rotating, but no motion is given to the scroll X. It is accordingly necessary to provide some means by which, during the outward run, the latter will be rotated so as to take up the winding chain preparatory for the recommencement of winding. This is found in the employment of a band S (Fig. 212), which is kept in tension by means of a weighted lever U hinged to a bracket fixed on the floor. S passes over the pulleys fixed on the carriage, and the tension is sufficient to cause it to rotate X, and thus wind the chain on to the winding scroll. In this way the parts are in the necessary position to recommence winding. There is another motion which is sometimes fitted to a mule about which some people speak in high terms. This is called a hastening motion, and consists in an arrangement by which the transfer of the strap to the fast pulley is accomplished prior to the completion of the inward run of the carriage. It will be easily understood that as at the completion of winding the spindles are revolving in their normal direction, the actual transference of the work of driving them to the rim

band is merely an acceleration. The question is whether this action should take place a little before the actual termination of the inward run. Where nosing motions of an inefficient character are used there is an advantage in this course, but otherwise the only gain from its employment is found in the more rapid commencement of the outward motion of the carriage. If used it requires constant attention, or the carriage will not "light in" so easily, and the slow motion thus produced will probably be more detrimental to good winding than the acceleration of the spindles in the manner described will be beneficial to the general operation.

(294) The machine which has hitherto been dealt with is designed for the purpose of spinning medium counts, and when

FIG. 212.

the finer counts are to be spun it is necessary to provide special means for the manipulation of the material. The finer the counts the greater number of twists contained in the yarn, and, as a consequence, the shortening effect, which takes place in each length of yarn by reason of the twisting, is proportionately increased. As the yarn is of smaller diameter, it is less fitted to sustain the extra strain thus put upon it, and if delivered and twisted in the same manner as a coarser yarn, it would be broken. In addition to this, there is another factor which has to be reckoned with. Yarns of medium counts are subjected to a draft, by means of the gain of the carriage, the amount of which is proportionate to the counts spun. The longer

the staple of the cotton the greater the draft which the yarn will stand. It follows, therefore, that the finer yarns being spun from the longer staples, a better draft can be given to each thread. It is very desirable that yarns of this class shall be as even in diameter as the best skill can make them, and the draft to which they are subjected, after some of the twist is put in, is well calculated to draw out the thick places. It is customary, in spinning fine yarns, to put in, during the outward run of the carriage until it arrives nearly at its termination, very little twist, and the amount of this is just sufficient to enable the thin places to be strengthened sufficiently to resist the final draft. When the carriage approaches within a few inches of its extreme outermost point, the rollers cease to deliver yarn while the carriage continues its outward run. There is thus an additional and final draft exercised which has some influence in evening the yarn. The full twist is put in when the carriage arrives at the end of its stretch, and a shortening of each length of yarn takes place. The extent to which this takes place is dependent solely upon the number of turns per inch put into the thread. The tension of the yarn, which is induced by the operation or "jacking" just described, entirely precludes the possibility or any further stretching of each length. If the tension is maintained during the final period of twisting rupture is inevitable, and a large percentage of breakages will occur. It is customary, therefore, to relieve the yarn either by shortening the length held between the spindles and rollers or by delivering a small length as twisting takes place. The first method involves the movement of the carriage towards the roller beam for a short distance. The weight of the carriage renders the regulation of the extent of this movement difficult to obtain, and this course has therefore ceased to be followed. The usual practice is to give the rollers a slight forward motion, so that they deliver a little yarn, sufficient to relieve the tension without affecting the twist in the yarn. This "roller delivery" has entirely superseded the "receding" motion, and can, as will be shown, be very easily effected.

(295) Referring now to Fig. 213, which is a plan view of a fine spinning mule, it will be seen that in all essential features it is similar to the machine previously described. The winding barrel X is in this case cylindrical, and the terminal acceleration of the spindles therefore depends upon the action of the nosing motion. In this machine the method adopted is, as has been mentioned, to draw the chain out of the

FIG. 213.

straight line to an increasing extent by means of a second chain which is shortened as required, the actuation of the mechanism for this purpose being regulated by the position of the locking lever. The mule, as shown, is adapted for spinning the finer medium and fine counts. The " jacking " motion is controlled from the side shaft J, which has fixed on it, in addition to the wheel J^1, the smaller bevel pinion J^2. This motion is shown in detail in Fig. 214. This engages with a larger wheel J^3, which is geared, by means of a catch and ratchet clutch arrangement

M M^1, similar in principle to the " click " motion previously des-
cribed, to the wheel Q^2 driven by the wheel Q on the roller shaft,
and forming one of the train of wheels driving the back shaft H.
So long as the motion is derived from the wheel Q, the velocity
of Q^2 being then higher than when driven from J^2, the catch
driving Q^2 slips over the ratchet teeth in the latter.   When the
friction clutch F Q is disengaged, then the wheel J^2 obtains
command of Q^2, and drives it and the back shaft at a slow
velocity until the Mendoza lever, in which the wheels driving Q^1
are carried, is raised, and the back shaft thus ceases to rotate.

FIG 214.

The amount of this extra " jacking " stretch is dependent upon
the timing of the motions controlling the disengagement of the
rollers and back shaft, which in this case can be varied as de-
sired.   The relative velocity of the carriage during the ordinary
period and when jacking varies in accordance with the require-
ments of the case, but an average is probably 6:1.   During the
period that the shaft J is running, which coincides with that of
the rim shaft, the supplementary shaft K is also rotated, being
driven by a pinion on J, which gears with a carrier also engaged
with a pinion on K (see also Figs. 213 and 215).   The shaft
K has on its outer end a worm K^2, which meshes with a

worm wheel K^1 fastened on a short transverse shaft. This is provided with a clutch box N, similar in construction to that in Q^2, one half of N being loose upon the shaft and compounded with a pinion N^1. N^1 drives a pinion N^2, fastened on the roller shaft E. When the roller shaft E is driven by the ordinary

FIG. 215.

clutch F Q the velocity of the wheels N^1 N^2 is such that the pawl in N slips over the teeth in the ratchet, but when F Q is disengaged, then the clutch box N takes command and drives the roller shaft E at a slow speed. Although this movement of the rollers accompanies the slow motion of the back shaft it lasts for a longer time, and only ceases when the strap is taken

off the fast pulley A. Thus it is possible, by timing these motions and providing suitable wheels, to enable the rollers to deliver any desired length of yarn, which is equivalent to the recession of the carriage. At one time motions which gave a backward movement to the carriage were used, and were known as "receding" motions. These are superseded by the one just described, which is called a "jacking delivery motion," from $\frac{1}{2}$ an inch to $1\frac{1}{2}$ inches being usually delivered by it. The worm wheel K^1 or the pinion or gain wheel which gears with Q^1 can be changed to give more or less delivery. The wheel G can also be substituted by any other, when it is desired to change the twist by altering the roller delivery. The relative velocities of the different lines of rollers is obtained by means of the wheel train F^1 F^2 Z Z^1, of which Z is the change pinion. It will be noticed that the middle and back lines of rollers are driven one from the other at the same velocity by the intervention of the wheel Y, the draft being entirely put in between the front and middle lines. A change can also be made by substituting one size of rim pulley for another. On the back shaft H is a pinion R, which drives by the intervention of a carrier wheel the wheel R^1, which, although not so shown, is provided with a catch box similar to N, and by its means drives the shaft E as the carriage is moving in. This motion is that which gives a "roller delivery during winding," and its object is to ensure the delivery of a little yarn as the inward run of the carriage is made. It is found that the winding of the yarn is more effectively performed in this way, and that better twisting is obtained in spinning fine yarns by reason of the short length of unspun yarn thus delivered. The action of this motion is obviously similar to that of N, and the catch in the box on R^1 does not obtain command of E until the back shaft H rotates during drawing up. The full length of yarn wound is of course lessened by the amount delivered, whatever that may be. It is only necessary further to point out that this machine is driven by a belt on A during spinning, but that the backing-off and taking-in mechanism is driven by a rope separately driven from the

countershaft and gearing with the grooved pulley D^8. The actuation of the strap fork after the completion of the twisting is the work of a small crank arm driven from the worm on the end of the rim shaft, as in the case of the mule previously described. The points of adjustment in this mule are very numerous, and enable a wide range of counts to be spun. In all fine mules special provision is made for the relief of the fallers at the conclusion of winding, and this is a matter of some importance.

(296) Akin to the motions just described is the arrangement which is usually made to give to the spindles a differential speed. It is obvious that yarns which are very fine will not spin so easily as those which are coarser. They are necessarily weaker, and although requiring more drawing are more difficult to handle. Thus the yarn delivery motion is intended to obviate the danger of breakage owing to the additional stress put upon the yarn when it is shortened by the introduction of twist. In like manner it is the custom to give the spindles two speeds—one a comparatively slow one when the carriage is moving outwards, and the second a much quicker one when it has reached the end of its outward run. The most ordinary method of doing this is to place on the countershaft, as shown in Fig. 216, two sets of fast and loose pulleys, B and C, to receive two belts driven by the line shaft. There are in all six pulleys, three in each set containing a fast and two loose pulleys. The diameter of one set is smaller than that of the other, and the pulleys are so arranged that the two belts are never on their respective fast pulleys together. During the outward run the larger sized driving pulley has its belt upon it, and the second belt is on its loose pulley. The whole of the work is being done, therefore, by this belt. When the carriage gets nearly out, the changes take place which bring into action the jacking motion, at which time the carriage is moved very slowly. A rod E is connected at one end to a lever F, rocked by a cam G, rotated by a train of wheels from the back shaft, and operates the rocking lever H during the outward run, by the end of which

the whole of the weight is taken off the latter. It actuates the slide bar K, which is acted on by a spring L, but the latter cannot act until, by a bracket on the carriage, the setting-on handle M is released, thus freeing the slide bar K. The spring then draws the slide bar, and the strap on the larger pulley D is moved on to its loose pulley, and that on the smaller one on to its fast pulley. The setting-on handle is again latched until twisting is finished, when it is released and the lever H freed. The belt from the countershaft to the rim shaft pulleys remains until this

FIG. 216.

time unmoved. The consequence is that the spindles are revolved at a much quicker velocity for a short time, and twist is rapidly introduced into the yarn. It is obvious that, as the element of draft is at this period practically eliminated, the yarn is subjected to much less strain than it is when twisting and drawing are practically simultaneous although the shortening action affects it. As soon as the twist is fully in the yarn the rest of the changes take place, the two driving belts make a further movement on to loose pulleys, and backing-off com-

mences. The description thus given shows that the controlling element is outside the mule proper, and entails the employment of a considerable amount of mechanism. To obviate this, Messrs. Threlfall have adopted the plan shown in Fig. 217. In this case the rim shaft is in two parts, one D, the longer portion, going to the front of the mule, and the shorter portion C going to the back. The two portions are brought together end to end, and there are three pulleys A B A³ placed in the headstock on the shaft. Of these, the two outer A A³ are fastened on the shaft C and D respectively, but all are of the same diameter. On the back end of the shaft is fixed a rim pulley C¹ of the usual construction, and

FIG. 217.

on the other portion of the shaft, at the front of the headstock, is placed a second rim pulley E. The rim band C² is passed over the two pulleys so that it can be set in motion by either of them. It is at once obvious that if the two rim pulleys are made of different diameters two speeds can be given to the rim band in accordance with the position of the driving belt on either of the fast pulleys. Further, when the front rim is being driven the back one becomes merely a carrier, and *vice versâ*. The action is a perfectly obvious one, and hardly needs explanation. When the carriage is coming out the driving belt is on the back pulley A³, and the rim band is being driven from the back rim C¹. As the latter is the smaller of the two, it follows

that at this period the spindles are revolving at the slower speed. When the carriage gets out the change takes place, and the belt is transferred to the front fast pulley. In this way the front or larger rim begins to drive, and the spindles are given their full velocity. It is quite obvious that the employment of rims of different sizes will enable a large variation in the velocity of the spindles to be made, and in this respect the Threlfall motion is notable. It is much easier to change a rim pulley than a pulley on the counter or driving shaft, and, as in all mules, the rim pulley is fitted so as to be easily changed, there is no trouble in getting a different speed, while at the same time the speed of the countershaft may be changed if desired. The change is generally made at the back rim C^1, because the twist wheel is driven from the front rim shaft. As it is desirable always to maintain uniformity in twist, it is clearly the best to make all changes in the relative velocity of the spindles by changing the back rim. As shown in the illustration, the backing-off friction clutch A^1 A^2 is fastened on the back rim shaft C, it being found that it gives a better result, bringing the winding faller down with much more steadiness. Where the terminal speed is very high, a brake E F is applied to the front fast pulley, which is actuated by the connecting rod H from the backing-off friction clutch, so that the latter and the brake move into gear simultaneously. The part E of the brake is formed in the boss of the pulley A, and the part F, with ratchet teeth, with which pawls engage. The latter, when put into gear, prevent F from moving, although it can freely rotate in the ordinary course of work.

(297) The description thus given of the mule and its mode of operation has necessarily been a very lengthy one; but if studied, it will enable a clear idea to be got of the operation generally. There is one point which deserves some notice, and that is the question of the power required to drive the machine. This is considerable, but is variable throughout the cycle of movements which together make up mule spinning. As is natural, the greatest power is taken when the spindles are

revolving at their highest velocity during the period of spinning, the friction of the spindles during this portion of the operation being greatest. In "Oesterrich Wollen-Industrie" a record appeared of a number of tests made with one of Rieter's brake dynamometers, by which the power required is approximately settled. The mule which was tested contained 600 spindles, 1½ inch gauge, and was spinning 20's yarn. The rim shaft, when spinning, made 578 revolutions per minute, and the spindles 7,450. The outward run of the carriage occupied 8·6 seconds, and the recorded diagram showed a pressure on the lever at the beginning of 235 kilogrammes. During the first three seconds the inertia of the carriage and other parts actuated is overcome and the pressure falls to 115 kilogrammes, at which it remains until the stretch is completed. Backing-off lasts 2·2 seconds, and the power required falls to 10 kilogrammes. Winding began at the end of 10·8 seconds, and lasted 2·6 seconds. The power absorbed rose during 1·7 second from 10 to 50 kilogrammes pressure on the lever, but fell during the next ·9 second to zero, which it reached at the termination of the cycle of movements. The mean pressure during the trial was stated to be 101 kilogrammes, and by using the formula $x = \dfrac{P \times n}{t \times 75}$ the horse power absorbed is obtained. In this formula P = mean pressure; n = number of revolutions of dynamometer pulley indicated on counter; and t = duration of trial in seconds. Applying this to the case in question, the formula is worked out as $\dfrac{101 \times 66·5}{13·4 \times 75} = 6·68$, which gives the total horse power registered, but deducting the power absorbed by the dynamometer itself, the net horse power required is found to be 6·59. This gives the power required for 100 spindles as 1·098 H.P., which approximates very closely to that generally assigned to the mule. There is a singular lack of reliable data as to the power absorbed during the whole cycle of movements of a mule, and this test, although obviously made with a slow speed of carriage traverse, is valuable as

throwing some light on the amount required at various periods.
Thus the mean pressure during the period of spinning is 134
kilos., but reaches 235.   The rise of pressure during winding is
obviously affected by the increase in the velocity of the carriage
about the middle of the outward run, which is the moment
when the greatest weight is being moved at the highest speed.
Thus a good deal of light is thrown upon the conditions of
working, and it is to be hoped that some further experiments
will enable the point to be still further cleared up.

(298) The actual twist which is put into the yarn is never
equal to the full calculated twist, the variation arising from the
slip of the bands and similar causes.   It is obvious that the
bands will slip more at one time than at another, atmospheric
variations and several other causes contributing to this result.
The question as to what is the right amount to allow for the
slip of bands is one which is largely settled by personal experi-
ence, which is not always accurately recorded.   It will vary,
however, from three to eight per cent, and the latter figure is
often nearer the mark than the former.   It is requisite, therefore,
in making any calculations to remember this fact, as it has an
important bearing upon the subject.   There is a little difference
in the twist put into yarn when being spun on a cop either
partially or fully built, this arising mainly from the better grip
which the yarn has in the one case than in the other.   This is
not an important point, but it has a little bearing on the subject,
and causes a slight variation in the weight of a lea.   In doffing
a mule, after a set of cops is finished, the following procedure is
adopted :—The mule is stopped during backing-off and the
counter faller is depressed and fastened down at a point below
the cop by a special catch.   The cops are first raised a little by
placing the thumb below them so as to free them ready for
removal.   The winding quadrant and shaper screws are then
turned by hand so as to bring the quadrant nut and shaper
plates back to their initial position.   A turn or two of yarn is
then wound on the spindle below the bottom of the cop so as to
hold it sufficiently to enable it to be broken when the cops are

finally removed, which is the next operation. Thus there is a connection remaining between the spindles and rollers. If paper tubes are used they must be fitted on the spindles immediately the cops are doffed, and in that case the quadrant nut should be wound back a few turns to compensate for the increased diameter. From 6 to 10 turns will be found sufficient. The counter faller is released, the carriage run up to the rollers, and spinning re-started. After a few stretches have been wound and the cop bottom formed, the starch may be applied if necessary. The size or starch used for this purpose is made from potato flour or farina, principally, with a little tallow and soft soap mixed with it. It is boiled for about half an hour, and is taken to the mule in buckets or cans. A good plan has been adopted by which, instead of handling a large bulk of starch, it is boiled at some convenient point and pumped up to the mule rooms by a special pump, being discharged over a trough or tray, into which the surplus starch can fall and be again used up.

CHAPTER X.

RING SPINNING.

(299) THE machine which replaced the old spinning wheel was
founded upon it, and accordingly both Wyatt's and Arkwright's
machines were constructed with a flyer revolving round a common
centre with a bobbin. The only rival to the mule for many
years was the flyer or throstle frame, and in many respects it was
the most perfect spinning machine ever used, so far, at any rate,
as the character of the product was concerned. The throstle
consists of an arrangement of rollers by which the roving is
delivered, and of twisting mechanism. The latter is similar in
principle to the roving spindle, but differs in constructive details.
The spindle is borne by a footstep and bolster, and the bobbin
is placed loosely upon it. On the upper end of the spindle a
flyer, with two downwardly projecting arms with curls at their
extremities, is fitted by means of a screwed nipple. The flyer
eyes revolve with the spindle round the bobbin, and the yarn is,
after leaving the rollers, passed through the curl or eye of the
flyer on to the bobbin. The latter rests upon the rail in which
the bolsters are fixed, and is formed with a comparatively broad

flange, which is recessed on its under side. The bobbin has also an upper flange, and upon the cylindrical barrel between the two the yarn is wound—this space being the " lift " of the bobbin. Below the bobbin, and between it and the rail, flannel washers are placed, the object of which is to so far retard the rotation of the bobbin as to cause it to lag behind the flyer and thus wind on the yarn. There are two things to notice in connection with this operation. The first is that the flyer always maintains a definite and uniform velocity, which thus establishes a constant relation between it and the rollers. The second is that the bobbin is drawn round the axis of the spindle by the pull of the yarn, and is held back sufficiently to ensure that it will take up the same length of yarn which is delivered by the rollers. The moment the tension on the yarn increases beyond the normal amount the bobbin is moved, and thus a constant relative velocity of the bobbin and flyer is obtained. The conditions of spinning thus established are marked by two characteristics. They are eminently fitted to produce a very evenly twisted thread, and are equally likely to result in a strong elastic yarn being obtained. It is well established that flyer or throstle yarn is the most even, cylindrical, and regularly twisted which has yet been produced, and there is little doubt that two factors contribute to this. These are first, the fact that the twisting is effected by the rotation of an eye which travels in the same orbit at a uniform velocity ; and, in the second place, the moderate velocity at which the operation is conducted. The first point does not require demonstration, and is only made in order that some little light may be thrown upon the conditions prevailing in the modern method which is substituted for flyer spinning. The second consideration is more important, and there is little doubt that a comparatively slow delivery of the roving and a positive steady turning of it on its axis is much more likely to produce an ideal thread than any system where these two factors are absent. Whatever be the explanation, the fact remains, that no yarn has ever been produced which, for evenness, strength, and elasticity, compares with flyer yarn. As

FIG. 218.

he process now is comparatively obsolete it is not necessary to
expend many words on it, but it is worth while emphasising that

it is eminently suited for the
production of a high quality
of yarn, although confined,
mainly, to the coarser counts.

(300) The system to which
the name of ring spinning is
given is in its elements very
simple, and it will be most
convenient to give a brief
description of the machinery
employed prior to considering
the problems involved. For
this purpose a reference to Figs.
218 and 219, which are, respec-
tively, transverse and partial
sectional views of a ring
frame, may be made. The
roving bobbins are placed in a
creel, and the yarn is guided,
in the manner shown, to the
rollers E E¹, through which it
is passed and drawn in a similar
manner to that described in
connection with the mule. It
may, however, be said at this
point that it is desirable to put
in the drafts for slightly finer
yarns than are intended to
be spun. As twist is intro-
duced there is a little con-
traction of the yarn, and it
is desirable, to avoid thin
and uneven places, to deliver
a little greater length than that

Fig. 219.

which is calculated by the strict rule. After leaving the rollers the yarn is taken through the wire eyes F fixed in hinged boards known as "thread boards," and thence to the ring R. The ring is a small cylinder formed with a lip or flange at its upper or both ends, being constructed as afterwards described. It is borne in a rail or plate sustained at the upper end of round rods or pokers P, which are guided by the double rail shown, and which receive an alternate vertical motion by suitable mechanism. At the end of the pokers it is customary either to use a crossbar or a nipple fitting a corresponding hole in the rail. By a recent arrangement Messrs. Tweedale and Smalley place on the top of the poker a flat disc fitting on the nipple. The edges of the disc are turned taper, and the flanges of the ring rail are correspondingly bored out and tapered, so that the rail fits on to the disc when it is pressed down. This makes a neat and effective holder, giving great firmness without any obstructing parts. Fixed in the rail S^1 is the spindle S, which is accurately adjusted and fastened in the exact centre of the ring. Thus the conditions of the operation are not dissimilar in principle to the operation of roving, but are different in the fact that, instead of the bobbin being given an alternate reciprocal vertical movement, while the flyer eye remains stationary, it is fixed, so far as its vertical position is concerned, and the part corresponding to the flyer eye receives a motion of that character. The above is a general description of the mechanism, which may now be treated in detail. The rollers are sustained in roller stands A, which are fastened to a longitudinal beam B, and are, as usual, in two lines E E^1. They are weighted by means of stirrups G^1, levers G, and weights G^2. It is customary to form the roller stands A so that a line through the centres of the rollers is angularly disposed to the horizontal. The reason for this procedure will be explained presently. A revolving clearer D is placed above the top rollers, so as to take up the fly from the two lines, and an underclearer D^1 is sustained below the bottom front rollers. The thread boards are connected by levers H to a central rocking lever J which can be oscillated by means of a handle on the

end of the shaft on which it is fixed. The thread boards are separately hinged to a wooden rail, which is in turn hinged to the roller beam and turned up as described. Messrs. Tweedale and Smalley have a very neat arrangement, which is shown in Fig. 220. This consists in cutting out a circular groove in the edge of the roller beam A. In this groove a rod B rests, and is supported at intervals by small brackets E. It is formed with a flat side to which the thread boards are hinged, so that by rotating the rod the whole of them can be turned up, as shown by the dotted lines. It will be noticed that there is a shaft G with a handle fixed on one end, which runs transversely of the machine, and which actuates a bevel wheel in which are two pins K L, one of which engages with the rod H coupled at the

FIG. 220.

front to a short crank on the axis of B, and the other with a second rod H[1] which actuates the eyes on the other side of the frame. The rotation of the shaft G therefore moves H and H[1], lengthways, and so lifts the two sets of thread boards D and wire eyes F clear of the bobbin C, which can thus be doffed easily. This is the procedure when doffing the whole frame, but when one bobbin only requires removal the thread board D, which is attached to B by a hinge, can be lifted singly. This is a compact arrangement, and leaves the top of the roller beam quite clear.

(301) The mechanism described up to this point is that which is concerned with the delivery and guiding of the yarn to the spindles S. The latter are now entirely self-contained— that is, they can be fixed in position at one operation—and, as

presently shown, carry wooden spools or bobbins upon which
the cop C is wound. They are driven by bands from the tin
rollers T. The ring R is fastened in a light rail, preferably of
wrought iron, which is given a reciprocal traverse up and down.
The ring is usually of the shape shown in Fig. 221, but a better
form is that shown in Fig. 222, which is Coulthard's double ring,
and which is fastened to the ring rail by means of a special
fastener. Ordinarily, the ring is formed with a cylindrical
portion at its lower end, fitting a hole in the rail, to which it is
firmly secured. On the ring a small clip, made of special wire,
is sprung, being of such a size that it can freely rotate round the

Fig. 221.

Fig. 222.

ring, but cannot come off easily. This "traveller," as it is
called, is the means by which the twist is put into the yarn, but
has a twofold object, of which something will be said hereafter.
The yarn is passed through the traveller on its way from the eye
F to the bobbin. The pokers P rest, as shown, on the ends of
a crossbar X^1, which is coupled by the chain P^1 (Fig. 219) to
small grooved pulleys fixed upon a shaft running longitudinally
of the machine. Reference may now be made to Fig. 223,
which is an end view of the machine, showing the method of
driving. Driven from the main shaft of the machine by the
train of wheels indicated, is the shaft Z, having on its lower end

a worm K meshing with a worm wheel L. On the axis of the latter is a heart-shaped cam M, eccentrically mounted, against

FIG. 223.

which is constantly pressing a bowl in the lever M¹. Thus when the heart revolves the lever M¹ is given a reciprocating

movement which varies in velocity according to the speed and shape of the cam M. The lever carries a small barrel at its outer end, receiving by means of the rotation of the worm O, gearing with the wheel Q on its axis, a rotatory motion when O is rotated. This happens when a pawl, suitably placed, is caused to rotate the wheel U geared to the wheel O^1 on the axis of the spindle on which the worm O is

Fig. 224.

fixed. Thus, when the arm N is pressed down by the cam M, the chain W is unwound from the barrel P^1, which is thus caused to rotate along with the shaft on which it is fixed. Thus the motion of the lever M^1 is transmitted to the barrel P^1 and the ring rails, which receive not only a traverse of a definite amount, but are also gradually raised as building progresses. Another arrangement, which is often preferred, is that shown in Fig. 224, which is a partial front view, and in Figs. 225

and 226, which are detailed views of the mechanism. The lever M^1 has a winding barrel Q, as in the arrangement shown in Fig. 223, on which the chain Q^1 is wound. Q^1 passes round a guide pulley, and is carried to the quadrant R, which is fixed on a cross-spindle R^1, on which is also fastened the arm P^1, the end of which supports the poker P. It is evident that the ascent and descent of the lever M^1, obtained by the rotation of the cam M, will give a similar movement to

FIG. 225.

the pokers and ring rail. Referring now more particularly to Figs. 225 and 226, the spindle on which the winding barrel is fixed carries a ratchet wheel U, with which a pawl V^1 engages. U^1 is carried at the end of a curved lever V, which is centred on the spindle. Also adjoining the spindle is an adjustable slotted bracket W, which is coupled to V by a pin W^1, which is held in the bracket N fastened to the spindle. It will be seen that as the lever rises and falls, W^1 will traverse the slot in W, and thus rock the curved lever V and pawl U^1. The stroke of the pawl can be regulated by the adjustment of the bracket W. On the spindle carrying the ratchet wheel in either arrangement is a pinion which drives a train of wheels terminating

at one on the chain barrel. It is thus possible to vary the
effect of the stroke of the pawl, and cause the barrel to take the
chain Q^1 up at a quicker or slower rate as desired. In this way
the necessary provision can be made for the required changes
to suit varying counts of yarn.

FIG. 226.

(302) There are one or two points to be considered with
reference to the question of driving the tin rollers. As constructed
in Fig. 223 the two rollers T are driven by pulleys, not shown
in the drawing, but fixed on the driving shaft. From this the
wheel T^2 is driven, being compounded with the pinion T^1, which
is the "twist" pinion. The wheel T^2 T^1 is borne in a spindle

which, as shown, is sustained in bearings on an arm N centred on the driving shaft, and fixed in position by a bolt passing through a radial slot in the bracket N^1. The motion of T^1 is communicated to the pinions V on the roller shaft by the train of wheels shown. In such an arrangement as this the only point

FIG. 227.

of change is the twist wheel, and this involves, when low counts are being spun, a high speed of the front roller unless the driving pulleys are changed. In order to get a wider range of variation without difficulty the plan of driving by means of a rim band has been adopted. Such an arrangement is shown in Figs. 227

and 228.   In this case an endless cord passing over a rim
pulley on the driving shaft, which is placed above the framing,
is used, the band following the course shown by the figures.
It passes first from the rim pulley to one tin roller pulley over

FIG. 228.

the compensating or tension pulley, round the other tin roller
and compensating pulleys, and twice thence to the rim, and
again round the first tin roller.   The effect is that each tin
roller is thoroughly driven at a high speed, while at the same
time there is an additional change place at the rim pulley.   The

latter can be easily changed by slackening the band, by means of the compensating or tightening pulley, which, as shown, is carried on a pin fixed in a nut sliding in a slot in a bracket, and controlled by means of a square threaded screw. This arrangement is of great value in places where great changes in the counts spun often occur. In this country it is not so much felt, because there is little change in the counts spun on individual frames, but the matter is one of some importance on the Continent and elsewhere where spinning mills are not so well organised as they are here.

(303) The action of this mechanism is as follows :—When a cop or spool is commenced the ring rail is at its lowest position, as shown in both figures, and two or three coils of yarn which are passed through the traveller are wound on the spindle below the bottom of the bobbin. These have been wound on prior to the operation of " doffing "—that is, the removal of the full bobbins —and when the latter operation is carried out the yarn is broken, but does not require piecing up. The empty bobbins having been put on the spindles, the frame is started, and the rotation of the bobbins causes them to wrap the yarn round them, very soon breaking the connection with the spindle. The traveller is thus caused, by the pull of the yarn, to travel round the ring, and twist begins to be introduced into the roving. At the same time the lever M^1 makes its first reciprocal movement, which is one of slow ascent and of more rapid descent. The yarn is thus coiled on the spindle in a manner to be shortly described, and layer after layer continues to be wound in the same way. In the meantime the ratchet wheel U is actuated by coming into contact with the pawl, and the chain W is thus gradually taken up by the barrel Q, rotated as described. The result is that the shaft on which is the chain pulley P^1 is slightly rotated, so as to take up the chain which is coupled to the crossbar X^1. Thus the ring rail is gradually raised, so that it has a higher initial point at each traverse, and finally a spool C of the shape shown in Fig. 218 is formed. It is necessary to note that the length of each " lift "—as the reciprocal traverse of the ring rail

R

is called—remains constant throughout, and that the character of the reciprocations also remains the same—that is to say, throughout the process of building, the upward traverse of the ring rail is comparatively slow and the downward traverse comparatively quick. It is sought, in this way, to form a firm nose, and thus enable unwinding to take place without entanglement. The operation of building in a ring frame is not a complex one, but the velocity at which it takes place is, of course, regulated by the fineness of the yarn which is being spun. While there is no attempt in the ring frame to give any differential winding, which is the work of the traveller, there is, as shown, a similar method of laying the yarn so as to form binder threads, thus ensuring the firmness and security of the nose. The shape of the heart-cam controls this point absolutely, and the only object of the remaining building mechanism is to gradually raise the initial point of the lift. In the train of wheels, shown in Fig. 223, there is ample adjustment for many changes. The velocity of the traverse or lift of the ring rail can be varied by an alteration of the size of the pinion driving the train of wheels shown, but this involves a similar change in the velocity of the front roller wheels V. By varying the shape of the heart or cam M the relative velocity or extent of the upward and downward lift of the ring rail can be changed as desired.

(304) We now come to deal with the question of the relative adjustments of the rollers. As shown, the axes of the rollers are not in a horizontal plane, but are angularly disposed. The reason for this procedure is as follows : As the yarn emerges from the bite of the front rollers, it is essential that it shall receive the twist at once, as the velocity at which the spindles run and the tension put into the yarn, owing to its work in pulling round the traveller, alike tend to break the ends. It is obvious that if the yarn had to press against a part of the circumference of the front roller the twist would not readily pass the point of contact. It is thus necessary to provide an adjustment which enables the twist to run right up to the nip of the rollers, and this necessity becomes greater when softer twisted

yarns are spun. The practice is, therefore, to vary the amount of inclination according to the character of the work, and the range of variation being from 5 to 35 degrees. Weft yarns require the greater inclination on account of the smaller number of turns put into them. Not, only, however, is it necessary to set the rollers angularly, but the nip of the front roller must in some cases be as nearly as possible arranged so as to allow the yarn to pass to the traveller in a straight line from the rollers. If it were bent to an acute angle round the wire eye F, for instance, it would be detrimental to the best work, and accordingly there is a growing tendency to approximate the line to a straight one. Before leaving this point it may be stated that the most common angles adopted are about 35° for weft and 25° to 30° for twist yarns. This is one of the most important features in a ring frame, and upon it largely depends the success or non-success of the machine.

(305) The ring is made almost universally now of mild steel, and is constructed without a weld; being, after it is turned to shape, case hardened, so as to present a very hard surface on which the traveller can travel. The absolute cylindricality of the rings is essential, and users of them should see that they are free from defects of any kind. The traveller is a ◯-shaped clip which, as was said, can be sprung into place on the ring, but, when in position, is quite free from any binding contact. Something will be said, at a later point, about the necessary grading of the weight of the travellers used for the various counts; but, in the meantime, it is necessary to deal with the character of the spindles used. Without going into the history of the subject, which has been amply treated by the author in a book of earlier date, it may be said that the first type of spindle was similar to the mule spindle, possessing considerable weight, and was sustained by a footstep and bearing. It was not long before the vibration set up by the increased speed at which they were run led to the construction of spindles with a bearing well within the bobbin, so that the position of the bolster was practically raised to a higher point on the

spindle. To Mr. Sawyer belongs the honour of first applying this principle successfully ; but although the spindle bearing his name was very successful, it was not in existence long before it was superseded by the Rabbeth spindle, which was introduced into this country by Messrs. Howard and Bullough. The Rabbeth spindle is illustrated in Fig. 229. It possessed the chief feature of the Sawyer by having its upper bearings within the bobbin, but this very decided advantage was accompanied by another—viz., the fact that the whole of the bearings of the spindle were self-contained, only one setting being required. Referring to the illustration, the spindle B is carried in a bolster, which is bored so as to form a footstep F at its lower end and an upper bearing at C. At the latter point it is fitted with a nickel tube which is cut with a very coarsely pitched spiral groove by which the oil, contained in the reservoir formed by the space shelled out in the body of the bolster, is raised. The bolster, at the lower end, has a flange formed on it, below which is a screwed shank on which is fitted a nut. The shank is passed through the spindle rail S^1, as it is called, which is pierced by holes a little larger than the shank of the spindle, thus allowing for adjustment. Fitting tightly upon the spindle at a point a little above the upper bearing is a cast-iron sleeve E, formed, at its lower end, with a warve round which the driving band passes. On the lower end of the sleeve, just above the warve, is a cup D, which receives the lower end of the bobbin A. It is not, however, good practice to allow the bobbin to fit the cup, and it should be so constructed that it will only fit the spindle tightly at its upper end. The sleeve is prevented from rising by a device consisting of a hooked wire G, which can be arranged to swivel, or which, as in the example shown, is fastened in a small frame, hinged to the bolster, which can be oscillated as required, to allow of the sleeve and spindle being lifted out when required to oil. The great merit of the Rabbeth spindle lay in the fact that it contained sufficient oil to last, without renewal, for many months, and it had a very large employment in a short time. It was, however, found that

although a largely accelerated velocity was possible with it, the bobbins did not run as steadily as could be desired, for which reason it was, after a time, abandoned in favour of another form, to which the name of the "top" or "elastic" spindle was given.

(306) The elastic type is founded on the principle that any rapidly revolving body which is in slightly uneven balance will tend to assume such a position that, although its axis of gravity

FIG. 229.   FIG. 230.   FIG. 231.   FIG. 232

is out of the perpendicular, it will continue to rotate steadily in that position. This tendency is observable in humming tops, as everybody is aware, and it is the application of the principle to spindles which forms the basis of the "top" or "elastic type. It is not permissible, nor, for reasons shortly to be given, would it be desirable, that the variation from the vertical position shall be too great, and means are taken to limit the movement of the spindle. For all the practical purposes of spinning, however, the freedom of the spindle to assume its true axis of

gravity is absolute.   One of these forms—the Whitin swindie—
is shown in Fig. 230.   In this type the spindle A is sustained
by a bolster of the ordinary type, but rotates entirely in an inner
sleeve B, which is turned at D to a diameter about $\frac{1}{500}$ inch less
than the inner diameter of the bolster at that point.   The lower
end F of the sleeve is turned with a cup or recess passing over
a nipple formed in the bolster, and the upper end of this recess
fits on a small pad of cork placed on the top of the nipple.
There is a certain space left for the movement of the sleeve B
in all directions at its foot, and this, combined with the freedom
at the point D, allows the sleeve B to assume any position
required by the want of balance in the bobbin.   The oil is
introduced into the cup E, and is contained in the recess
shown, being raised in a similar manner as in the Rabbeth.
The sediment contained in it can be deposited at the point G.
Another form of elastic spindle is that shown in Fig. 231,
this being the invention of Mr. John Dodd.   In this case an
inner sleeve D is fitted, which is prevented from rotating by a
rectangular nipple C formed at its lower end.   The sleeve is
made of such a size that it practically oscillates on its upper end
when the exigencies of the case necessitate it, and it will be
noticed that there is an increase in the size of the spindle up to
and above the top bearing, by which, with a slight increase in
weight, great strength and increased steadiness is obtained.   A
small ring B is fitted which prevents the rise of the oil to a point
above the top of the bolster, and causes it to flow back into the
reservoir.   The spindle is driven, like the Rabbeth, by a short
sleeve formed with a cup for the reception of the bottom
of the bobbin.   There are a large number of spindles in the
market varying from those described in small details, but not
in any essential principle.   In some forms the bottom of the
bolster is open and is covered by a withdrawable cap, so
that the removal of the dirty oil and its substitution by fresh
lubricant can be easily effected.   In another form made, a
cork cushion surrounds the bolster at its upper end, thus
supplying the necessary yielding when required.   One of the

more recent developments which has received the test of actual practice is that shown in Fig. 232. This is the device of Mr. Thomas Wrigley, and is chiefly notable for the method of driving the bobbin. Only the spindle and bobbin is here shown, because the spindle can be fitted to any form of bolster as desired. On the spindle is fixed a warve, the upper portion of which is formed with a conical surface. On this rests a bobbin, turned out to a corresponding cone at the underside of its lower flange. Except for the contact thus established the bobbin is free, and is not in any way jammed on the spindle. The driving is wholly effected by the frictional contact of the bobbin and cone, and the bobbin is, instead of being of the shape shown in Fig. 229, double flanged with a cylindrical barrel between the flanges. The lift of the ring rail is, in this case, equal to the lift of the bobbin—that is, the space between its flanges—and the yarn is therefore wound throughout each traverse of the ring rail upon a surface of the same instead of upon one of a varying diameter. It is found that the driving of this type of bobbin is perfectly effected, and there are one or two features about it which will be dealt with in due course. In order to effect the removal of the oil, it is sometimes the custom to leave the bottom end of the bolster open, and cover it by a cup which can be readily applied or removed. By a recent invention, however, this plan has been improved upon, the inside of the bolster being formed with a multiple quick thread, which can be fitted with a plug or cup correspondingly threaded. A half-turn of the cup brings it into position, and it is so shaped at the top that a little further movement by a spanner makes it quite oil tight. A further development of interest is shown in Fig. 233. It consists of applying to the spindle an upwardly projecting tube, which is connected by a horizontal duct with the bolster. By filling the tube with oil a constant level of oil is maintained in the bolster, so that there is substantially bath lubrication. A hinged cover is fitted, as shown, which has a neb on it acting as a holder down for the spindle and

sleeve. It is perhaps necessary to say, in closing this brief description of the various types of spindles, that they are all **very** accurately constructed. By means of special machine

FIG. 233.

tools the greatest nicety is obtained in their manufacture, and they form one of the best instances of the admirable results of the systems of construction which have been adopted in recent years.

(307) We have now to consider the relations of the ring and spindle to each other. It is absolutely necessary that these two parts shall be concentric, and for this purpose means of adjustment are provided both for the ring and the spindle. In setting, it depends whether the fixed or elastic type of spindle be used, whether the ring is set to the spindle or *vice versâ*. It is a common practice to fix the spindle and set the ring to it when an ordinary Rabbeth spindle is used; but it is much preferable to reverse this procedure, and set the spindle to the ring when the elastic or top type is employed. It is quite clear that, owing to the fact that an elastic spindle may vary from the perpendicular, there may be moments during the lift of the ring rail, when the concentricity of the two parts is destroyed, but owing to the limitation of the motion of the spindle previously referred to, the amount of variation is not great. The relation which the sizes of the bobbins and rings bear to one another is a matter also of some importance. The bobbins used in ring spinning are very important factors. That shown in Fig. 234 is an ordinary Rabbeth bobbin, and that in Fig. 235 an improved type. All the efforts of inventors during recent years have been directed to strengthening the bobbin at the foot, mainly by means of metallic shields or protectors, and as now made there are bobbins to be obtained which are noteworthy in this respect. The spool shown in Fig. 236, is used for spinning weft yarns. It is well established now by practice that the best results are obtained in spinning certain counts with a ring of a definite diameter. Thus counts of about Nos. 28 to 32's can be well spun with a 1⅝ inch ring, and it is important that the size of the full and empty bobbins is carefully adjusted to suit this. The reason of this will be explained immediately, but in the meantime it is well to record the fact. It is especially desirable to remember this when dealing with the finer numbers, but it always has a considerable bearing upon the case. In the instance given above a bobbin of ¾ inch diameter when empty and 1½ inch when full will give good results. Generally speaking a difference of ⅛ inch in the

respective diameters of the ring and full bobbin will give sufficient clearance for practical working, but less than this amount should never be given. The setting of the building motion should, therefore, be such that as soon as the full size is reached the gradual elevation of the ring rail which takes place will be sufficient to build the spool of a cylindrical form. Care should be taken to see that all bobbins are free from defects,

FIG. 234.   FIG. 235.   FIG. 236.

and that the spindles and rings are kept clean, for, as will be shown, it is a matter of great importance to maintain perfect cleanliness.

(308) Enough has now been said to enable the principle of the ring frame to be dealt with, and for this purpose a reference to Fig. 237 may be made. In this figure A represents the spindle, B the empty bobbin, C the full bobbin, and D the circumference of the ring. It will be noticed that, assuming the yarn

to be passing through the traveller at the point E, it is taken to the surface of the full and empty bobbins in a line disposed tangentially, in each case, to the circumference of the ring. The traction thus exercised upon the traveller causes it to rotate round the ring at a velocity which depends upon that of the spindle and the diameter of the latter. For the present it is only necessary to note that this is the manner in which the traveller receives its motion, and that the yarn, in passing from the rollers to the bobbin, is bent round at a sharp angle—practically, at a right angle—to the vertical line occupied by it as it travels from the rollers. It is quite obvious that in the length

FIG. 237.

between the traveller and the bobbin a considerable tension will exist, and that as all that is taking place is the direct passage of the yarn on to the bobbin there cannot be any turning of the yarn upon its axis, which is necessary to put in twist. The latter is put in by means of the rotation of the traveller at a defined relative velocity during the delivery by the rollers of a definite length of yarn. In short, the traveller performs the same functions as the flyer eye in the throstle or the presser eye in the roving frame. It is, however, necessary to note that the motion of the traveller, instead of being obtained from any direct connection with the spindle, is one which is only derived from it. In ring spinning the primary rotation is that of the

spindle, that of the traveller being purely secondary and derived.
The effect, however, is that being caused to rotate round the
ring it gives a rotating movement to the thread, and twists it.
It is a corollary from this that the velocity of the spindle deter-
mines that of the traveller, which, in turn, fixes the twist intro-
duced into the yarn. The traveller, therefore, plays an impor-
tant part in the economy of the ring frame, and it is highly
necessary to understand its precise action. In addition to the
effect which it has upon the twisting of the yarn, it also has the
function of causing the winding of the yarn upon the bobbin.
In order to enable it to do this its weight is arranged so that it
will lag behind the periphery of the spindle sufficiently to enable
the length of yarn delivered by the rollers to be wrapped on the
bobbin. There is thus a two-fold action going on, in con-
sequence of the rotation of the traveller, and, as there is much
misapprehension existing as to its precise action, it will be as
well to enquire into its operation in each case.

(309) Referring to Fig. 237, it will be seen that the traveller
receives a pull in two different ways when the yarn passes from
it on to the full bobbin C and the empty bobbin B. In the
latter case the pull is more directly towards the centre, and is
not, therefore, so well suited to draw the traveller round the
ring D. To make this point clear, let it be assumed that the
yarn was drawn round the ring before going to the bobbin; it
can at once be seen that the tractive force exerted would be
such as to cause the traveller to rotate at the speed at which
the yarn moves. The nearer the yarn approaches a radial line,
the less the tractive force which is applied becomes, and, con-
sequently, the slower relatively the rotation of the traveller.
This is one source of loss, but there is another of equal import-
ance. The power exerted is applied from the periphery of the
bobbin at every point, and consequently is varying throughout
the lift of the ring rail. Thus, the yarn when held at the base
of the cone formed during building, is—if the full bobbin be
$1\frac{3}{4}$ inch diameter—being carried round through a space of
4·31 inches at each revolution. When it is held on the surface

of the bare bobbin, which is ¾ inch diameter, it only travels at the rate of 2·35 inches at each revolution. It is thus clear that, if no retardation of the traveller took place, it would travel during each revolution of the spindle a distance equal in each case to that stated. The effect of this upon the twist is easily seen. Suppose that 100 revolutions of the spindles are made in each case, and the rollers deliver 5 inches of yarn, the effect would be that the traveller in one case would travel 431 inches, and in the other only 235 inches. The circumference of the ring being 5·1, this means that the traveller makes 84·5 and 46 revolutions respectively. There would thus be introduced into the yarn 16·9 and 9·2 turns per inch respectively at each of these periods, which is a considerable variation. This instance illustrates the principle, and shows the effect of the varying diameter of the bobbin; but the reader should be warned against supposing that this degree of variation actually occurs. It will be shown presently that there are a number of elements entering into the problem of more or less importance and complexity. There is, beyond doubt, a considerable influence exerted by this factor alone, but it is partially overcome by others, to which reference will be made. The fact remains, however, that the smaller the diameter of the bobbin the slower the speed of the traveller.

(310) This variable size of the bobbin has another effect besides that on the question of twist. It was shown in dealing with the roving frame that an increased diameter of the surface upon which the yarn is wound necessitates a reduction of its velocity. This is obtained in the roving frame by a reduction of the velocity of the bobbin, which there rotates independently of the flyer eye. It is obvious that this solution of the difficulty is not possible with the ring frame, because the flyer eye, or its equivalent—the traveller—only receives its motion as a consequence of the rotation of the bobbin with the spindle. In one sense there is a resemblance between the roving and ring frames to the extent that each has a bobbin lead, but the resemblance in this respect only deepens the contrast actually existing.

This point may be briefly put as follows : The bobbin in the roving frame draws the roving on to it by reason of the excess of its speed over that of the flyer, both of these factors being determined by suitable mechanism. The bobbin in the ring frame winds the yarn on to its surface because of its excess of speed over the traveller ; but the rotation of the bobbin is constant, while that of the traveller is slower only on account of its retardation from various causes. The amount of lagging is determined by a set of conditions to which fuller attention will be presently given. The problem of winding in the ring frame is also like and unlike that of the mule. Here also there is the difficulty of winding on a surface of variable diameter, and taking up a given length of yarn. But the likeness does not extend further, because the spindle in this case rotates at a uniform velocity, and the roving is being constantly delivered to the bobbin. Thus it is clear that other means must be found to enable the yarn to be wound throughout building at an even tension. Reverting to the illustration given in the last paragraph, where the diameters of the full and empty bobbins were 1⅜ inch and ¾ inch, and their circumferences 4·31 inches and 2·35 inches each, it will be seen that when the yarn is being wound on the smaller circumference it will require more revolutions to take up any given length of yarn delivered by the rollers than when it is being wound on the larger diameter. But we have shown that the velocity of these two points is uniformly the same, so that they cannot take up more than the lengths named at each revolution. To ensure proper winding, therefore, there must be some compensating arrangement, and this is found in the variable motion of the traveller previously referred to. It was observed that it was not likely that there would be between the highest and lowest velocity of the traveller the variation calculated in the manner given. The matter which really determines the amount of lagging of the traveller is the tension upon the yarn between it and the spindle combined with the direction of the pull exercised on it. The action which takes place is affected by these two factors in different degrees at

different times, but they are always the determining factors.
If the spindle is revolving at 1,000 revolutions a minute during
the time the rollers are delivering 50 inches of yarn, the first
result is that the yarn receives 20 turns per inch.   But the
tension put upon it during the rotation of the spindle drags the
traveller after it, at a velocity depending entirely upon the main-
tenance of this tension.   Suppose that the tension is relieved
by a slightly increased delivery of yarn, the effect would be that
the traveller would lag until a tension was again established
sufficient to overcome its resistance and drag it round the ring.
Thus, the pull upon the traveller is entirely determined by its
weight, the speed of the surface of the bobbin, and the delivery
of the yarn by the rollers.   It can thus be seen that the weight
of the traveller must be graded so that it will lag behind the
bobbin at all times to maintain a uniform tension sufficient to
cause the bobbin to take up the same length of yarn as that
delivered by the rollers, less the shortening consequent upon
twisting.   It follows, therefore, from this, that, as the bobbin
will only take up, when the yarn is being wound on the nose,
2·35 inches of yarn, while it will take up 4·31 inches when it is
being wound on the full bobbin, there must be a variation in
the speed of the traveller of a like amount.   This is presuming
that the ring rail remains opposite each of these points for the
same length of time, but, as a matter of fact, this does not take
place.   Owing to the shape of the builder cam or heart, there is
a great variation in the speed of the lift at various points, and
this has an influence upon the problem.   The smaller diameter
of the bobbin would necessitate more rotations of the spindle to
wind the same length, and as it cannot get this, the tension on
the yarn becomes relaxed, the pull on the traveller consequently
relieved, and the latter falls behind the bobbin a little more, on
account of the decreased tension.   The converse of this is the
case when the yarn is being wound on the larger diameter, the
traveller being then · drawn a little further forward.   Thus, sup-
posing the front roller to be 1 inch diameter revolving 100 times
per minute, and the full and empty bobbins to be of the sizes

given, then the following will be the result. In every minute
314·16 inches of yarn would be delivered by the front roller.
Now, the circumference of the empty bobbin being 2·35 inches,
the traveller would have to lag behind the bobbin 314·16 ÷ 2·35
or 133·7 turns. When the yarn is being wound on the full bobbin,
with a circumference of 4·31, then the lagging is 314·16 ÷ 4·31 or
73 turns, nearly. Assuming the spindle speed to be 9,000 revo-
lutions, then the relative velocity of the traveller, at each of these
points, is 8,866·3 and 8,927 revolutions respectively. In other
words, the twist would be, in each case, 28 and 28·4 respectively.
This more nearly approximates to the actual condition of things
than the calculation previously deduced from the speed, but
neither of them are actually exact. The above gives an accurate
theoretical explanation of the action of the traveller, both in its
effect upon the twist and upon winding, and it is, in the main,
correct, when applied to practice. There are, however, one or
two considerations which require taking into account, and which
very materially modify the conclusions thus arrived at. It is
quite true that if the variable speed of the traveller, to which
reference has been made, takes place, there will be a considerable
difference in the twist of the yarn, but it can also be seen that
the greatest amount of twist should, according to this reckoning,
be found in the yarn at the base of the cop and the least in
that at the nose. Between these points there should be, accor-
ding to this theory, a gradual increase or decrease of twist accor-
ding to the direction of the lift of the ring rail and, acting on
this assumption, calculations, such as that given, have been made
by which the exact variation between the maximum and mini-
mum is obtained. The observations of the author have led
him to reject this theory in its entirety, and a few words may be
expended to make the matter clear.

(311) So far the demonstration has proceeded upon the
hypothesis that the only forces which affect the traveller are
the pull of the yarn being wound and the weight of the traveller
itself. It does not, however, require much thought to see that
these are the converse of and antagonistic to each other, and

that each has other effects than those just stated. The tendency for every rapidly revolving body is to fly outwards from the centre, which it will do unless it is controlled. Now it is quite clear that a traveller, although a comparatively light body, is yet by reason of its high velocity necessarily impelled to move from the centre round which it revolves. Its motion in this direction is, however, limited in two ways, viz., by the ring and by the pull of the yarn between it and the ring upon it. It is quite clear from the construction of the parts that a very slight outward movement would bring one end of the traveller into contact with the inner surface of the ring, and thus retard its motion. On the other hand, the pull exercised upon it by the yarn draws the traveller away from the ring, and thus prevents this friction taking place. There are, therefore, two forces which play an important part, each of which is the complement of the other. It is when they are balanced that the most steady rotation of the traveller is obtained ; but the description of the action of the bobbin recently given shows that there cannot be any preservation of this balance throughout the lift of the ring rail. When the centrifugal force exerted by the traveller is exactly met and held in check by the tangential pull of the yarn, then the traveller will revolve round the ring without any appreciable friction, and the drag depends entirely upon its weight. It is obvious that this set of conditions can only exist at one point, and that when it is necessary for the traveller to fall back in order to wind on the yarn, as is the case when the ring rail is opposite the nose of the spool, this balance, if it previously existed, is destroyed. There must be therefore periods when each of these forces is in the ascendant, and when that is the case there will be entirely different results obtained. When the pull of the yarn, owing to the large diameter of the bobbin, is at its maximum, then the traveller will, as was shown, rotate at its highest speed. In this case its momentum is necessarily increased, and it will tend to overrun the yarn and fly out. When it makes a slight outward movement it comes into contact with the ring, and the

speed of its rotation is immediately checked.   But so long
as the surface speed of the bobbin is large, the drag on the
traveller is sufficient to re-establish its velocity and momentum.
The effect is that throughout the building of a bobbin there
is a constant series of alternate accelerations and retardations
of the velocity of the traveller, according as the centrifugal
or tangential tractional forces are in the ascendant.   The
"balloon," as it is called, also affects the problem to some extent,
as will be presently pointed out.   It is therefore easily ascer-
tainable by careful observation that instead of there being the
maximum twist put in at the base of the cop and the minimum
at the nose, the amount varies throughout the whole of the lift
of the ring rail.   It is customary, as stated, to base all calcula-
tions of the loss of twist upon the difference in the maximum
and minimum circumferences of the bobbin, as if no other factor
entered into the calculation.   For the reasons stated, the author
is of opinion that this is an erroneous assumption, and his
attention was first called to the subject by an observation made
to him by a gentleman of long experience in ring spinning.
This was to the effect that although there was a good deal of
talk about loss of twist at one point, it was very difficult to find.
Observation has led the author to come to the same opinion,
with the modification that throughout the whole length of a
ring cop there is a variation of twist occurring, and that it does
not merely happen at one point in each lift.   The rapidity with
which each lift is made is sufficient to prevent the traveller from
entirely losing its momentum when it is opposite the nose of the
cop, although it will naturally tend to do so, and on this account
the difference in twist arising from the variation in circumference
is not so great as a calculation would show it to be.   That there
is a difference is certain, but the conditions under which the
operation is conducted are such that it is impossible to localise
the place where it occurs.   The action of the traveller is an
extremely complex one, and depends on several conditions,
which may be summed up as follows : The velocity of the
spindle, the velocity of that portion of the surface of the

bobbin, on which winding is taking place, the weight of the traveller, which affects its centrifugal action and the amount of its retardation, and finally, the direction of the pull of the yarn towards the bobbin. If the remarks previously made were not considered, it would be seen that there are several opposing elements existing, and that it is extremely difficult to establish a balance between them. Although great care is taken in grading the weight of the traveller so that the most regular action takes place, it is impossible under the conditions of practical work to obtain an equilibrium of forces. Even if it were perfectly established, a small change in the tightness of the driving bands, the speed of the engine, and many other causes would lead to its destruction. Thus it is deduced that throughout the practical operation of the machine there is a continual variation in the effect of the traveller which is faithfully reproduced in the yarn. So far as the author is concerned, it appears that the difference in twist exists alike in the yarn wound at the base and at the apex of the ordinary cone, and actual countings of twists have shown this assumption to be correct.

(312) Reference was made a short time since to a method of winding ring yarn on a cylindrical surface, which was shown in Fig. 231. Now, in this case, it will be seen that throughout each lift the circumference upon which the yarn is wound is approximately equal. It follows, therefore, that the amount of the tangential pull upon the traveller will remain the same from the beginning to the end of each lift. Under these circumstances it might be expected to find a greater evenness in the twisting of the yarn than in that spun in the ordinary manner. The variation observed is naturally greatest between the initial and terminal lifts, which is not altogether an advantage, especially when two ends have to be doubled together. Careful tests, made by independent observers, show that, as gauged by the strength of the yarn, this is undoubtedly the case, and this is, perhaps, as good a rough test as can be applied. But even with this system there is evidence of the alternate preponderance of the centrifugal and frictional forces referred to, and it appears

to be inseparable from any system of ring spinning. The subject is one of great interest, and opens a field for the observer which ought not to be neglected, and regarding which it is probable that some important facts may be brought to light. There is one advantage in this method of building a ring bobbin, which may at this stage be referred to. A greater length of yarn is wound on each bobbin, and in unwinding, a higher speed can be obtained, owing to the fact that for a considerable period the yarn is being drawn from a circumference of the same size, instead of being unwound from a surface varying considerably within a comparatively short length. On the whole, however, the characteristics of ring spun yarn are preserved, and there is no reason to doubt that although one of the elements which tend to vary the twist is removed, the rest remain and exert their due influence.

(313) It is now necessary to say a few words on a subject of extensive interest, which has received a large amount of attention without, however, having been very successfully dealt with hitherto. We refer to the question of spinning, as in the mule, on the bare spindle. The importance of this may be understood when it is stated that a large quantity of yarn is exported in the cop; that a still larger quantity is sent from spinning mills to the weaving factories in that form, and that weft cops are used, as they are produced, in the shuttles of looms to an enormous extent. If, therefore, it is necessary to wind the yarns on bobbins in the spinning frame, this implies the carriage of the bobbins to and from the place to which the yarn is sent, which, in addition to an increase in the cost of carriage, is also subject to the disadvantage of the loss of large numbers of the bobbins. Further, when weft is so spun, the length put on each spool is somewhat decreased, this involving more frequent renewals in the loom. For these reasons—which are, of course, of greater cogency when the yarn is used in establishments apart from those in which it is spun—the spinning of ring yarn is somewhat handicapped, but, as will be shown hereafter, there are a number of advan-

tages which must be set against the disadvantages. At the
same time a solution of the problem of spinning on the
bare spindle would be of enormous advantage to spinners, and
it is not therefore surprising that many strenuous efforts have
been made to accomplish it. The chief difficulty has been found
in the direction of the pull of the yarn when it is being wound
on the spindle at the nose of the cop. Referring to Fig. 243,
it will be seen that at this point the direction of the yarn from
the ring to the spindle is almost a radial line, and that in
consequence very little traction is at this point exercised on the
traveller. Now although it is quite true that the momentum
of the traveller must not be neglected, it is not sufficient to
maintain the balance of forces to which attention has been
directed. In addition to this, the angle at which the yarn is
bent is much more acute, and therefore the strain on the yarn
at this point is greater. Weft yarn is more commonly spun on
the bare spindle, and as this is more softly twisted than warp
yarn, it follows that this excess of strain is thrown upon yarn
in which the cohesion of the fibres is less than in other varieties.
Thus all the elements of the case are against the successful
accomplishment of the operation, and it is found, that it is
precisely at the point where it might be looked for, that failure
takes place. The defect of most of the machines constructed
for this purpose has been the difficulty experienced in restarting
the machine, when it has stopped with the ring rail opposite the
nose of the cop, without an excessive number of breakages of
the ends. The explanation of this occurrence is found in the
fact that the friction of the traveller and of the yarn through it
is greater at this period than at any other. This has been
noted by several observers, and coming at the period when the
direction of the pull is also nearer the radial, the strain is too
severe, thus leading to breakage. A few particulars of the
various devices adopted in the endeavour to overcome this
trouble will not therefore be without interest. One of the
earliest methods used was to give the ring rail such a velocity
of traverse as to cause it to move much faster than usual as it

left the nose of the cop. This plan was only partially successful and in the most important feature it was practically a failure. After this attempt the only approximately successful efforts have proceeded upon the principle of diverting the course of the yarn from a straight line. The traveller D was constructed (as in Figs. 238 and 239) with two loops or hooks, C and E, and the yarn passed under the first of these, which was in a position corresponding to the ordinary traveller, thus having the twist put in in the usual manner. The second loop or eye C lies close up to the surface of the bobbin or spindle, so that as the latter revolves it sets up such a pull on the outer end of the traveller as to cause it to move rapidly round the ring. The traveller, in fact, was a lever with its fulcrum on the spindle, and the appli-

FIG. 238   FIG. 239.

cation of the force of the yarn was sufficient to cause its outer end to move rapidly in a circular direction. The fulcrum or inner end of the traveller is, of course, always changing its position, being retarded in the usual manner, and so effecting the winding. In the instance illustrated the ring was in two parts, A and B, and the traveller worked in the groove between them. Although machines thus constructed were fairly success-ful, they were not completely so, but they constituted a very considerable advance on anything previously devised. The mastery of this problem may be accomplished in time, but it is surrounded with difficulties, and is accompanied by many features of mechanical intricacy.

(314) There is another matter to which reference may be made at this point. A reference to Fig. 219 will show that,

between the wire eye F and the ring R, there is at times a considerable distance, especially when the building of the cop is just commencing. The result is, that even when the ring is at its highest point in each lift, there is a certain length of yarn which is being carried round at a high speed by the rotation of the traveller. In its passage through the air it naturally encounters a considerable resistance, and this combined with the centrifugal force set up causes it to fly outwards, so as to assume the shape shown in Fig. 219. This is called, technically, "ballooning," and it is not without some advantages. Ballooning is caused largely by the centrifugal force of the yarn between the thread board and the traveller, and it follows that the greater this distance the more ballooning is produced. It is clear that precisely the same effect will be produced by the tension in this length of yarn as is caused by the tangential tension. In either case the traveller is drawn in the direction of the tension, and is aided in its rotation. Thus a well-formed balloon permits of a heavier traveller being used, while its limitation necessitates a lighter one. It is quite certain, from the facts which are available, that the tension of the "balloon" thread, as it may be called, must be taken into account in considering the balance of forces which exists and effects the problem of spinning. As, however, the distance from centre to centre of the spindles is limited, if there is too large a balloon the "ends" of yarn lash, become entangled, and break. Means are therefore adopted to check this tendency, and restrain the distance which the yarn can fly out. These consist of the placing of guards on each side of the spindle, so that the ends are limited in their outward movement. Devices of this character are in this country called anti-ballooners, and in America separators. The most primitive method of checking the balloon is that shown in Fig. 240, which consists of the placing of a wire B, held in the fingers A, hinged on brackets fixed to the roller beam at a point behind the spindle. The wire ran the whole length of the frame and met and checked the balloon. In another device the anti-ballooner consists of a plate A mounted on supports fixed to either

the ring or spindle rail, and shaped as in Fig. 241. The gaps are cut out so as to give a clear space at the back while confining the balloon at the sides, as shown by the

FIG. 240.

dotted lines, and the projecting pieces B enable the adjoining balloon to be kept quite clear. In the arrangement shown in Fig. 219, a second rail R¹ is employed, which is formed with

FIG. 241.

holes surrounding the bobbins of such a size as to permit of the formation of a certain size of balloon. This procedure is found to be advantageous, as it is proved by practice that if the yarn is not unduly restrained it greatly aids the drag of the

traveller, and that, in consequence, a lighter traveller can be used than is otherwise possible. The balloon rail R^1 is mounted on the ends of pokers R^2, which receive movement from the same shaft as the ring rail, but have a reciprocal traverse much more limited in extent. Thus, the balloon rail rises with the ring rail, and its motion is arranged to give, as nearly as possible, the best results. Although this device has undoubtedly many merits, there is one feature in connection with it which ought to be mentioned. There is of necessity a certain retarding influence in the friction of the yarn against the separator or guard, which is not without its influence upon the twist, because the greater the length of yarn between the thread guide F and the ring rail R, the greater the tendency to balloon, and the consequent frictional contact of the yarn and separator. Before leaving this subject, it is necessary to say that there is a well-defined influence exerted alike by the guide F and the position of the balloon guard or separator. If the angle formed by the yarn on passing through the wire eye is too great, the twist cannot pass up to the bite of the rollers, and is practically put in in two stages. If the separator is too low, relatively, to the length of yarn, between the wire eye and the ring, instead of checking the balloon at its larger diameter it does so below that point, and consequently the yarn presses over the top of the separator, with the necessary consequences. The most recent type of device is that which consists of a thin plate or casting which is introduced between adjoining spindles. It is this device to which the distinctive name of "separator" is given, although, as said, this is substantially applicable to all devices used for this purpose. When originally designed, the separator plates were fastened either to a fixed rail or to a rail attached to a poker which could rise or fall with the ring rail. In either case the fixing of the position of the separator became difficult, and the best effect was never produced. In the device shown in Fig. 242, which is the invention of Mr. Alfred Hitchon, these difficulties have been overcome. In order to economise space, the frame end is shown as broken off, but the spindle mechanism is shown

at each side. The reference letters used for parts other than
those now dealt with are the same as those in the other illustra-
tions. The ring rail R is cut away at the back so as to receive
and act as bearing for a rod T, to which a partially rotary move-

FIG. 242.

ment is given. The rod is kept in position by small brackets
fixed to the ring rail, but not shown in the drawing,. The sec-
tion of T is such that when fitted in the eye of the separator
plate M, the latter is practically fixed to T. The separator plate
is shown at the left hand side in working position, and it will

be noticed that it must rise and fall with the ring rail. It follows that there is always a considerable length of the balloon enclosed between the bobbin and separator, a factor which is absent in all devices which consist merely of thin plates, but one which has a great influence upon the operation. Looking at the right hand view in Fig. 242, the separator is shown in position when the bobbins are being doffed, and it is clearly seen to be quite out of the way of the operative, in which respect it differs from all fixed separators. As the ring rail rises when the frame is restarted, say into position R^1, the separator comes into contact with a curved bracket H, and is thrown into the position M^1. It will be noted that gravity, which kept M in its backward position, now ensures its falling forward into working position, and as the rail rises to the position R^2, M takes the position M^2. The guide brackets F are cut so as to permit of the passage of M between them, and thus, at all points of the lift, the separator is in position presenting the greatest surface when most required. The employment of this device permits the gauge of the spindles to be largely decreased, as shown in the plan view, without any risk of lashing of adjoining ends. The drag given to the yarn has also led to the use of much lighter travellers without affecting the winding, which is a most important point. Larger bobbins and rings can be used, and counts so fine as 36's can be spun with 2 inch rings, the gauge of the frame being only 2⅝ inch.

(315) There are, therefore, a well-defined set of conditions which affect the proper carrying out of spinning on the ring frame, and they may be summarised thus : A correct inclination of the roller stand, a definite ratio between the diameter of the ring and size of bobbin, a traveller of correct weight, and an effective separating appliance. The second and third of these are the most important, and although the principles on which they are founded have been fully explained, there are several considerations which still require noticing. With reference to the relative size of the bobbin and the ring this is important, because of the direction of the traction on the traveller, which,

if varying to any great extent, has an important bearing on the character of the product. This is especially noticeable when spinning the finer yarns, and as there is, especially in America, a determined effort being made to spin the finer counts on the ring frame, the subject is of importance. Thus, in spinning 100's yarn at a spindle speed of 10,000 revolutions per minute, the ring used was $1\frac{5}{8}$ inch diameter, and the bobbin $1\frac{1}{16}$ inch, leaving only a difference of $\frac{9}{16}$ inch. Allowing for the clearance of $\frac{1}{8}$ inch between the ring and full bobbin, this reduces the difference in the space to $\frac{7}{16}$ inch, or in other words, only $\frac{7}{32}$ inch of yarn is wound on the bobbin. The diameter of the bobbin when full is, therefore, $1\frac{1}{2}$ inch, and a little examination will show how small is the difference in the velocity of the ring at the two points. At a velocity of 10,000 revolutions, the traveller would—neglecting its drag—move through 33,379 inches when the bobbin was empty, and 47,124 inches when it was full. If this be compared with the calculation given in paragraph 310, it will be seen that the loss of speed, and consequently of twist, is proportionately much less between the full and empty bobbin than it was in the case there supposed. Further, the necessary difference in the retardation of the traveller to wind on the yarn is considerably reduced, owing to the smaller variation in the diameter of the full and empty bobbins. It is evident that this is the true condition when dealing with fine yarns, which possess much less absolute strength than do the coarser counts. A variation, which in the former case was permissible, would be in the other fatal, and this is a fact which must not be lost sight of. There is, therefore, a close connection existing between the size of the bobbin and that of the ring, and it will be easily understood after this explanation upon what principle the sizes are adopted, but in order to make the matter clear, a full sized diagram is given in Fig. 243 illustrative of this point. If the direction of the yarn in its passage from the traveller to the full and empty bobbin A and B be compared with the line A C, it will be seen that the variation in the angle formed by it in the former case is slight

when compared with the latter. Usually, counts from 10's to 26's are spun with a ring 1¾ inch diameter, and from 28's to 40's on one of 1½ inch, or 1⅝ inch diameter.

(316) We now come to deal with the second of the two special points named—the weight of the traveller. The traveller is, as may be easily imagined, probably the most important instrument in ring spinning, and performs a variety of functions. Not only does it guide the yarn from the ring to the bobbin, but, as has been shown, it is the means by which it is twisted Equally as important as these functions is that of regulating the tension so as to lead to effective winding. Not only is its weight of importance in that respect but its form also, and this

FIG. 243.

latter feature furnishes grounds for careful study. If a traveller which is too heavy is adopted it is evident that not only will the tractive force necessary to rotate it be excessive, but the traveller will not accommodate itself so readily to the variable pull exercised. When it acquires its full speed its momentum will be so great that it is likely to overrun, and thus wind imperfectly. On the other hand its weight would prevent it from acquiring the full speed, and the result would be that an excessive tension would exist. A traveller which is too light would be so easily moved that its retardation would be very imperfectly obtained, thus causing over-running, and the result would be that the winding would be only partially effected, so as to produce a soft

bobbin. Over-running takes place in this case to a much larger extent than with a heavy traveller. It is impossible to give any empirical rule by which the weight of the traveller can be arrived at, as many considerations enter into the calculation. The temperature of the spinning room, the velocity of the spindles, and the amount of fly which collects have each an effect upon the traveller. In consequence it is necessary for the attendant or overlooker to carefully grade the traveller in accordance with the observed conditions, and a little practice speedily enables the right weight to be determined. The travellers are made of certain sizes of wire, so that a given number have a definite weight. The basis upon which travellers are graded is kept a secret by the makers, but the general practice can be ascertained by weighing a few sizes. The travellers of ⌒ shape are most commonly used, and a certain number of any size equals an ascertainable weight, or conversely a fixed weight will contain a definite number of travellers, according to the size. A second system is to make what are called grain travellers, which are made from wire of triangular section, and which advance one grain in weight for each size. They are accordingly designated by certain numbers, which can be referred to when necessary. There are two standards of weight, one being that adopted in Scotland and the other that used in the United States. A few common sizes are given herewith, but it must be distinctly understood that they are only given as a guide and not as fixed practice.

SIZES OF TRAVELLERS AND RINGS.

MESSRS. HOWARD AND BULLOUGH'S FRAMES.

Counts being Spun.		Diameter of Ring in inches.		Counts of Travellers. U.S. standard.
10	... ..	$1\frac{3}{4}$	......	7 or 6
16	......	$1\frac{3}{4}$	......	4 or 3
20	......	$1\frac{3}{4}$	......	2 or 1
24	......	$1\frac{3}{4}$	......	1/0 or 2/0
28	......	$1\frac{1}{2}$	......	2/0 or 3/0
30	......	$1\frac{1}{2}$	......	3/0 or 4/0
32	......	$1\frac{1}{2}$	......	4/0 or 5/0
34	......	$1\frac{1}{2}$	......	5/0 or 6/0
36	......	$1\frac{1}{2}$	......	6/0 or 7/0
38	......	$1\frac{1}{2}$	......	7/0 or 8/0
40	......	$1\frac{1}{2}$	......	8/0 or 9/0

MESSRS. BROOKS AND DOXEY'S FRAMES.

Counts being Spun.		Diameter of Ring in inches.		Counts of Travellers. U.S. standard.
0 to 4	......	$2\frac{1}{2}$ to 3	......	—
4 to 10	......	2 to $2\frac{1}{4}$	......	—
10	......	2	......	6
14	......	$1\frac{3}{4}$ or 2	......	4
18	......	$1\frac{3}{4}$	......	2
22	......	$1\frac{3}{4}$	......	1
26	......	$1\frac{5}{8}$	......	3/0
30	......	$1\frac{5}{8}$	......	4/0
32	......	$1\frac{5}{8}$	......	5/0
36	......	$1\frac{1}{2}$	......	7/0
40	......	$1\frac{1}{2}$	......	9/0

The following figures relate to special American practice for hard twisted yarns $\sqrt{\text{counts}} \times 4\cdot7$ with a spindle speed of 9,000 :—

Counts.		Traveller.		Counts.		Traveller.
3	.....	40		18	......	4
4	......	34		20	......	2 or 1
4·7	......	28		22	......	1/0
5·5	......	24		25	......	3/0
12	......	9		30	......	6/0
14	......	8		35	......	10/0
16	......	6		40	......	22/0

The accumulations of fly about the traveller must be carefully watched, and it is the practice to fit to the ring rail a clearer or cleaner, which is simply an upwardly projecting piece of metal which catches the fly on the traveller in its rotation and removes it. The clearer should be set so that it approaches the traveller, when the latter is pushed outwards as far as it will go, within the space of a piece of writing paper. It is highly important to keep the traveller free from fly, as any accumulation of it speedily adds to the friction on the ring. In doubling it is necessary to lubricate the ring well. For this purpose a special grease is used which adheres to the surface of the ring very tenaciously.

(317) The spindles are driven, as shown in Fig. 218, by means of two tin rollers. It was formerly customary, and is still

largely the practice, to drive one tin roller from the other by passing the spindle bands from the driven roller over it. That is to say, the bands driving the spindles on the left hand side of the frame are those which are driven from the right hand tin roller, and *vice versâ*. It is obvious that by a method of this kind there must be necessarily some uncertainty as to the actual velocity of the driven roller, and it is this which forms the basis of the arrangement shown in Fig. 227, by which each of the tin rollers is driven by means of an endless cord or band, similar to a rim band. In this way the speed of the tin rollers can be ascertained and relied upon, and much more even work can be produced on each frame. Allied to this factor is the question of the construction of the bands, and the first remark which it is necessary to make is that it does not pay to use the spindle bands made of inferior material. When it is considered that the band is bent round a half circle of three-eighth inch radius from 8,000 to 10,000 times per minute, it will be seen that it is subjected to a strain which, unless great care is taken, will prove fatal. It is, therefore, the truest economy to have them made of good cotton, carefully prepared and twisted. In putting them on care should be taken that the joins are as free from lumps as possible, and that the tension on the bands is even throughout. It is preferable to stretch them a little before putting on, which can easily be done by giving them a smart pull while held in some convenient way. Opinions vary as to whether the bands should be put on when the machine is running, or when it is stopped ; but, on the whole, the latter is probably the best course. The condition in which the bands are kept is an important factor, and this requires steady and constant attention. Of the importance of these various points there will be no doubt in the minds of any one who has carefully followed the previous reasoning. If the bands are not equally effective in driving, the spindles will revolve at too high a speed in some cases and too low a one in others, with the result that all the care taken in selecting the travellers will be entirely lost, and twist and winding will alike be affected.

(318) We have now touched upon all the points which practically affect the working of the ring frame, and the rules by which the various calculations are made in it can now be given.

To find the number of revolutions of the spindles—

Ascertain the velocity of the tin roller, then

$$\frac{\text{Revolutions of tin roller} \times \text{its diameter.}}{\text{Diameter of spindle warve.}}$$

To ascertain the twist in turns per inch—

$$\frac{\text{Diameter of tin roller} \times \text{carrier or arm wheel} \times \text{front roller wheel.}}{\text{Wheel on tin roller} \times \text{twist pinion} \times \text{circumference of front roller} \times \text{diameter of warve.}}$$

To find change pinion for twist—

$$\frac{\text{Constant number}}{\text{Turns per inch}} = \text{change pinion.}$$

The constant number is found by the method given in the preceding rule, omitting the twist change pinion. From the result thus obtained deduct five per cent as an allowance for winding on.

In conclusion it may be said that in the ring frame, as in the mule, absolute cleanliness is essential to complete success. It would be going over much of the ground previously traversed in connection with the mule to deal with a number of points of more or less importance, and it may just be said briefly that the conditions of the spindles, rollers, and bobbins are as important in one case as in the other. Constant vigilance is required, and in a well organised mill the cleaning of the machines will be a regular and not a spasmodic operation. Not only is this the best course for efficient work, but it is distinctly the most economical, and this should be borne in mind.

(319) It will be advisable at this point, as the spinning processes have now been dealt with, to say a few words on the subject of the commercial qualities of and dealings in yarn. The counts of yarn are ascertained by the employment of what is known as a wrap reel, Fig. 244. This consists of a light metallic

s

swift R revolving in bearings, attached to a wooden base, and
rotated by a handle H, carrying on its tail a small bevel wheel B
forming one of an epicyclic train, similar to that employed in
connection with the roving frame.   The effect is that one
revolution of the handle gives two turns to the swift.   The
swift, 54 inches circumference, is made wide enough to wind a
skein from several cops, fixed on skewers in the holders F, if

FIG. 244.

desired at the same time, which is occasionally useful.   The
frame F is given a transverse horizontal reciprocation by the
lever L pivoted at D and rocked from the wheel W.   Eighty
revolutions of the swift winds 120 yards of yarn, and when this
is concluded a bell C is struck by a hammer actuated by the
worm T, this calling attention to the fact that the full length
is wound.   By ascertaining the weight of one lea in grains the
counts can be calculated, as described on page 366, by dividing

1,000 grains by the number of grains in each lea. To save the trouble of calculation, tables are published giving the weights of from one to seven leas of various counts of yarn, so that a reference is all that is necessary. The calculation, however, is such a simple one that it is not necessary to reproduce the table. If more than one lea is weighed the corresponding number of thousands must be used as a dividend and the weight of all the leas as divisor. After having got a lea it is sometimes necessary to test its strength. This is done by a machine called a yarn tester, which consists of a fixed hook and a hook attached to a slide controlled by a hand wheel and screw, the position of which causes a greater or lesser pull to be exerted on the yarn. The breaking strain is shown by a finger traversing the face of a circular dial plate. The breaking strain of the same counts varies under different conditions, and it is hardly possible to fix any standard strength. The conditions which affect this problem are so many and numerous that it is quite impossible to specify them all. The character of the cotton, its early treatment, the atmospheric conditions during spinning, the exact twist inserted, are only a few of the things which affect the strength. It is, therefore, customary in ordering yarn, where strength is needed, to specify the amount which should exist. For instance, in a table issued by Messrs. George Draper and Sons, of Hopedale, Mass., U.S.A., the strength of 32's American ring warp yarn per lea is given as 54lbs. Dr. Bowman gives the strength of that counts spun from American cotton as 54·7lbs., although they were a little lighter than standard. Mr. James Hyde, in his well-known and admirable book, gives the strength of 32's yarn as follows: Ordinary, 45·6; fair, 46·4; good, 47·3; extra, 48·2; super-extra, 49·1. There is thus a considerable disparity in the figures, and, except as a mean of comparison, the tables given are not very serviceable. Generally the strengths given for American yarns are higher than those common in England, this being accounted for by the harder twist and the better mixture necessary, owing to the difficulties of spinning. The French counts of yarn are based upon the

metrical system.   The measures of length and weight employed
are the metre = 39·37 inches, and the kilogram (kilo.) =
2·2047lbs.   The yarn which is called No. 1 count is that of
which 1,000 metres weighs half a kilogram or 500 grammes,
there being 1,000 grammes in a kilogram.   The hank is divided
into ten skeins (échevettes), each 100 metres long, the full 1,000
metres long being the hank (écheveau).   The circumference of
the swift of the reel which is employed to form the hank is
1·425 metre—56·122 inches—so that it takes seventy revolu-
tions to wind one hank.   The following rules will enable all the
necessary calculations to be made :—

$$\text{Counts} \quad = \frac{\text{Length in metres}}{2 \text{ weight in grammes.}}$$

$$\text{English counts} = \text{French counts} \times 1\cdot18.$$

$$\text{French counts} = \frac{\text{English counts}}{1\cdot18}$$

(320) Yarn in England is, when .produced, dealt with in
several ways.   In America, except for hosiery purposes, the
trade in yarn is not great, as most of the great establishments
in that country utilise their output in the production of cloth.
In England, on the contrary, there is a division between the two
operations, although there are a large number of factories in
which both the operations of spinning and weaving are carried
on.   Yarn is often sold through an intermediary, known as a
yarn agent.   He charges a commission of 1 per cent, with an
extra ½ per cent if the account is guaranteed.   In many
instances yarn is sold by the direct representatives of the mill,
and in Manchester 14 days' credit is given, with a discount of
2½ per cent at the end of that period, or an extra ½ per cent is
given for prompt cash.   There are, of course, many classes of
yarns prepared for special purposes which are sold outside of
Manchester.   For instance, fine yarns are sold as warps, to mix
with worsted yarns in Bradford dress goods.   These are sold on
monthly terms for all deliveries on and before the 25th day of
each month, payment being made on the third Thursday in the
following month.   This means nearly two months' credit in some

cases. In Glasgow, yarns are largely sold for thread purposes, and are subject to a maximum discount of $7\frac{1}{2}$ per cent for payment before the 20th of the month succeeding delivery. Cotton yarns for mixed linen goods are sold for payment less $2\frac{1}{2}$ per cent, on the 4th of every month, for deliveries made up to the 15th of the preceding month. In Nottingham, where yarns are sold for the purposes of lace and hosiery, all deliveries made up to the end of any month are paid for on the first Thursday of the second month following, that is, goods delivered up to the 31st December would be paid for on the first Thursday in February. Sometimes the agent buys his yarn and makes it up into bundles for the special market it is intended for, whilst in other cases this operation is performed at the mill. In most cases specific instructions are given as to the mode of making up. A bundle is usually made of 10lbs. net weight of yarn, and the number of hanks it contains depends upon the counts of yarn included. It is tied, as a rule, with four strings in its length, although occasionally five are used. If the hank is wound in leas, it is tied so as to keep each lea separate, and the hanks are laid in the bundles either straight or tied so as to form a figure of eight, being so ordered.

The details of a make-up can be varied, but are easily understood by a little study. This matter was raised by a question put in a recent examination, which is here repeated, with the answer. " Define exactly what is meant by the following particulars, given with an order for bundle yarn, taking them in the same order as given — 10lbs. net, 40's, 36lbs. test, grandrelle, 20 hank halshed, 8, blue facing, back, no type stamp, black press twine, full length, say how many ends of knots would show at the end of the bundle?" Interpreted, this means that a bundle consisting of 10lbs. net of 40's yarn, each lea capable of sustaining 36lbs. weight, with hanks of full length, is wanted. It must be made up so as to have blue facing paper on the face of the bundle, and back paper in the bundles, the twine being hemp and black. The hanks must be tied up in twenties in the form of the figure 8 with grandrelle yarn, and

twenty knots would show at the end of the bundle. Yarns in the form of cops are also shipped to the Continent packed in casks, and are thus known as cask yarns. The counts sent in this form range in counts from 20's to 60's, all higher counts being sent packed in boxes. There is a growing trade in yarn wound on quick traverse winding machines into cheeses, as previously described ; and ring yarn is now shipped in that form.

CHAPTER XI.

REELING, WINDING, AND THE MANUFACTURE OF THREAD.

SYNOPSIS.—Varieties of reels, 321—Description of reeling machine, 322—Doffing motions, 323—Bundling, 324—Doubling, 325—Doubling winding machine, 326—Cross winding, 327—Twining, 328—Ring doubling machines, 329—Flyer doubling, 330—Gassing, 331—Polishing thread, 332—Spooling thread, 333—Balling thread, 334.

(321) YARN, whether spun on the mule or ring frame, is used mainly for three purposes, weaving, knitting, or thread. With that used for the first purpose we have not to do beyond the stage of reeling, and the same remark applies to hosiery yarns. Very large quantities of both kinds are shipped abroad, and in this case the yarn is made into hanks and formed into bundles for convenience of carriage and the saving of cost. For this purpose there is a special class of machines made, which are part of the outfit of any mill in which yarns are prepared for export. The first of these machines is intended to wind the yarn into hanks of any determined or defined length In this country, as previously stated, a hank is usually 840 yards long, and is wound in coils or layers, each of which is $1\frac{1}{2}$ yard or 54 inches long. These are produced on a machine called a " reel," and its construction depends upon whether it winds the yarn from cops or bobbins. A " cop " and " bobbin " reel are widely different in appearance, but in each the operating instrument is a light frame called a " swift " or " fly." This consists of a central axis or barrel made either of light iron tube, or of tin cylinders, and having mounted upon it several arms on the ends of which are fixed longitudinal wooden laths or rails, the outer surface of each of which is equidistant from the centre of the shaft. The arms are either formed in pairs with a central

boss, or are part of a light iron spider, that being the course
when a "drop motion" is used. The latter is an arrangement
by means of which two of the staves can be dropped so as to
release or free the hank and facilitate its removal. This object
in an ordinary reel is effected by oscillating the arms on the
barrel, so as to draw the various staves together (see dotted
lines in Fig. 246). In either case a "swift" is formed,
on which coils of yarn of the required length can be easily
wound. The fly or swift revolves in suitable bearings at
each end, and is driven by hand or power in the case of a
cop reel, or by power mainly if bobbin reels are used. The
yarn is drawn from the bobbin on which it is spun and is
wound on to the fly, being in the process guided by means
of a "guide rail" which is actuated by suitable mechanism.
When cops are to be reeled they are mounted on skewers, which
are fixed in small holes in longitudinal rails, and the yarn is
taken to the fly through a guide rail, as described. In conse-
quence of the method of winding the bobbins formed on ring
frames, and the extra twist put into the yarn, it is necessary to
subject the latter in reeling to a considerable tension, in order
that they will wind properly. For this purpose a special wire
guide is used, which is so constructed as to draw out the snarls
as the yarn passes.

(322) The form in which the yarn is wound on the fly de-
pends upon the purpose to which it is to be put. It may be
either formed into seven "leas" or small hanks of 120 yards
each in length; "crossed" wound—that is, laid by the rapid
reciprocal traverse of the guide rail in a crossed condition; or
"skeined," in which case it is wound into hanks of some
defined length. Cross reeling is resorted to when the hank
is to be dyed, the yarn being left in such an open condition that
it not only receives the dye better, but is more easily unwound
without entanglement. Latterly a system of cross reeling has
been adopted, which is called "Grant" reeling. It consists
simply of giving a more rapid and longer traverse to the guide
rail. In this way the yarn is much better crossed, and presents

openings which facilitate the tying up of the various crossed portions so as to avoid any entanglement in dyeing. In this system of reeling the length of 840 yards is not adhered to, as a hank often contains many thousands of yards, and there is practically no fixed limit. If the hank is to be formed with seven leas, the guide rail is actuated as shown in Fig. 245.

FIG. 245.

The rail K is fitted with an arm in which is fixed a pin H engaging constantly with the face of the stepped rack R. A spring is attached to K, so as constantly to draw it towards R, so that when any one of the seven steps comes opposite the pin, the rail can make a movement so as to bring the pin into contact with the face of the rack R. The latter forms the head of a

vertical bar G guided in suitable bearings attached to the frame,
and having at its lower end a second rack F with a corresponding
number of teeth to steps in the upper rack. On the barrel B
of the swift is a worm W, gearing with a worm wheel D, on the
axis of which a tooth E is fixed so as to engage with the rack F.
Thus every revolution of D is followed by the raising of the
rack G to the extent of one of the teeth in F, which is sufficient
to lift the next step in R high enough to enable the pin H to
fall into it. The guide rail F is moved to that extent, and the
yarn is thus laid on another part of the staves A, a small space
being left between each lea. It is, therefore, obvious that the
length of yarn wound on the swift, during the period occupied
between one lift of G and the next, will be regulated by the
velocity of the swift barrel B, and the size of the worm wheel D.
Thus, if D has 80 teeth, the barrel and swift require to make 80
revolutions before the pin E raises the rack F one tooth. The
swift being 1½ yard circumference, it follows that 80 times that
length, or 120 yards, is wound in each lea. To cross reel yarn
the pin H is removed, and the rail K coupled to a small disc
crank fixed in the head of a small upright shaft, and rotated
from the barrel B, so that K receives the necessary rapid re-
ciprocal motion, the rack F being, however, raised as before.
In skeining, a plate is fixed to the head R of the rack G in such
a way that it projects beyond the steps in the rack. The pin H
presses against the plate, so that the hank is wound in a regularly
spiral manner. By arranging the speed at which the rack F is
driven any length of a hank or "skein" can be wound. It is
customary, when skeins are required, to substitute for the rack
F a finely-pitched tooth rack with which a pinion gears. The
pinion is driven by a train of wheels, which in turn receive
their motion from the worm on the barrel, and, by simply
changing a pinion forming one of the train, the rack can be
raised at any desired speed. Skeining is usually resorted to
with doubled yarns. Whatever system of reeling is adopted,
when the rack F has been raised sufficiently high to wind on the
proper length, the stop rod of the reel is released, and by means

of a spring is traversed so as to stop the machine by transferring
the strap from the fast to the loose pulley.   The creel used in a
reel can be adapted either for cops, bobbins, or "cheeses."   In
the first case the reel is specially constructed, and the cops are
held in skewers.   The bobbins are mounted in a creel something
like that in Fig. 249, shown as applied to the gassing frame,
being placed on spindle free to revolve, but braked by a friction
band.   When reeling is conducted from a cheese the latter is
placed end up on a peg, and the yarn is drawn from it.   As a
good deal of slack yarn is caused during this operation special
tension rails or rods are provided by which all chances of unequal
tension are avoided.

(323) The weight of a swift with the hanks wound on it is
considerable, and requires a good deal of power to lift.   As
the hanks require "doffing," it is necessary to provide some
means by which they can be easily removed from the swift.   If
this operation is manually performed, it is effected by collecting
all the hanks at one end of the machine, and lifting the swift
with one hand while with the other the hanks are removed.
There are two objections to this course.   The first is, that the
operatives, being generally women, the strain caused by the
weight, especially of doubled yarns, is excessive ; and the
second is, that there is a great danger of greasing the yarn.   It
is, therefore, customary to fit to the machines what are called
doffing motions, which are mainly of three forms, the " wheel,"
the " gate," and the " bridge " motions.   Of these, the last two
were introduced by Mr. Joseph Stubbs, and the first is now
obsolete.   The " bridge " motion is mechanically the simplest,
consisting merely of a small slotted bracket of sufficient length
to bridge a gap formed in the end frame F of the machine.
The motion is shown in Fig. 246, the bridge B when working
being shown in full, and when doffing by dotted lines.   It is
pivoted on the two pins D, one at each end.   The hanks are
drawn up to the end of the fly as in ordinary practice, and are
partially placed in the gap.   By means of a smart push the
bridge piece is forced over with the fly, so that it rests on its

pivot in a bearing constructed to receive it at the inner side of the gap. The hanks can thus be readily removed and the fly pulled back to its place. It can be seen that the bridge bracket

FIG. 246.

is in a vertical position both during reeling and doffing, and rests upon pivots formed in each end, respectively, during this period. To avoid greasing, the end of the fly is borne in a

sleeve arranged to lubricate it perfectly, and, at the same time, to avoid the escape of the oil. The nipple of the sleeve is cylindrical, and fits in the slot formed in the bridge bracket. The chief advantage of doffing motions is, of course, the ease with which the hanks are removed, but there is also much less danger of their being oiled.

(324) The hanks after being doffed are, if for export, formed into bundles ; these are either 5lb. or 10lb. weight each, and are formed in a press which contains, within a strong frame, powerful gearing by which a sliding table is pressed upwards. By a recent improvement the table is raised by the action of an eccentric, the throw of which regulates the elevation of the table. The advantage of this is that no undue pressure can be applied, and the bundles are made of a uniform size. Attached to the side frames are wrought-iron plates, five or six in number, separated from each other sufficiently to permit the passage of string. To one of the sets of plates other bars are hinged, which pass across the top of the space between the two sets, and are locked by levers jointed to the second set. The hanks are placed in the box thus formed, the bottom resting on a specially grooved wooden block, the covering plates are drawn down and locked, and the machine is started. The table thus ascends and presses the bundle to the required size. When it reaches a determined point the machine is automatically stopped, the bundle is tied up, after which, the pressure is relieved, the box thrown open, and the bundle removed.

(325) We now come to deal with the "doubling" of yarn, which is the name given to the process by which two or more strands or "ends" of yarn are twisted together. There are many purposes for which doubled yarn is used. Sometimes the warp threads used in weaving are doubled, and in many of the better classes of cloth this is the custom. Doubled yarn is used for the manufacture of lace, crotchet and knitting cotton, embroidery yarns, and sewing thread. The yarn used for crotchet and knitting purposes is carefully made and free from knots, and lace yarn is generally "gassed" with the same

object. Sewing thread is almost invariably doubled by two operations, being in most cases composed of six or nine separate ends twisted up into one, being known as "six" or "nine" cord. The practice is in manufacturing it to twist together first two or three strands of yarn, and subsequently to twist a similar number of the threads so produced into the finished thread. There are several ways in which yarn can be arranged for doubling. The cops can he fixed on skewers threaded into them, and placed in the creel of the doubling machine, from which they are drawn in the ordinary way. This is a practice which has largely fallen into disuse except for the very finest counts of yarn, two ends of which are doubled together for lace purposes, and for warps for fine mixed cotton and worsted goods. It is now the usual practice to wind the yarn to be doubled on to bobbins produced in a machine known as a doubling winding machine. This is a drum winding machine—that is, the bobbins on to which the yarn is wound are rotated by surface contact with a series of drums fixed upon a shaft suitably driven. The bobbins are formed with a cylindrical barrel, at each end of which is a broad flange. The distance between the two flanges is the "lift" of the bobbin, and the yarn is guided by the traverse of a guide rail between these two points in each direction alternately. The object of using a machine of this character is to avoid the production of "single" and "corkscrewed" thread. "Single" is a name which, although technically understood, is inaccurate as a description of the true character of the defective thread. It has arisen from the fact that when two ends are twisted together the failure of one of them is likely to result in the winding on to the doubling bobbin of one end only. This is only true when the ends are twisted together in the same direction to that in which they are spun, but, as a matter of fact, doubling is always conducted by twisting up the ends in the opposite direction. Thus, if two ends were being doubled, the only result of the failure of either of them would be that the other would be untwisted, and would, by the tension put upon it, be

speedily broken. When more than two ends are being twisted, this effect does not take place, as the breakage of one does not prevent the other two or more from being twisted together. In this case there will be a certain length in which the number of ends in the thread will be less than the normal number. " Corkscrewed " yarn is caused by the uneven tension of the threads being twisted, and is very likely to occur when they are drawn from a surface varying in diameter like that of a cop. This was referred to in paragraph 283, in Chapter IX., and the overrunning of cops is a fruitful cause of this defect. When such a state of uneven tension exists, one end, being slacker, is wrapped round the other in coils which are not regular in pitch, but are irregular and slackly formed. This tendency is utilised in the production of fancy yarns, which are employed for various classes of dress goods, but when it is desired to obtain a perfectly even thread, such as must be used for sewing machines, or for any other purpose where it has to be passed through needles, such as hosiery or lace, it is fatal in its effect.

(326) For these reasons, therefore, the use of a doubling winding machine is desirable. The Stubbs machine is shown diagrammatically in Fig. 247, and consists of one or two lines of drums A—generally one—fixed upon shafts usually driven by a belt. Against the face of this drum the barrel of the bobbin B is pressed, the latter being held on a spindle or mandril borne in a forked cradle C. The necessary pressure on the bobbin is exerted by means of weights J, which are coupled by chains to the tail end of C. Also hinged to the cradle C is a frame E, which is forked at its outer end, and formed with bearings in which rest the pivots of a small box free to oscillate. The box is provided with guides for several light wires, with eyes or curls G at their upper extremities, through which the yarn passes on its way to the bobbin. The wires are usually sustained by the tension of the yarn during winding, but are heavy enough to fall quickly as soon as an end either breaks or fails. When this happens the lower end F of the wire comes into contact with one of the wings of a revolving wiper

H, and the pressure thus exerted on the wire causes it to oscillate the box. A catch I which holds down the frame E is thus released, and the weight J is thus free to act on the cradle C and its attached parts. The pull so set up causes the bobbin B to be drawn slightly away from the drum on to a brake surface B, so as to arrest its motion at once. A further movement of the cradle C can be made so as to draw it away from the drum, and thus entirely free it, enabling the piecing of the broken end to be done with ease. The position of the parts during winding is shown on the left hand side of Fig. 247, and when an end is ready for piecing, on the right hand side of the same figure. The yarn is wound from the cops, which are borne in brackets fixed to a central shaft O. If bobbins are being wound a special creel is constructed to receive them. Each of the ends is taken through a slit in a thin metal plate, and then over a flannel-covered rail Y, the angular position of which can be adjusted to give more or less tension. By the time the yarn has passed this point, if the flannel rail has been properly covered and set, the tension on the ends will be equalised. After passing the detector wire eye the yarn is taken over a light roller X, and thence through the guide eye W, fastened on a rail Z, to which the necessary reciprocal traverse is given. The box T is used for the reception of the wound bobbins, and the rollers X are carried by brackets fastened to the underside of T, T itself being borne by brackets from the frames of the machine, the same brackets acting as guides for the traverse rail Z. The latter is actuated by suitable mechanism from the driving shaft, and the traverse should be so arranged as to be a little shorter than the full lift of the bobbin. Doubling winding machines of this construction will wind yarn at speeds up to 7,300 inches per minute, but for ordinary working purposes 5,000 inches is a good speed. If this operation is properly conducted there should be wound upon the bobbins a number of ends contiguous to each other, and each in the same state of tension. Care should be taken that in piecing the winder does not make

"bunch knots"—that is, tie all the ends together—but should simply tie together the broken ends of each strand singly. Unless this is done the subsequent twisting will be very

FIG. 247.

ineffectively performed, and the thread will be full of lumps, which are very objectionable. If the machine is well looked to, and care is taken in its operation, there will be a great improvement in the resultant thread with a very slight increase in the cost.

(327) Instead of using a machine in which double-flanged bobbins must be employed, it is now largely the custom to wind cylindrical spools on wooden or paper tubes without flanges. In order to do this it is necessary to increase the velocity of the guide wire traverse relatively to the speed of the bobbin, so that the yarn, instead of being laid in finely pitched spirals, is wound in coils, which rapidly cross the surface of the bobbin. It is, therefore, requisite to alter the mechanism actuating the guide rail, so that the latter will receive the rapid reciprocation necessary. In doing this there is a mechanical effect produced which is somewhat of a difficulty. The guide rail should be given such a movement as will practically ensure uniformity of speed throughout. In order to obtain the required velocity of traverse, a cam or cam course of suitable shape is ordinarily employed. It has, however, the defect that, at the points which represent the end of the stroke in each case, the reversal of the movement of the guide rail is not made quickly enough. However little the time occupied it is sufficient to cause a slight dwell during the change, and the yarn is held at the ends of the bobbins a little too long. This results in a bobbin being made with the ends slightly raised, which is very objectionable. All forms of cams employed are, from their shape, liable to this defect, and a slight wear at the point speedily increases it. Perhaps the simplest method of attaining this object is the employment of a divided drum of the Hill and Brown type. The drum, instead of being made in one piece is in two, and the edges which adjoin are shaped so as to form a widely pitched spiral. Through this slit the yarn is passed, being retained in one position by a guide arranged within the drum, and is, by the rotation of the bobbin itself, very rapidly traversed. The yarn passes on to the spool from below, the spindle on which it is wound being held in a suitable cradle. It is desirable that as far as possible a uniform speed is attained throughout the whole of the traverse of the rail, and that no dwell is either visible or can be traced in the character of the bobbin produced. This is a more important point than it

appears at first sight, because, unless the yarn is taken away rapidly from the ends of the bobbin it is very liable to unravel when it is being handled. As the object of this method of winding is to form bobbins or spools which can be handled with the utmost freedom, it is obvious that any defect such as that named will be fatal to true efficiency. Machines of this character are now largely employed, and their use is extending. When bobbins are formed in this way they can be transported without difficulty, and the reduction in the cost of carriage is very great. The yarn unwinds much better, and owing to the greater length which can be put on a cheese, fewer piecings are required either in reeling or doubling.

(328) The actual operation of doubling is carried out on a machine similar in general construction to the ring frame, or in a modification of the mule, known as a twiner. Of these the first named is most largely used, and the twiner is chiefly confined to the production of doubled yarn for warps. The twiner differs from the mule in the fact that the spindles are sustained in a stationary frame, being rotated at a definite speed by a rim band. The faller motion is, in principle, identical with that of the mule, but the necessary lift of the locking lever is obtained by giving a sliding movement to the copping rail instead of letting it remain stationary. This entails, of course, a different method of constructing the rail, which is much shorter than that used in the mule, and there is also a different mode of unlocking, but the principle of the operation is the same. The rollers are entirely done away with, and their place is taken by a creel, in which the cops are mounted in such a way that the yarn can be readily unwound from them while being held in sufficient tension to permit of the insertion of the twist. This creel is fixed on a slide which receives a to and fro motion from the spindles, the construction of this portion of the machine being completely reversed. The drawing out shaft is driven by a train of wheels from the tin roller shaft, no draft being needed in the operation of twisting, so that it is only necessary to deliver the yarn at the proper

tension during the revolution of the spindles at a speed which is sufficient to supply the quantity required. When the period of winding comes the yarn is firmly gripped by a sliding nipper, so that it can be formed into a cop free from snarls. Winding is conducted, in all respects, as it is in the mule, the motions being practically identical. Twiners are used almost exclusively for twisting two-fold yarns, but the wheel trains are so arranged that they are capable of giving a great variation in the effect produced. The spindles revolve from 7,500 to 9,000 revolutions per minute, and an allowance of 2½ per cent for the slip of bands is necessary in calculating the twist. It is not requisite to give the rules for the various motions in the twiner, but the following will give the number of turns per inch.

$$\frac{\text{Revolutions of spindles per minute}}{\text{Length in inches of movements of slide.}}$$

Each of these can be ascertained by making the calculations of the effects of the various trains of gearing in the machine. In calculating the necessary twist wheel to make any desired change, recourse must be had to the square root, as in the case of the mule. It may however be said, finally, that the size of the rim pulley has no effect upon the twist, which is entirely controlled by the rate of movement of the slide, which, in turn, is driven from the tin roller shaft. In most of its essential features the twiner is like the mule, and the methods of calculating the turns per inch, speed of spindles, etc., are similar to those given for that machine.

(329) The difference existing between the ring doubling and spinning frames is principally one of size. The gauge of the spindles, the diameter of the ring, the shape of the traveller, the size of the spindles, and the arrangement of the drawing rollers constitute the chief differences existing. Taking these in order, the gauge of the spindles varies from 2½ inches to 4 inches, and the diameter of the rings from 1½ inch to 3 inches. The traveller, instead of being constructed so as to clip the upper bead of the ring, is made of such a shape that it passes over both the upper and lower beads, and is consequently much

heavier than the spinning travellers. The spindles are made generally larger and heavier, and the top of the sleeve is provided with two projections, one on each side of the spindle, which take into recesses formed on the upper side of the lower flange of the bobbin, which is thus absolutely and positively driven. Knee

FIG. 248.

brakes, as in Fig. 248, are provided to facilitate piecing, the attendant pressing against the ninged bracket B with her knee, thus giving such a frictional resistance on the spindle as to stop it. The removal of the knee pressure permits B to fall back, and the spindle restarts. Similar arrangements are made as with spinning spindles to ensure the steadiness of running of the spindle, but the necessity for limiting the movement of the sleeve is greater than is the case with spinning spindles. Another point which is allied to this is the character and length of the lift. There are two ways of arranging this. The first is similar to the one described in the last chapter, which is used when the doubled yarn is to be wound into a cop or spool. The second method is to give the ring rail a traverse equal to the lift of the bobbin, thus winding the yarn in parallel layers throughout. The latter is the most usual procedure. With reference to the drawing rollers, the chief characteristic is the fact that there is only one pair, both being covered with brass, and the upper roller being heavy enough to establish a good nip. As the doubling frame is not

required to draw the twisted yarn, but only to deliver it, all that is necessary is to provide means by which it will be emitted from the rollers at a regular and defined speed. The function of this machine is, therefore, that of twisting only, and no draft need be calculated. Once the relation of the roller delivery and the spindle speed is established for any number of twists, that is all that is required. The rollers are arranged differently in the two existing systems, the English and Scotch. In the former they are fixed in front of a shallow water trough which has running along its entire length, a glass rod immersed in the water. The yarn can be passed under the rod when wet doubling is required, or taken directly to the rollers when the yarn is doubled in a dry state. In the Scotch system the rollers are carried in arms fixed upon a rocking shaft, which can be oscillated, as required, by means of suitable gearing. In this way, the yarn, which is wrapped round the top roller, can be made to absorb the required amount of moisture by simply lowering the bottom roller into a water trough placed for the purpose. The rollers can be raised as required, for cleaning purposes.

(330) The flyer doubling frame is still used to some extent for special classes of work, and everything which was said of the employment of the flyer for spinning is equally applicable in this case. For a really well twisted thread, in which cylindricality and regularity are requisite, the flyer has not been excelled, but its use is mainly confined to the coarser counts. The amount of twist put into thread varies largely with the class of thread being produced, but there is no rule to which all firms adhere. The same counts of yarn are twisted with widely varying numbers of turns per inch by different people even when intended for similar work. In manufacturing sewing thread, as has been said, the best practice is to "cable" the yarn—that is, twist up two ends together, and then twist three of the doubled threads so produced into one. It is found that by this practice a more even and stronger thread is produced, and it is practically universal in this

specific branch of the business. Thread so produced is called " six cord," and the counts or numbers given to it depend entirely on those of the yarn used from which it is made. Thus, 30's six-fold or cord means that six ends of 30's yarn have been twisted up together, producing the thread in question, which is, really, 5's counts.

(331) The doubled yarn having been produced, its further treatment is determined by the purpose for which it is intended. If for lace purposes, it is cleared and gassed. The first operation consists in passing the yarn through a slit or nick which is wide enough to permit it to pass, but which, when a knot or lump is presented, prevents its passage. The winding in this case is effected by a frictionally driven bobbin, which either has its rotation arrested, or if the yarn is not strong enough for that, breaks the latter. In either case, whether the yarn is broken or the knots arrested, the effect is the same. The attention of the winder is called to it, and the lumpy place can be cut out and removed. As an aid to this process a small appliance known as Balfe's piecing machine is very useful. It consists of two small spindles which are slit in such a way that the thread can readily be placed in them. When a knot comes up to the slit in the clearer, the winder lifts off the bobbin from the creel spindle, and also that on which the thread is being wound, and takes it to the piecing machine, which is conveniently situated for the purpose. A short length of yarn—about 12 inches long—with the knot in it, is attached to the two spindles, being firmly held by a spring clip in the very centre of the spindle, the slits permitting of this adjustment. One of the spindles is then rotated by means of a hand wheel, so as to untwist the thread, and the knot is then cut out. The threads are then *pieced*, not tied, by twisting two strands in one of the portions of the several threads together with one strand in the other portion, and *vice versâ* if the thread is three-fold. If more than three strands are in the thread, a correspondingly varied piecing is effected. When the ends are thus attached the rotation of the spindle is reversed until the whole of the twist is again

restored to the thread, when the bobbins are replaced in their position in the machine. Clearing, if properly effected, greatly improves lace yarns, and is, indeed, absolutely necessary. When thread is intended for lace purposes it is generally dry doubled and "gassed." A sectional view of one side of a Stubbs' gassing frame is shown in Fig. 249. The yarn to be gassed is either wound on clearing bobbins M, as in the illustration, or is on cops, or cheeses. In the latter case the creel is arranged so as to ensure a uniform tension being maintained in the yarn by means of properly arranged tension rods. In the machine as shown in Fig. 249 the yarn is taken from the bobbin over the tension rod L to the runners R. The latter are held on pins fixed in brackets attached to the beam R, and are quite free to rotate. They have usually four or five grooves in their peripheries, and the yarn is wound over them, as shown in the illustration. Midway between them is a Bunsen gas burner B, at the end of a swivel tube, which is supported on the nipple in the gas supply tube F. On the inner pipe an arm E is fastened, which engages with the inner end of the setting on handle H. The latter, at its inner end, is slotted so as to allow it to have a certain inward and outward movement. At its front end the handle is curved as shown, and engages with a projecting part on the cradle C, which is two-armed, and carries the spool, being weighted as shown. After the yarn has passed the runners R it is taken over the rod L to the guide G, and so on to the bobbin. The position of the bobbin cradle and handle, when the bobbin is removed from the drum, is shown by the dotted lines. By the adjustment of the arm E, and the shape of the handle H, the bobbin is rotating before the gaslight passes under the yarn, so that all chance of burning down is avoided. For the reasons stated with regard to doubling winding it is desirable to give the guide G a quick traverse, which is done in this particular frame.

(332) Having produced the thread, it is necessary to make it up for the market. There are two methods of doing this, thread being sold either in its ordinary or "soft" condition, or polished.

In preparing the latter class of thread, 360 bobbins are placed in a creel and are wound on to a beam, which is similar in con-

FIG. 249.

struction to those used in receiving the warp in weaving, the ends being wound side by side. A "chain" of ends is made, which consists of the 360 threads loosely gathered together, and

in this form the material is bleached or dyed, as the case may be. After dyeing, it is wound by means of a special arrangement, which ensures the proper tension of the threads, on to a beam similar to the one described. This is placed in bearings formed in the frame of the polishing machine, and the threads are drawn off the beam and passed through a box in which a mixture of pure size or starch is placed, which is taken up by the thread. Immediately it has passed this point it is subjected to the action of brushes which are revolving at a high velocity, the frictional contact of the bristles giving it a very high polish. The thread is then dried, and finally wound on three rollers, each of which is divided in the centre, so that 60 threads are laid in each division. These rollers are used to feed the yarn to a winding machine, which winds the thread on to specially shaped wooden spools, each of which has about 1¼ lb. of the polished thread laid upon it. Soft or unpolished thread is not, of course, passed through the polishing machine, but is, after being dried, beamed in the manner described. There is another system by which the thread is polished in the hank, but it has the objection that the length of thread treated is comparatively small, and that on this account there are more knots required in the same length of yarn. The wages cost entailed is also lighter in the system named.

(333) Sewing thread is sold principally in the form of small wooden reels or bobbins, which are made with a cylindrical barrel and end flanges bevelled on their inner side. Thus the distance between the flanges is less at their roots than at their peripheries, so that the thread has to be laid on a continually lengthening surface. This operation is called spooling, and it is conducted on a machine of great ingenuity, invented by the late Mr. William Weild. The machine is usually made with six or eight heads—that is, that number of reels are wound at one time. It is, therefore, necessary to actuate the mechanism of all of the heads separately, but simultaneously, and the necessary regulation is obtained from a headstock placed at one end of the machine. The empty spools are held in troughs,

the lower orifice of which is directly opposite the different heads, and in the latter are two spindles with conical ends which grip the holes in the centre of the bobbins. After a bobbin is finished, these spindles open, the bobbin drops, and an empty one falls from the trough into a plate which is automatically raised so as to place it between the two spindles. These immediately close and begin to rotate the bobbin. As the ends of the threads which are drawn from the spools are held in a suitable position, the beginning of the rotary motion of the bobbin causes them to be wound on to the latter. In its passage from the spool on which it is wound the thread is taken through a tension clip, by which the required amount of tension is put upon it, and is then passed over a groove formed in a thin steel guide. This is mounted on a shaft which can rock on its centres, but which has also a longitudinal reciprocal movement. The under edge of the steel guide is cut in such a way that it corresponds to the pitch of the spirals formed by the threads as they are wound, the reason of this being that the guides rest upon the thread during winding. It is obvious that the rate of the longitudinal movement of the guide must be identical with the pitch of the spirals, as otherwise there would be a rubbing action which would be very injurious to the thread. The guide rods are, therefore, actuated from a finely pitched screw, to which a definite speed of rotation is given which can be regulated as desired by suitable gearing. With this, two half-nuts correspondingly threaded and on different sides of the centre engage alternately, so that the guide rod is given the necessary reciprocal movement. By an ingenious arrangement the exact time when they are alternately geared with the screw is regulated, so as to compensate for the increasing distance between the flanges as the bobbin fills. When the required number of layers of thread have been wound—which can be regulated as desired—the shaft, on which is a driving wheel engaging with a pinion on one of the spindles in each head, is stopped, so that winding ceases. A knife descends and cuts a nick in one of the flanges of the bobbin, immediately after which the thread is drawn down into

this nick and across a knife edge, thus severing its connection. The guide which pulls the thread into the nick and cuts it off, leaves it in such a position that it is gripped by the new bobbin and immediately begins to wind on the latter as soon as it is rotated. As soon as this operation is completed the spindles open automatically and release the reel, after which a new reel is fed and the operation again begins. By means of the various machines described a large quantity of thread can be prepared for the market in a week : 120lbs. weight of 30's three-cord can be polished in ten hours, and soft thread can be turned out at the rate of 5,670lbs. in a week of 56 hours. An eight-headed spooling machine will produce spools or reels, each containing 200yds. of thread, at the rate of 26 gross per day of $10\frac{1}{2}$ hours.

(334) Cotton thread, which is employed for crotchet and mending purposes, is often wound into a barrel-shaped spool called a " ball." The balls are formed on a mandril, which is mounted on an oscillating frame, and which is placed between the forks of a flyer. This has eyes at the ends of its arms, and by passing the thread through one of these and rotating the flyer, the thread can be wound on the mandril. By oscillating the mandril in each direction alternately for any defined distance, the thread is wrapped on it in coarse spirals until at last a " ball " is formed. The length of thread wound is not usually great, and the operation of balling is generally a manual one, although there are one or two machines which are approximately automatic. Compared with spooling, " balling " is a very small trade, and does not require any further explanation.

CHAPTER XII.

WASTE SPINNING.

SYNOPSIS.—Definition of waste, 335—Method of breaking, 336—
Methods of carding, 337—Feed arrangements, Derby doubler,
drum, Blamire's, and Scotch, 338—Methods of condensing, Saxon
and Bolette's, 339—Spinning waste, 340—Mixed cotton and
waste, 341.

(335) IN the series of processes which have thus been
described there is necessarily a large quantity of waste produced.
The amount varies naturally with the quality of the cotton
and the skill of the workpeople, but it is always large.
Over the whole series of operations the amount varies from
12 to 20 per cent, but some of this is the dust and similar
impurities deposited in scutching and opening. While there is
always a certain part of the waste made in the two stages
named which consists of fibres of more or less value, on the
whole, the usable waste—if the phrase may be employed—is
principally that which is made in the carding engine and
subsequent processes. Waste is defined as being "hard" or
"soft," the former including all cotton into which twist has
been put, and the latter, untwisted or partially twisted material.
These are the broad distinctions made, and are sufficient for
practical purposes. At present the trade in yarns spun from
waste is principally a Continental one, and in England it is the
exception to produce this class of yarn. The reason for this is
probably that to spin it requires a special plant, which is different
in many cases from that usually found in the spinning-mill. It
is, however, an undoubted fact that waste spinning is an
operation which repays the trouble entailed, and a brief treat-
ment of the method usually pursued is likely to prove interesting.

(336) Much of the waste which it is possible to spin into yarn is of a greasy nature, and this partially facilitates and partially retards the performance of the operation. It is obviously the first thing to do, when dealing with hard waste, to restore the material to its fleecy condition and detach the fibres from each other. For this purpose it is obvious that the machines employed to deal with cotton in its ordinary open condition are absolutely useless, and that the treatment given to it must be quite different. Accordingly waste is first treated in the Oldham willow, which has already been referred to. The willow is constructed with a drum or cylinder, having its surface covered with spikes or teeth. It is surrounded for the greater part of its circumference with a grid also fitted with projections on its inner side. By the rotation of the cylinder, the twisted cotton is rapidly broken up, as it is called, and reduced to a soft fleecy mass. The form of machine employed varies a little in its details. In one type, which is constructed for dealing with hard waste, more especially in the form of cop bottoms, there are several cylinders used one after the other, each provided with round taper teeth, and revolving at a rapid rate. The cylinder shafts are made long enough to project beyond each side of the machine, so as to receive the necessary pair of driving pulleys. This construction is adopted in order to enable the cylinders to be reversed after the teeth have become bent out of their true position, which sometimes happens. When they become too much inclined, the reversal of the cylinder is necessary, in order that they will be fully effective. Machines on this principle are made with three, four, or six cylinders, and the hardest waste is speedily reduced into a condition resembling raw cotton. The length of staple obtained depends largely upon the character of the cotton broken up, and it must, of course, be understood that the fibres have lost part of their strength by their repeated manipulation. Still, an excellent product can be obtained from clean hard waste, and it is worth noting that for this class it is found that a treatment by six cylinders gives the best result. Soft waste—such as that made in the processes of scutching,

carding, and drawing—obviously does not need the same severe treatment as that described, only requiring to be dealt with so as to remove any dirt or other extraneous matter which may be mixed with it. Two courses may be pursued with the waste opened in the willow or breaker. It may be passed through a Crighton opener or a scutching machine, fitted with a lap attachment, and fed to a breaker carding engine. In the former case, a modification in the details of the machine is necessary, in order to allow of the effective treatment of the material. An extra picker or breaker cylinder is provided, and the cotton is fed by means of a lattice apron, it being, of course, essential that this operation is conducted with care, so as to produce a good and even lap. A pedal motion being fitted, the latter object is naturally considerably aided To all machines for cleaning and opening waste it is advisable to apply fans to carry away the dust, of which there is a considerable quantity.

(337) When the opened or broken-up cotton is thus obtained, it is carded, and in this operation we meet with a distinct departure from the methods previously described in connection with the carding of cotton. It was shown in Chapter IV. that the cotton was fed to the carding engine ordinarily in the form of a single lap, the regularity and evenness of which was obtained by the mode of producing it on the scutching machines. In proceeding to card waste, a different course is followed. If the cotton has been formed into a lap on the scutching machine, two of these are placed on a lattice apron fitted to the end of the machine, so that a certain amount of doubling takes place at this point. For reasons which will be detailed later, it is desirable to obtain an even weight in the sliver at the earliest possible time. If the cotton is in the open or loose condition, the practice is to weigh a certain portion and spread it upon the feed lattice, thus pursuing a similar course to that which is followed in carding wool. Sometimes, but not often, weighing is resorted to as in dealing with wool. In many respects the manipulation of cotton waste resembles that of wool, and it is found that, like the latter material, the carding is better performed

if the waste is a little greasy. When the material is too dry, it is therefore the custom to use a lubricant to increase its working qualities. The object aimed at in feeding the breaker card is to get a regular and uniform supply delivered to the action of the machine. So far as the construction of the latter is concerned, that described in paragraph 112, Chapter IV., is closely followed, except that the number of worker and clearer rollers is greater. There are also in some cases extra or "fancy" rollers fitted, these being practically similar in construction to the workers, by which the cotton is raised from the surface of the cylinder, and is more effectively delivered to the doffer than it otherwise would be. The material is doffed from the cylinder in the usual way, and the web taken from the doffer is variously treated. There are three ways of dealing with it, but the object in each case is the same, and a few words may be expended in explaining it. As there is not any very effective separation possible of the various grades of waste produced, it is at once obvious that there will be a great variation in the component parts of the opened mass, so far as quality and length of staple is concerned. This is especially the case when waste spinning is conducted as a special business, and the raw material is bought from dealers in it, or from several mills. To produce really satisfactory results, it is therefore of the highest importance that the mixture of the various elements in the broken waste shall be as intimately made as possible. When a six-cylinder breaking machine, such as was described, is used, this object is to a large extent attained, but it is absolutely necessary not to neglect it, and no precautions are too great to ensure its full attainment. It is therefore the practice so to deal with the web, as taken off the breaker carding engine, as to ensure the fibres within it receiving this intimate mixture, and the four principal methods of doing this will now be described.

(338) The first plan of which notice need be taken is to form the web into a sliver, and coil it into a can in the same way as if cotton were being carded. If this course is pursued, it is necessary to take special precautions to prevent the sliver

being broken, as it is very liable to rupture owing to the short staple and the weakness of the cotton fibres within it. It is obvious that if a fibre has been twisted on its axis as described, the separation of it from its fellows in the severe manner which is requisite must weaken it, and there is every reason to suppose that the effect of its natural convolutions is largely destroyed. After slivers have been obtained, however, they are drawn from the cans, and passed through a machine known as a Derby Doubler. This machine, although at one time extensively employed in the preparation of cotton for spinning, has not hitherto been described, because the methods of spinning used at the present day in this country have largely rendered it obsolete. A number of cans are placed so that the slivers can be readily drawn from them and traversed along a polished plate alongside each other, after which they are combined and passed through a pair of compression rollers, and are afterwards rolled into a lap of about 25 inches wide. The lap is by these means made very solid, and is usually about 15lbs. to 20lbs. in weight. As the various slivers are possibly composed of different qualities of fibre, a combination is thus obtained, which, when treated by the finishing carding machine, results in their intimate mixture. The second method of dealing with the web is to wind it upon a large drum constructed of wood, and of such a size that a bulky web is obtained. When the required thickness is thus wound, the web is taken off the drum by being cut across at one point, the sheet thus produced being fed to the finishing carding engine. As there are several layers in this sheet—which resembles wadding—it is evident that when it is treated by the teeth of the licker-in, the fibres will be laid upon the cylinder promiscuously, and will be intimately mixed, but they will not be crossed. The third plan pursued is to use what is known as Blamire's feed. This consists of an apron or lattice of the same width as the cylinder, fitted immediately behind the doffer upon which the web is deposited. The lattice in turn delivers the web to a transverse lattice, placed below, and running at right angles to

T

it. The delivery is made by rollers, in such a way that the fleece or web is laid all over the surface of the second lattice in folds. As this formation takes place the second lattice slowly traverses and delivers the web to a lap roll, by which it is rolled up into a lap of the requisite width. It is important to note that the direction of the fibres on the first lattice and in the lap is necessarily different, they being disposed at right angles to their former direction when in the lap. This, although at first sight a defect, is not really so, as the fibres are laid in every direction within the delivered web, and further, this peculiar arrangement, when the lap is afterwards carded, greatly aids the proper mixture, the importance of which has been described. When the laps are formed, they are fed to the finishing carding machine, and, as in the first mode of dealing with the material which was described, two laps are placed on the lattice, so that they are doubled and presented simultaneously to the action of the licker-in. In the Scotch feed the plan pursued is to take the web as it leaves the doffer of the first carding engine, and form it into a band three or four inches wide, which is taken upwards by a duplex feed tape or apron, and carried to the feed lattice of the finishing carding machine. Here the web is laid across the feed apron in successive layers, which overlap each other for about half their width, and is carried to the cylinder, so that the fibres are presented to the latter with their length running across its face.

(339) Whatever form the cotton is given it is carded a second time on a machine which is of similar construction to the one used for breaking, so far as the carding part of the machine is concerned. The object of the second or finishing carding is to complete the blending of the fibres, so as to obtain a better and more uniform thread than is otherwise possible. As the web leaves the doffer it is dealt with by a device known as a "condenser." This is an arrangement by which the web is cut or divided into narrow strips which are rolled up into the form of a round strand. The number of divisions made depends

upon circumstances, but the range is from about 40 to 120. There are two chief forms of condenser, the Bolette steel tape and Saxon or leather tape. In each case the operating instrument is a narrow tape which, in combination with rollers consisting of alternate rings and grooves, divides the web into a number of separate filaments or ends. The Saxon condenser, however, divides the web after it is taken from the doffer. The web is first compressed by a pair of calender rollers over which the tapers pass. The rollers are grooved, and are so set relatively, that the grooves of one are opposite the raised part of the other, the leather tape resting in the grooves. They are, therefore, alternately placed, and by guiding the lower set upwards and the upper set downwards, a division of the web is obtained in accordance with the number of tapes used. The exact number employed depends, of course, upon requirements, but this can be arranged as desired. Opinions differ as to the merits of the two systems of division ; but, in late years, the steel tape condenser has met with great favour. It is desirable, in using the machines, that the dividing mechanism is kept in good order, as it is requisite to get a clean, sharp division of the web and thus avoid any unevenness in the roving produced. After the slivers —as they may be called—leave the dividing tapes they are passed between broad bands of leather, very smooth on their surface, and stretched over rollers to which a rotative motion is given. The leather bands are being constantly traversed longitudinally, so that the strips of carded material placed between them will be carried forward and delivered at the point where the leathers pass round their respective rollers. The surface velocity of each band must, therefore, be identical, and it is highly desirable that the bands shall be quite free from any unevenness or roughness. In addition to the longitudinal motion, the bands are given a transverse reciprocal movement in opposite directions by means of eccentrics fixed on an upright shaft driven from the cylinder shaft. Thus the strips are rubbed up between the leathers, and are formed into a roving which, while acquiring a large amount of cohesion, has no twist, in the proper sense of

the word, but is very cylindrical. The pressure exercised upon it is sufficient for all practical purposes and is considerable, so that the roving, when it emerges, has strength enough to enable it to be wound on to specially constructed bobbins, and to be unwound from them with equal facility. The name of the apparatus is, therefore, evidently derived from the method of treating the material, the strips formed from the web being literally condensed by the action of the "rubbing leathers." The bobbins upon which the rovings are wound are light barrels of metal or wood, with light flanges at each end, and mounted so that they can be readily and freely rotated. From twenty to thirty ends are ordinarily wound on each bobbin, which thus is capable of containing a considerable length of material. It is sometimes the practice to provide each of the finishing cards with two sets of rubbers, this entailing two rollers for removing the web from the doffer. It is, on the whole, preferable, if this arrangement be used, to spin the bobbins produced on the upper and lower condenser separately, as it is difficult to get the doffing quite equal in each case. The whole of the arrangements of the condenser require care and watchfulness, and the leathers used should neither be too rough nor too dry. It is also necessary to keep them clean, as any adhesiveness would speedily result in a defective roving. In some cases an ordinary doffer is applied to the machine, and by the removal of part of its clothing at intervals the web is divided into several parts which can be taken off in the form of long strips. This does not give so good a result as the condenser. The operation of carding waste, generally speaking, is not a difficult one to effect, but it naturally possesses several points of difference to the carding of raw cotton.

(340) Having obtained the rovings in the shape named—viz., on bobbins from 24 to 30 inches long—it is necessary to spin them. The twisting of waste varies from that of ordinary cotton, mainly because the character of the material has been so changed that it will not permit of any draft being put into it until it is partially twisted. It is this fact which necessitates the great care to which we have referred as being essential in

the preparation of the roving. There is no chance of rectifying by means of a draft exercised on a combined sliver any unevenness which may be found in it, and it becomes the more requisite therefore to obtain from the finishing carding machine a web as even in weight and thickness over its whole area as it is possible to make. The intimate mixture of the fibres to which reference has been made has this object, and the formation of laps or the weighing of the cotton fed to the carding engines are directed towards the same end. Whatever unevenness exists in the roving when formed will be found in the twisted thread, with such reductions as follow upon the operation of spinning. This factor affects the construction of the spinning machine, because it is necessary to provide means by which, subsequently to the introduction of twist, a little draft can be exercised. Waste spinning is therefore generally conducted on a mule of a construction which, in its main features, resembles that employed for spinning woollen threads. It deals with the thread in an entirely different way to that in which ordinary yarn is formed, and the characteristics of the thread correspondingly vary. It was shown that the twisting of cotton yarn, although completed in some cases after the draft had ceased, was, to a large extent, put in simultaneously with the reduction of the roving by the rollers. Further, the draft of the carriage takes place at the same time as the twisting, and thus the attenuation and spinning of the material are effected during one period of the cycle of movements. In consequence of these factors, a thread is produced which is remarkably level, but the counts which can be spun are naturally limited. In some cases an attempt is made to get a little draft by means of rollers, but, on the whole, the best results are obtained by the employment of mules in which this element is absent. Accordingly only one line of rollers is used, and it is principally in the arrangement of the parts affecting these that the difference between a waste spinning and ordinary mule is found. The condenser bobbins are placed in a creel, and the various ends are taken from them and guided to the rollers.

These are made 1¼ inch diameter, and the top rollers are self-weighted.   The rollers may be made with two bottom lines, on which the top rollers rest, the roving being passed between the rollers, and being thus nipped twice.   The cops are formed in the usual way, the turns per inch depending upon the same conditions as those ordinarily existing.   At first the carriage runs out at its highest speed, and the rollers deliver the roving at the same or a little quicker speed than the travel of the carriage.   The exact amount of the excess of roller speed depends, of course, upon the strength of the roving, which is determined by the character of the mixing made.   When the carriage has made a certain portion of its outward run the rollers are disengaged and the delivery of the roving entirely ceases, but the traverse of the carriage continues at a slower velocity.   In this way the twisted yarn is drawn, and for the reasons explained in Chapter VIII., this results in a certain reduction of the thick places owing to the hardening of the thinner ones by the twist.   This, it will be noticed, is a somewhat similar procedure to that adopted with fine yarns, being a species of "jacking," but it differs from it because it is the only draft which is exercised on the yarn throughout.   There is a wheel provided on which figures are stamped, and by setting a finger to the required figure the detachment of the rollers takes place at the right moment.   A draft of a few inches is given, and instead of calculating this, and making elaborate wheel changes, the adjustment of the setting finger is all that is needed.   If required, a drawback motion can be fitted.   As the cops spun are naturally large the gauge of the spindles is great, varying from 1¾ inch to 2½ inches, and from 300 to 500 spindles are usually fitted in one mule.   Productions vary naturally with the counts being spun, but 7½lbs. per spindle per week of 56 hours is a common production when producing No. 4's yarn.   The strength of waste yarn depends upon two factors—the quality of cotton used in the waste from which it is spun, and the twist introduced—but is in some cases considerable.   As was said, it is possible to spin waste yarn from condenser bobbins on

continuous flyer or ring spinning machines, but, generally speaking, the method described is that adopted.

(341) Although soft waste may be dealt with by a set of machines such as those described, it is a common practice to use it up in the mill in which it is spun by mixing it—judiciously, of course—with the cotton as it is passing through. For some classes of yarns a mixture of two-thirds soft waste and one-third cotton can be advantageously used, and it must not be forgotten that waste in this condition consists of fibres which have not been twisted, and are not, therefore, so liable to damage in opening them. Of course the drafts of the rollers must be arranged to suit this special mixing, and the resultant yarn is sure to be weaker than one spun from cotton solely, but by careful arrangement the whole of the soft waste can be easily utilised in the ordinary work of the mill. A certain loss is inevitable, however great the precautions taken, but the utilisation of the waste in the best manner is a most important thing in the economy of a mill. It is recommended by some persons that soft waste of all kinds should be made a mixing of by themselves, and spun in the ordinary manner, but this is an objectionable and expensive course. It is much preferable to use this class of material along with cop bottom waste, and spin it by the series of machines previously described. On the Continent Vigogne and Barchant yarns, which are the specific names given to waste spun material, are produced on machines of this character, and as the principal seat of the manufacture is found in Germany and Italy it may be taken for granted that the system described is the best and most economical.

CHAPTER XIII.

ARRANGEMENT OF DRAFTS AND PRODUCTION.

(342) THE various operations described are those which are usually carried on in spinning mills, and the full explanation given needs only to be supplemented by a consideration of the methods of arranging the machinery and mill for any specific counts. There is one subject which requires special treatment, and which has been repeatedly named. This is the arrangement of the drafts in the various machines. It is evidently of the highest importance that in the management of a mill due regard should be paid to the proper drafting of the machines, even though the range of counts and the production of the machines should be limited by their special construction. This is a duty which falls into the province of administrative work, but is one of the most vital matters in the actual operation of a mill. There are several circumstances which have a bearing upon it, and not the least of these is the number of the machines of various kinds provided. It is obvious that this factor will affect the problem very materially, but within limits it is possible to vary the numbers of the machines used in the different stages, and still obtain a satisfactory scheme of drafts.

(343) Among the chief elements which affect this question is that of the class of cotton used. It is clear that a scheme of drafts which is suitable for a long stapled cotton like Egyptian

is utterly unsuitable for a short stapled variety, such as Surat.
It follows that at no stage when spinning the latter can there be
any approach to the long drafts which are quite permissible—
nay, necessary—in spinning the longer stapled cottons. When
arranging a scheme of drafts, therefore, the character of the
material employed must be taken into consideration, and, as
will be shown, leads to a good deal of variation. Another point
which exercises a great influence on the question is the number
of machines which are employed. As was pointed out in para-
graphs 61 and 202, the sliver is treated in two, three, or four
roving machines, according to the quality of the cotton used.
It is obvious that in accordance with the number of stages
which are employed, the reduction of the sliver must take place
differently in each case. Another factor which has an influence
upon the subject is whether the slubbings are doubled—that is,
two of them fed simultaneously—in the intermediate, roving,
and spinning machines. When this is the case a more severe
draft can be given in the machines than is exercised when a
single roving is used. Then again the class of yarn which is
being produced must be considered. For instance, hosiery
yarn, which must be as level as it is possible to make it, in
addition to being pliable and soft, requires careful and special
preparation in the earlier stages. Any excessive draft speedily
has an effect upon the roving, inducing uneven places in it, and,
as this special yarn receives only a small amount of twist, the
draft in the mule has not so great an effect upon it as is the case
with other varieties. Finally it may be said that, without
absolute uniformity being preserved at each stage of the whole
set of drawing processes, it is better that the reduction should
be gradual and continuous. All these various matters and
many others have an influence upon this subject. In considering
the remarks and instances which follow, a special warning must
be given that it is not intended when giving a set of drafts for
any counts to infer that these are fixed, and will work out
successfully in every case and under all circumstances, but only
that having been employed, they form a guide which may be

useful. Nothing is more fatal to any proper treatment of this subject than to accept as inflexible, arrangements which work well under given conditions, but which if the conditions are varied, even slightly, will not do so. The reader must, therefore, understand that the different schemes of drafts given are merely illustrative and not fixed.

(344) It will be convenient to commence with a system of drafts for the lower counts, and subsequently deal with those which are finer. One of the most important points to be considered in dealing with this subject is the weight of the scutcher lap which is fed to the carding engine. This should not be too heavy, as, if it is, the draft in the carding engine, or those in the succeeding machines, must be materially increased. For counts from 10's to 20's, a lap of from 11 to 12 ounces per yard is heavy enough, and as the yarn to be spun becomes finer, the lap is necessarily lighter, although the difference in the weight is not proportionate to the increasing fineness of the yarn. Another matter requiring special care is the draft in the carding engine. There is no rule observed in this case, and, judging by results, a draft of 85 and one of 105 give equally satisfactory results. Generally speaking, however, the shorter the staple of the cotton the less the draft in the carding engine. Having made these preliminary remarks, a few instances may be given of typical drafts. In spinning the lower counts, say up to 20's, short stapled American and Indian, or a mixture of these cottons, are used, and the drafts are regulated accordingly. Assuming that an 11oz. lap of Indian cotton is used, and that such speeds are adopted in the card as to produce a sliver of 60 grains weight per yard, a draft of about 85 will be found sufficient. A 60 grains sliver is ·139 hank, and assuming that the usual procedure was followed of putting up six ends at each passage through the drawing frame—two passages being thought sufficient in some cases for such coarse work—and a draft of 6 being arranged for in each head, the hank roving is the same. Thus, to reduce this to a slubbing of ·625 hank, a draft of 4·5 is wanted in that machine. In

some cases it is preferred to give a little less draft in the draw-
ing frame, so as to get a heavier sliver for presentation to the
slubbing frame, the draft in which is increased, but with a
cotton so short in the staple as some classes of Indian, it would
probably be better to keep the draft as low as possible in
the drawing and slubbing frames. This can be done by getting
a finer carded sliver, but the weights given will be found to work
fairly well. Having got a slubbing of the hank named, a draft
of 2·8 will give a roving of 1·75. Drafts of 5·7 or 6·85 will be
needed to spin 10's or 12's yarn respectively. These drafts are
all arranged for single roving. If the slubbing were doubled at
the roving frame, the draft in that machine would necessarily be
double that stated, or, in other words, it would be 5·6. If
American cotton is used, then the drafts in the drawing frame
can be arranged to increase the weight of the sliver, or a heavier
sliver can be employed, in which case the draft in the roving
frame would be increased, as would be also that in the spinning
machine. In spinning Indian cotton into 16's yarn, and using
three roving frames beginning with a carded sliver of ·144 hank,
and passing it through three heads of drawing in which the
number of ends and the drafts are equal, then the following are
a good set of drafts. Slubbing 3·5, intermediate 2, roving 2·75,
spinning machine 5·8. This scheme has the fault that the
drafts in the drawing machine are too great, and in the three
passages an increase in the weight of the sliver may very advan-
tageously be made. If the draft at this stage be reduced, and
that at the slubbing and intermediate arranged to compensate
for it, an improvement would result. In spinning the same counts,
leaving out the intermediate machine, the sliver can be reduced in
weight in the drawing machine, and the draft in the slubbing
frame increased, leaving that of the roving frame about the same,
but increasing that of the spinning. In producing counts from 20's
to 24's, a little lighter finished scutcher lap is used, and a draft
of about 90 in the card will be sufficient. In this class of yarn,
whatever may be the carded sliver produced, it is good practice
to obtain the same weight of drawn sliver. Assuming this to be

done by making the draft and number of ends put up at each head to be equal, and that the slubbing should be ·625 hank, a drawn sliver of ·16 hank will give good results. If the material used be Indian cotton, this weight may be slightly increased, and if American is employed it may be a little decreased. If, however, this is the sliver used, a draft of 3·9 in the slubber, of 2 in the intermediate, and of 2·4 to 2·8 in the roving machine, will enable a draft of 8·3 to 8·6 in the spinning machine to produce 20's or 24's yarn.

(345) Twist yarn can be spun either on the ring frame or mule, but there is not in the main much difference in the preparatory stages. As stated when dealing with the ring frame, it is necessary to rather increase the draft in that machine to compensate for the shortening action which takes place, but this is a matter affecting the final draft, and not those in the preparatory stages. In preparing twist yarn, say 22's or 24's, and beginning with a carded sliver ·15 hank, the common draft of 6 in each of the drawings and doubling of 6 ends will give a similar hank drawing. Now let the drafts in the three rovings be respectively 4, 4, and 5—the intermediate and roving frames being fed by double slubbings—then a roving will be produced of 3 hank, which being used single in the mule or ring frame, can be spun—in the first case with a draft of 8, and in the latter with a draft of 8·2, which will give a yarn of 24's. It is possible to vary these drafts by using a slightly heavier carded sliver, increasing the drafts in the roving frames, and decreasing that in spinning, but this is a matter which must be left to the discretion of the spinner. Now let it be supposed that the yarn so made has been produced from laps made at the opener, which have been passed through two scutchers, three being fed to each. The doublings given to the cotton under this system would be $3 \times 3 \times 6 \times 6 \times 6 \times 2 \times 2 = 7,776$. In spinning counts coarser than 20's the drafts do not greatly vary if an intermediate slubbing frame is used, but a heavier sliver is employed. Say that 16's yarn is being spun, then the

drafts in the drawing head can be well arranged to reduce the sliver to the necessary extent as it passes the first head, preserving its weight in the subsequent passages. A final drawn sliver of ·155 to ·165 will give good results in the subsequent processes. If only two machines be used for producing the roving, then the draft in the roving frame must be largely in excess of that in the slubbing frame. The latter can be about 4·5, while the former may be as high as 5·8. A draft in spinning of about 7·5 will give the desired counts of yarn. If, on the other hand, an intermediate frame is added, then the weight of the sliver must be increased, and the draft in the slubbing frame can be reduced materially, that in the intermediate be a little higher, and that in the roving frame somewhat less than that stated above. Suppose, for instance, that we commence with a carded sliver of ·14, and double six at each of the drawing heads, but give drafts of 6·4, 6·2, and 6 respectively, then the drawn sliver will be ·154. If, however, only two machines are being used to further prepare the sliver for spinning, then a draft of, say, 4·7 given in the slubbing will give 72 slubbing. Double this in the roving frame creel, and give a draft of 5·8 in that machine, then a roving will be produced which will be 2·09 hank. To spin this into 16's yarn from a single roving requires a draft of 7·7. If the same procedure be followed, with the exception of introducing an intermediate frame, then the sliver can be made as heavy as ·12 hank when it leaves the drawing frame, and the drafts must be arranged accordingly. Thus, giving drafts of 3·6, 4, and 5·1 in the three machines respectively, and using double, slubbing, and intermediate, will give a 2·24 hank roving, which, with a draft of 7·14 in the mule with single roving, will give the necessary yarn.

(346) In arranging the drafts for 20's hosiery yarn, the carded sliver should be from ·15 to ·18 hank, and a good result is got by putting up six ends to each head of the drawing frame, and giving a draft of 6, by which a similar weight of drawn sliver is got. The following are good drafts in the rollers of the drawbox for most classes of cotton :—From back to third

roller, 1·25; from third to second roller, 1·48; and from second to front roller, 3·222. The total draft is, therefore, 1·25 × 1·48 × 3·222 = 5·96, or, practically 6. The cotton from which hosiery yarn is spun being of the softer varieties, the distances of the rollers apart can be regulated as indicated in paragraph 188. Assuming that the sliver from the drawing frame is ·15, the following is a good scheme of drafts throughout. In the slubbing frame the draft is 5, and the hank slubbing produced 5 × ·15 = ·75. For the best work it is preferable and necessary to double the slubbing and roving at each subsequent stage, as this conduces largely to the regularity which is essential. Whenever two ends are put up and drawn together, it is equivalent to doubling the weight of the slivers put up, and thus, in the present case, the slubbing would practically be, when presented to the intermediate frame, ·75 ÷ 2 = ·375 hank. The draft in the intermediate frame being 5·865, the hank roving produced is ·375 × 5·865 = 2·2. The intermediate slubbing being doubled, and the draft in the roving frame being 5·2, the hank roving produced is $\frac{2·2}{2} \times 5·2 = 5·72$. When placed in the mule creel two ends are doubled, and the rollers in the mule having a draft of 7, the yarn produced is $\frac{5·72}{2} \times 7 = 20·02$. If the hank sliver produced in the drawing frame be, say ·17 hank, then the draft in the intermediate and roving frames could be reduced, but that in the mule ought to be kept constant. In spinning hosiery yarns, a speed of about 7,000 revolutions is a good one for the spindles. Weft yarns for medium counts, say 36's to 40's, are spun much in the same way as hosiery yarns. Taking a weft yarn of, say 36's counts spun from average American cotton, the drafts could be averaged thus. Let a carded sliver of ·16 hank be obtained, it is desirable to have a triple passage through the drawing frame, putting up six ends to each head and giving a draft at each passage of 6. The drawn sliver would therefore have the same weight. The drafts in the roving frames are determined by the question

whether a single or double roving is to be used in the inter-
mediate and roving frames and mules, or any of them, but it
is a very common practice to put up double rovings throughout.
In that case the drafts could be arranged as follows :—

Slubbing, one end up, draft 4·5, gives ·16 × 4·5 = ·72 hank.

Intermediate, two ends up, draft 4·8, gives $\frac{·72}{2} × 4·8 = 1·72$ hank.

Roving, two ends up, draft 6·25, gives $\frac{1·72}{2} × 6·25 = 5·33$ hank.

Mule, two ends up, draft 13·5, gives $\frac{5·33}{2} × 13·5 = 36·0$ hank.

There are one or two remarks which may be made on this. The
drafts given will work out very well, but it is the practice in
some cases to give a greater draft in the mule, using not more
than a 5-hank roving for this yarn.   In that case the drafts in
the intermediate and roving frames require reducing, and that
in the mule increasing.   Drafts of 4·6, 6, and 14·5 in these
machines respectively will give the desired results. Now, let it be
assumed that only one end is put to the mule, so that the yarn is
spun from single rovings, then the hank roving could be reduced
to, say 4·5, and the drafts in the mule 8. It is therefore possible
within certain limits to alter the drafts very considerably, and
yet get good results.   For instance, the following are the drafts
which are actually used in spinning 40's weft from an ·18-carded
sliver in a mill in which the drawing frames are too few in
number. It is therefore essential to compensate for this at a
later stage.

Drawing, 1st head, six ends up, draft 4·01, gives sliver ·12 hank.
   „   2nd head, six ends up, draft 6·02, gives sliver ·12 hank.
   „   3rd head, six ends up, draft 6·02, gives sliver ·12 hank.
Slubbing, one end up, draft 5·3, gives sliver ·636 hank.
Intermediate, two ends up, draft 5·2, gives sliver 1·64 hank
Roving, two ends up, draft 6·21, gives sliver 5 hank.

The drafts show an important variation from those previously
given, and may be compared with the following, which
are also actual instances, with single rovings throughout
For 32's yarn. a draft in slubbing frame of 3·8, with a ·16 sliver

of 2·8 in the intermediate, of 2·6 and of 7·3 in the spinning machine will be sufficient : 40's yarn can be spun from a similar sliver, with drafts of 4·7, 2·5, 2·53, and 8·4 in the slubbing, intermediate, roving, and spinning machines, respectively. 50's yarn can be produced with drafts in the same machines of 5·4, 2·3, 2·5, and 10 ; but these drafts can be very advantageously changed by using a finer sliver and reducing the draft in the slubbing machine ; say a ·17 sliver and a 5·1 draft. If the slubbings and rovings are doubled the drafts in the intermediate and roving frame must be proportionately increased, as has been previously shown.   All the above are drafts for American cotton.

(347) Fine yarns can be best spun when the slivers are combed, but the higher medium counts are often spun without a combing machine. In spinning yarn of 45's to 50's counts, using a good staple and double rovings, with a draft in the slubbing frame of 4·5, a drawn sliver of ·194 hank may be used, which will make the slubbing ·875 hank. Doubling the slubbing and intermediate in the creel, then drafts of 6·3 and 6·6 will give a 9-hank roving, which spun with a draft of 10 (with double roving) will give 45's, or of 11·2 will give 50's yarn. It is not necessary to give, in full detail, all the drafts for the various counts, so far as the drawing is concerned, but it may be stated that a sliver of from ·19 to ·21 hank may be used for counts from 60's to 150's, getting finer as the yarn is also made finer. It may also be noted that the draft must not, in the finer numbers, be always understood, when applied to the mule, as meaning the total, but only the roller draft, the difference required to produce the yarn being that given by the extra stretch referred to previously in dealing with the mule. The drafts and ends at the drawing frame are also increased as finer counts are produced, counts of over 150's having 7 or 8 respectively. After this explanation the drafts for various counts may now be given tabularly, these only relating to the slubbing, roving, jack-frames, and mule, double rovings being presumed in each case. The hank given with the mule is, of course,

PARTICULARS OF DRAFTS. ALL DOUBLE ROVINGS)

Machine.	1 Hank.	1 Draft.	2 Hank.	2 Draft.	3 Hank.	3 Draft.	4 Hank.	4 Draft.	5 Hank.	5 Draft.	6 Hank.	6 Draft.	Remarks.
Slubbing	1·125	—	1·25	—	1·375	—	1·0	4·6	1·5	—	1·5	—	
Intermediate	3·25	5·75	3·5	5·6	4·0	5·8	2·2	4·2	4·25	5·6	5·0	6·7	Egyptian
Roving	11·0	6·8	12·0	6·9	·14·0	7·0	5·54	5·0	15·0	7·1	17·0	6·8	Cotton.
Jack	—	—	—	—	...	—	16·0	5·75	—	—	—	—	
Mule	60's	10·9	70's	11·7	80's	11·4	80's	10·0	90's	12·0	100's	11·8	

Machine	7 Hank.	7 Draft.	8 Hank.	8 Draft	9 Hank.	9 Draft.	10 Hank.	10 Draft.	11 Hank.	11 Draft.	Remarks.
Slubbing	1·0	4·8	1·25	—	1·125	—	1·375	—	2·5	—	
Intermediate	2·2	4·4	2·25	3·6	2·5	4·4	3·0	4·36	6·0	4·8	No. 7 with Egyptian Cotton.
Roving	6·0	5·5	6·25	5·55	6·5	5·2	7·5	5·0	16·0	5·3	No. 8 with Short Sea Islands.
Jack	18·0	6·0	21·0	6·72	22·0	6·7	28·0	7·4	48·0	6·0	Nos. 9 and 10 Sea Islands,
Mule	100's	11·1	120's	11·2	140's	12·0	160's	11·0	250's	9·25	

The drafts given in Nos. 7, 9, 10, and 11, are extracted from "Progress in Cotton Carding," by the late F. A. Leigh, of Boston, U.S.A.

the counts of yarn spun, as will be easily understood. It will be noticed in reviewing these drafts that there is a considerable change in procedure taking place as the counts are varied, and that even when the same numbers are being spun there is a good deal of variation possible in the drafts. The following is a scheme of drafts for double combed yarns from good Sea Island cotton, as given recently by Mr. H. Walmsley. The cotton is prepared with one porcupine beater and one two-bladed scutcher, running at 900 revolutions per minute. The lap is ·8 ounce per yard, and the carded sliver 15 grains per yard. The combing machines are arranged to give a sliver of 20 grains per yard. In the drawing frames 8 ends are put up, and the draft is 7·75, giving a sliver 24 grains per yard or ·347 hank. The slubbing draft is 5·65, and the slubbing 2 hank; two ends at intermediate and draft of 5·5 gives roving 5·5 hank; two ends up at roving with draft 6·66 gives 15 hank roving; two ends up at jack frame 5·33 draft gives 40 hank roving, which doubled in mule with draft 7·5 gives 300's yarn. Although the drafts given can, of course, not be taken as actually applicable to all cases in which the same counts are being spun, they are founded upon actual practice, and will serve as a guide for the formulation of a complete set when any given counts are being spun. The ground is thus cleared for a consideration of the number of machines of each class needed in any mill which is intended to spin a given range of counts.

(348) We are now able to calculate the necessary number of machines and their size in order to produce any given kind of yarn, and will take a mill producing 32's twist only and containing 60,000 spindles. A good average production for this class of yarn is one pound per spindle per week, although this is sometimes exceeded. Such a mill will, therefore, produce 60,000lbs. of yarn per week, and this weight of cotton must, consequently, be supplied by each set of machines. In the calculation which follows waste is not taken into account, but the amount made will be subsequently indicated, so that the corrections can be readily made. It must be again pointed out

that all these instances are illustrative of the principle rather than definite examples. Assuming that it is spun from a four-hank roving, the production of which is 10·62lbs. per spindle per week, with a front roller speed of 119, 5,650 roving spindles are required. The hank of the intermediate roving used being 1·75, which enables a production of 31lbs. per spindle to be obtained with a front roller speed of 132, the number of inter-mediate spindles required is 1,936. This is produced from a slubbing of ·625 hank, which can be produced at a rate of 89·26lbs. per week with a roller speed of 161. This implies the use of 672 slubbing spindles. Now, these spindles have to be supplied by the drawing frames, which will deliver a varying quantity of sliver, depending upon its weight and the diameter and velocity of the front roller. Assuming this to be produced from a drawn sliver of ·16 hank, or 52 grains to the yard, and the front roller to run at 340 revolutions, then the production of each drawing head will be in 56½ hours, with a front roller 1¼ inch diameter, 1,057lbs. Thus, to supply 60,000lbs. of cotton, 56 deliveries would be required, which could be got by using eight machines of seven deliveries each. If revolving flat carding engines are employed, and it be assumed that they produce 850lbs. of finished sliver per week, then 70 will be wanted. The necessary opening and scutching machinery required would be three finishing scutchers, three intermediate scutchers, and two combined openers and lap machines. Thus we arrive at the needs of a mill of this description, to be as follows :—

<div style="padding-left:3em">

2 or 3 combined opening and lap machines.
  3 breaker scutching machines.
  3 finishing scutching machines.
 70 revolving flat carding engines.
  8 drawing frames with seven deliveries each.
 672 slubbing spindles.
1,936 intermediate spindles.
5,650 roving spindles.
60,000 mule spindles.

</div>

It only remains, therefore, to fix the size of the slubbing and roving frames and mules to arrive at the arrangement of the

machines in the mill. If it was not thought advisable to have so
many deliveries in the drawing frames the number could be in-
creased say to 11 frames of five deliveries each, which, with a
slightly accelerated speed of front roller, would provide all the
drawing power required. As the mill building would probably be
arranged to get in mules as long as possible, this is the determin-
ing feature in designing it, and would to some extent control the
length of the roving frames. Assume the mules to have 1,044
spindles, and to be 1⅜ gauge, then the spinning rooms would have
to be 125ft. wide plus the space required for alleys or passages
at each end. Assuming these to be 3ft. each, this gives a total
width of mill of 131ft. within walls; and if four spinning rooms
are used, then there would be 14 mules in each room, and a
length of 172ft. would provide for these. Thus the lower floor
would be 172ft. by about 128ft., because, as will be shown here-
after, the width of the rooms gradually narrows as the basement
is reached. In a room of this size, therefore, the whole of the
carding, drawing, and roving machines have to be fitted. The
carding engines are sometimes provided for in modern mills of
a large size by the erection of a shed adjoining and forming
part of the lower room; and the blowing room is also separately
arranged. It must, of course, be understood that these dimen-
sions are only approximate, although in the main accurate. It
is useless following the calculation and fixing the size of the
machines, because this can only be done when the whole cir-
cumstances of the case are known. In Fig. 250, however, the
card room of a mill containing 86,494 spindles is shown in
plan, which will give an idea of the method of arrangement. It
will suffice therefore to demonstrate the method of calculating
the number of spindles required, but it may perhaps be stated
that for spinning counts of this character the roving frames
would be made with 8 spindles in 20 inches or 20½ inches space,
with bobbins of 7 inches or 8 inches lift. The intermediate
frames could be conveniently made about 6 spindles in 19 inches,
with bobbins of about 9 inches lift, and the slubbing frames
with 4 spindles in 19 inches or 20 inches, and a bobbin 10 inches

FIG. 250.

to 11 inches lift. The drawing frames are made of various gauges, from 15 inches to 20 inches, but a convenient gauge for frames of the character required is 18 inches, and as many as 8 deliveries can be got from each head of these machines. In arranging the blowing rooms, it is now customary to separate them from the main building by the rope race, and to have a mixing room on an upper floor, from whence, by pneumatic means, the cotton can be conveyed to the first opening machine in the manner illustrated in Chapter III. The latter is arranged so that its lap end adjoins the feed end of the breaker scutcher, which in turn is succeeded by a finisher scutcher in an approximately similar position. The laps do not therefore require much handling, and the expenditure of labour is thus reduced.

(349) The instance just given will enable the general principles upon which mills are planned to be understood, and in order to give a little better guide than the purely illustrative case stated, a few actual instances will be given. It may be taken as a general rule that the finer the counts the greater the number of spinning spindles required to the same number of drawing deliveries and roving spindles. This will be quite evident if the table of productions be considered. Not only so, but in low counts the number of machines used can be varied, the intermediate frames being dispensed with; while in the higher counts, with Egyptian cotton, the number of scutching machines can be reduced. In double carded Egyptian yarns a Derby doubler is introduced between the breaking and finishing cards. In producing very fine combed yarns the machines necessary to form the lap for the comber are added, and, as indicated in Chapter II., a fourth roving or jack frame is used. In the first instance chosen the mill is designed to spin from American cotton, 40's or 50's twist and 50's to 70's weft. There are the following machines employed :—

22 weft mules, 1⅛ inch gauge each, 1,260 spindles = 27,720
22 weft mules, 1⅛ inch gauge each, 1,272 spindles = 27,984

Total........................... 55,704

22 twist mules, 1⅜ inch gauge each, 1,038 spindles = 22,836

22 twist mules, 1⅜ inch gauge each, 1,044 spindles = 22,968

Total.......................... 45 804

52 roving frames, 8 spindles in 20½ inches, 7 inches lift, 168 spindles in each = 8,736.

18 intermediate frames, 6 spindles in 19½ inches, 10 inches lift, 132 spindles in each = 2,376.

12 slubbing frames, 4 spindles in 19 inches, 10 inches lift, 90 spindles in each = 1,080.

9 drawing frames, 4 heads, 7 deliveries each = 252.

128 revolving flat carding machines, 50 inches cylinder, 38 inches wire.

6 finishing scutchers, fed from 4 laps.

6 breaker scutchers, fed from 3 laps.

4 opening machines, with lap attachment.

4 porcupine feed tables in mixing room.

The following are the details of the machinery in the plan given in Fig. 250 :—

40 mules, each 1,308 spindles, 1½ inch gauge = 52,320

32 mules, each 1,066 spindles, 1⅜ inch gauge = 34,174

Total.......................... 86,494

40 roving frames, 8 spindles in 20 inches, each 172 spindles = 6,880.

16 intermediate frames, 6 spindles in 19¾ inches, each 132 spindles = 2,112.

8 slubbing frames, 4 spindles in 20 inches, each 86 spindles = 688.

8 drawing frames, each 3 heads of 7 deliveries = 168.

67 revolving flat carding engines, 50 inches cylinder, 38 inches on wire.

4 single beater finishing scutchers.

4 single beater breaker scutchers.

2 combined openers and single scutchers.

1 bale breaker.

(350) The following are the particulars of the machinery in a modern spinning mill devoted to the production of good yarns for sewing cottons, the mules being arranged for spinning medium fine counts :—

74 mules, 1,016 spindles each, 1¾ inch gauge.

60 roving frames, 182 spindles each, 8 spindles in 18 inches, 7 inches lift.

30 intermediate frames, 126 spindles each, 6 spindles in 19½ inches, 10 inches lift.

14 slubbing frames, 84 spindles each, 4 spindles in 16 inches, 10 inches lift.

6 drawing frames, 4 heads, 6 deliveries each.

1 drawing frame, 3 heads, 6 deliveries each.

3 drawing frames, $\begin{cases} 2 \text{ heads, 7 deliveries each.} \\ 1 \text{ head, 6 deliveries each} \end{cases}$

140 combing machines, 8 heads each.

20 ribbon lap machines.

20 sliver lap machines.

140 revolving flat carding machines, cylinders 50 inches diameter, 44¼ inches wide.

6 finisher scutching machines.

6 combined opening, scutching, and lap machines.

1 bale breaker, used as a mixer.

As there is a considerable variation existing in designing mills for countries in which spindles are not run at so high a speed as in England, nor the productions so great, a few details of the spinning department of a mill fitted in Portugal by Messrs. John Hetherington and Sons, Limited, will be of interest.   In these works weaving and bleaching are also carried on, but as these lie outside the scope of this book, nothing is said of that class of machinery.   It will be noticed that a large variety of yarn is made, which renders it necessary to make special provision for it.

4 mules, each 404 spindles, 1½ inch gauge, for hosiery yarns.

2 mules, each 780 spindles, 1½ inch gauge, for reeled weft.

8 ring frames, each 408 spindles, 2¾ inches gauge, for twist yarn.

4 ring frames, each 428 spindles, 2⅝ inches gauge, for twist yarn.

4 mules, each 1,040 spindles, 1⅛ inch gauge, for weft. ⎫

22 ring frames, each 500 spindles, 2¼ inches gauge, for weft. ⎬ Weaving.

18 ring frames, each 428 spindles, 2⅝ inches gauge, for twist. ⎪

3 ring frames, each 408 spindles, 2¾ inches gauge, for twist. ⎭

3 ring frames, each 428 spindles, 2⅝ inches, gauge, for reeled yarn.

33 roving frames, each 164 spindles, 8 spindles in 20 inches, 7 inches lift.

24 intermediate frames, each 124 spindles, 6 spindles in $19\frac{3}{4}$ inches, 10 inches lift.

17 slubbing frames, each 82 spindles, 4 spindles in 20 inches, 10 inches lift.

18 drawing frames, each 3 heads, with 6 coilers to each head.

140 revolving flat carding engines, 50 inches cylinder, 38 inches wide.

3 finisher scutchers for 40 inches laps.

3 breaker scutchers for 40 inches laps.

2 single Crighton openers and lap machine.

1 bale breaker.

In addition there are—

14 forty-hank double reeling machines.

15 cop reels.

2 bundling presses.

The following particulars of the equipment of a recently erected ring spinning mill will be of interest :—

21 ring spinning frames, $2\frac{5}{8}$ inches gauge, 5 inches lift, each 372 spindles = 7,812.

32 ring spinning frames, $2\frac{5}{8}$ inches gauge, 376 spindles = 12,032.

34 ring spinning frames, $2\frac{5}{8}$ inches gauge, 380 spindles = 12,920.

31 roving frames, 8 spindles in $20\frac{1}{2}$ inches each, 180 spindles = 5,580.

12 intermediate frames, 6 spindles in $19\frac{1}{2}$ inches each, 140 spindles = 1,680.

7 slubbing frames, 4 spindles in $17\frac{1}{2}$ inches each, 98 spindles = 686.

4 drawing frames, 3 heads, 8 deliveries } = deliveries 104.
9 drawing frames, 1 head, 8 deliveries. }

56 revolving flat cards.

3 finisher scutchers.

3 breaker scutchers.

2 openers.

(351) In order to enable the necessary calculations to be made, a few particulars of productions of various machines are given. Scutching machines may be taken as being able to produce 20,000lbs. weight of laps per week, and opening machines up to 30,000lbs. weight. Carding engines of the revolving flat type will produce 800lbs. to 1,000lbs. per week, and roller and clearer machines from 600lbs. to 700lbs. It is not desirable to overload carding engines, and 850lbs. per week may be taken as a base in calculating the number of revolving flat carding

engines wanted. When dealing with good cottons, such as Egyptian, the weight obtained is only from 450 to 500lbs. per week, and with Sea Islands from 200 to 350lbs. It is very essential not to overload cards when preparing fine yarns. Combing machines will produce from 30lbs. to 75lbs. per day, according to the quality of yarn. The production of drawing frames depends upon the number of deliveries and the speed and diameter of the front roller. It can easily be obtained by calculating the number of yards delivered by the front roller in a week, and then multiplying that product by the weight of the sliver in grains per yard. If 10 per cent be allowed for stoppages, a fair margin is given. With reference to the remainder of the machines, the table on page 591 gives a number of average productions, but it must be understood that these can be varied according to the circumstances of the case. In dealing with Indian cotton and low counts it is, of course, necessary to adopt a different scale of productions. This is evident when the characters of the material and of the available labour are considered, but in the main the productions which are given are correct. They are, indeed, rather in excess of those actually obtained, but with this reservation may be accepted as a guide. The waste made naturally depends upon the quality of the cotton, and even in the same variety differs largely in various seasons. In the opener and scutching machines this factor plays the greatest part, but there is an excess of productive power in these machines, so that the calculation of the number wanted is not much affected. The waste at the carding machine averages about 5 per cent; in the combing machine about 15 to 18 per cent; in the drawing frame about 2 to 2½ per cent; in the slubbing and intermediate about 1½ per cent each; and the roving frame about 1 per cent. The waste in the spinning machines is light, and does not need special consideration. In making a calculation of the number of spindles, etc., wanted at each stage, it is necessarily subject to the correction indicated for the waste produced. The figures are derived from data collected by the author, and are given as a guide

PRODUCTIONS OF MACHINES FOR ROVING AND SPINNING FOR VARIOUS COUNTS PER WEEK OF FIFTY-SIX HOURS.

Slubbing Spindle Speed, 700 Revs. Lift 10 inches.		Intermediate Spindle Speed, 800 Revs. Lift 8 or 9 inches.		Roving Spindle Speed, 1,000 Revs. Lift 7 or 8 inches.		Jack Frame Spindle Speed, 1,400 Revs. Lift 5 or 6 inches.		Mule Spindle Speed 7,000 to 8,000 Revs.				Ring Frame Spindle Speed, 7,000 Revs.	
								Twist		Weft			
Hank.	Lb. per Spindle.	Hank.	Lb. per Spindle.	Hank.	Lb. per Spindle.	Hank.	Lb. per Spindle.	Counts.	Lb. per Spindle.	Counts.	Lb. per Spindle.	Counts.	Lb. per Spindle.
0·35	195	0·8	79	1·75	40·0	7	7·25	6	4·5	28	1·4	10	6·0
0·4	154	0·9	68	2·0	33·0	8	6·0	8	3·5	29	1·3	12	4·5
0·5	115	1·0	60	2·5	23·0	9	5·25	10	2·75	34	0·96	16	3·0
0·6	92	1·1	54	3·0	17·0	10	4·5	12	2·4	36	0·88	18	2·75
0·7	83	1·2	49	3·5	13·5	12	3·5	16	2·0	38	0·8	20	2·5
0·9	62	1·3	44	4·0	11·0	14	2·5	20	1·75	40	0·75	24	2·0
1·0	56	1·4	39	5·0	7·75	16	2·0	24	1·5	46	0·66	28	1·625
1·25	38	1·5	36	5·5	6·8	18	1·8	28	1·2			32	1·25
		1·6	33	6·0	6·0	20	1·5	30	1·1			36	1·0
						25	1·0	32	1·0			40	0·875
								34	0·9				
								36	0·85				
								40	0·75				
								50	0·56				
								55	0·47				
								60	0·4				
								70	0·32				
								80	0·21				

and not as fixed productions. The speeds of the various parts can be altered at will, thus affecting the production.

(352) The question of the power required to drive a mill is a matter of some importance, and one which has not been properly formulated. The powers which are usually given are as follows, but it must be obvious that these will differ considerably under different circumstances :—

Single opening machine, 4 to 5 h.p.

Double scutching machine, 1,400 revolutions of beater per minute, 6 h.p.

Revolving flat carding engine, $\frac{5}{8}$ to $\frac{3}{4}$ h.p.

Roller and clearer carding engine (single), $\frac{3}{4}$ h.p.

Roller and clearer carding engine (double), $1\frac{1}{2}$ h.p.

Drawing frames, per delivery, $\frac{1}{4}$ h.p.

Slubbing frames, 68 spindles, 600 revolutions, $1\frac{5}{8}$ h.p.

Intermediate frames, 74 spindles, 700 revolutions, $1\frac{1}{3}$ h.p.

Roving frames, 160 spindles, 1,000 revolutions, 2 h.p.

Mule spindles, 230 spindles, 9,000 revolutions, 1 h.p.

Ring spindles, 120 spindles, 7,000 revolutions, 1 h.p.

As a rule, it is considered that about 85 mule spindles, with the necessary preparation machinery, require one-horse power, the number of ring spindles being somewhat less. From some results of mills of equal size and of similar conditions 100 mule spindles, with preparation, spinning coarse and medium counts, take $1\frac{3}{8}$ h.p., while ring spindles take $2\frac{1}{4}$ h.p. for the same number. The power required, however, is only a part of the question, as the number of pounds of yarn produced per h.p. is much more important. In this respect, if ring yarn answers the purpose for which it is intended, there is little doubt that in counts up to 32's the ring has an advantage over the mule. In other respects there is some advantage, as the class of labour employed is remunerated at a cheaper rate. The power needed is naturally affected by the speed of the machines, which enormously affects the friction of the numerous small bearings. This is a factor which depends largely upon the judgment of the user, and it is often found that a slower speed is more economical than a faster one. For fair average counts and cottons the speeds may be taken to be as follows :—

Crighton opener beater..................... from	800 to 1,100	
,, ,, fan .... ,,	1,000 to 1,200	
Porcupine opener beater .... ,,	800 to 1,200	
Scutcher beater, 2 bladed .... ,,	1,200 to 1,500	
,, 3 bladed .... ,,	900 to 1,000	
Revolving flat carding engine cylinder ,,	160 to	180
,, ,, ,, doffer ... ,,	12 to	14
Drawing frame front roller .... ,,	300 to	350
Slubbing frames spindles................. ,,	650 to	750
Intermediate ,, ,, ... ,,	750 to	850
Roving ,, ,, ... ,,	1,000 to 1,100	
Mule rim shaft .... ,,	700 to	800
Ring frame twist spindles................. ,,	7,000 to 8,000	
,, ,, weft ,, ... ,,	6,500 to 7,500	

Ring frames are run at higher speeds than those indicated
but in the most successful cases those given are not exceeded.
It may be taken as a guiding rule that the finer the grade of
cotton used the slower the speeds of the machines used,
and great care is necessary in this respect. Another point
which also affects this matter is the character of the lubri-
cant used. This speedily has its effect upon the power
required, and unsuitable oils are responsible for a great loss.
Mr. J. Veitch Wilson, who has given great thought to this
matter, says that the viscosity of oils for use in textile purposes
should be for ring spindles equal to sperm oil, and for mule and
throstle spindles 50 per cent greater. This is a very important
matter, and deserves the most serious consideration of all
spinners. The author knows of one case in which a rapidly
drying oil was supplied for the lubrication of the rollers of roving
frames, with the result that there was a jerky delivery and much
uneven roving.

INDEX OF ILLUSTRATIONS.

U

*

GENERAL INDEX.

A

**

N

O

P

T

33 138 25

Date Due

8-30-51			